MILITARY
SPECIFICATION

MIL-A-12945(SigC)
5 August 1953
Superseding U. S. Army
Specification No. 71-3361
29 November 1948

AMPLIFIER, AUDIO FREQUENCY AM-243( )/U

1. SCOPE

1.1 This specification covers one type of an audio frequency amplifier designated AM-243( )/U. The amplifier operates from a power source of 115 or 230 volts, 50 to 60 cycles with a power drain not in excess of 145 watts, and has a power output of 12 watts. Amplifier AM-243( )/U covers a frequency range from 30 to 15,000 c.p.s.

2. APPLICABLE SPECIFICATIONS, STANDARDS AND DRAWINGS

2.1 The following specifications, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

FEDERAL

UU-T-111	Tape; Paper, Gummed (Sealing and Securing).

MILITARY

MIL-P-75	Packaging, Packing, and Container-Marking of Electron Tubes.
JAN-P-105	Packaging and Packing for Overseas Shipment - Boxes, Wood, Cleated, Plywood (For Boxes Whose Weight of Contents Does Not Exceed 1000 Pounds).
JAN-P-106	Boxes, Wood, Nailed (Military Type)
JAN-P-108	Packaging and Packing for Overseas Shipment - Boxes, Fiberboard (V-Board and W-Board), Exterior and Interior.
MIL-P-116	Preservation, Methods of.
JAN-P-117	Packaging and Packing for Overseas Shipment - Bags, Interior Packaging.
JAN-P-120	Packaging and Packing for Overseas Shipment - Cartons, Folding Paperboard.
JAN-P-127	Packaging and Packing for Overseas Shipment - Tape, Adhesive, Pressure-Sensitive, Water Resistant.
MIL-B-131	Barrier-Material; Water-Vaporproof, Flexible.
JAN-P-133	Packaging and Packing for Overseas Shipment - Boxes, Set-Up, Paperboard.

Source: https://assist.dla.mil -- Downloaded: 20260-17T23:52Z
Check the source to verify that this is the current version before use.

MILITARY (CONTD)

JAN-T-152	Treatment, Moisture- and Fungus-Resistant, of Communications, Electronic, and Associated Electrical Equipment: General Process For.
MIL-P-11268	Parts, Materials and Processes Used in Signal Corps Equipment.

U. S. ARMY

19-10	Filler, Interior Packing, Fiberboard, Corrugated Single and Double Faced, For General Packing Purposes.

STANDARDS

MILITARY

JAN-STD-15	Electric and Electronic Symbols.
MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking of Shipments.

DRAWINGS

SIGNAL CORPS

SC-D-15800	Oscilloscope BC-000-( ), Circuit Label (Schematic Diagram).
SC-D-15914	Moisture Resistance Test Cycle for Ground Signal Equipment.
SC-D-19999	Standard Extreme-Temperature Cycle.
SC-D-25128	Power Cable Assembly CX-1208/U.

(Copies of specifications, standards and drawings required by contractors in connection with specific procurement functions should be obtained from or as directed by the contracting officer. Both the title and identifying number or symbol should be stipulated when requesting copies.)

Source: https://assist.dla.mil -- Downloaded: 20261O-17T23:52Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Parts, materials, and processes; general.- In addition to any requirements of this specification covering parts, materials, and processes, such items shall conform to Specification MIL-P-11268 including the selection requirements therein.

3.2 Electrical characteristics.-

3.2.1 Power source.- Amplifier AM-243( )/U shall operate from an a.c. power source of 115 or 230 volts ± 10%, 50 to 60 cycles ± 3 cycles at a power drain not in excess of 145 watts. The equipment shall be wired for 115 volts a.c. operation unless otherwise specified (see 6.2).

3.2.2 Power output.- The amplifier shall have a power output of 12 watts.

3.2.3 Amplifier input impedance.- The input transformer shall have dual primary windings which may be connected in series or parallel to provide input impedance of 600 to 150 ohms respectively. The equipment shall be wired for 150 ohms input impedance unless otherwise specified (see 6.2).

3.2.4 Amplifier output impedance.- The output shall match a 4,7.5, 15, 250 or 600 ohm line.

3.2.5 Low frequency control.- Full rotation of the low frequency equalizer control shall cause a minimum rise of 8.5 db at 40 cps, with respect to the normal curve. The departure from the normal shall begin at 500 cps plus 100 or minus 50 cps.

3.2.6 High frequency control.- Full rotation of the high frequency equalizer control shall cause a minimum rise of 10 db at 10,000 cps with respect to the normal curve. The departure from the normal shall begin at 1,000 cps, plus 200 or minus 50 cps.

3.2.7 Input level.- The amplifier shall handle a maximum input signal of minus 27 dbm.

3.2.8 Noise level.- The noise level for the amplifier with the volume control in the maximum position shall not exceed -19 dbm. The noise level for the amplifier with the volume control in the minimum position shall not exceed -25 dbm. (Total noise level shall be measured with a 150 ohm resistor across the input terminals.)

3.2.9 Distortion.- For normal power output, 12 watts at 400 cps, over the range of 50 to 7,500 cps the total harmonic distortion shall not exceed 2.5%; over the range 30 to 15,000 cps the total harmonic distortion shall not exceed 5%.

3.2.10 Gain.- The amplifier shall have an overall gain of 94 ±2 db at 400 cps when operating from a 150-ohm source into a matched resistance load with the volume control full on, tone controls at minimum position.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:52Z
Check the source to verify that this is the current version before use.

3.2.11 Frequency response.- Amplifier AM-243( )/U shall be tested over a frequency range of 30 cps to 15,000 cps in a properly matched circuit. The frequency response shall be uniformly level within 4 db, with the high and low frequency controls at minimum.

3.3 Physical requirements.-

3.3.1 The amplifier shall be designed to permit its being mounted in standard 19 inch cabinet rack and shall not occupy more than 10 inches of rack mounting space. The overall depth of the amplifier shall not exceed 8-1/4 inches. The amplifier chassis shall be designed to mount vertically so that the equipment may be serviced without removing the main chassis assembly from the rack when a large center panel is removed.

3.3.2 The input connector shall be Cannon Electric type XL-3-14 or equal.

3.3.3 Screw terminals permitting connection to either 4, 7.5, 15, 250 or 600 ohm output circuit shall be mounted on the chassis.

3.3.4 An a-c. power cord 8' long in accordance with Drawing SC-D-24128 shall be furnished.

3.3.5 A standard a.c. receptable Hubbell Type No. 7466, or equal, shall be mounted on the chassis.

3.3.6 A high frequency equalizer control shall be mounted on the panel.

3.3.7 A low frequency equalizer control shall be mounted on the panel.

3.3.8 An "On-Off Switch" shall be mounted on the panel.

3.3.9 A fuse and a pilot light shall be mounted on the panel.

3.3.10 A volume control shall be mounted on the panel.

3.3.11 The weight of the complete amplifier shall not exceed 22 pounds.

3.4 Tropicalization.- The assembled equipment shall be treated in accordance with Specification JAN-T-152.

3.5 Adjustment and repair.- The equipment shall be so constructed that parts, terminals, wiring, etc., are accessible for circuit checking, adjustment, maintenance, repair, and replacement with minimum disturbance to other parts and wiring and with use of the minimum number and variety of special tools, particularly those needed for tuning and adjustment. When tools for tuning or adjustment are needed, the equipment shall provide convenient means for mounting them.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:52Z
Check the source to verify that this is the current version before use.

3.6 Circuit diagram.- A circuit diagram shall be furnished to facilitate installation, operation and maintenance of the equipment. The diagram shall be in the form of a label.

3.6.1 Schematic diagram.- A schematic wiring diagram suitable for use by maintenance personnel shall be mounted on an inside surface where it will be protected from abrasion but will be readily accessible to maintenance personnel. Graphical symbols on the schematic diagram shall conform to Standard JAN-STD-15. The schematic diagram shall conform to the sample drawing SC-D-15800 Circuit Label (Schematic Diagram).

3.7 Labels.- All materials and processes for labels as specified in Specification MIL-P-11268, may be used on external as well as internal surfaces of the equipment.

3.8 Facsimiles.- In addition to any facsimiles specified by applicable documents, 4 copies of the circuit label shall be submitted for approval to the contracting officer.

3.9 Service conditions.- The equipment shall meet the following service conditions:

3.9.1 Equipment operating.-

(a) Temperature.- Any ambient temperature in the range of -40° to +150°F. (The 150°F temperature includes effect of sun load.)

(b) Relative humidity.- Any relative humidity up to 98 percent.

3.9.2 Equipment nonoperating.- The equipment shall meet the requirements of 3.9.1 after subjection to any one or more of the following nonoperating conditions:

(a) Temperature.- Continuous exposure for 72 hours at 160°F and 72 hours at -80°F at any orientation.

(b) Relative humidity.- Relative humidity up to 100 percent, including condensation caused by temperature changes. Following subjection to such conditions and a power-on period of 16 hours at normal room temperature and relative humidity, the equipment shall meet the requirements of 3.9.1 except that the output may be 25 percent less than specified value.

(c) Vibration and bounce.- See 3.10.

3.10 Vibration and bounce.-

3.10.1 Vibration.- Except for internal resonance of specified parts and subassemblies, the equipment shall have no mechanical resonance below 55 cycles per second.

Source: https://assist.dla.mil -- Downloaded: 20261017T23:52Z
Check the source to verify that this is the current version before use.

3.10.2 Bounce.- The equipment shall meet full specification performance and show no physical damage except surface abrasion after subjection to the test of 4.12.

3.11 Bounce conditioning.- After final assembly, each equipment on contract, shall be placed in its normal operating position on the table of the Package Tester as made by the L.A.B. Corporation, Summit, New Jersey, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32-inch-thick strip of material under one corner or edge of the equipment to a distance of 3 inches as the equipment bounces. The equipment shall be subjected to this conditioning for 1 minute. After conditioning the equipment shall be capable of meeting the inspection of Section 4.

3.12 Preproduction samples.-

3.12.1 Quantities.- After award of contract, in addition to the samples listed in Specification MIL-P-11268, two complete equipments shall be furnished.

3.12.2 Compliance with specified requirements.-

3.12.2.1 Preproduction samples shall meet specified requirements, shall be made and assembled by tools and methods that will be used for quantity production and shall be accompanied by a statement to that effect.

3.12.2.2 Approval of preproduction samples shall not be construed as a waiver of any specified requirement . After being released to the contractor, preproduction samples to be offered as units on contract shall be refabricated by the contractor if necessary to meet specified requirements.

3.12.2.3 When deviation from 3.12.2.1 is unavoidable, the preproduction samples may be submitted for approval provided that the accompanying statement describes in detail each nonconforming feature, reason therefor, and manner in which it will be corrected in production of equipment on contract.

3.12.3 Test data.- The preproduction samples shall be accompanied by test data showing compliance with specified performance. The test data shall comprise an engineering report giving test procedure, observations and other data, calculations, test results and essential details of the testing equipment (manufacturer's model serial number, date of calibration, and similar data).

3.12.4 Preproduction inspection.- Preproduction samples may be submitted by the Government to the group A inspection specified in table II and to the preproduction inspection specified in table I. Unlisted nondestructive inspection on preproduction samples of equipment and unlisted destructive or nondestructive inspection on separate preproduction samples of parts or materials may be performed to determine compliance with specified requirements.

Source: https://assist.dla.mil -- Downloaded: 20261017T23:52Z
Check the source to verify that this is the current version before use.

Table I.- Preproduction inspection

Inspection	Rqt. Par.	Test Par.
Temperature	3.9	4.9
Moisture Resistance	3.9	4.10
Vibration	3.10.1	4.11
Bounce	3.10.2	4.12

3.12.5 Reference standards.- After preproduction samples have been approved and returned to the contractor's plant, they shall be kept intact in custody of the Government inspector until released by him. They shall be used as reference standards to resolve any difference of opinion regarding interpretation of requirements.

3.13 Technical literature, and running spare parts.- Technical literature, and running spare parts shall be furnished as specified by the contract. Running spare parts shall be identical to corresponding parts in the equipment furnished on the order (see 6.2).

3.14 Workmanship.- Components, subassemblies, and parts shall be manufactured and assembled in a thoroughly workmanlike manner.

4. SAMPLING INSPECTION AND TEST PROCEDURES

4.1 Inspection, general.- Government inspection shall consist of group A inspection as specified in 4.1.1.

4.1.1 Group A inspection.- Group A inspection shall be in accordance with table II and Standard MIL-STD-105. Group A inspection shall be performed in any order which is satisfactory to the Government inspector.

Table II. - Government group A inspection

Inspection	Req. Par.	Test Par.	AQL
Visual and mechanical, major	-	4.2	2.5 dphu*
Visual and mechanical, minor	-	4.2	10.0 dphu
Input impedance	3.2.3	4.3	2.5 dphu for the group
Output impedance	3.2.4	4.4	
Frequency response and control	3.2.5, 3.2.6, 3.2.11	4.5	
Power gain	3.2.10	4.6	
Distortion	3.2.9	4.7	
Noise level	3.2.8	4.9	
Power drain	3.2.1	4.13	
Power Output	3.2.2	4.14	
Operation	-	4.15	

*dphu - Defects per hundred units.

Source: https://assist.dla.mil -- Downloaded: 2026-04-17T23:52Z
Check the source to verify that this is the current version before use.

4.1.2 Disposition of nonconforming product.- When defective sample units or rejected lots are resubmitted for acceptance, such items shall be suitably tagged o identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The record shall be presented to the Government when the ite are resubmitted and shall become the property of the Government.

4.2 Visual and mechanical inspection.- Parts and equipment shall be inspecte for workmanship, mechanical fit, loose nuts and screws, application of specified tropicalization treatments, and miscellaneous defects. Controls and fastening devices shall be inspected for mechanical operation. Wiring, soldered connections, ground connections, welds, finishes, etc. shall be inspected for workmanship. Clearances, dimensions, and mechanical adjustments shall be measured. Labels and markings shall be inspected for conformance with approved facsimiles. Examination also may be made for other visual or mechanical defects, similar to those described above, that are contrary to specified requirements for the equipment. Visual and mechanical defects shall be classified by the Government as major or minor in accordance with the definitions of Standard MIL-STD-105.

4.3 Input impedance.- The equipment shall be tested to show compliance with 3.2.3.

4.4 Output impedance.- The equipment shall be tested to show compliance with 3.2.4.

4.5 Frequency response and control.- The output tap shall be terminated with a matching resistive load. A signal generator shall be connected to a resist matching the input impedance and connected in series with the input of the am With the volume control set for maximum gain, the output of the signal generator a 400 c.p.s. shall then be measured. With the output voltage of the signal generato held constant at this voltage, the frequency of the signal generator shall be vari from 30 to 15,000 c.p.s. to determine compliance with 3.2.11. The low frequency and high frequency controls shall then be varied to determine compliance with 3.2. and 3.2.6.

4.6 Power gain.- The power gain shall be tested to show compliance with 3.2.10.

4.7 Distortion.- With a total noise and distortion meter, such as the Hewle Packard Type 330 B or equal, connected to the load resistor, and with constant vol age output from the signal generator, as in the circuit described in 4.5, the tota distortion in the output shall be measured at frequencies of 30 to 15,000 c.p.s. t determine compliance with 3.2.9.

4.8 Noise level.- The equipment shall be tested to show compliance with 3.2.8.

4.9 Temperature.- The equipment shall be subjected to the temperature cycle shown on Drawing SC-D-19999. The tests of 4.3 through 4.8 shall be made at step and step 8. The equipment shall conform to full specification performance.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:52Z
Check the source to verify that this is the current version before use.

4.10 Moisture-resistance test for equipment.-

4.10.1 Test conditions.-

(a) Do not move components from the humidity chamber for measurements.

(b) Complete measurements as rapidly as possible.

4.10.2 Test procedure.- The components will be tested as follows:

(a) Dry at 130° ± 5°F. for 24 hours.

(b) Condition at 77° ± 5°F. and 40 to 50 percent relative humidity for 24 hours.

(c) Take measurements as specified in 4.10.3 and readjust or realign as necessary to meet specification requirements.

(d) Subject to continuous cycling for 5, 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Drawing SC-D-15914. The measurements specified in 4.10.3 shall be made during the periods shown on the drawing and shall comply with 4.10.3.

(e) After cycling has been completed, condition the components for 24 hours at 77° ± 5°F. and 40 to 60 percent relative humidity. The equipment shall meet full specification requirements for those measurements specified in 4.10.3.

4.10.3 Performance.- Measurements made during test and specified performance during cycling shall be as specified in 4.3 through 4.8.

4.10.4 Failure.- If the equipment fails to meet the performance specified in 4.10.3 it shall be rejected.

4.11 Vibration test.- The equipment shall be tested for resonant frequencies below 55 cycles per second, to determine compliance with 3.10.1, as follows:

(a) The equipment shall be fastened in its normal mounting position on a vibration table that can be controlled within 10 percent of the specified amplitude. The vibration table shall provide approximately sinusoidal vibration.

(b) The equipment shall be vibrated successively in three mutually perpendicular directions that are parallel respectively to the edges of the equipment, over a frequency range of 10 to 55 cycles per second, in 1-cycle-per-second steps. The total excursion shall be constant at 1/64 inch.

Source: https://assist.dla.mil -- Downloaded: 2020-10-17T23:52Z
Check the source to verify that this is the current version before use.

(c) Mechanical resonance, if any, of the complete structure, or subassemblies, and of component parts shall be determined visually by means of a Strobotac, as made by the General Radio Corporation, Cambridge, Massachusetts, or equal, or by energizing the equipment and detecting mechanical vibration through electrical output indications.

(d) If it is not practical to determine completely any mechanical resonances on the assembled equipment unit because of its compactness or the inaccessibility of its subassemblies or component parts, the unit shall be broken down into logical subassemblies for the above vibration test. Such subassemblies shall be secured to the vibration table in the same manner as they are secured in the equipment unit.

4.12 Bounce test.- The equipment, as packaged for shipment, shall be placed on the table of the Package Tester as made by the L.A.B. Corporation, Summit, New Jersey, or equal, and shall be constrained from horizontal motion of more than 2 inches by suitable wooden fences. The package tester, shafts in phase, shall be operated at a speed of 285 r.p.m. ± 1 percent, for a total of 3 hours. During each 1/2-hour period of the test, the packaged equipment shall rest on a different face.

4.13 Power drain.- The power drain shall be tested for compliance with 3.2.1.

4.14 Power output.- The power output shall be tested for compliance with 3.2.2.

4.15 Operational test.- A voice signal shall be supplied to the amplifier input and a loudspeaker shall be connected to the amplifier output. A listening test shall then be made to determine that the amplifier operates and responds properly to its controls.

Source: https://assist.dla.mil -- Downloaded: 20261017T23:52Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 For domestic shipment (immediate use).- Amplifier AM-243( )/U shall be packaged in accordance with Method III of Specification MIL-P-116.

5.1.2 For overseas shipment or domestic shipment involving extended storage.- Preserve and package Amplifier AM-243( )/U in accordance with procedures specified for the designated methods as prescribed in Specification MIL-P-116, and further described in the following paragraphs.

5.1.2.1 Technical manual.- Package each technical manual Method IC-3, as follows: Inclose each technical manual within a close-fitting Type II class b bag, conforming to Specification JAN-P-117. Properly seal closure.

5.1.2.2 Remove all operating tubes over 4 inches in length not securely clamped in place and package together with spare tubes, determined in quantity and number from the bid request or contract, individually in accordance with the applicable provisions of Specification MIL-P-75.

5.1.2.3 Fuse and lamp.- Package each item Method III, as follows: Cushion each item individually by wrapping in flexible corrugated paper. Secure cushioning with gummed Kraft tape, conforming to Specification UU-T-111. Place items cushioned as above, bearing same stock number, together within a close-fitting, folding carton or set-up box, complying with Specification JAN-P-120 or JAN-P-133 respectively. Seal entire closure with gummed Kraft tape.

5.1.2.4 Consolidated package.- Consolidate the items, packaged as specified in 5.1.2.2 and 5.1.2.3, together within a suitable style and grade corrugated fiberboard box. Fill all voids with flexible corrugated paper to prevent movement. Seal box closure with suitable tape, adhesive or stapling.

5.1.2.5 Amplifier AM-243( )/U.- Package each amplifier Method IIb, as follows: Place over the instrument panel, a blocking assembly, fabricated of wood panel and wood blocks to bridge projections on the instrument panel. Surfaces of blocks contacting the article shall be covered with suitable cushioning material to prevent abrasion. Secure the blocking assembly over the instrument panel. Cushion each amplifier on all surfaces with cells or pads or both fabricated of corrugated fiberboard, conforming to Specification 19-10 and designed to absorb the shock of impact encountered in handling and transit. Place each cushioned amplifier and consolidated package, packaged as specified in 5.1.2.4 together with the required amount of desiccant as prescribed in Specification MIL-P-116, within a close-fitting suitable style and grade corrugated fiberboard box. Seal entire closure with gummed Kraft tape conforming to Specification UU-T-111. Blunt all corners of the box. Place the boxed amplifier within a water-vapor-proof barrier, qualified for Class 1 application in accordance with the requirements of Specification MIL-B-131. Heat seal closure. Place the water-vapor-proofed amplifier within a close-fitting suitable style and grade fiberboard box conforming to Specification JAN-P-108. Seal entire box closure, corners and joints with water-resistant pressure-sensitive tape, conforming to Specification JAN-P-127.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:52Z
Check the source to verify that this is the current version before use.

5.2 Packing.-

5.2.1 For domestic shipment (immediate use).- Amplifier AM-243( )/U shall be packed so as to insure arrival at destination in satisfactory condition, and in containers complying with the Consolidated Freight Classification Rules at lowest rate.

5.2.2 For export shipment or domestic shipment involving extended storage.- Each Amplifier AM-243( )/U packaged as specified in 5.1.2.5 shall be packed in a wood cleated plywood or nailed wood box conforming to the requirements of Specification JAN-P-105 or JAN-P-106 respectively. Fabricate the box to fit the contents snugly. Place the technical manual packaged as specified in 5.1.2.1 between the contents and lid of the shipping container. Close the shipping container as specified in the appendix of the applicable box specification.

5.2.2.1 Shipping containers shall be strapped in conformance with the requirements of the appendix of the applicable container specification only for direct shipment to ports.

5.3 Marking for shipment.- Interior packages and exterior shipping containers shall be marked in accordance with applicable provisions of MIL-STD-129.

6. NOTES

6.1 Intended use.- Amplifier AM-243( )/U is intended for use in monitoring, recording, and audition applications.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Whether domestic or overseas shipment is required. (See 5.1 and 5.2.)
(c) Samples required. (See 3.12.1.)
(d) Technical literature required. (See 3.13.)
(e) Running spare parts. (See 3.13.)
(f) Whether wiring is required for other than 115 V. a.c. power and 150 ohm input impedance. (See 3.2.1 and 3.2.3.)

6.3 Contractual requirements.- It is recommended that the following be included in the contract:

6.3.1 Additional inspection.- It should be understood that additional examination, measurement, and nondestructive testing of equipment may be performed by the Government when considered necessary to determine compliance with this specification and other applicable documents. Accordingly, the Government inspector may withdraw materials, parts, subassemblies, or components temporarily from production for such inspection performed either at a Government laboratory or the contractor's plant.

Source: https://assist.dla.mil -- Downloaded: 2026-04-17T23:52Z
Check the source to verify that this is the current version before use.

6.3.2 Waiver of preproduction samples.- When items for which preproduction samples are required are currently in production on a Government order, the contractor may apply to the contracting officer for waiver of preproduction samples on the new order. Any request for waiver should be made by the prime contractor and should include a statement indicating that: the specified samples have been submitted and approved on the current contract, production of the item under the new order will be concurrent with, or follow without interruption, production on the current order and will be at the same plant; and current production is in strict compliance with specified requirements for the new equipment except for such deviations as may be authorized on the current order. These deviations should be described in the statement. Waiver of preproduction samples may be contingent on renegotiation of the contract to reflect the saving in cost to the contractor.

6.4 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design, for example, AM-243W/U. As soon as possible after the award of the contract, the contractor should apply to the contracting officer for such information.

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 20261017T23:52Z
Check the source to verify that this is the current version before use.