MIL-J-12959D(MK)
15 July 1976
SUPERSEDING
MIL-J-12959C(MK)
30 October 1969

MILITARY SPECIFICATION

JETTING SET, PORTABLE: FOR PILEDRIVING OPERATION, PACKAGING OF

This specification is approved for use by the Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the requirements for the preservation, packing, and marking of a Portable Jetting Set: For Piledriving Operation (SC 3895-97-CL-E02).

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-636	- Boxes, Shipping, Fiberboard.

MILITARY

MIL-C-104	- Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116	- Preservation-Packaging, Methods of.
MIL-P-10603	- Pumps and Pumping Units, Centrifugal, Power-Driven, for Water, Packaging of.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

STANDARDS
FEDERAL

FED. STD. No. 356	- Commercial Packaging of Supplies and Equipment.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking and Waterproofing; with Appropriate Test Methods.

(Copies of specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2) to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3).

3.2 Materials. Materials shall be as specified herein and in applicable specifications and standards. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Materials shall be free of defects.

3.3 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

3.3.1 Level A.

3.3.1.1 Preservative. Preservative specified herein shall conform to the applicable specification listed in and shall be applied in accordance with MIL-P-116.

3.3.1.2 Pipe and pipe fittings. All threads of pipe and pipe fittings shall be coated with Type P-1 preservative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

3.3.1.3 Hose assemblies. Each hose assembly shall be coiled to the minimum safe diameter and the coil shall be secured with evenly spaced ties of cotton tape. Threads of couplings shall be coated with Type P-1 preservative.

3.3.1.4 Gaskets. The gaskets for each set shall be preserved together in accordance with MIL-P-116, Method IC-1 and shall be placed in the box with the bent pipe as specified in 3.3.1.5.

3.3.1.5 Bent pipe and nozzle. The bent pipe and the nozzle shall be placed individually in a close-fitting box conforming to PPP-B-636, W5c, Style RSC. The gaskets shall be placed in the box with the bent pipe (see 3.3.1.4). Box closure shall be in accordance with the appendix to the box specification, Method V.

3.3.1.6 Bushing, couplings, nipples, reducers, and union. These items comprising a complete set shall be placed together in a close-fitting box conforming to PPP-B-636, W5c, Style RSC. Items shall be wrapped or cushioned to prevent damage to threads. Box closure shall be in accordance with the appendix to the box specification, Method V.

3.3.1.7 Pump unit (MAP). The pump unit shall be preserved in accordance with MIL-P-10603, Level A, and shall be secured to the base of the crate specified in 3.4.1.

3.3.1.8 Consolidation.

3.3.1.8.1 Components in fiberboard boxes. The components preserved in fiberboard boxes shall be consolidated together in a close-fitting box conforming to PPP-B-601, Domestic Type, Style I. Strapping shall not be required.

3.3.1.8.2 Coiled hose assemblies. The coiled hose assemblies for each set shall be consolidated together in a close-fitting box conforming to PPP-B-601, Domestic Type, Style I. Strapping shall not be required.

3.3.2 Commercial. Components of each jetting set shall be preserved in accordance with FED. STD. No. 356.

3.4 Packing. Packing shall be Level A or Commercial as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

3.4.1 Level A. The lengths of pipe and other components comprising a complete set, preserved as specified in 3.3 shall be packed together in a crate conforming to MIL-C-104, Type I, Class 2, Style 2. The components shall be arranged within the crate to provide a pack of minimum cube. The contents shall be blocked, braced, and anchored in accordance with MIL-STD-1186.

3.4.2 Commercial. The components of each jetting set shall be packed in accordance with FED. STD. No. 356.

3.5 Marking.

3.5.1 Military packaging. Marking shall be in accordance with MIL-STD-129.

3.5.2 Commercial packaging. Marking shall be in accordance with FED. STD. No. 356.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1. Material inspection. The contractor is responsible for insuring that supplies and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction pack inspection (see 4.3)
(b) Quality conformance inspection (see 4.4).

4.3. Preproduction pack inspection.

4.3.1 Examination. The preproduction pack shall be examined for the defects listed in 4.4.4. Presence of one or more defects shall be cause for rejection of the preproduction pack.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

4.4 Quality conformance inspection.

4.4.1. Inspection stages. Inspection shall be in three stages as follows:

(a) The first stage shall include inspection of procedures, methods, materials, containers, and marking prior to placing the components into consolidated containers.
(b) The second stage shall include inspection of closure and marking of consolidated containers, and the arrangement and blocking and bracing of packed components in the shipping container.
(c) The third stage shall include inspection of the closed, strapped, and marked shipping containers prepared for shipment.

4.4.2 Unit of product. For the purpose of inspection, all components prepared for any applicable inspection stage that will comprise a complete pack, shall be considered a unit of product.

4.4.3 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.4 Examination. Samples selected in accordance with 4.4.3 shall be examined for the following defects. Acceptable Quality Level (AQL) shall be 2.5 percent defective.

101. Materials, methods, or containers not as specified. Each incorrect material, method, or container shall constitute one defect.
102. Threads of pipe and fittings not coated with preservative as specified.
103. Hose assemblies not coiled and the coils secured as specified.
104. Gaskets not preserved together and placed in the box with the bent pipe as specified.
105. Fiberboard boxes not closed Method V as specified.
106. Consolidation of components not as specified.
107. Marking illegible, incomplete, incorrect, or missing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

5. PACKAGING

(This section not applicable to this specification.)

6. NOTES

6.1 Intended use. This specification is intended to be used for direct reference in contracts or purchase orders for the preservation, packing, and marking of a Jetting Set, Portable: For Piledriving Operation (NSN 389-00-641-7982) or (NSN 3895-00-926-1035) for MAP use.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and data of this specification.
(b) Time frame required for submission of the preproduction pack (see 3.1).
(c) Degree of preservation and of packing required (see 3.3 and 3.4).

6.3 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, package, pack, and mark the set components in accordance with this specification.

Custodian:
Army - ME

Review activity:
Army - SM,AT

Preparing activity:
Army - ME

Project 3895-A156

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE MIL-J-12959D(ME) - JETTING SET, PORTABLE: FOR PILEDRIVING OPERATION, PACKAGING OF

NAME OF ORGANIZATION AND ADDRESS	CONTRACT NUMBER
	MATERIAL PROCURED UNDER A ☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?
   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*	TELEPHONE NO.
	DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 68 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research and
Development Command
ATTN: DRXFB-DS
Fort Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:54Z
Check the source to verify that this is the current version before use.