RADIOSONDE BASELINE CHECK SET AN/GMM-1( )
(COMPONENTS OF)

1. Paragraph 3.9.1 General.- Delete the following:

"except that the notation 'US' shall be replaced with 'Signal Corps, U.S. Army' on the nameplate data for articles and equipment".

2. Paragraph 3.12.6 Connections.- Add the following: "Electrical continuity of wiring and other connections including ground connections shall conform to Drawing SC-DL-21271". (See 4.8.2)

3. Add new paragraphs following 3.12.7.1:

"3.12.8 Cable Assemblies.-

3.12.8.1 General.- Cable assemblies and harnesses shall meet the requirements of Drawing SC-DL-21271. (See 4.7)

3.12.8.2 Continuity.- Each conductor in the assemblies and harnesses shall be electrically continuous. (4.7.1)

3.12.8.3 Dielectric-strength and insulation resistance.- The assemblies and harnesses shall withstand, without breakdown, a d.c. potential of not less than 500 volts or an alternating current (a.c.) potential not less than 350 volts root mean square (RMS), and shall show an insulation resistance of not less 100 megohms, at or corrected to 15.6°C. If the value of insulation resistance is equal to or greater than 100 megohms when measured at a temperature greater than 15.6°C, no correction factor need be applied. (See 4.7.2.1)".

4. Section 4.- Insert the following as the first paragraph:

"Contractor responsibility.- Unless otherwise specified herein, the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acdeptance. Except as otherwise specified, the supplier may use his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order".

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T14:31Z
Check the source to verify that this is the current version before use.

5. Table III. Group A Inspection.- Delete in its entirety and substitute the following:

"Table III Group A Inspection

Inspection or test	Reqt. Par.	Insp. Par.	AQL Major	AQL Minor
Visual and Mechanical	3.17	4.5	--	--
Control unit			*1.00 dphu	*4.0 dphu
Temperature-humidity chamber			*1.0 dphu	*4.0 dphu
Cable assemblies			1.0 %	4.0 %
Carrying case			1.0 %	4.0 %
Electrical				
Control unit to chamber continuity	3.12.6	4.8.2)	1.0	--
Control unit operation	3.16.1.1	4.8.3)	dphu	--
Air circulation	3.16.1.2	4.8.1)		
Equilibrium	3.16.1.3	4.8.4)	1.0 %	--
Cable assembly	3.12.8.1	4.7		
Continuity	3.12.8.2	4.7.1)		
Dielectric strength) Insulation resistance)	3.12.8.3	4.7.2)	1.0 %	--

*Defects per hundred units."

6. Paragraph 4.4 Bounce preconditioning; Paragraph 4.9 Bounce test; and paragraph 4.11 Shock test, drop: Change the address of the L.A.B. Corporation from "Summit, New Jersey" to "Skaneateles, New York".

7. Add new paragraph following 4.8.3.4.4:

4.8.4 Chamber equilibrium.- Chamber equilibrium shall be checked for conformance to 3.16.1.3 as follows:

(a) Condition unit at existing ambient room conditions for a minimum of 2 hours after the performance tests of 4.8.1, 4.8.2, and 4.8.3.

(b) With chamber door closed and latched, and component psychrometer emplaced, operate power circuits and blower motor for a period of at least 15 minutes. During this operation take one temperature and humidity reading 10 minutes after starting blower, then observe the maximum deviations from these readings during the following 5 minutes. The maximum deviations shall not be greater than ±2% relative humidity and ±.05°C. If the unit fails to meet the above requirements, repeat the test, turning on the heater as necessary. The unit shall pass the test if specified stability is obtained in the specified time interval with or without use of the heater.

Source: https://assist.dla.mil 2 Downloaded: 2026-10-17T14:31Z
Check the source to verify that this is the current version before use.