INCH-POUND

A-A-55228

August 20, 1993

COMMERCIAL ITEM DESCRIPTION

SHOWER PAIL, COLLAPSIBLE, COTTON DUCK, 5-GALLON CAPACITY

The General Services Administration has authorized the use of this commercial item description in preference to MIL-S-43674.

Abstract. This commercial item description covers a 5-gallon capacity collapsible shower pail with metal or plastic showerhead construction. The shower pail is intended for use in tropical combat zones.

Description. The stitching used for the shower pail shall be Type 301. Ends of all stitching shall be backstitched or overstitched 1 inch minimum except when caught in other stitching or turned under in a hem. Thread tension shall be maintained so that there will be no loose bobbin, or top thread, or excessively tight stitching resulting in puckering of the materials sewn. The inter lock shall be embedded in the material sewn. The showerhead assembly shall be attached to the bottom of the pail as shown on Drawing 5-4-984 (see NOTES). The water shower valve shall turn "on" or "off" without binding. The pail with showerhead assembly

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Defense Personnel Support Center, Clothing and Textiles Directorate, Attn: DPSC-FSSD, 2800 South 20th Street,Philadelphia, PA 19101-8419, by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A

FSC 8465

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:45Z
Check the source to verify that this is the current version before use.

attached shall not leak more than 10 percent of its volume (11 oz) over a 1 1/2 hour period when subjected to the Leak Test. This Leak Test requirement applies to both the metal and plastic showerhead assembly. The flange nut shall be tightly secured to prevent rotation of the flange when rotating the showerhead. The bottom reinforcement webbing shall be stretched taut when stitching to bottom. Soldering (for metal showerhead assembly only) shall be adherent and the soldered joint shall be free from splatter or excess solder as specified in Drawing 5-4-986 (see NOTES). Welds (for metal showerhead only) shall be smooth and free from porosity, cracks, incomplete fusion, and deformation of material.

Materials and Components. Materials and components shall conform to the requirements specified herein and on applicable drawings.

Marking. The identification marking shall be applied in the location shown on Drawing 5-4-984. The letters "U.S." and the warning marking "NOT TO BE USED FOR THE STORAGE OF DRINKING WATER" shall be applied in the size characters and in the locations on the drawing.

Label/Tag. Each item shall be individually bar-coded with the type VIII, class 17 label/tag of DDD-L-20. This label/tag shall be located so that it is completely visible on each item and causes no damage to the item.

Workmanship. The finished shower pail shall conform to the quality of product established by this document. The occurrence of defects shall not exceed the contracter's own quality assurance standards and the quality assurance standards defined by the technical data in the bid package.

Product Demonstration Model. When required, offerers shall submit two (2) of their intended production. The product demonstration model will consist of units independently developed. These two product demonstration models (PDM) will be analyzed and evaluated by the government. Evaluation criteria and basis for award are contained in the solicitation. Product demonstration models will be retained by the government. One (1) product demonstration model approved by DPSC under the resultant contract will serve as a manufacturing standard for the corresponding production items delivered under this contract. Offerers are advised that the product demonstration model does not relieve the successful offerer of his responsibility to perform in accordance with the commercial item description specified above.

Regulatory Requirements. The offeror/contractor is encouraged to use recovered materials in accordance with Public Law 94-580 to the maximum extent practicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:45Z
Check the source to verify that this is the current version before use.

Responsibility for Inspection. The supplier is responsible for assuring the product conforms to the requirements. pail lots will be inspected to determine conformance with the Commercial Item Description and the successful offerer's technical proposal as negotiated. Acceptability of Pail lots will be determined by the use of "Sampling Procedures and Tables for Inspection by Attributes," ANSI Z1.4, published by the American Society for Quality Control. Sampling procedures will be designated by the Government at the time of award. The sample unit is one pail.

Quality Assurance

Certification. The contractor shall certify that the product offered meets the salient characteristics of this description and that the product conforms to the producer's own drawings, specifications, standards and quality assurance practices. The government reserves the right to require proof of such conformance prior to the first delivery and thereafter as may be otherwise provided for under the provisions of the contract. Reliance on contractor quality assurance systems shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the government for acceptance comply with all requirements of the contract.

Examination

Visual Examination. The shower pail shall be examined for the defects listed below. The lot size shall be expressed in units of shower pails. The sample unit is one shower pail.

Defects. The shower pail shall be examined for the following defects: any hole, cut, tear, or color not as specified; any spot or stain (outside); thread ends not removed; label missing, incorrect, or illegible; measurement of item not as specified; broken or missing yarns; multiple floats clearly visible at normal inspection distance (approximately 3 feet); edge frayed or scalloped; webbing not taut stitched to bottom; an open seam on stitch type 301 of more than 1 inch 1/; two or more rows of stitching omitted in boxstitching; wrong seam or stitch type; loose stitching resulting in loosely exposed top or bottom thread for more than 6 inches; stitching margin larger than specified by more than 1/4 inch; stitching margin less than specified; stitching ends secured with less than three tying, overlapping, or backstitches when automatic stitching is performed; any component broken or fractured, or required operation omitted; any component of showerhead broken or fractured, water valve does not turn "ON" or "OFF" without binding; metal showerhead not smooth or not free from burrs, sharp edges, cracks, porosity, or corroded area; plastic showerhead not smooth or not free from variable thickness or surface warpage; loosening of cemented parts on plastic showerhead or showerhead cracked, broken, or deformed; handle not constructed as specified on applicable drawing; handle not set to body of pail as specified on drawing;

Source: https://assist.dla.mil -- Downloaded: 202610-26T09:45Z
Check the source to verify that this is the current version before use.

bar-code omitted or not readable by scanner, Human-Readable Interpretation (HRI) omitted or illegible; bar-coded type not as specified, code density not as specified.

1/ A seam shall be classified as open when one or more stitches joining a seam are broken or when one or more skipped stitches or runoffs occur. On double stitched seams, a seam shall be classified as open when either one or both sides of a seam are open.

Dimensional Examination. The finished shower pail shall conform to the dimensions specified. Any dimension that is not within the established tolerance shall be classified as a defect. The sample unit shall be one shower pail.

Packaging Examination. The fully packaged shipping containers shall be examined in accordance with defects listed below. The lot size shall be the number of shipping containers in the inspection lot.

EXAMINE	DEFECT
Marking (exterior and interior)	Omitted; incorrect; illegible; of improper size, location, or method of application
Materials	Any component missing, damaged, or not as specified
Workmanship	Inadequate application of components, such as: incomplete closure of container flaps, loose strapping, improper taping, or inadequate stapling
Content	Number of items in container is more or less than required
	NSN shown on one or more items is not as specified on shipping container
Palletization	Length, width, or height exceeds specified maximum requirements
	Pallet type not as specified
	Load not bonded as specified

Source: https://assist.dla.mil -- Downloaded: 202610-26T09:45Z
Check the source to verify that this is the current version before use.

End Item Performance Testing

Leak Test. At 65°F ambient conditions, the shower pail shall be filled with water and suspended for four hours. The shower pail shall then be refilled, the showerhead turned to the "ON" position, and a check made for the starting of the water shower and leaks at the connection between the canvas pail and the showerhead. The showerhead shall then be turned to the "OFF" position, the pail refilled if needed, and checked again for leaks at the connection of the canvas pail and showerhead. For the plastic showerhead, the leak test shall be conducted after the cold soak test and the heat soak test.

Cold Soak Test. A dry, empty, shower pail with the plastic showerhead shall be cold soaked at -0°F temperature for 24 hours and in this cold soaked condition with the showerhead spray plate facing down and at a height of 42 inches, the pail shall be dropped in free fall on a concrete floor. The showerhead shall then be examined for fracture, breakage, contour deformation, and loosening of cemented parts.

Heat Soak Test. A shower pail with the plastic showerhead shall be heat soaked at 125°F temperature for 24 hours and in this heat soaked condition shall be dropped tested. The shower pail will then be examined for fractures, breakage, contour deformation and loosening of cemented parts.

Preservation, Packing, and Marking. The preservation, packing, and marking shall be as specified in the contract or order.

Notes

Source of Government Documents. Drawings are available from:

US Army Natick Research, Development and Engineering Center
ATTN: SATNC-UXT
Natick, MA 01760-5017

Copies of Military and Federal documents are available from:

Standardization Documents Order Desk
Bldg. 4D
700 Robbins Avenue
Philadelphia, PA 19111-5094

Source of Nongovernment Documents

ANSI/ASQC Z1.4 - Sampling Procedures and Tables for Inspection By Attributes

(Applications for copies should be addressed to American Nationals Standards Institute, 11 West 42nd Street, New York, NY 10036-8002.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:45Z
Check the source to verify that this is the current version before use.

Custodian:

Army - GL

Review Activity:

Army - MD

Civil Agency Coordinating Activity:
GSA - FSS

Preparing Activity
DLA - CT
Project No. 8465-0096

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:45Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	A-A-55228	August 20, 1993

3. DOCUMENT TITLE

Shower Pail, Collapsible, Cotton Duck, 5-Gallon Capacity

4. NATURE OF CHANGE *(Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)*

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code)	
Defense Personnel Support Center ATTN: DPSC-FSSD (12-3-D)	(1) Commercial (215) 737-8105	(2) AUTOVON 444-8105
c. ADDRESS (Include Zip Code) 2800 South 20th Street P. O. Box 8419 Philadelphia, Pennsylvania 19101-8419	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: Defense Quality and Standardization Office 5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466 Telephone (703) 756-2340 AUTOVON 289-2340	

DD Form 1426, OCT 89

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:45Z
Check the source to verify that this is the current version before use.