MILITARY SPECIFICATION

TELESCOPE, PANORAMIC: M1

This amendment forms a part of Military Specification MIL-T-12711A(MU), dated 11 December 1964, and is approved for use by all Departments and Agencies of the Department of Defense.

* Paragraph 3.3.1 and 3.5: Delete.

Paragraph 3.10: Delete "vertical within 40 minutes of arc" and substitute "vertical within 1 degree of arc".

Paragraph 3.11: Delete "within 20 minutes at any azimuth setting" and substitute "within 40 minutes at any azimuth setting".

* Paragraph 3.16 and 3.17: Change "1.0 Mil" to "1.5 Mils".

Paragraph 3.21: Delete "shall be 10 seconds of arc" and substitute "shall be 25 seconds of arc".

Delete paragraphs 4.1 through 4.4.2.3 and substitute:

"4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 General provisions.- The component and subassembly inspection requirements of MIL-F-13926 form a part of the Quality Assurance Provisions of this specification. Definitions of inspection terms shall be as listed in MIL-STD-109.

4.2 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three panoramic telescopes and three each of every component and subassembly covered by SQAP. The sample shall be manufactured in the same manner, using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:12Z
Check the source to verify that this is the currentversion before use.

and packing, shall be obtained from the same source of supply as used in regular production.

4.2.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.2.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection.

4.3 Inspection provisions.

4.3.1 Submission of product.- Unless otherwise specified by the contracting officer, inspection lot size, lot formation and presentation of lots shall be in accordance with "Submission of Product" provisions of MIL-STD-105.

4.3.2 Examination and tests.- Components and subassemblies shall be inspected in accordance with the inspection provisions contained in MIL-F-13926, and the Supplementary Quality Assurance Provisions (SQAP) listed in the List of Inspection Documents (LID) when provided with the technical data package (TDP). Examinations and tests related to Section 3 herein shall be performed on a single defect (individual characteristic) basis in accordance with MIL-STD-105, and the sampling plans specified in Tables I and II. Examinations and tests for Packaging, Packing and Marking shall be in accordance with MIL-P-14232 and Section 5 herein. The tabulated classification of defects in Table I shall constitute the minimum inspection to be performed by the supplier prior to Government acceptance or rejection by lot.

TABLE I - CLASSIFICATION OF DEFECTS

Use Inspection Level II of Table I with
Sampling Plan Table II-A of MIL-STD-105

CRITICAL: NONE	REQUIREMENT	TEST PROCEDURES
MAJOR: AQL 1.0 Defective		
101. Post vibration	3.3.3	4.5.3
102. Cleanliness	3.4	4.5.4
103. Elevation	3.7	4.5.7
104. Azimuth	3.8	4.5.8
105. Open sight	3.9	4.5.9
106. Image tilt	3.10	4.5.10

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T23:12Z
Check the source to verify that this is the current version before use.

		REQUIREMENT	TEST PROCEDURES
107.	Parallelism of image and reticle	3.11	4.5.11
108.	Elevation travel	3.12	4.5.12
109.	Plumb travel	3.13	4.5.13
110.	Backlash elevation & azimuth	3.14	4.5.14 & 4.5.15
111.	Vertical displacement	3.15	4.5.16
112.	Level travel	3.16	4.5.17
113.	Azimuth error	3.17	4.5.18
114.	Elevation scale	3.18.1	4.5.19
115.	Azimuth scale	3.18.2	4.5.20
116.	Eyepiece focus	3.19	4.5.21
117.	Parallax	3.20	4.5.22
118.	Resolution	3.21	4.5.23
119.	Eyepiece rotation	3.22	4.5.24
120.	Knob operability	3.23.1	4.5.25
121.	Rapid traverse	3.23.2	4.5.26

MINOR: NONE

4.3.3 Acceptance and rejection.- Rejected lots shall be screened for all defective characteristics. Removal or correction of defective units and resubmittance of rejected lots shall be in accordance with "Acceptance and Rejection" as specified in MIL-STD-105.

4.3.4 Certification.- Certification shall include test data and results from all material specified below. Certification shall be required prior to performing final acceptance and shall suffice for the remainder of the contract provided the manufacturing processes and techniques used to produce the items for which certification was issued have not been revised or changed. Any alteration in processes, techniques or materials that indicate an adverse change in performance capabilities or reliability as determined by the Contracting Officer shall require a new certification.

201.	Fabrication	3.1
202.	General Specification	3.2

4.4 Environmental.- Three (3) telescopes shall be selected at random from each 50 produced or from each month's production, whichever occurs first, for the following tests specified in Table II.

TABLE II

	CONTROL TEST	REQUIREMENT	TEST PROCEDURE
* 301.	Operating temperature	3.3.2	4.5.1
302.	Operability	3.23	4.5.25 & 4.5.26

4.4.1 Failure of sample.- Should any one item of a special sampling

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:12Z
Check the source to verify that this is the current version before use.

fail to meet the specified test requirements, acceptance of the product will be suspended by the Government until necessary corrections have been made by the contractor and the resubmitted samples have been approved (see 4.3.3).

4.4.2 Inspection equipment.- Except as otherwise provided for by the contract, the contractor shall supply and maintain inspection equipment in accordance with the applicable requirements of MIL-I-45607.

4.4.3 Government furnished inspection equipment.- Where the contract provides for Government furnished test equipment, supply and maintenance of test equipment shall be in accordance with the applicable requirements specified in MIL-I-45607.

4.4.4 Contractor furnished inspection equipment.

4.4.4.1 Government design.- Unless otherwise specified in the contract, all inspection equipment specified by drawing number in specification or SQAP forming a part of the contract shall be supplied by the contractor in accordance with technical data listed in the List of Inspection Documents (LID), when provided with the Technical Data Package (TDP).

4.4.4.2 Contractor design.- The contractor shall provide inspection equipment compatible with the "Test Methods and Procedures" specified in 4.6 and with the "Component Inspection" and "Test Facilities" requirements of MIL-F-13926. Since tolerance of test equipment is normally considered to be within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials, dimensions and tolerances used in the design of test equipment shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit, and permit positive rejection when non-conforming. Construction shall be such as to facilitate routine calibration of test equipment.

* Paragraph 4.5.1 and 4.5.5: Delete.

*The margin of this specification is marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1240-A586

Source: https://assist.dla.mil -- Downloaded: 202610-17T23:12Z
Check the source to verify that this is the current version before use.