MIL-B-3630D
20 January 1983
SUPERSEDING
MIL-B-3630C
9 May 1977

MILITARY SPECIFICATION

BATCHING PLANT, AGGREGATE, MOBILE, THREE-COMPARTMENT, 60-TON CAPACITY

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a mobile, three-compartment, aggregate batching plant, hereinafter called plant, of 60-ton, (44 cubic yard (cu yd)) minimum capacity.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

L-P-378 - Plastic Sheet and Strip, Thin Gauge, Polyolefin.
TT-P-664 - Primer Coating, Synthetic, Rust-Inhibiting, Lacquer Resisting.
PPP-B-601 - Boxes, Wood, Cleated-Plywood.
PPP-B-621 - Boxes, Wood, Nailed and Lock-Corner.
PPP-T-60 - Tape, Packaging, Waterproof.
PPP-P-40 - Packaging and Packing of Hand Tools.

MILITARY

MIL-C-104 - Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted.
MIL-P-116 - Preservation, Methods of.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3895

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

MIL-B-121 - Barrier material, Greaseproofed, Waterproofed, Flexible.
MIL-P-130 - Paper, Wrapping, Laminated and Creped.
MIL-C-3600 - Compressors, Rotary, Power-Driven; and Compressors, Reciprocating, Power-Driven: Air and Gas (Except Oxygen and Refrigerant), Packaging of.
MIL-C-3774 - Crate, Wood, Open, 12,000 and 16,000 Pound Capacity.
MIL-C-16298 - Electric Machines Having Rotating Parts and Associated Repair Parts, Packaging of.
MIL-T-22085 - Tape, Adhesive, Preservation and Sealing.
MIL-B-22191 - Barrier Material, Transparent, Flexible, Heat Sealable.
MIL-P-46093 - Primer Coating, Synthetic (For Brake Drums).

STANDARDS

MILITARY

MIL-STD-129 - Marking for Shipment and Storage.
MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified (see 6.2), the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation, form a part of this specification to the extent specified herein.

NATIONAL BUREAU OF STANDARDS (NBS)

H44 - Specifications, Tolerances and Regulations for Commercial Weighing and Measuring Devices.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated the issue in effect date of invitation for bids or request for proposal shall apply.

CONCRETE PLANT MANUFACTURERS BUREAU (CPMB)

Concrete Plant Standards.

(Application for copies should be addressed to the Concrete Plant Manufacturers Bureau, 900 Spring Street, Silver Springs, MD 20910.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

A242 - High Strength Low Alloy Structural Steel.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

Technical society and technical association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal Agencies.

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 Description. The plant shall consist of a three-compartment wheel mounted compartmented unit for dispensing concrete aggregates, overhead storage bin with gates, a weighing hopper, weighing scales, supports and all parts and components necessary for operation of the plant. The batcher shall be capable of holding a batch of concrete aggregate sufficient for a 5 cu yd batch. Structural framework shall be provided for supporting an operating platform. The overhead, open-end, storage bin shall be suitable for loading concrete aggregates by cranes with clamshell buckets, conveyors, or elevators. Except for the operating accessories, the plant shall be constructed of steel. The plant shall be designed for quick assembly and disassembly, the plant shall be equipped with retractable or removable pneumatic-tired wheels and with suitable means for towing. All hardware necessary for erection shall be furnished. The plant shall comply with the current standards of the CPMB.

3.2 First article. When specified (see 6.2), the contractor shall furnish a plant for first article inspection and approval (see 4.2.1, 4.4, and 6.4).

3.3 Transportability. The plant shall be capable of being towed at 10 miles per hour when empty.

3.4 Standard commercial product. The plant shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the plant being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.

3.5 Materials. Materials shall be as specified herein. Materials not definitely specified shall be the best quality used for the purpose in commercial practice. Material shall be free from all defects and imperfections that might affect the serviceability of the finished product. All portions of hoppers, chutes, plates, and metal surfaces subject to abrasive wear caused by aggregate movement shall be constructed of abrasive-resistant steel plates conforming to ASTM A242, or better. All bolt heads subjected to the flow of material shall not extend beyond surfaces exposed to the material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

3.5.1 Construction. Where no specific construction requirements are specified herein, the manufacturer's best commercial practice shall apply. All parts, components, and attachments shall be identical for each plant furnished under any specific contract. No deviations will be accepted without prior written approval of the contracting officer.

3.6 Ease of maintenance. Design of the plant shall permit ready accessibility to all parts of maintenance end repair by the use of conventional general-purpose handtools. Replacement and adjustment of component parts and accessories shall be accomplished with minimum drainage requirements and disturbance to other elements on the plant. Ease of maintenance provisions shall incorporate features insuring clearances between adjacent components to facilitate maintenance and servicing operation.

3.7 Identical items. All plants furnished under any specific contract shall be physically and mechanically identical. This requirement includes parts, assemblies, components, and accessories. No deviations will be acceptable without written approval of the contracting officer.

3.8 Safety. All rotating or reciprocating parts and all parts subject to high operational temperatures, that are of such nature or are so located as to be or become a hazard to operating or attending personnel shall be adequately guarded or insulated to the extent necessary to eliminate the hazard.

3.9 Storage bin. The storage bin shall have a total heaped capacity of not less than 60 tons based aggregates weighing 100 pounds per cubic foot. The storage bin shall be divided into three compartments, approximately equal volume, by means of steel bulkheads projecting to a height of approximately 2 feet 6 inches above the rim level of the bin. The bin shall be designed for aggregates having an angle of repose of 40° with the horizontal. The slope of the sides of the bin hopper shall be not less than 45° with the horizontal. The interior surfaces of the bin shall be free from obstruction, and all joints and connections shall be finished so as to allow free movement of aggregates. The bin wall and sloping bottom shall be fabricated of sheet steel not less than 3/16 inches in thickness.

3.10 Bin gates. Bin gates shall be provided for the bottom of the compartment openings. The bin gates shall be of the single-clam or double-clam type air operated, durable, and shall be accurate on cutting off the flow of material. Clear openings of bin gates shall be not less than 180 square inches.

3.11 Weighing hopper. The weighing hopper shall be located under the storage bin, shall have a capacity for weighing aggregates for a 5 cu yd batch, and shall be of all welded construction with steep slopes to insure clean and rapid discharge of the aggregate. The discharge gate shall be of the single-clam or double-clam type with air control. The batcher shall be equipped with a discharge opening so that material may be discharged into both truck-mounted mixers and batching trucks. Openings shall be provided in the hopper for the removal of overweight.

3.12 Weighing scales. The weighing scales shall conform to the applicable requirements of the section on scales in NBS H44 and as specified herein. Scales shall be of the lever balance, dial type. The aggregate scale shall be of the accumulative three material type capable of automatically weighing

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

preset amounts of the three materials. Scales shall be equipped with zero interlocks to prevent charging of a new batch, or the next material of the batch, or discharging of the batch until the preset weights are reached.

3.13 Supports. Four structural steel supports shall be provided to support the fully loaded storage bins, weighing hopper, weighing scales and the operator's platform. The supports shall be of such length as to provide a minimum clearance of 11 feet from the lowest point on the batcher to the base of the columns. Each column shall be equipped with a base plate having approximately 1 square foot of bearing area with not less than two holes that will accommodate bolts of at least 1 inch in diameter. Lateral clearance for trucks shall not be less than 11 feet at the base of the columns. Two complete sets of erection drawings shall be furnished with each plant. All parts of the equipment shall bear a piece mark corresponding to the piece mark on the erection drawing.

3.14 Operator's platform. Each plant shall be provided with a demountable steel platform with steel sills and a guard rail. The platform shall be constructed of checkered floor plate or expanded metal. Sections of the platform shall be numbered and abutting edges shall be matchmarked. A steel ladder, not less than 15 inches wide with rungs having not more than 15-inch spacing, shall be provided for access from the ground to the operator's platform and bin. A steel safety cage shall be provided for the ladder.

3.15 Air system. A complete air system with electric motor driven air compressor shall be provided for operation of the bin gates.

3.16 Lubrication. Lubrication means shall be provided for all parts of the equipment normally requiring lubrication. Where the use of high lubrication pressure will damage grease seals or other parts, fittings with pressure release shall be used.

3.17 Lifting and tying down attachments. When specified (see 6.2), the plant shall be equipped with lifting and tying down attachments. Lifting and tying down attachments shall conform to MIL-STD-209, type III. Tying down attachments shall be identified by stenciling or other suitable marking on the plant. Tying down marking shall clearly indicate that the attachments are intended for tying down of the plant on the carrier when shipped.

3.18 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants, such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion products, or any other interfering substances. As soon as practicable, after cleaning and before any corrosion product or other coating interfering material can result, the surface shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. The color of the finish coat shall be as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

3.19 Stenciling. The gross weight of each unit of equipment shall be stenciled on each side of the unit in such manner as to be discernible.

3.20 Data plates.

3.20.1 Instruction plates. The component units which require operational instructions shall be equipped with instruction plates, including warnings and cautions suitably located and permanently affixed, describing any special or important procedure to be followed in operating and servicing the machine, including complete lubricating instructions. All controls shall be identified indicating the direction of motion and the operation to be performed. This may be accomplished by the use of one or more plates. Plates shall be manufactured of noncorrosive durable material, and shall be permanently secured on the plant.

3.20.2 Nameplate. A nameplate will be furnished by the contracting officer for each component unit. The contractor shall stamp all necessary data in the blank spaces provided for that purpose, and securely affix it to each unit in a conspicuous place with brass screws or bolts not less than 1/8 inch in diameter. The applicable nomenclature contained in contract item description shall be placed in the top blank.

3.21 Workmanship.

3.21.1 Steel fabrication. Steel used in the fabrication of equipment shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and chipping shall be done neatly and accurately. All bends of a major character shall be made with controlled means in order to insure uniformity of size and shape.

3.21.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.21.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member

3.21.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Spot, tack, or intermittent welds for strength will not be permitted. Weld penetration shall be such as to provide transference of maximum design stress through the base metal juncture. Fillet welds shall be provided when necessary to reduce stress concentration.

3.21.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Material inspection. The contractor is responsible for insuring that supplies and materials are inspected for compliance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one item when a first article is required (see 3.2 and 6.2). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.4, and the packaging inspection of 4.5.

4.3 Examination. Each plant shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. The first article shall be subjected to the tests specified in 4.4.1 through 4.4.3 and, if applicable, to the test specified in 4.4.4. Failure to pass any phase of the required tests shall be cause for the Government to refuse acceptance of all plants until corrective action has been taken.

4.4.1 Erection. The plant shall be completely assembled and errected using the hardware provided. The drawing furnished (see 3.13), shall be used as a guide during erection. Failure to assemble the plant with the hardware provided, failure of the erected plant to meet the clearances specified in 3.13, incorrect matchmarking of parts, and incompatibility between part numbers and drawing numbers shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

4.4.2 Capacity. After erection, the bins shall be filled to capacity with aggregate. The aggregate shall be emptied through the scales and weighed. Inability to obtain the capacities specified in 3.1 and 3.9 or failure of the steel supports to support the loaded bins shall constitute failure of this test.

4.4.3 Disassembly. After completion of the capacity test, the plant shall be disassembled. Failure to meet the requirements of 3.1 and 3.3 shall constitute failure of this test.

4.4.4 Lifting attachments. The static load as specified in 3.18 shall be applied to the attachment when it is mounted on its structural member. Weld failure or permanent deformation of the attachment or the structural member shall constitute failure of this test.

4.5 Packaging inspection. The preservation, packing, and marking of the item shall be inspected to verify conformance to the requirements of section 5.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A.

5.1.1.1 Methods of preservation. Cleaning processes, drying procedures, preservatives, and methods of preservation are listed in MIL-P-116 and shall conform to the requirements of MIL-P-116 and any applicable specifications.

5.1.1.2 Disassembly. Disassembly shall be the minimum necessary to protect parts subject to damage or loss, and to accomplish reduction in cube. Removed bolts, nuts, pins, screws and washers shall be reinstalled in mating parts and secured to prevent their loss.

5.1.1.3 Matchmarking. Parts removed and mating parts on the equipment and attachments shall be matchmarked to facilitate reassembly. Parts and accessories removed, and mating parts on the equipment, shall be identified with weatherproof tags attached to mating parts and locations. Markings shall be applied to the tags with a waterproof material.

5.1.1.4 Cleaning and drying. Prior to the application of preservative compounds or paint, surfaces shall be cleaned by process C-1 and dried by any applicable procedure of MIL-P-116.

5.1.1.5 Unprotected surfaces. Unprotected exterior metal surfaces requiring the application of a contact preservative in accordance with MIL-P-116 and not specifically provided for herein shall be preserved as follows:

5.1.1.5.1 Unfinished (not machined) surfaces. Unfinished exterior metal surfaces shall be coated with type P-1 preservative.

5.1.1.5.2 Machined surfaces. Exposed machined surfaces shall be coated with type P-6 or P-11 preservative and wrapped or covered, as applicable, with barrier material conforming to MIL-B-121, type I, grade A, class 2 or MIL-B-22191, type II. The material shall be secured in place with waterproof tape.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

5.1.1.6 Drive belts and pulleys. Drive belts shall be removed or released from tension. Removed belts shall be preserved method IC-1 or IC-3. Unpainted surfaces shall be coated with primer conforming to TT-P-664 or MIL-P-46093. A weatherproof tag shall be attached in a conspicuous location indicating: "Belts have been (removed or released from tension.) (Install or tension) prior to operation." Markings shall be applied to the tags with a waterproof material.

5.1.1.7 Compressor. The compressor shall be preserved in accordance with the level A requirements of MIL-C-3600.

5.1.1.8 Electrical motors. Preserve level A by the alternate method of MIL-E-16298.

5.1.1.9 Electrical modules. Circuitry modules, printed circuit boards, and panel boards that are not hermetically sealed should be removed, if possible, and packaged method II. If the complexity of the circuitry will not allow removal, seal area with a waterproof barrier conforming to L-P-378 or MIL-B-22191, type III, or tape conforming to MIL-T-22085.

5.1.1.10 Rubber tires. Tires mounted on the wheels (road tires) of the equipment shall be inflated to 10 pounds above pressure value recommended for maximum load.

5.1.1.11 Wheels, axles, and bearings. When wheels and hubs are removed from axles, the interior bearing surfaces of the hubs and the exterior surfaces of the axles shall be coated with P-6 preservative. The coated surfaces of the axles shall be wrapped and hub openings shall be covered with barrier material conforming to MIL-B-121, type I, grade A, class 2. The barrier shall be secured in place with tape conforming to PPP-T-60, type IV. Bearing removed from wheels shall be coated with P-6 preservative and preserved method I-A.

5.1.1.12 Weighing scales.

5.1.1.12.1 Torque lever assembly U-bolts and hook bolts. The U-bolts and hook bolts shall be wrapped in sets with paper conforming to MIL-P-130, type II, secured with waterproof tape conforming to PPP-T-60, type IV.

5.1.1.12.2 Scale beam box. The interior surfaces of the scale beam box, including all moving parts, shall be coated with type P-7 or type P-10, grade 2 preservative. Where practicable, the assemblies within the scale beam box shall be wrapped or covered with barrier material conforming to MIL-B-121, type I, grade A, class 2; secure in place with waterproof tape. The poises, weights, weighing beams, and the dash pot shall be cushioned and securely blocked in place to prevent movement.

5.1.1.12.3 Dial indicator. The interior surfaces of the dial including all moving parts shall be coated with type P-7 or P-10, grade 2 preservative. The fulcrum arm shall be secured to prevent movement. The dial glass shall be protected from breakage with a fitted piece of suitable material (e.g., hard-board, plywood, fiberboard, styrofoam, etc.), tape conforming to PPP-T-60, type IV, the dial indicator shall be wrapped with barrier material conforming to MIL-B-121, type II, grade A, class 2, secured with waterproof tape.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

5.1.1.12.4. Dial indicator connecting rod. The dial indicator connecting rod shall be wrapped with barrier material conforming to MIL-B-121, type II, grade A, class 2, and the wrap secured with waterproof tape. The package shall be placed in the scale beam box and cushioned and blocked to prevent movement.

5.1.1.12.5. Closure. The cover of the scale beam box shall be secured in place and the cover joint sealed with waterproof tape conforming to PPP-T-60, type IV.

5.1.1.13. Bolts, nuts, and washers. Bolts, nuts, washers, and other fasteners shall be preserved method III.

5.1.1.14 Maintenance tools. Maintenance tools shall be preserved in accordance with level A preservation and packaging requirements of PPP-P-40.

5.1.1.15 Technical publications. Technical publications for each piece of equipment shall be preserved method IC-1 or IC-3.

5.1.1.16. Consolidation. Only components of one batch plant shall be consolidated together. Tool boxes shall be utilized for the consolidation of loose components, tools, and publications. The remainder of the components that will not fit in tool boxes shall be consolidated, along with dissembled components, in boxes conforming to PPP-B-601, overseas type or PPP-B-621, class 2. Contents shall be cushioned, blocked, and braced to prevent movement within the container. Boxes shall be secured to the equipment with appropriate strapping. Arrangement and location on the equipment shall be such so as not to increase cubage or interfere with lifting or mobility of the equipment.

5.1.2 Commercial. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent deterioration and damage.

5.2 Packing. Packing shall be level A or commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Plant (except storage bin). The weighing hopper, disassembled components, structural members of the supporting frame, extension panels, wheels and axles, and tow bar shall be packed in crates conforming to MIL-C-3774, type II, style a. The contents shall be anchored, blocked, and braced in accordance with the crate specification.

5.2.1.2 Storage bin. The storage bin with the extension panels removed shall be placed and secured on a crate base conforming to MIL-C-104, style a. Blocks, bracing, and anchoring shall be in accordance with the crate specification.

5.2.2 Commercial. The equipment shall be prepared for shipment in a manner which will insure arrival at destination in a satisfactory condition. Preparation for delivery shall comply with applicable carrier rules and regulations.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The plant is intended to be used to hold and dispense measured amount of concrete aggregate by weight.

6.2 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.
b. When first article is required for inspection and approval (see 3.2, 4.2.1 and 6.4).
c. When lifting and tying down attachments are required (see 3.17).
d. Color of finish coat to be specified (see 3.18).
e. Level of preservation-packaging and level of packing required (see 5.1 and 5.2).

6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL) and invokes the provisions of paragraph 7-104.9(n) of the Defense Acquisition Regulations (DAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL (DD Form 1423) incorporated into the contract. When the provisions of DAR 7-104.9(n) are not invoked, the data shall be delivered in accordance with the contract requirements.

6.4 First article. When a first article inspection is required, the item will be tested and should be a first production item consisting of the complete plant, or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.5 Title change. The title of this specification was changed to: Batching Plant, Aggregate, Mobile, Three-Compartment, 60 Ton Capacity.

6.6 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodians:

Navy - YD
Air Force - 99

Review activities:

Army - ME
Air Force - 84

User activity:

Army - CE

Preparing activity:

Navy - YD

Project No. 3895-0263

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.
NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. 3895-0263

DOCUMENT IDENTIFIER *(Number)* AND TITLE
MIL-B-3630D - BATCHING PLANT, AGGREGATE MOBILE, THREE-COMPARTMENT, 60-TON CAPACITY

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1426 1 OCT 76

Replaces edition of 1 Jan 72 which may be used.

S/N 0102-LF-001-4260

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T20:33Z
Check the source to verify that this is the current version before use.