MIL-T-60506A(MU)
AMENDMENT 5
15 September 1972
SUPERSEDING
AMENDMENT 4
28 April 1972

MILITARY SPECIFICATION
TELESCOPE ASSEMBLY: 10540506

This amendment forms a part of Military Specification MIL-T-60506A(MU) dated 18 June 1970.

Page 3, paragraph 3.4.6 Sealing.- Delete and substitute the following: "The optical cavities of the transmitter and sighting telescopes shall be flushed with dry nitrogen until the gaseous mixture bled from each cavity has a dew point at least as low as -25°F. The gray colored port shall be used as an entrance while the yellow colored port is the escape during flushing with dry nitrogen. The interior of each cavity shall be capable of maintaining 5 pounds per square inch gage (psig) for a period of 2 hours ± 10 minutes at a temperature of 75° ± 2°F. At the end of the 2 hour period, the leakage shall not have exceeded 0.2 psig. The pressure within each cavity shall then be returned to normal atmospheric pressure and the cavity sealed. The interior atmosphere of each optical cavity of the accepted telescope assembly shall be nitrogen (see 3.4)."

* Page 3, paragraph 3.5.1: Continuity.- Delete the period at the end of the paragraph and add "With the exception of: Wires #2, 2S, 3 and 3S. These wires, which are in the pre-amp cavity shall be checked just prior to sealing the pre-amp cover onto the housing."

* Page 3, paragraph 3.5.3: Insulation resistance.- Add "However, Wires #1, 2, 2S, 3 and 3S which are in the start pre-amp assembly shall be tested just prior to the sealing of pre-amp cover."

Page 9, paragraph 4.4.2: Change 70' to 70°.

* Page 13, paragraph 4.6.1.3: Shock.- In the third line, delete "In Procedure II" and substitute "In Procedure I."

Page 13, paragraph 4.6.2: Sealing.- Delete fifth and sixth sentences and respectively substitute the following:

"Subsequent to reaching the pressure specified, the source of pressure to the cavity shall be shut off. At the conclusion of the specified time period, the leakage shall not have exceeded the requirements of 3.4.6 as indicated on the pressure gage of the testing equipment."

FSC 1240

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:39Z
Check the source to verify that this is the current version before use.

* Page 13, paragraph 4.6.3.1: Electrical continuity.- Add "Wires #2, 2S, 3 and 3S will be tested just prior to sealing of pre-amp cover."

Page 14, paragraph 4.6.6: Add the following:

"An opthalmic or equivalent type lens may be used with the telescope system to compensate for differences in testing distances."

* The margin of this specification is marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous issue were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous issue."

Custodian:

Army - MU

Preparing activity:

Activity - MU

Project No. 1240 - A389

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:39Z
Check the source to verify that this is the current version before use.