MIL-C-0043584C(GL)
7 October 1985
USED IN LIEU OF
MIL-C-43584B
23 September 1974

MILITARY SPECIFICATION

COUNTER, CHECKOUT, CONVEYOR

This military specification has been prepared by the U.S. Army Research and Development Center (GL), Natick, MA 01760-5014 based upon currently available technical information but it has not been approved for promulgation as a coordinated revision of MIL-C-43584B. It is subject to modification. However, pending its promulgation as a coordinated military specification, it may be used in acquisition.

1. SCOPE

1.1 Scope. This document covers electric motor driven, dual conveyor belt, checkout counters complete with accessories.

1.2 Classification. The counter shall be of the following types, classes, and sizes specified (see 6.2).

Type I - Counter with electronic optical scanner
Type II - Counter without electronic optical scanner
Class A - Right hand take away
Class B - Left hand take away

Size 1 - 130 to 139 inches (overall length)
Size 2 - 140 to 149 inches (overall length)
Size 3 - 150 to 159 inches (overall length)
Size 4 - 160 to 172 inches (overall length)

2. APPLICABLE DOCUMENTS

2.1 Government documents. Unless otherwise specified, the following documents of the issue on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

Beneficial comments (recommendations, additions, deletions) and any pertenent data which may be of use in improving this document should be addressed to: U.S. Army Natick Research and Development Center, Natick, MA 01760-5014 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document by letter.

FSC 7195

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

CC-M-1807 - Motors, Alternating Current, Fractional and Integral Horsepower (500 MP and Smaller)

MILITARY

MIL-C-104 - Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129 - Marking for Shipment and Storage
MIL-STD-130 - Identification Marking of U.S. Military Property

FEDERAL

FED-STD-595 - Colors

(Copies of documents required by contractors in connection with specific acquisition functions should be obtained from the procuring activity or as directed by the contracting activity.)

2.2 Other publications. Unless otherwise specified, the following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this document to the extent specified herein.

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

No. 70 - National Electrical Code

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02196.)

UNDERWRITERS LABORATORIES, INC.

Electrical Appliance and Utilization Equipment List

(Application for copies of UL publications should be addressed to the Underwriters' Laboratories, Inc., 333 Pfingsten Road, Northbrook, IL 60062.)

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the currentversion before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D3951 - Standard Practice for Commercial Packing

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race St., Philadelphia, PA 19103.)

(Technical society and technical association documents are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document shall take precedence.

3. REQUIREMENTS

3.1 First article. When specified a sample shall be subjected to first article inspection. (see 4.3, 6.2 and 6.3).

3.2 Codes and standards. The electrical components of the counters shall conform to the Underwriters Laboratories Standards (UL), as applicable and all wiring of the counter shall be in accordance with the applicable requirements of NFPA No. 70.

3.2.1 Compliance. Prior to the approval of the first article, or if none is submitted, prior to the approval of the first shipment, the contractor shall submit satisfactory evidence to the contracting officer or his authorized representative satisfactory evidence that the electrical components, and the installation thereof, conform to the applicable requirements of UL and NFPA No. 70.

3.2.1.1 UL. Acceptable evidence of meeting the applicable requirements of UL shall be the UL listing mark, or a certified test report from a recognized independent testing laboratory, acceptable to the Government indicating that the counter electrical components have been tested and conform to applicable UL requirements.

3.2.1.2 NFPA. Acceptable evidence of meeting requirements of NFPA standard shall be the manufacturer's certified statement that the counter electrical components conforms to the applicable requirements of NFPA No. 70.

3.3 Materials and components. Materials and components shall be as specified herein. Materials and components not definitely specified shall be of the quality normally used by the manufacturer provided the completed item complies with all provisions of this document.

3.4 Design and construction. The checkout counters shall be designed and constructed for electronic optical scanner operations. The checkout counter

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

scanning kit shall be compatible with NCR, IBM, Spectra Physics, Sweda, Data Checker or Data Terminal. The checkout counters shall have scanner conversion kits available. The checkout counters shall be of modular construction with conveyor type belts, one front transport belt and one rear take away belt. The front transport belt unit, the rear take away belt unit, and the cash register stand shall be separate modules. Timing of the front transport belt shall be synchronized with the ability of the particular scanning unit (see 3.4.6). The counters shall include a stainless steel take away slide to fit between the front and rear belts. The height between the two belts shall provide a sufficient slope for the cashier to slide the items checked onto the rear belt. The rear belt shall move the items, from the cashier, to be accumulated in the bagging area. The front belt shall be operated by a three position electric eye, foot control and toggle switch. The rear belt shall be operated by a separated switch. The base and frame shall be steel and finished as specified in 3.6. The top deck, (excluding belts), shall be made of corrosion resistant steel, reinforced and with at least a 2B finish. When specified (see 6.2), the bagging area shall have a one piece plastic (or similar material) top. The plastic surface shall not show any scratches that catches a fingernail, any cracks or dents deeper than 1/16 of an inch and any deflection more than 1/4 of an inch when tested as specified in 4.5.2. The counters shall enclose all working parts, including paper bag storage at bagging area, and shall have an enclosed base at the floor. Top and edge molding shall be corrosion-resisting steel or anodized aluminum. Cart guards shall be provided along the customer side of the counter and cart guards shall be provided on the cash register stand and also the front or loading end finish shall be protected from cart damage. Bagging shelves shall be centered on the baggers end of the checkout counter and bagging shelves and other pull out shelves shall be rounded or edge molded to prevent injury. When tested as specified in 4.5.1, the completely assembled conveyer shall show that the assembly of components have:

a. Complete and proper relationship of moving parts.
b. Motor bearings operating with no evidence of overheating.
c. Starting and stopping devices operating smoothly and positively.
d. No structural failures.
e. No undue vibration or noise.

The type I counter shall be:

a. With a kit to receive an electronic optical scanner.
b. A left or right hand power take away system, as specified.

The type II counter shall be:

a. Without an electronic optical scanner.
b. Capable of operating in the convention non-scanning mode and a stainless steel scanner housing cover is to be provided for such operation.
c. A left or right hand power take away system, as specified.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

3.4.1 Overall dimensions.

3.4.1.1 Height overall. The overall height of the counters at the customers loading end shall be 33 to 36 inches.

3.4.1.2 Width overall. The overall width of the counter including protective or guard molding shall not exceed 49 inches for the type I and shall not exceed 48 inches for the type II. The width of the customer loading end shall be the width of the belt (see 3.4.3) plus no more than 5 inches.

3.4.1.3 Length. The overall length of the counter shall be as follows:

Size 1 - 130 to 139 inches
Size 2 - 140 to 149 inches
Size 3 - 150 to 159 inches
Size 4 - 160 to 172 inches

3.4.2 Bagging accumulation area. The checkout counter bagging accumulation area shall have a minimum of 14 square feet accumulation area, (exclusive of the rear belt), to accommodate two baggers at the rear of the counter. That portion of the take away belt within the accumulation area intercepted by a plane parallel with the baggers end, measuring approximately 49 inches across, forming a rectangle, may be counted as accumulation area. The bagging area shall be equipped with pullout bagging shelf/shelves of sufficient size to hold a minimum of two bags a simultaneously and shall have bag storage bins or dividers to accommodate a minimum of three separate bag sizes. The bagging shelves shall be centered midway between the two sides.

3.4.3 Belts. The belts shall be double ply neoprene or triple nylon cord. The front transport belt shall be 22 to 24 inches wide. The minimum length of the exposed surface of the front transport belt shall be as follows:

Size 1 - 48 inches
Size 2 - 55 inches
Size 3 - 60 inches
Size 4 - 72 inches

The rear take away belt shall be 14 to 16 inches wide with a minimum exposed length of 34 inches.

3.4.4 Register stand, type I. The type I register stand shall be of sufficient size to accommodate the cash register or terminal, scale platform riser, customer receipt printer, journal printer/slip provided, scales, and auxiliary cash drawer with lock and three keys. A duplex electrical outlet receptable shall be provided in an accessible location for use with the cash register and other equipment. The register stand shall be equipped with a rear door for accessibility and also have protection from cart damage. A trapezoid shape flat platform, 23 to 24 x 25 to 34 x 5 to 6 inches high shall be provided on top of register stand to receive checkstand scales with

Source: https://assist.dla.mil -- Downloaded: 202640-21T21:46Z
Check the source to verify that this is the currenversion before use.

provisions for storing cash drawer below platform top. This flat scale platform shall be perpendicular to the cash register guard and parallel to the top of the checkout stand and will also accommodate keyboard, slip printer, journal/printer supplied by others.

3.4.4.1 Register stand, type II. The register stand for type II shall be equipped with a drawer, lock, and three keys. The stand shall be of sufficient size to accommodate a cash register. A duplex electrical outlet shall be provided in an accessible location for use with the cash register and other equipment.

3.4.5 Switches.

3.4.5.1 Switch, type I. The type I counter front belt shall be operated by a foot control switch and a toggle switch, in addition to the electric eye. The type I counter rear belt shall be actuated by a separate switch.

3.4.5.2 Switch, type II. The type II counter front belt shall be provided with switch to stop the front belt (see 4.5.1). The type II counter rear belt shall be actuated by a switch. All switches including foot controls shall be located in the cashier's area.

3.4.6 Drive mechanism. The drive mechanism for the checkout counter shall have integral motor and gear reduction units or separate motors and gear reduction units.

3.4.6.1 Belt speed, type I. The type I counter front transport belt speed shall be 22 to 25 feet per minute and the type I rear belt speed shall be 36 to 44 feet per minute when tested as specified in 4.5.1.

3.4.6.2 Belt speed, type II. The type II counter front and rear belt speeds shall be 43 to 50 feet per minute when tested as specified in 4.5.1.

3.4.7 Accessories. The following accessories shall be supplied with all checkout counters:

a. Aisle close off such as chain, swivel gate or sliding bar.
b. Cleanout drawer or chute at end of each belt.
c. Three (3) order separators.
d. Refuse container.
e. Check writing stand.
f. For type II checkout scales swivel scale platform shall be adjustable in height from 14 to 20 inches. A flat platform shall be furnished for the type I counters (see 3.4.4). The scale platform shall be 17 inches wide by 17 inches long $\pm$ 1 inch.
g. Cash register guard is required. The cash register guard shall be perpendicular to the scale platform riser (see 3.4.4).

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

h. Pull-out or hinged checker seat.
i. Change dispenser platform is not required.
j. Three, floating dividing bars, to separate orders.

3.5 Electrical characteristics. The electrical components shall be designed to operate on a power source with the voltage, frequency, and phrase specified (see 6.2).

3.5.1 Motors. The checkout counter shall be furnished with two motors (one for each belt), minimum 1/4 horsepower each, or 1/6 horsepower energy efficient split capacitor motors conforming to CC-M-1807. The motors shall be wired to a single outlet.

3.6 Finish. The steel base and frame, side and end panels shall be enameled in accordance with the manufacturer's current commercial practice. The colors shall be selected from the manufacturer's standard shades (see 6.2).

3.7 Marking. The checkout counter shall be marked in accordance with unit marking requirements of MIL-STD-130 and shall include the manufacturer's name or trademark, model number and electrical characteristics. Unless otherwise specified, for Army use, the color of the counters shall be equal to color No. 13613 (beige) of FED-STD-595.

3.8 Workmanship. The end item shall be clean and free of burrs, snags, rough or sharp edges or other similar defects hazardous to personnel. All functioning components shall operate smoothly without binding. There shall be no loose or misplaced components. Enameled surfaces shall be uniformly coated, dry, smooth, adherent, and free of runs, teardrops, foreign matter, chips and scratches. Parts welded or brazed shall be free of grease or foreign matter. Welding and brazing shall be continuous, sound and complete. Scale and flux deposits shall be removed. Threads shall not be missing, broken, stripped or fractured. Fasteners shall not be loose, broken, or missing. Electrical wires shall have no loose connections or terminals. There shall be no cut or abraded wires and there shall be adequate slack between connections.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the document where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:46Z
Check the source to verify that this is the current version before use.

4.2 Classification of inspection. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).

4.3 First article inspection. When a first article is required (see 6.2), it shall be examined for the defects in table I and 4.4.2.2 and tested as specified in 4.5.1 and 4.5.2. The presence of any defect or failure of any test shall be cause for rejection of the first article.

4.4 Quality conformance inspection. Unless otherwise specified, sampling for inspection shall be performed in accordance with MIL-STD-105.

4.4.1 Component and material inspection. In accordance with 4.1, components and materials shall be inspected in accordance with all the requirements of referenced documents unless otherwise excluded, amended, modified or qualified in this document or applicable purchase document.

4.4.2 End item inspection. The lot shall consist of all checkout counters offered for inspection at one time. The sample unit shall be one completely fabricated checkout counter.

4.4.2.1 End item visual examination. The end item shall be examined for defects listed in table I. The inspection level shall be level II and the acceptable quality level (AQL), expressed in terms of defects per hundred units, shall be 2.5 for major defects and 6.5 for total (major and minor combined) defects.

TABLE I. Visual defects

Examine	Defect	Classification Major	Minor
Finish	Not finished where specified	X	
	Finish not as specified	X	
	Top deck not corrosion resistant steel 2B finish		X
	Enamel not color specified		X
	Enameled surfaces not smooth, uniform and adherent		X
	Enameled surfaces not free of runs, teardrops, foreign matter, chips and scratches		X

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

TABLE I. Visual defects (cont'd)

Examine	Defect	Classification Major	Minor
Construction and workmanship	Type, class and size of counter not as specified	X	
	Burrs, snags, rough or sharp edges	X	
	Any component missing or not as specified	X	
	Component loose		X
	Component misplaced, not in proper alignment, or not joined properly	X	
	Any functioning component that is inoperative or will not function as intended	X	
	Any functioning component that requires abnormal force to operate	X	
	Not all steel constructed (except belts, trim and plastic when specified)	X	
	Bagging area not corrosion resistant or plastic where applicable	X	
	Cart guard hardware not corrosion resistant steel or anodized aluminum	X	
	Front end protection missing		X
	Bagging stand not suitable for two baggers	X	
	Pull-out bagging shelf missing	X	
	Bag storage missing or not as specified	X	
	Plastic bagging area not one piece molded	X	
	Belts not double ply neoprene or triple nylon cord	X	
	Register stand does not accommodate register	X	
	Auxiliary cash drawer missing	X	
	Cash drawer not furnished with lock, or number of keys not as specified	X	
	Duplex electrical outlet missing	X	
	Required accessories missing or not as specified	X	
	No chain, swivel gate or sliding bar aisle close off	X	
	No cleanout drawer or chute at the end of each belt	X	

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

TABLE I. Visual defects (cont'd)

Examine	Defect	Classification Major	Minor
Construction and workmanship (cont'd)	No three order separators	X	
	No refuse container	X	
	No check writing stand	X	
	Swivel scale platform not adjustable in height	X	
	No cash register guard	X	
	No pull-out or hinged checker seat	X	
	A change dispenser platform	X	
	No three flat dividing bars to separate orders	X	
Welding	Missing, incomplete, fractured or not fused		X
	Slag inclusion, undercut, not smooth and uniform or deposits of scale and flux not removed		X
Fasteners	Threaded fasteners missing, broken, stripped or fractured	X	
	Fasteners loose		X
Wiring	Wiring cut or abraded	X	
	Loose connections on terminals		X
	Adequate slack not proved for wiring	X	
Identification marking	Missing, incomplete, illegible		X

4.4.2.2 End item dimensional examination. The end item shall be examined for compliance with dimensions specified in 3.4.1, 3.4.2, 3.4.3 and 3.4.7 (f). Any dimension that is not within the specified tolerance shall be classified as a defect. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

4.4.3 End item testing. When a first article is not required the initial production unit shall be tested as specified in 4.5.2 (when applicable). Each unit of production shall be tested as specified in 4.5.1. Failure of any test shall be cause for rejection of the end item involved.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

4.4.4 Packaging inspection. An examination shall be made to determine that preservation, packing and marking comply with by section 5 requirements. Defects shall be scored as set forth in table II. The sample unit shall be one shipping container fully packaged. The lot shall be all of the containers offered for delivery at one time. The inspection level shall be S-2 and the AQL, expressed in terms of defects per hundred units, shall be 4.0.

TABLE II. Packaging defect

Examine	Defect
Markings	Omitted; incorrect; illegible; of improper size, location, sequence, or method of application
Materials	Component missing or damaged
Workmanship	Distortion of container, incomplete closure, loose strapping, inadequate stapling Cushioning inadequate, improper or missing

4.5 Methods of inspection.

4.5.1 Operational test. The checkout counter shall be connected to a suitable power source. Items of various weights and shapes shall be loaded on the front belt and operated continuously for 30 minutes to determine compliance with the following requirements of 3.4:

a. The assembly of components (see 3.4)
b. Overheating of parts, i.e., bearings (see 3.4)
c. Smooth and positive starting and stopping devices (see 3.4)
d. Structural failures (see 3.4)
e. Undue vibration or noise (see 3.4)
f. Automatic control stops item (see 3.4) (when applicable)
g. Toggle switch actuates rear belt (see 3.4)
h. Toggle switch stops front belt (see 3.4.5)
i. Belt speed (see 3.4.6)

Any nonconformance shall constitute failure of this test.

4.5.2 Bagging area (molded plastic top) test. The surface of the molded plastic bagging area when furnished, shall be observed for any deep scratches that catch a fingernail after a 6 lb. $\pm$ 1 lb. can shall be slid across the surface at least ten times. No cracking or dents deeper than 1/16 inch shall appear after dropping the 6 lb. can from a 12 inch height. There shall be no deflection of the bagging area greater than 1/4 inch when a 175 pound person sits in the center of the area. Any nonconformance to the above shall constitute failure of this test.

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or Commercial as specified (see 6.2).

5.1.1 Level A. Removable accessories such as the register guard and chain or swivel gate, customer order dividers, and refuse containers shall be disassembled from the checkout counter and unit packed in a commercial fiberboard box or boxes. Fiberboard inserts or other cushioning material shall be used as necessary to isolate and immobilize contents of each box. Any manuals shall be placed in a paper or plastic envelope and unit packaged in the same box as the accessories. The auxiliary cash drawer on the register stand shall be locked and the keys secured to the drawer handle with minimum 0.059-inch diameter annealed wire. All components of the checkout counter that are free to move shall be secured in such a manner as to prevent movement and damage while in transit.

5.1.2 Commercial. The checkout counters shall be preserved in accordance with ASTM D 3951.

5.2 Packing. Packing shall be level A, B or Commercial, as specified (see 6.2).

5.2.1 Level A packing. Each checkout counter, preserved as specified in 5.1, shall be packed in a crate conforming to type I, class 1 or 2, style a of MIL-C-104. A minimum 1-inch clearance shall be provided between the checkout counter and the interior surfaces of the top, sides and ends of the crate. Disassembled components preserved as specified in 5.1, shall be secured within the checkout counter or in an unused portion of the crate. The contents shall be anchored in accordance with the appendix of MIL-C-104.

5.2.2 Level B packing. Each checkout counter, preserved as specified in 5.1, shall be packed in a crate conforming to type V, style B of MIL-C-52950. A minimum 1-inch clearance shall be provided between the checkout counter and the interior surfaces of the top, sides and ends of the crate. Disassembled components preserved specified in 5.1, shall be secured within the checkout counter or in an unused portion of the crate. The contents shall be anchored in accordance with the appendix of MIL-C-52950.

5.2.3 Commercial packing. Checkout counters, preserved as specified in 5.1, shall be packed in accordance with ASTM D 3951.

5.3 Marking. In addition to any special marking required by the contract or purchase order, unit packs and shipping containers shall be marked in accordance with MIL-STD-129 or ASTM D 3951, as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:46Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. The checkout counter is intended for use in commissaries, and is to be used to replace checkout counters when replacement is required.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number and date of this document.
b. Type, class and size of counter required (see 1.2).
c. When a first article is required (see 3.1, 4.3 and 6.3).
d. When plastic bagging area is required (see 3.4).
e. Electrical characteristics (voltage, frequency, and phases, see 3.5).
f. Color required (see 3.6).
g. Selection of the applicable levels of preservation and packing (see 5.1 and 5.2).

6.3 First article. When a first article is required, it shall be inspected and approved under the appropriate provisions of FAR 52.209. The first article should be preproduction sample consisting of one checkout counter. The contracting officer should include specific instructions in all acquisition documents regarding arrangements for inspection of the first article.

6.4 Changes from previous issue. Asteriks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness to the changes.

Custodian:

Army - GL

Preparing activity:

Army - GL

Project No. 7195-0092

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

US ARMY NATICK RESEARCH
and DEVELOPMENT CENTER
ATTN: STRNC-ES
Natick, MA 01760-5014

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Natick Research
and Development Center
ATTN: STRNC-ES
Natick, MA 01760-5014

15

Source: https://assist.dla.mil -- Downloaded: 202610-21T21:46Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-C-0043584C(GL)	Counter, Checkout, Conveyor

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE

NATICK OP 20 Nov 84

Source: https://assist.dla.mil -- Downloaded: 2026-10-21T21:46Z
Check the source to verify that this is the current version before use.