MILITARY
SPECIFICATION

MIL-M-12320A(SigC)
17 July 1958
Superseding MIL-M-12320(SigC)
3 November 1952

MAST BASES, SECTIONS, AND ADAPTER KIT

1. SCOPE

1.1 This specification covers the following Mast Bases, Sections and Adapter Kit normally used in vehicular installations and standard manpack antenna equipment. (See 6.3)

Mast Base AB-15( )/GR
Mast Section AB-21( )/GR
Mast Section AB-22( )/GR
Mast Section AB-23( )/GR
Mast Section AB-24( )/GR
Mast Base MP-65( )
Mast Base MP-76( )
Mast Section MS-116( )
Mast Section MS-117( )
Mast Section MS-118( )
Antenna Spring Section AB-129( )/PR
Adapter Kit M-459

2. APPLICABLE DOCUMENTS

2.1 The following specifications, standards, drawings, and publications, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

FEDERAL

UU-T-111	Tape, Paper, Gummed (Kraft)
UU-P-268	Paper, Kraft, Wrapping
PPP-B-601	Boxes, Wood, Cleated Plywood
PPP-B-621	Boxes, Wood, Nailed and Lock-corner
PPP-B-636	Boxes, Fiber

MILITARY

MIL-P-116	Preservation, methods of

FSC 5985

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	Marking of Shipments.
MIL-STD-169	Extreme-temperature cycle.
MIL-STD-170	Moisture resistance test cycle for ground signal equipment.

DRAWINGS

SIGNAL CORPS

SC-D-17226	Bend Test Jig for Mast Section MS-116-A, MS-117-A, MS-118-A, AB-21/GR, AB-22/GR, AB-23/GR and AB-24/GR Assembly.
SC-D-17227	Bend Test Jig for Mast Sections MS-116-A, MS-117-A, MS-118-A, AB-21/GR, AB-22/GR, AB-23/GR and AB-24/GR Details.
SC-D-17228	Bend Test Jig for Mast Sections MS-116-A, MS-117-A, MS-118-A, AB-21/GR, AB-22/GR, AB-23/GR and AB-24/GR Details.
SC-C-33073	Form to be used for pilot pack process sheet.
SC-DL-73589	Antenna Spring Section AB-129/PR
SC-DL-83061	Mast Sections AB-21/GR, AB-22/GR, AB-23/GR and AB-24/GR
SC-DL-100579	Mast Base MP-65-( )
SC-DL-100580	Mast Base MP-76
SC-DL-100581	Mast Base AB-15/GR
SC-DL-100586	Adapter Kit M-459
SC-DL-100588	Mast Sections MS-116-( ), MS-117-( ) and MS-118-( )

(Copies of specifications, standards, and drawings, required by contractors in connection with specific procurement functions, may be obtained from, or as directed by, the contracting officer. Both the title and identifying number or symbol should be stipulated when requesting copies.)

2.2 Other publications.- The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

a. For rail

(1) Uniform Freight Classification No. 4 Uniform Freight Classification, 202 Union Station, Chicago 6, Illinois.

(2) Consolidated Freight Classification Rules No. 21 Consolidated Classification Committee, 1 Park Avenue and 33rd Street, New York 16, New York.

b. For Truck

National Motor Freight Classification No. A-3 and No. 14 American Trucking Association, Inc., 1424 Sixteenth Street, Washington 6, D. C.

3. REQUIREMENTS.-

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

3.1 Description.- The equipment covered by this specification consists of Mast Bases AB-15( )/GR, MP-65( ), MP-76( ) and various mast sections which can be used with the mast bases. Mast Sections MS-116-( ), MS-117-( ) and MS-118-( ) are each approximately 3 feet long. Mast Section MS-118-( ) is a top section, Mast Section MS-117-( ) is commonly an intermediate section, and one or more Mast Sections MS-116-( ) form the bottom section or sections. A 6-foot antenna can be constructed of a Mast Section MS-117-( ) and a Mast Section MS-118-( ). A 9-foot antenna can be constructed from one of each type of Mast Section MS-116-( ), MS-117-( ) and MS-118-( ), and a 15-foot antenna can be constructed with 2 additional Mast Sections MS-116-( ). The Mast Sections AB-21( )/GR, AB-22( )/GR, AB-23( )/GR and AB-24( )/GR are each approximately 23 inches long. Mast Section AB-24( )/GR is a top section; Mast Section AB-21( )/GR forms the bottom section; Mast Section AB-22( )/GR and Mast Section AB-23( )/GR are normally intermediate sections. An antenna can be constructed using any required combination of Mast Sections AB-21( )/GR, AB-22( )/GR, AB-23( )/GR, AB-24( )/GR to give required length. These mast sections may be also used in conjunction with Mast Sections MS-116-( ), MS-117-( ) and MS-118-( ). Antenna Spring Section AB-129( )/PR is normally used with Antenna AT-271( )/PRC. Adapter Kit M-459 is intended to convert Mast Base MP-65A for use with coaxial cable.

3.2 Construction.- Each equipment shall be fabricated in accordance with the applicable drawing listed in Section 2 and performance characteristics contained herein.

3.3 Preproduction samples.- The contractor shall furnish preproduction samples for approval, as required by the invitation for bids and contract. (See 6.2(e) (1).)

3.4 Technical literature, tools, and running spare parts.- Technical literature, tools, and running spare parts shall be furnished as specified in the contract. Running spare parts shall be identical to corresponding parts in the items furnished on the order (See 6.2)

3.5 Service conditions.- The equipment shall meet the following service conditions:

3.5.1 Equipment nonoperating.- Except as stated in 3.5.1(b) the equipment shall comply with the operational requirements of 3.5.2 after subjection to any of the following nonoperating conditions successively or in combinations encountered during worldwide short-term storage and transit:

(a) Temperature.- Exposure in the range of +160°F to -80°F; however, exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 24 hours at any one time. (See 4.4.1).

(b) Relative humidity.- Relative humidity up to 97 percent, for an indefinite period of time; and exposure at 100 percent relative humidity, with condensation for 4 hours.

3.5.2 Equipment operating.- The equipment shall meet the performance requirements of this specification while subjected to any of the following conditions successively or in combinations likely to be encountered during worldwide operations:

(a) Operation.- Continuous operation, with no more than normal maintenance and replacement of parts. Compliance will be determined by examination of the preproduction sample.

(b) Temperature.- Ambient temperature in the range of -150°F to -65°F. (The 150°F temperature includes effect of sun-load.) Exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 72 hours.

(c) Relative humidity.- Relative humidity up to 97 percent; and exposure at 100 percent relative humidity, with condensation, for 4 hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

3.6 Interchangeability.- Corresponding components, on contract shall be physically and functionally interchangeable as units without modification thereof or of other items with which the units are used. When dimensions, ratings, characteristics, etc. are not specified, the manufacturer's design limits shall be used to determine compliance with the foregoing.

3.7 Thread engagement (mast sections.) Any two or more mast sections when assembled together shall be capable of withstanding an axial pull of 500 pounds without loosening of the thread engagement between the mast sections. (See 4.5).

3.8 Soldering of wire in the mast base.- The wire in the mast base after having been soldered in the body shall show no evidence of loosening of the soldered joints nor permanent set in the individual wires when subjected to the test of 4.6.

3.9 Torsion requirements of subassembly of body, socket, ferrule and flexible case.- Each ferrule and casing when assembled shall be capable of withstanding a torque of 150 inch-pounds when applied through the ferrule at right angles to the axis of the assembly in a counter clockwise direction with no permanent deformation. The swaged joints shall show no signs of loosening or displacement, and the ferrule shall be secure and unrotated from its original position when subjected to this 150 inch-pound torque.

3.10 Neoprene covering:

3.10.1 Bonding and curing.- The neoprene covering shall be molded and securely bonded in place. The covering shall be smooth and free of grooves. Curing shall not be injurious nor cause deterioration of the covering.

3.10.2 Flexibility.- The neoprene covering shall be flexible and capable of bending through 90 degrees while maintained at a temperature of -40 F without developing any cracks.

3.11 Flexibility of assembled mast bases.- Each completely assembled mast base when bent 90 degrees from its normal position and then slowly returned to its normal position shall do so smoothly without internal catching, binding, scraping, or loosening. The bending moment, measured from the axis of the mast base, required for a 90 degree bend shall be from 600 to 800 inch-pounds for Mast Base MP-65( ) and MP-76( ) and from 180 to 260 inch pounds for Mast Base AB-15/GR and Antenna Spring Section AB-129( )/PR.

3.12 Mast sections, physical properties of steel.- The steel used for the mast sections shall have physical properties that enable the mast sections to pass the test of 4.10.

3.13 Shock absorbing qualities of mast bases.- Mast Base MP-65( ) and MP-76( ) shall be capable of withstanding 2500 blows at the rate of one blow per second, and Mast Base AB-15( )/GR, and Antenna Spring Section AB-129( )/PR shall be capable of withstanding 1500 blows at the rate of one blow per second, of such force that the mast bases are bent to an angle of 90 degrees by each blow, with no evidence of dimensional changes, loosening of parts or other damage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

3.14 Workmanship.- Workmanship on components covered by this specification shall be such as to meet all the requirements of this specification when inspected in accordance with 4.13 including the applicable portions of the following paragraphs:

3.1 Description.

3.2 Construction.

4. QUALITY ASSURANCE PROVISIONS

4.1 Classification of inspection.- Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery). (See 4.2).

(b) Procurement inspection. (Procurement inspection shall be the inspection performed by the contractor and by the Government, as specified by 4.3 and 4.14).

(1) Procurement inspection of items before preparation for delivery. (See 4.3).

(2) Procurement inspection of preparation for delivery. (See 4.14 and section 5).

4.2 Preproduction inspection.- This inspection shall consist of the preproduction inspection specified in Table I and the group A, group B, and group C inspection specified in Tables II, III, and IV, respectively.

Table I - Preproduction inspection

Inspection (For additional preproduction inspection, see 4.2)	Rqt Para.	Insp. Para.
Storage:		
1. Temperature	3.5.1	4.4.1
2. Humidity	3.5.1	4.4.2

4.3 Procurement inspection of items before preparation for delivery.- The minimum inspection performed by the contractor shall be as specified by (a) through (c) below--to demonstrate compliance with specified requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's records. In addition, the Government--at its discretion--will verify, by product inspection, the contractor's compliance with specified requirements. Such verification shall not exceed the amount of inspection required herein of the contractor.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.3 Procurement inspection of items before preparation for delivery.- (Contd)

(a) Procurement inspection shall consist of group A, group B, and group C inspection as specified in 4.3.1 through 4.3.2.3.

(b) When Standard MIL-STD-105 specifies actions by the Government, the Government may authorize the contractor to perform any of such actions except that responsibility for acceptance rests with the Government.

(c) Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. In addition, group C inspection shall normally be performed on sample units that have been subjected to and met group B inspection. However, the order may be varied when it is considered more practical to select separate samples for group B or group C inspection or both.

4.3.1 Group A inspection.- This inspection (including sampling) shall conform to Table II and Standard MIL-STD-105. Unless otherwise specified, normal inspection shall be used at the start of the contract. Group A inspection shall be performed in any order which is satisfactory to the Government.

Table II - Group A Inspection procedures

Inspection	Rqt Para.	Test Para.	AQL Major	AQL Minor
Visual and Mechanical				
Mast base sections Mast sections Antenna spring section Adapter kit	3.1, 3.2 and 3.14	4.13	1%	4%
Mechanical Tests				
Mast base				
Soldering	3.8	4.6	1%	*
Torsion	3.9	4.7	1%	
Neoprene bonding	3.10.1	4.8	1%	
Bend	3.11	4.11	1%	
Mast section				
Bend	3.12	4.10	1%	

* All mechanical tests are major category.

4.3.2 Group B inspection.- This inspection (including sampling) shall conform to Table III and the Appendix to Standard MIL-STD-105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with 4.3.3 and the requirements of Standard MIL-STD-105 for disposition of rejected product.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.3.2.1 Group B sampling plans.- The group B sampling plans, as listed in Table III, shall be as follows:

Group B plan	AQL	Inspection level for normal inspection	Inspection level for reduced inspection
B-1	4.0%	L-8	L-6

4.3.2.2 Order of inspection within group B.- Group B inspection shall be performed in any order which is satisfactory to the Government.

4.3.2.3 Procedure in case of failure.- When an inspection lot fails, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken. If the contractor and Government inspector cannot agree on the effectiveness of the corrective action, the matter shall be referred to the contracting officer for resolution

Table III - Group B inspection

Inspection	Rqt Para.	Insp. Para.	Sampling Plan
Thread engagement Interchangeability	3.7 3.6	4.5 4.13	B-1 B-1

Table IV - Group C inspection

Inspection	Rqt Para.	Insp. Para.
Cold bend test of neoprene covering Shock absorbing qualities of mast bases	3.10.2 3.13	4.9 * 4.12

* Sample units subjected to this inspection shall not be furnished on contract.

4.3.3 Group C inspection.- This inspection shall be as listed in Table IV.

4.3.3.1 Sampling for inspection of equipment.- For each group C inspection two units out of the first production lot and one for each 250 (or fraction thereof) produced thereafter shall be selected without regard to their quality.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.3.3.2 Noncompliance.- If a sample unit fails group C inspection, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken on the process and all units of product which were manufactured with the same conditions, materials, processes, etc. If the Government inspector does not consider that the corrective action will enable the product to meet specified requirements, or if the contractor cannot determine the cause of failure, the matter shall be referred to the contracting officer. (See 6.4)

4.3.3.3 Disposition of group C samples.- Specimens submitted to group C inspection shall not be furnished on the contract.

4.3.4 Disposition of nonconforming product.- When defective sample units or failed inspection lots are submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.4 Storage test.-

4.4.1 Temperature test for equipment.- The equipment shall be subjected to the temperature cycle shown on Standard MIL-STD-169. After completion of the temperature cycle the equipment shall meet full specification requirements.

4.4.2 Humidity test for equipment.- The equipment shall be subjected to five cycles of Standard MIL-STD-170. After completion of the five cycles the equipment shall meet full specification requirements.

4.5 Test of thread engagement (mast sections).- Two or more samples shall be assembled together and subjected to an axial pull of 500 pounds. Both ends of Mast Sections MS-116-( ), MS-117( ), AB-21( )/GR, AB-22( )/GR, AB-23( )/GR and the threaded end of Mast Sections MS-118-( ) and AB-24( )/GR shall be tested in this manner. If the thread engagement between any 2 mast sections loosens when subjected to this test, it fails the test.

4.6 Test of soldering.- After the wires have been soldered in the body, they shall be subjected to the following tests, after which there shall be no evidence of loosening of the soldered joints nor permanent set in the individual wires.

4.6.1 Five wires near the center of the group shall be subjected to an axial pull of 30 pounds.

4.6.2 The individual wires around the periphery of the group, shall each be bent to an angle of 90 degrees with reference to the axis, and then allowed to return slowly to the normal position.

4.7 Torsion test of mast-base, sub-assembly of body, socket, ferrule and flexible case.- The sub-assembly used on the order shall be tested as follows: A torque of 150-inch pounds shall be applied through the ferrule, at right angles to the axis of the assembly,

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.7 Torsion test of mast-base, sub-assembly of body, socket, ferrule and flexible case.- (Contd)

in a counter-clockwise direction. After the torque has been released, the casing shall show no evidence of permanent deformation, there shall be no loosening nor displacement at the swaged joints, and the ferrule shall be secure and unrotated from its original position.

4.8 Test of bonding of the neoprene covering.- After the neoprene covering has been bonded and cured in place, the sub-assembly of the mast bases furnished on the order shall be inspected and tested as follows:

(1) The edges of the bonded covering shall be inspected for satisfactory adhesion.

(2) Before the greasing operation, air at a pressure of 50 pounds per square inch shall be forced into the grease hole. The sub-assembly shall be completely covered with soap bubble lather during the test. There shall be no evidence of air leakage, as shown by bubbles in the lather, and the neoprene covering shall not bulge at any point. If the leakage is caused by an unsatisfactory neoprene bond, the mast base may be rebonded.

4.9 Cold-bend test of neoprene covering.- The mast bases shall be maintained at a temperature of -40°F for 24 hours. After this conditioning period, the sample, while still at -40°F shall be quickly bent to an angle of 90 degrees and allowed to snap back to normal position. The samples shall then be allowed to return to room temperature, and shall then be bent to the 90-degree position, so that the same side of the covering will again be stretched. While in the bent position, the covering shall be examined for cracks. Any sample that evidences cracks shall be considered to have failed the test.

4.10 Bend test on mast sections.- The mast section shall be checked to determine the physical properties of the steel used as specified in 4.10.1.

4.10.1 Details of test.- The mast section shall be tested in the bend test jig, Drawing SC-D-17226. The appropriate insert, test ring, and target circle shall be employed. The mast section shall be pressed firmly into Insert, Details (3) or (4), SC-D-17227 and Target, Detail (17), SC-D-17228 shall be centered over top end of the mast section. The mast section shall be bent slowly to extremes of Test Ring, Details (6) or (7), SC-D-17227 and shall be allowed to return slowly to its free position. The end of the mast section shall then be viewed through Target. Any mast section whose end projection appears outside of the appropriate circle after this test shall be rejected.

4.11 Bend test on assembled mast bases.- The completely assembled mast base shall be secured in a vise or equivalent holding device, bent to a 90-degree position, and then allowed to return slowly to its normal position by decreasing the restraining force from the maximum value corresponding to the 90-degree position, to zero. The mast base shall return to its normal vertical position smoothly, with no evidence or sound of internal catching, binding, or scraping and there shall be no perceptible looseness. The bending moment, measured from the axis of the mast base, required for a 90-degree bend shall be from 600 to 800 inch-pounds for Mast Base MP-65( ) and MP-76( ) and from 180 to 260 inch-pounds for Mast Base AB-15/GR and Antenna Spring Section AB-129( )/PR.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.12 Test for shock-absorbing qualities of mast bases.- Mast Base MP-65-( ) and MP-76( ) shall be given 2500 blows at the rate of one blow per second, and Mast Base AB-15( )/GR, Antenna Spring Section AB-129( )/FR shall be given 1500 blows at the rate of one blow per second, of such force that the mast bases are bent to an angle of 90 degrees by each blow. The required number of blows may be accumulated at the specified rate successively or intermittently if necessary to prevent excessive heating of the mast bases. Mast Bases MP-76( ) and AB-129( )/FR shall be mounted during test, under same conditions as MP-65( ) and AB-15( )/GR respectively.

4.12.1 After this test, there shall be no evidence of dimensional changes, loosening of parts, nor other damage, and upon disassembling there shall be no evidence of excessive internal wear, damage or correction.

4.12.1.1 The units so tested shall not be supplied on an order.

4.13 Visual and mechanical inspection.- Parts and components shall be inspected for workmanship, mechanical fit, loose nuts and screws, application of specified tropicalization treatments, and miscellaneous defects. Fastening devices shall be inspected for mechanical operation. Wiring, soldered connections, ground connections, welds, finishes, etc. shall be inspected for workmanship. Clearances, dimensions, and mechanical adjustments shall be measured. Labels and markings shall be inspected for conformance with approved facsimiles, when facsimiles are required. Examination also may be made for other visual or mechanical defects, similar to those described above, that are contrary to specified requirements for the equipment. Visual and mechanical defects shall be classified by the Government inspector as major or minor in accordance with the definitions of Standard MIL-STD-105.

4.14 Procurement inspection of preparation for delivery.- The minimum inspection performed by the contractor shall be as specified in 4.14.1 and 4.14.2. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's records. In addition, the Government-at its discretion--will verify, by product inspection, the contractor's compliance with specified requirements. Such verification shall not exceed the amount of inspection required herein of the contractor. When Standard MIL-STD-105 specifies actions by the Government, the Government may authorize the contractor to perform any of such actions except that responsibility for acceptance rests with the Government.

4.14.1 Preservation and packaging.- Inspection of preservation and packaging shall be as specified in Specification MIL-P-116. Classification of defects shall be as shown on Table V.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

TABLE V

PRESERVATION, AND PACKAGING AND MARKING THEREOF

MAJOR	MINOR
1. Use of improper or defective material.	1. Item not properly blocked or braced within the unit package to prevent movement.
2. Quantity in unit package not as specified.	2. Packaging material damaged.
3. Incorrect packaging method applied.	3. Conforming wraps are not snug-fitting and contain voids.
4. Cushioning or padding omitted.	4. Any item of marking information other than 7 thru 9 omitted, incorrect, or illegible.
5. Cushioning inadequate for the physical and mechanical protection of the item.	
6. Unsealed, punctured, or improperly sealed barrier bag, wrap, or envelope.	
7. Stock number omitted, incorrect, or illegible.	
8. Nomenclature omitted, incorrect or illegible.	
9. Marking of quantity of items in package omitted, incorrect or illegible.	
10. Different stock numbered items in the same unit package.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.14.2 Packing and marking of exterior containers.- Packing and marking of exterior containers shall be given visual inspection for the defects listed below and to determine conformance with the approved process sheet furnished by the contractor as required by the contract. This inspection shall conform to the Appendix to Standard MIL-STD-105. Inspection level L-8 shall be used for normal inspection and L-6 for reduced inspection. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1. The AQL for major defects shall be four percent and the AQL for minor defects shall be ten percent. Classification of defects shall be as shown on Table VI.

TABLE VI

MAJOR	MINOR
1. Use of improper or defective material.	1. Unsealed carton.
2. Quantity in pack not as specified.	2. Defective taping or sealing of carton.
3. Gross weight in excess of specified amount.	3. Any other box defect which may be considered minor by definition of Standard MIL-STD-105.
4. Box closure not as specified.	4. Any item of required marking information other than 10 thru 16 listed under major defects omitted, incorrect, or illegible.
5. Type, grade, class, and style of the shipping container not as specified.	
6. Strapping omitted.	
7. Strapping inadequate or incorrectly applied.	
8. Items not adequately blocked, braced, or cushioned within the shipping container to prevent movement or damage.	
9. Shipping documents or packing list omitted.	
10. Stock number omitted, incorrect, or illegible.	
11. Nomenclature omitted, incorrect, or illegible.	
12. Marking of quantity of items in pack omitted, incorrect, or illegible.	
13. Destination marking omitted, incorrect, or illegible.	
14. Service designation (color marking) omitted.	
15. Specified special marking and labeling such as MAP labels, shipment digit markings, etc., omitted, incorrect, or illegible.	
16. Overseas code marking omitted, incorrect, or illegible.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

4.14.2.1 Inspection lot.- A lot for visual inspection of the pack shall be all completed packs which are identical and will be submitted for acceptance at one time.

4.14.2.2 Procedure in case of failure.- If an inspection lot fails, the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken. If the contractor and Government inspector cannot agree on the effectiveness of the corrective action, the matter shall be referred to the contracting officer for resolution.

4.14.2.3 Disposition of nonconforming product. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with the requirements of Standard MIL-STD-105 for disposition of rejected product. When submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.15 Rough handling test (preparation for delivery).- When rough handling test is required by the contract (see 6.2(e), the following functional tests shall be conducted to determine freedom from operational malfunction caused by the rough handling.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.-

5.1.1 Level A.- Mast bases, sections and adapter kit shall be preserved, packaged and tested in accordance with the procedures specified for the designated methods as prescribed in Specification MIL-P-116 and as described herein.

5.1.1.1 Mast Bases.- Mast bases shall be packaged individually Method III as follows: Place one each mast base within a full telescope design box type I, class 1 conforming to the requirements of Specification PPP-B-636. The inside dimensions of the full telescope box shall be such as to receive cells or pads or both, fabricated of double faced corrugated fiberboard designed to surround all surfaces of the mast base, and to absorb the shock of impact in handling and transit, and prevent independent movement of the box contents. Box closure shall be in conformance with the appendix of Specification PPP-B-636.

5.1.1.2 Mast sections, antenna spring section, and adapter kit.- Each item shall be packaged individually Method III as follows: Place one each item within a close fitting wrap of kraft wrapping paper, grade A, No. 1, 35 pound weight, conforming to Specification UU-P-268. Closure shall be effected by means of class 2, gummed paper tape conforming to Specification UU-T-111.

5.1.1.3 Intermediate package.-

5.1.1.3.1 Mast bases.- Place a quantity of mast base bearing like type number (see 5.1.1.1) within a close fitting regular slotted style corrugated fiberboard box class 2, grade 6 (W6c) conforming to Specification PPP-B-636. The maximum weight of box and contents shall not exceed 30 pounds. Box closure shall be in conformance with the appendix of the referenced box specification.

5.1.1.3.2 Mast sections, antenna spring section, and adapter kit.- Place a quantity of each item bearing like description (see 5.1.1.2) within a respective close-fitting five panel folder, conforming to Table II, Specification PPP-B-636. The maximum weight of box and contents shall not exceed 20 pounds. Box closure shall be as specified in 5.1.1.3.1.

5.1.2 Level C.- Mast bases, mast sections, antenna spring sections, and adapter kit shall be packaged in accordance with commercial practice and in a manner that will afford protection against corrosion, deterioration and physical damage during direct shipment to the first receiving activity.

5.2 Packing.-

5.2.1 Level A.- Mast bases, mast sections, antenna spring sections and adapter kit, packaged as specified in 5.1.1.3 shall be packed for shipment within style 4, class 2, nailed wood boxes conforming to Specification PPP-B-621, or wood cleated - plywood boxes, style A, type I, class 2 conforming to Specification PPP-B-601. Fabricate the box to fit the contents snugly. The maximum weight of any one box with contents shall not exceed 200 pounds. Box closure shall be in conformance with the requirements of the box specification or appendix thereto, as applicable.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

5.2.1.1 Metal strapping.- Shipping containers shall be strapped with flat metal strapping in conformance with the requirements of the appendix of the applicable container specification only for direct shipment to ports.

5.2.2 Level B.- Mast bases, mast sections, antenna spring sections, and adapter kit, shall be packed for shipment as specified in 5.2.1, except the shipping containers shall be domestic style or type.

5.2.3 Level C.- Mast bases, mast sections, antenna spring sections and adapter kit shall be packed for shipment in a manner conforming to the requirements of Uniform Freight Classification No. 4 and Consolidated Freight, Classification Rule 21 for rail shipment, National Motor Freight Classification No. A-3 and No. 14 for truck shipment, Parcel Post Regulations, and the regulations of other carriers as applicable to the mode of transportation employed at lowest transportation rate.

5.3 Marking.- Interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use.- The mast bases and sections are used to construct antennas of various specified lengths conforming to the requirements of vehicular and manpack equipments.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.

(b) Type required.

(c) Level of packaging and level of packing required for shipment. (Level A, level B, or level C.)

(d) The specific paragraphs of section 5 which are applicable to the particular procurement.

(e) Preproduction inspection:

(1) Four samples of each item cited in section 1 are generally required so that lengthy environmental tests can be completed on some samples while complete performance measurements can be made on the other samples.

(2) . . . . . .

(3) Preproduction pack(s) as follows:

a. Makeup of pack(s).

b. Number of each kind of pack to be submitted.

c. Inspection to be performed thereon--including rough handling test, which will not be performed as procurement inspection.

d. Five copies of process sheet, using format shown on Drawing SC-C-33073 and accompanied by such drawings, sketches, and other data as may be necessary to completely describe the procedure followed in fabrication of the preproduction pack(s) and to identify the items therein. This data should be submitted to the contracting officer with the preproduction pack.

e. A packaging technician from the procuring agency will evaluate the preproduction pack(s).

(f) Marking and shipping of samples.

(g) Place of final inspection. (See 3.4)

(h) Technical literature required. (See 3.4)

(i) Quantity of tools and running spare parts required. (See 3.4)

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

6.3 Nomenclature.- The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: AN/PIQ-1W. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1)

6.4 Group C inspection.- Approval to ship may be withheld, at the discretion of the Government, pending the decision from the contracting officer on the adequacy of corrective action. (See 4.3.3.2)

NOTICE: When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

POSTAGE AND FEES PAID
NAVY DEPARTMENT

OFFICIAL BUSINESS

COMMANDING GENERAL
U.S. ARMY ELECTRONICS COM.
ATTN: AMSEL-PP-E-SED
FORT MONMOUTH, N.J. 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION

ORGANIZATION *(Of submitter)* | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 APR 63 1426 REPLACES NAVSHIPS FORM 4863, WHICH IS OBSOLETE PLATE NO. 15419

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T22:41Z
Check the source to verify that this is the current version before use.