MIL-B-11353D
2 June 1976
SUPERSEDING
MIL-B-11353C
8 December 1969

MILITARY SPECIFICATION

BRIDGE, FLOATING: ALUMINUM; FOOT,

PACKAGING OF

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the requirements for the preservation packing, and marking for a floating aluminum foot bridge (SC 5420-97-CL-E28) (NSN 5420-00-267-0009).

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

FEDERAL

MMM-A-260	- Adhesive, Water-Resistant, (for Sealing Waterproofed Paper).
PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-1055	- Barrier Material, Waterproofed, Flexible.

MILITARY

MIL-P-116	- Preservation-Packaging, Methods of.

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:57Z
Check the source to verify that this is the current version before use.

STANDARDS

FEDERAL

FED. STD. No. 356	- Commercial Packaging of Supplies and Equipment.

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.

DRAWINGS

ME

D13217E2267	- Packing of Bridge, Floating, Aluminum, Foot, Ponton and Treadway.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Preproduction pack. The contractor shall furnish a preproduction pack for examination within the time frame specified (see 6.2), to prove prior to starting production packaging that the applied preservation, packing, and marking comply with the requirements of this specification. Examination shall be as specified in Section 4 and shall be subject to surveillance and approval by the Government (see 6.3). The preproduction pack may be prepared utilizing either the preproduction model or a production bridge. When the preproduction model is utilized, any preservation and packing shall be removed by the contractor at no expense to the Government, when requested by the Government, to facilitate comparison between the preproduction model and production bridges.

3.2 Materials. Material shall be as specified herein and on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:57Z
Check the source to verify that this is the current version before use.

3.3 Preservation. Preservation shall be Level A or Commercial as specified (see 6.2).

3.3.1 Level A.

3.3.1.1 Reflective tape. The roll of reflective tape shall be preserved in accordance with MIL-P-116, Method IC-1.

3.3.1.2 Fibrous rope. Each coil of rope shall be wrapped with barrier material conforming to PPP-B-1055, Class E-1, with all folds, laps, and seams sealed with adhesive conforming to MMM-A-260, Type II, Grade B, class optional.

3.3.1.3 Consolidation. The holdfast assemblies, hinge clamps, wire rope, wire rope clamps, hook snaps, handrail posts, approach posts, and the roll of reflective tape shall be consolidated in accordance with Drawing D13217E2267, Sheet 1. Boxes required for consolidation of components shall conform to PPP-B-601, Overseas Type, Style I. Strapping of the boxes shall not be required.

3.3.2 Commercial. The components of each complete bridge shall be preserved in accordance with FED. STD. No. 356.

3.4 Packing. Packing shall be Level A or Commercial as specified (see 6.2).

3.4.1 Level A. The components of each complete bridge, preserved as specified in 3.3, shall be packed in accordance with Drawing D13217E2267, Sheets 1 and 2.

3.4.2 Commercial. The components of each complete bridge, preserved as specified in 3.3, shall be packed in accordance with FED. STD. No. 356.

3.5 Marking.

3.5.1 Level A. Marking for Level A shall be in accordance with MIL-STD-129.

3.5.2 Commercial. Commercial marking shall be in accordance with FED. STD. No. 356.

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:57Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Material inspection. The contractor is responsible for insuring that materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings as applicable.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Quality conformance inspection (see 4.4).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction pack shall be examined for the defects listed in 4.4.4. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Inspection stages. Inspection shall be in three stages as follows:

(a) The first stage shall include inspection of procedures, methods, materials, containers, and unit marking prior to placing components into consolidation containers.
(b) The second stage shall include inspection of closure and marking of consolidation containers and the arrangement and blocking and bracing of consolidation containers in the shipping container.
(c) The third stage shall include inspection of the shipping container prepared for shipment.

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:57Z
Check the source to verify that this is the currentversion before use.

4.4.2 Unit of product. For the purpose of inspection, all components prepared for any applicable stage that will comprise a complete pack shall be considered a unit of product.

4.4.3 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.4.4 Examination. Samples selected in accordance with 4.4.3 shall be examined for the following defects. Acceptable Quality Level (AQL) shall be 2.5 percent defective.

101.	Materials, methods, or containers not as specified. Each incorrect material, method, or container shall constitute one defect.
102.	Fibrous rope not wrapped as specified or the wrap not sealed as specified.
103.	Consolidation of components not in accordance with the drawing as specified.
104.	Packing not in accordance with the drawings as specified.
105.	Marking illegible, incorrect, incomplete, or missing.

5. PACKAGING (Not applicable to this specification).

6. NOTES

6.1 Intended use. This specification is intended to be used for direct reference in contracts or orders for the preservation, packing, and marking of a Bridge, Floating: Aluminum, Foot (NSN 5420-00-267-0009).

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of the preproduction pack (see 3.1).
(c) Degree of preservation and of packing required (see 3.3 and 3.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:57Z
Check the source to verify that this is the current version before use.

6.3 Preproduction pack. Any changes or deviations of production packs from the approved preproduction pack will be subject to the approval of the contracting officer. Approval of the preproduction pack will not relieve the contractor of his obligation to preserve, pack, and mark the bridge set components in accordance with this specification.

Custodians:

Army - ME
Navy - MC

Review activity:

Army - SM

Preparing activity:

Army - ME

Project 5420-0131

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:57Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE: This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE ARMY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12062 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

Commander
US Army Mobility Equipment Research & Development Command
ATTN: DRXFB-DS
Fort Belvoir, VA 22060

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:57Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions - Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ USER
	☐ MANUFACTURER
	☐ OTHER *(Specify)*: _____

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil/ - Downloaded: 2026-10-17T15:57Z
Check the source to verify that this is the current version before use.