MIL-L-11296B(EL)
6 July 1966
Superseding
MIL-L-11296A(SigC)
23 December 1954

MILITARY SPECIFICATION

LIGHT ASSEMBLIES, ELECTRIC

MX-1291( )/PAQ AND MX-1292( )/PAQ

1. SCOPE

1.1 This specification covers two Light Assemblies used for investigations, identification, interception and detections. They are designated Light Assembly, Electric MX-1291( )/PAQ and Light Assembly, Electric MX-1292( )/PAQ. (See 6.3)

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

T-T-871	Twine, Cotton, Wrapping
PPP-B-566	Boxes, Folding, Paperboard
PPP-B-636	Boxes, Fiberboard
PPP-C-843	Cushioning Material, Cellulosic
PPP-F-320	Fiberboard, Sheet, Stock and Cut Shapes
PPP-P-291	Paperboard, Wrapping, Cushioning
PPP-T-76	Tape, Pressure-Sensitive Adhesive, Paper, Water Resistant
PPP-T-97	Tape, Pressure-Sensitive Adhesive, Filament Reinforced

MILITARY

MIL-P-116	Preservation, Methods of
MIL-B-117	Bags, Interior Packaging

FSC 6695

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

MIL-C-3885	Cable Assemblies and Cord Assemblies, Electrical (for use in Electronic, Communication and Associated Electrical Equipment)
MIL-P-11268	Parts, Materials, and Processes Used in Signal Corps Equipment
MIL-M-13231	Marking of Electronic Items
MIL-F-14072	Finishes for Ground Signal Equipment

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-169	Extreme-Temperature Cycle
MIL-STD-170	Moisture Resistance Test Cycle for Ground Signal Equipment
MIL-STD-252	Wired Equipment, Classification of Visual and Mechanical Defects

DRAWINGS

SIGNAL CORPS

SC-DL-288384	MX-1291( )/PAQ, Light Assembly Electric
SM-B-288407	Filter, Light

(Copies of specifications, standards, and drawings, required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. - The Electric Light Assemblies MX-1291( )/PAQ and MX-1292( )/PAQ are lightweight, portable, ultraviolet, detection sets used in the field or laboratory for investigation, identification, interception and detection.

3.2 Preproduction samples. - The contractor shall furnish two (2) preproduction samples of the light assembly on order for approval as required by the invitation for bids and contract. (See 4.3 and 6.1)

3.3 Light Assembly, Electric MX-1291( )/PAQ. -

3.3.1 Construction. - The MX-2191( )/PAQ shall be constructed in accordance with the requirements of this specification, and of Drawing SC-DL-288384 (including the requirements for parts, materials, and processes thereon).

3.3.2 Filter, light, ultraviolet, 2200 to 4400 Angstrom Units. - The Filter shall conform to Drawing Nr. SM-B-288407.

1% Maximum Permissable Transmission at 2200 Angstrom Units.
10% Minimum Permissable Transmission between 2500 and 3000 Angstrom Units.
40% Minimum Permissable Transmission between 3000 and 3400 Angstrom Units.
10% Minimum Permissable Transmission between 3400 and 3800 Angstrom Units.
1% Maximum Permissable Transmission at 4400 Angstrom Units.

3.3.3 Overall Performance. - The equipment shall meet the operational tests of 4.12.

3.4 Light Assembly, Electric MX-1292( )/PAQ. - Light Assembly, Electric MX-1292 ( )/PAQ, shall consist of two major components: A long-wave transmitting light assembly (long-wave unit) and a short-wave transmitting light assembly (short-wave unit), which together provide three separate sources of ultraviolet light. Either assembly shall be capable of operating independently, or both used at one time.

3.4.1 Procurement model. - A procurement model of the equipment will be available for inspection by prospective bidders and will be lent to the contractor. Unless otherwise

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

specified herein or in the invitation for bids, the equipment shall conform to the following:

3.4.2 Physical construction. - Physical construction of the equipment shall conform to the model.

3.4.3 Features. - The equipment shall incorporate all features of the model.

3.4.4 Performance. - The contractor shall adjust and aline the model for optimum performance and then shall measure its performance characteristics. Performance of the equipment shall conform to those measurements, except that, in case of conflict between specified performance characteristics and the performance of the model, specified performance characteristics and the performance of the model, specified performance characteristics shall govern. The contractor shall immediately prepare copies of a test report on the measurements, and forward it as required by the contract.

3.4.5 Parts, materials, and processes; general. - Except as otherwise specified herein parts, materials, and processes shall conform to Specification MIL-P-11268 including the selection requirements therein.

3.4.5.1 Cable assembly, power, electrical. - Cable assembly, power electrical, used to supply AC power to the equipment shall be a 2-conductor #18 AWG stranded cable, 12 feet long, including connectors. It shall be constructed in accordance with the model, and shall meet the requirements of 3.8.

3.4.5.2 Cable assembly, power, electrical, extension. - Cable assembly, power, electrical extension, used as an extension to the regular power cable, to permit remote operation of the mercury-vapor lamp, shall be 12 feet long. It shall be constructed in accordance with the model and shall meet the requirements of 3.8.

3.4.5.3 Cable assembly, power, electrical. - Cable assembly, power, electrical, used to supply AC power to the short-wave unit, shall be a 2-conductor #18 AWG stranded cable, 6 feet long, including connectors. It shall be constructed in accordance with the model and shall meet the requirements of 3.8.

3.4.6 Filter, light (2280 to 4200). - Filter, light (2280 to 4200), shall be capable of absorbing some of the wavelengths of the three, fluorescent-type, mercury-vapor, germicidal lamps in the short-wave unit to provide ultraviolet light in the middle and for ultraviolet regions. This filter shall be Sirchie Finger-Print Laboratories #399, or equal.

3.4.6.1 Filter, light (3130 to 4050 Angstrom Units). - Filter, light (3130 to 4050), is used as a photographic filter for the mercury-vapor lamp and shall be Corning Glass #5876A,

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

or equal.

3.4.6.2 Filter, Light (3100 to 4800 Angstrom Units). - Filter, light (3100 to 4800) is used as a wide transmission filter for the mercury-vapor lamp and shall be Corning Glass #5873A, or equal.

3.4.7 Overall Performance. - The equipment shall meet the operational tests of 4.13.

3.5 Light Assemblies, Electric MX-1291( )/PAQ and MX-1292( )/PAQ. - The following requirements are applicable to both Light Assemblies.

3.6 Finish. - The equipment shall be finished in accordance with Specification MIL-F-14072 and the equipment drawings or Specification MIL-F-14072 and the model, as applicable.

3.7 Marking. - Marking shall conform to Specification MIL-M-13231.

3.7.1 Serial numbers. - The following articles shall be serial numbered:

(a) Light Assembly, Electric MX-1291( )/PAQ

(b) Light Assembly, Electric MX-1292( )/PAQ

3.8 Cable and Cord Assemblies. - Cable and Cord Assemblies shall be assembled in accordance with Specification MIL-C-3885.

3.9 Interchangeability. - Like units, assemblies, subassemblies, and replaceable parts shall be physically and functionally interchangeable, without modification of such items or of the equipment. (See 4.7). Individual items shall not be hand-picked for fit or performance.

3.10 Service conditions. - The equipment shall meet the following service conditions. Where a test is referenced, meeting the test requirements shall be considered as compliance with the condition specified.

3.10.1 Operation. - Continuous use for a period of 3 years, under the worldwide environmental conditions specified in 3.10.2 and 3.10.3 with a duty cycle of one hour on and one hour off and with no more than normal maintenance and replacement of parts. Where the contractor is required to make a selection of parts, materials, processes, construction methods, etc., he shall be guided by this requirement. Approval of the preproduction sample (See 3.2) shall be considered as compliance with this requirement.

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

3.10.2 Temperature (See 4.9). -

(a) Operating: Ambient temperature in the range of +150°F to -65°F. (The 150°F temperature includes effect on sun-load.) Exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 72 hours, at any one time.

(b) Nonoperating: Exposure in the range of +160°F to -80°F; exposure at the high temperature extreme not to exceed 4 hours, and at the low temperature extreme not to exceed 24 hours, at any one time.

3.10.3 Relative humidity (See 4.8). - Up to 97 percent relative humidity for 20 hours; and exposure at 100 percent relative humidity, with condensation, for 4 hours.

3.11 Preconditioning. - The equipment shall be capable of meeting the requirements herein, without subsequent processing, after subjection to the bounce preconditioning of 4.6. (Also see 4.5).

3.12 Workmanship. - The equipment shall be manufactured and assembled in accordance with the applicable portions of the following paragraphs:

In Specification MIL-P-11268:

General requirements for plastic material and plastic parts.

Wiring and cabling, including:
- Slack.
- Protection.
- Clearance.
- Splicing.
- Connections, general.
- Grounding, general.
- Shielding on wire and cable.

Flux and cleaning agents for soldering.

Process for soldering

Cleaning.

Riveting.

General requirements for securing of parts.

Cleaning of welding.

Process for welding.

Mechanical operation of controls.

Self-tapping screws.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspection. - Inspection shall be classified as follows:

(a) Preproduction inspection (does not include preparation for delivery). (See 4.3).

(b) Inspection covered by subsidiary documents. (See 4.4).

(c) Quality conformance inspection.

(1) Quality conformance inspection of equipment before preparation for delivery. (See 4.5).

(2) Quality conformance inspection of preparation for delivery. (See 4.14)

4.3 Preproduction inspection. - This inspection will be performed by the Government unless otherwise specified in the contract. It shall consist of the preproduction inspection specified in Table I, the inspection specified in the subsidiary documents covering the items listed in 4.4, and the inspection specified for group A and group B (See Table II and 4.5.2).

Table I - Preproduction Inspection

Inspection (For Additional preproduction inspection see 4.3)	Rqt. Par.	Insp Par.
Temperature	3.10.2	4.9
Moisture resistance	3.10.3	4.8

4.4 Inspection covered by subsidiary documents. - The following shall be inspected under the applicable subsidiary documents as part of the inspection of equipment before preparation for delivery:

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

Item	Where required
Cable Assy.	3.8
Finish	3.6
Marking	3.7

4.5 Quality conformance inspection of equipment before preparation for delivery. - The contractor shall perform the inspection specified in 4.4, 4.5.1, 4.5.2 and 4.5.3. This does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition the Government--at its discretion--may perform all or any part of the specified inspection, to verify the contractor's compliance with specified requirements. (See 6.4). Test equipment for Government verification inspection shall be made available by the contractor. Each unit which will be subjected to group A inspection, except preproduction samples, shall be preconditioned after final assembly. (See 3.11).

4.5.1 Group A inspection. - This inspection including sampling, shall conform to Table II and the inspection procedures of Standard MIL-STD-105, using the general inspection levels. Group A inspection shall be performed in any order which is satisfactory to the Government.

Table II - Group A Inspection

Inspection	Rqt. Par.	Test Par.	AQL Major	AQL Minor
Visual and mechanical	3.12	4.11	1%	4%
Filter, light	3.3.2	4.12.1	1%	4%
Overall Performance				
MX-1291( )/PAQ	3.3.3	4.12	1% *	
MX-1292( )/PAQ	3.4.7	4.13	1% *	

* All electrical defects are in major category.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

4.5.2 Group B inspection. - This inspection, including sampling, shall conform to 3.9 and to the procedures for small-sample inspection of Standard MIL-STD-105. The AQL shall be 4 percent defective and the inspection level shall be S-4 for normal, tightened and reduced inspection. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection.

4.5.3 Reinspection of Conforming Group B Sample Units. - Unless otherwise specified, sample units which have been subjected to and passed group B inspection may be accepted on the contract or order provided all damage is repaired and the sample units are resubjected to and pass group A inspection.

4.6 Bounce preconditioning. - The unit, with shock mounts (if any) removed or blocked, shall be placed in its normal operation position on the table of the Package Tester, Type 1000-SC, as made by the L.A.B. Corporation, Skaneateles, New York, or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a 1/32-inch-thick strip of material under one corner or edge of the unit to a distance of 3 inches as the unit bounces. The unit shall be subjected to this preconditioning for 5 minutes. After bounce preconditioning, the unit shall not be repaired, alined, cleaned, or otherwise changed prior to subjection to acceptance inspection. (See 3.11).

4.7 Inspection for dimensional interchangeability. - The dimensions listed below shall be gaged or measured to determine conformance to the physical interchangeability requirement of 3.9. When a listed dimension is not within specified or design limits, it shall be considered a major defect.

(a) External and internal dimensions of cases, covers, and insertable assemblies, when such dimensions affect mating of parts.

(b) Dimensions of cavities, when such dimensions affect insertion of items.

(c) Location of hinges and fasteners on separable parts or assemblies which must mate, such as cases, covers, and mountings.

(d) Location of connectors, locking pins, fasteners, slides, and mountings which receive mating parts of plug-in assemblies and major units; and location of the mating parts on the plug-in assembly or major unit.

4.8 Moisture-resistance test. - The equipment shall be tested as follows: (The filter glass shall not be subjected to the moisture-resistance test.)

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the currentversion before use.

4.8.1 Test conditions. -

(a) Do not move equipment from the humidity chamber for measurements.

(b) Start measurements not more than 5 minutes after power is applied to the equipment. Complete measurements as rapidly as possible. Do not leave power on after measurements have been completed.

4.8.2 Test method. -

(a) Dry at 130° +5°F for 24 hours.

(b) Condition at 77° ± 5°F and 40 to 50 percent relative humidity for 24 hours.

(c) Take measurements as specified in 4.8.3, and readjust or realine as necessary to meet full specification requirements.

(d) Subject to continuous cycling for five 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Standard MIL-STD-170. The measurements specified in 4.8.3 shall be made during the periods shown on the standard and shall comply with 4.8.3.

(e) After cycling has been completed, condition the equipment for 24 hours at 77° +5°F and 40 to 60 percent relative humidity. Then adjust for optimum performance, using only those means provided by the equipment. Repair or replacement of parts shall not be made. After adjustment, the equipment shall meet full specified performance for those measurements specified in 4.8.3.

NOTE: The battery shall not be in the equipment during this test, except when measurements are being made.

4.8.3 Performance. - Measurements made during test, and specified performance during cycling shall be as follows:

	Paragraph	
	Rqt.	Performance
MX-1291( )/PAQ	3.3.3	4.12
MX-1292( )/PAQ	3.4.7	4.13

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

4.9 Temperature test. - The equipment shall be subjected to the temperature cycle shown on STANDARD MIL-STD-169, except that the maximum exposure for Step 2 (+ 160 F) and Step 6 (- 80°F) shall be 4 and 24 hours, respectively. Measurements shall be taken as follows: (The filter glass shall not be subjected to the temperature test).

	Step	Paragraph Rqt.	Performance
MX-1291( )/PAQ	1, 3, 7, 10	3.3.3	4.12
MX-1292( )/PAQ	1, 3, 7, 10	3.4.7	4.13

NOTE: The battery shall not be in the equipment during this test, except when measurements are being made.

4.9.1 Failure. - If any component fails 4.8.3 or 4.9 during cycling, it does not pass the test.

4.10 Cable and cord assemblies. - The equipment shall conform to 3.8.

4.11 Visual and mechanical inspection. - Parts and equipment shall be examined for defects listed in Standard MIL-STD-252.

4.12 Operations, MX-1291( )/PAQ. - Light Assembly, Electric MX-1291( )/PAQ shall be tested for normal operation as follows:

(a) Connect the power cable to a 110 to 120 volt, a-c power sources and to the receptacle on the control panel. Throw the power switch to the AC ON position, and check each of the lamps for satisfactory operation by turning on the associated switch for each lamp.

NOTE: After one lamp has been turned on, the power switch must be thrown to the OFF position and then back to the AC ON position before the other lamp is energized.

(b) Disconnect the equipment from the a-c power source, and connect it to a battery power source. Then check the lamps again as in (a) above.

(c) Repeat (a) and (b) at least four consecutive times to determine operational capability. If the respective lamps fail to operate during this test the equipment fails the test.

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

4.12.1 Filter, light, ultraviolet (2200 to 4400 Angstrom Units). - The percent transmission of the filter shall be measured with a spectrophotometer or equivalent and it shall conform to 3.3.2.

4.13 Operation, MX-1292( )/PAQ. - The Light Assembly, Electric MX-1292( )/PAQ shall be tested for normal operation as follows:

(a) Connect the power cable to a 110- to 120- volt, a-c power source and to the control panel receptacle marked 110 V. POWER INPUT.

(b) Plug the 3-foot power cord of the extension light into the control panel receptacle marked 245 V FOR MV LAMP. Check the lamp for satisfactory operation by throwing its associated switch marked 245 V FOR MV LAMP to the ON position. Operate lamp for 1 minute then turn switch to OFF position.

(c) Install the blacklight lamp in the adapter and plug into the control panel receptacle marked 110 V FOR 250-W LAMP. Check the lamp for satisfactory operation by throwing its associated switch marked 110 V FOR 250-W LAMP to the ON position, Operate lamp for 1 minute then turn switch to OFF position.

CAUTION: The emergency black light lamp reaches a high temperature within a very short time. The operator must avoid contact with the lamp or severe burns may result. The lamp is designed for intermittent operation; the burning period should not exceed 5 minutes and the cooling period should be twice the duration of the burning period.

(d) Repeat (b) and (c) at least four consecutive times to determine operational capability. If the respective lamps fail to operate during this test the equipment fails the test.

4.14 Quality conformance inspection of preparation for delivery. - Preparation for delivery shall be inspected in accordance with Specification MIL-P-116 to determine conformance to the requirements of Section 5.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. - Preservation and packaging shall be level A or C as specified in the contract or order (See 6.1).

5.1.1 Level A. -

5.1.1.1 Cleaning. - Components for Light Assemblies, Electric MX-2191( )/PAQ

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

and MX-1292( )/PAQ shall be cleaned in accordance with process C-1 of MIL-P-116.

5.1.1.2 Unit packaging. - Unit protection shall be as specified herein.

5.1.1.2.1 Light Assembly, Electric MX-1291( )/PAQ. - Each Light Assembly, Electric MX-1291( )/PAQ shall be packaged in accordance with item 1 through 4 of Table III.

5.1.1.2.2 Light Assembly, Electric MX-1292( )/PAQ. - Each Light Assembly, Electric MX-1292( )/PAQ shall be packaged in accordance with item 8 through 12 of Tables IV and IVA.

5.1.2 Level C. - Each Light Assembly, Electric MX-1291( )/PAQ and Light Assembly, Electric MX-1292( )/PAQ shall be preserved and packaged in a manner which will afford adequate protection against corrosion, deterioration, and damage during shipment from the supply source to the first receiving activity. The supplier's commercial practice will be acceptable when it fulfills the above requirements.

5.2 Packing. - Packing shall be level A, B, or C as specified in the contract or order (See 6.1).

5.2.1 Levels A and B. -

5.2.1.1 Six each Light Assembly, Electric MX-1291( )/PAQ, preserved and packaged as specified in 5.1 shall be packed in accordance with Items 5, 6, and 7 of Table III. Containers shall be closed in accordance with the appendix of the box specification.

5.2.1.2 One each Light Assembly, Electric MX-1292( )/PAQ, preserved and packaged as specified in 5.1, shall serve as the exterior container. Container shall be reinforced in accordance with Item 13 of Table IVA.

5.2.2 Level C. - Light Assembly, Electric MX-1291( )/PAQ and Light Assembly, Electric MX-1292( )/PAQ, preserved and packaged as specified in 5.1 shall be packed in a manner which will afford protection against damage during shipment within the Continental United States from the supply source to the first receiving activity at the lowest applicable rate for safe delivery.

5.3 Marking. - In addition to any special marking required by the contract or order, interior packages and exterior shipping containers shall be marked in accordance with S Standard MIL-STD-129.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

BILL OF MATERIAL
TABLE III
Box 1 of 1

REF No.	ITEM Nomenclature	No. Reqd.	Method MIL-P-116	SIZE - INCHES L	W	D	Spec No.	REQUIREMENT T	C	V	G	F	S
1	Technical Manual	2	IC-6										
	Bag	2		7-1/2	9-1/2		MIL-B-117	II	D				
2	Light Assembly Electrical MX-1291()/PAQ	1	IC-5	11-11/16	6-7/8	5-1/8							
	Install: Operating Lamp, fluorescent; Spare Lamp, fluorescent; Operating Lamp, mercury vapor; Operating Filter, Light and Screwdriver in designated location, no packaging required.												
	Lamp, Mercury Vapor	1	III										
	Cushion	1		5	7		PPP-P-291	III					2
	Box, paperboard	1		2	1-1/4	5-3/4	PPP-B-566	A	a	1			III
	Filter, Light	1	III										
	Cushion	1		8	5	1/8	PPP-C-843	II	B				
	Box, paperboard	1		1-3/4	7/16	6-1/8	PPP-B-566	A	a	1			III
	Cable Assembly	1	III										
	Twine	1		10	6 ply		T-T-871	1					
	Place the above packaged items in area provided in unit.												
3	Liner	1		12	7-1/8	5-1/8	PPP-F-320	CF	WR	SW	6	C	
4	Box, Fiberboard	1		12-1/8	7-1/4	5-1/4	PPP-B-636	CF	WR	SW	W6c		RSC
	Tape, P.S.	2		18	2		PPP-T-76						
		4		13-1/4	2								
		1		5-1/4	2								
5	Light Assembly Electrical MX-1291()/PAQ												
	Pkg item 4	6											
6	Box, Fiberboard	1		17-1/4	14-3/4	12-1/4	PPP-B-636	CF	WR	SW	V3c		RSC
7	Tape, Filament	2		60	1/2		PPP-T-97	IV					

Lev. A - PACKED WEIGHT - 60 lbs
Lev. A - PACKED VOLUME - 1.97 Cu. ft.

T-Type V - Variety F-Flute
C-Class G - Grade S-Style

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

BILL OF MATERIAL
Table IV
Box 1 of 1

REF No.	ITEM Nomenclature	No. Reqd	Method MIL-P-116	SIZE - INCHES L	W	D	REQUIREMENT Spec No.	T	C	V	G	F	S
8	Technical Manual	2	IC-6										
	Bag	2		7-1/2	9-1/2		MIL-B-117	II	D				
9	Light Assembly, Electrical MX-1292()/PAQ	1	IC-5	19-3/4	9-7/8	11-1/4							
	Prepackaging: Short Wave Unit												
	Cushion	1		11	5	1/4	PPP-C-843	II	B				
	(Place under operating lamps.)												
	Cushion	1		12	8	1/4	PPP-C-843	II	B				
	Place on top of (installed) operating and spare lamps. Close the hinged cover and secure with screws provided.												
	Prepackaging: Long Wave Unit												
	Assembly operating filters and mounting rings on operating and spare mercury vapor lamps. Install one assembly within the lamp assembly hood. Place lamp assembly, lamp base, and screwdriver in place within the compartment. Assemble one (1) spare filter and mounting ring on the spare mercury vapor lamp.												
	Cushion	1		12	12	1/4	PPP-C-843	II	B				
	Box, paperboard	1		5-1/4	5-1/4	6-1/2	PPP-B-566	A	a	1			III
	Cable Assembly	3		(Fold and Tie)									
	Twine	3		10	6 ply		T-T-871	I					
	Goggles	2	III										
	Box, paperboard	2		5-7/8	2-7/8	1-1/2	PPP-B-566	A	a	1			II
	Adapter, Lamp Holder	1	III										
	Box, paperboard	1		1-3/4	1-3/4	2-1/4	PPP-B-566	A	a	1			II

Lev. A - PACKED WEIGHT
Lev. A - PACKED VOLUME

T - Type V - Variety F - Flute
C - Class G - Grade S - Style

Source: https://assist.dla.mil -- Downloaded: 202640-17T15:54Z
Check the source to verify that this is the current version before use.

BILL OF MATERIAL
TABLE IVA
Box 1 of 1

REF No.	ITEM Nomenclature	No. Reqd	Method MIL-P-116	SIZE - INCHES L	W	D	Spec No.	T	C	V	G	F	S
	Lamp, Incandescent	2	III										
	Cushion	2		8	11		PPP-P-291	III					2
	Box paperboard	2		3	3	5-3/8	PPP-B-566	A	a	1			II
	Filter 5" Dia.	2											
	Cushion	2		15	5-1/2	1/4	PPP-C-843	II	B				
	Box, paperboard	2		5-1/4	1-1/4	5-1/4	PPP-B-566	A	a	1			II
	Filter	1											
	Cushion	1		8	11	1/4	PPP-C-843	II	B				
	Box, paperboard	1		3-1/2	7/8	6-3/4	PPP-B-566	A	a	1			II
	Place the above items in space provided in the Long Wave Unit. Secure the Short Wave Unit to the Long Wave Unit.												
10	Pads, corner	4		10-3/4	6-1/2	3-1/4	PPP-F-320	CF	WR	SW	5	C	
11	Cell, top	1		20-3/4	9-7/8	1-1/8	PPP-F-320	CF	WR	SW	5	C	
12	Box, fiberboard	1		20-3/4	10	12	PPP-B-636	CF	WR	SW	V3c		RSC
	Tape, P.S.	2		27	3		PPP-T-76						
		4		16	3								
		1		12	3								
13	Tape, filament	2		54	1/2		PPP-T-97	IV					

Lev. A - PACKED WEIGHT - 56 lbs
Lev. A - PACKED Volume - 1.51 Cu. ft.

T - Type
C - Class
V - Variety
G - Grade
F - Flute
S - Style

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Ordering data. - Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.

(b) Level of preservation, packaging, packing and marking required. (See Section 5).

(c) The specific paragraphs of Section 5 which are applicable to the particular procurement.

(d) Two each preproduction samples required. (See 3.2).

(e) Marking and shipping of samples.

(f) Place of final inspection.

6.2 Definition of Level B. - Level B packaging requirements detailed herein are designed to furnish protection against corrosion, deterioration, and physical damage during domestic shipments; covered storage for a period of three years or less; and distribution within the continental limits of the United States.

6.3 Nomenclature. - The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design; for example: AN/PIQ-1W. The contractor should apply for nomenclature in accordance with the applicable clause in the contract. (See 1.1.).

6.4 Verification inspection. - Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of verification inspection by the Government will be adjusted to make maximum utilization of the contractor's quality control system and the quality history of the product.

Custodian

Army - EL

Preparing Activity

Army - EL

Project Number 6695-A006

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the currentversion before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION | CITY AND STATE

CONTRACT NO. | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)* | DATE

DD FORM 1 OCT 64 1426

ESC-FM 2011-66

Source: https://assist.dla.mil -- Downloaded: 202610-17T15:54Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
HEADQUARTERS
U.S.ARMY ELECTRONICS COMMAND
FORT MONMOUTH, NEW JERSEY 07703

OFFICIAL BUSINESS

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

Commanding General
U. S. Army Electronics Command
ATTN: AMSEL-PP-
Fort Monmouth, New Jersey 07703

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T15:54Z
Check the source to verify that this is the current version before use.