MILITARY SPECIFICATION

INVERTERS, AIRCRAFT, GENERAL SPECIFICATION FOR

This amendment forms a part of Military Specification MIL-I-7032F of 4 April 1966 and is approved for use by all Departments and Agencies of the Department of Defense.

Page 7

3.5.8 *Starting Contactor.* Change "is used" to read "if used".

Page 8

Figure 2. Change "Zero time is the instant at which both the input terminals are energized simultaneously," to read "Zero time is the instant the input terminals are energized".

Page 14

Add the following new paragraph:

4.3.5 Qualification verification of inverters. Each inverter of the same part number (as listed on the QPL) delivered as a qualified item under this specification shall be numbered sequentially in essentially the order that they are submitted for government acceptance regardless of the contract under which delivery, or the purchasing agency. To meet the delivery requirements for the first 50 components, 51 components must successfully complete the required acceptance tests; 50 of which are to be shipped as directed by the applicable contracts; and one inverter selected at random by the Government Inspector, is to be forwarded to the Naval Air Test Center (WST-33) Patuxent River, Md. marked "For Work Unit NATC-8P7-101". To meet the delivery for each succeeding 150 inverters, 151 inverters must successfully complete the required acceptance tests, 150 of which are to be shipped as directed by the applicable contract, and one component selected and forwarded as above. The inverters forwarded to the Naval Air Test Center will be inspected and tested for conformance to the applicable detail specification or drawing.

FSC 6125

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T07:48Z
Check the source to verify that this is the current version before use.

Delivery of production components are not to be delayed pending results of any tests conducted on qualification verification samples. Once qualified, production inverters successfully passing the acceptance tests are to be accepted until qualification is officially rescinded, or until cognizant DCAS personnel are advised that a Qualification Verification Sample does not meet the requirements of this specification and the applicable MS drawing. All Qualification Verification Samples become Government property when accepted by the Government Inspector for shipment to the Naval Air Test Center.

Page 20

4.6.10.1 Output Voltage Modulation. In the third sentence, add "under" between "oscillations" and "any".

Page 27

4.6.19.2 (a) Resonance. Delete the 6th and 7th sentences and substitute the following:

"When more than one resonance is encountered with vibration applied along any one axis, each resonance shall be sustained for the period shown in the applicable portion of the vibration test schedule. If more than four resonances are encountered with vibration applied along any one axis, the four most severe resonances shall be chosen for test. Cycling time indicated in Table I shall include the time required to perform the resonant frequency survey."

Page 27

Delete Table I and substitute the following Table I:

VIBRATION TEST SCHEDULE

(Times shown refer to one axis of vibration)

Number of resonances	0	1	2	3	4
Total vibration time at resonance *	-	30 min	1 hr	1-1/2 hr	2 hr
Cycling time	3 hr	2-1/2 hr	2 hr	1-1/2 hr	1 hr

* 30 minutes at each resonance.

Page 30

4.6.23.1 Synthetic Sea Water Solution. In the first sentence, delete "as prescribed".

Source: https://assist.dla.mil -- Downloaded: 2026-10-17T07:48Z
Check the source to verify that this is the current version before use.