MIL-F-82098C
24 January 1983
SUPERSEDING
MIL-F-82098B
24 June 1976

MILITARY SPECIFICATION

FINISHING MACHINE, CONCRETE-PAVING, SLIP-FORM, FULL TRACKED

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a self-propelled, full tracked, slip-form, concrete-paving, finishing machine, hereinafter called machine, capable of spreading and consolidating concrete mixtures as low as 1-inch slump to form a concrete slab.

1.2 Classification. The machine shall be one of the following types, as specified (see 6.2).

Type I - 25-foot width of spread with guided self-steering and grade leveling controls.
Type II - Variable width of spread (12- to 24-feet), without guided self-steering and grade leveling controls.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards, and handbooks. Unless otherwise specified (see 6.2), the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

VV-F-800 - Fuel Oil, Diesel.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3895

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

MILITARY

MIL-V-173 - Varnish, Moisture-and-Fungus-Resistant (for Treatment of Communications, Electronic, and Associated Equipment).
MIL-T-704 - Treatment and Painting of Material.
MIL-T-3351 - Tractor, Full-Tracked, Low Speed; Tractor Wheeled, Agricultural; and Tractor Wheeled, Industrial: and Their Attachments, Packaging of.

STANDARD

MILITARY

MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.

(Copies of specifications, standards, handbooks, drawings, and publications required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting officer.)

2.2 Other publications. The following document(s) form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE, INC. (ANSI)

B15.1 - Mechanical Power, Transmission Apparatus.

(Application for copies should be addresssed to the American National Standards Institute, Inc., 1430 Broadway, New York, NY 10018.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

MG - 1 - Motors and Generators.

(Application for copies should be addressed to the National Electrical Manufacturers Association, 2101 L Street, N.W., Washington, DC 20037.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.3 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The machine shall be a self-contained and self-propelled unit, consisting essentially of crawler end tracks of the individually driven type, a spreading mechanism, a tamping or vibrating device and an extrusion pan or plate, a vibratory consolidation mechanism, a hydraulic system, a main control panel, a powerplant, and operator's platform all of which are to be mounted on a transverse steel frame for paving width of 25 feet on slip-forms for type I, and variable paving widths of 12- to 24-feet on slip-forms for type II. The machine shall be capable of being retracted or disassembled in sections for shipment and also reassembled, within 8 hours, ready for operation without using special tools or hoisting equipment requiring a capacity greater than 20 tons.

3.2 First article. When specified (see 6.2), the contractor shall furnish a complete machine for first article inspection and approval (see 4.2.1 and 6.4).

3.3 Standard commercial product. The machine shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the machine being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.

3.4 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.5 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.6 Ease of maintenance. Design of the machine shall permit ready accessibility to all parts for maintenance and repair by the use of conventional general-purpose handtools. Replacement and adjustment of component parts and accessories shall be accomplished with minimum drainage requirements and disturbance to other elements on the machine. Ease of maintenance provisions shall incorporate features insuring clearances between adjacent components to facilitate maintenance and servicing operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

3.7 Safety. All rotating or reciprocating parts and all parts subject to high operational temperatures, that are of such nature or are so located as to be or become a hazard to operating or attending personnel, shall be adequately guarded or insulated to the extent necessary to eliminate the hazard. Suitably located nonskid steel plate with nonslip tread or abrasive surfaces shall be furnished to provide access from either side of the machine to the operating position.

3.7.1 Noise hazard. If the steady state noise level in the area occupied by the operator is 85 decibels absolute or greater when measured in accordance with SAE J919, a caution plate shall be permanently affixed on the machine in a conspicuous protected location and shall be clearly visible and legible to all personnel exposed to the excessive noise levels. The plate(s) shall read "CAUTION HEARING PROTECTION REQUIRED" or "CAUTION HEARING PROTECTION REQUIRED WITHIN X FEET OF THIS MACHINE". The plate(s) shall have a yellow background with black lettering and be made of corrosion-resistant material.

3.8 Performance. The differences in performance between types I and II finishing machines are the width of paving capability and the crown. Type I machine shall pave a road slab 25 feet wide with a crown adjustable from zero to not less than a positive 3 inches. Type II machine shall pave a road slab 12 feet to 24 feet wide with a crown adjustable from a negative 1 inch to a positive 3 inches when paving at the 24 foot width. Both types shall be capable of spreading concrete mixtures of up to a 2-inch slump for from 6- to 12-inch thickness in 2-inch increments. Both types of machines shall have a minimum paving speed of not less than 2 feet per minute (fpm) and a maximum paving speed of not less than 45 fpm. Both types shall pave with slip-forms in place. The machines shall also have a capability of paving concrete road slabs at not less than 150 cubic yards of 1-inch slump concrete per hour for a period of not less than 8 consecutive hours, without breakdown. The machines shall have the capability of placing concrete road slabs against an existing slab, and between existing slabs of the same thickness. The machines shall be capable of forming a road surface finish not to exceed a variation of 1/8-inch tolerance per 10 feet. Consolidation of the concrete slab shall be accomplished by vibrating, tamping, or extruding mechanisms. The degree of road surface roughness shall be accomplished by the dragging of burlap cloths attached on the rear end of trailing trusses, by medium size metal pipes hung on the rear end of machine, by the scraping action of a floating pan located on the rear end of the machine, or by the slapping action of an oscillating rubber conveyor belt covering the full width of concrete slab.

3.9 Frame. The frame of the machine shall be of steel, constructed as a unit to support the various parts of the machine which must be held in alinement during operation or when an adjustment in width is made. The frame shall be furnished with an operator's platform made of steel with skidproof-type tread. The adjustment of the frame width shall be accomplished by attaching the end-tracks to the transverse frame members at the required widths. The end-tracks shall be fastened to the frame and be constructed as rigid units so as to hold the crawler tracks, drive, and other parts of the tracks in alinement at all times. The transverse frame members and end-tracks shall be so constructed as to prevent excessive deflection of these parts of the machine during operation. Lifting means shall be provided for raising and supporting the end frames in an elevated position for the purpose of changing or repairing the tracks.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

3.10 Steering and grade controls. A steering mechanism shall be provided to permit squaring the machine within the full range of grades and curves encountered in paving operations, including curves from a minimum radius of 300 feet. The steering mechanism shall be equipped with holding brakes which may be applied to stop or hold the machine when the power is disengaged. The type I machine shall have each end-track independently controlled by the steering arrangement, operated by electric, hydraulic, or direct power drive, guided by a sensing device upon a preset reference guide wire for automatic self-steering. The present reference guide wire shall also act as an automatic grade controller through the means of an automatic sensing control over the pneumatic, electric, or hydraulic grade leveling cylinders or hydraulic screw jacks. A 1,000 foot reference guide system, including wire and stakes, shall be provided.

3.11 Spreading mechanism. Means shall be provided to spread and distribute the concrete over the full width of the slab. The spreading mechanism may incorporate vertical adjustment to form a crown. End wings shall be supplied to contain the concrete within the area to be paved. Adapters or additional end wings shall be provided to allow paving next to an existing concrete slab.

3.12 Hydraulic system. The hydraulic system shall include a hydraulic pump with suitable drive, a tank and valve unit equipped with a pressure relief valve, valve control, pressure gage, suction, and pressure lines with fittings and connections, rams, cylinders, and brackets for mounting the various parts. The system shall be furnished with full flow filter(s) having a micron rating not greater than 10. The hydraulic system shall be so arranged that the valve control levers will be located conveniently for the operator or shall be controlled by an electrically energized operating valve. Hydraulic hose and tubing lines shall be located within the protective area of frame members whenever possible. Unprotected hose and tubing lines shall be attached to the rigid frame by clips spaced not more than 36 inches apart.

3.13 Vibrator attachment. Unless otherwise specified (see 6.2), the vibrator attachment shall be either of the tubular, submerged spud, or pan type. The vibrator shall be driven by the engine, or by separate mechanical, electric, or pneumatic power with sufficient capacity for the consolidation of low slump concrete mixes. When equipped with pan type vibrator, means shall be provided for rapid adjustment for the crown of the pavement.

3.14 Powerplant. The machine shall be furnished with a complete, self-contained, powerplant of sufficient capacity to enable performance of all requirements specified herein.

3.14.1 Engine. The machine shall be furnished with a multicylinder diesel engine of the two or four-stroke cycle type. The power and speed required to operate the machine shall not exceed the continuous horsepower rating of the engine at the applicable speed. The engine shall be capable of operation on diesel fuel conforming to VV-F-800. The engine shall be the manufacturer's standard commercial engine normally furnished to the commercial market, and shall be furnished complete with at least the following commercial accessories:

a. An electric starting system shall be provided. Electric system shall be not less than 12-volt potential and shall be complete with battery(s), shipped dry charged, without a filling of electrolyte, and a generator-regulator or alternator-rectifier battery charging system.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

b. A fuel tank with sufficient capacity for not less than 8 hours normal operation and a fuel level indicator.
c. An instrument panel, located so as to be readily seen by the operator, containing manufacturer's standard instruments, including, but not limited to, a lubricating oil pressure indicator, a battery charging indicator, and a coolant temperature indicator.
d. An engine housing.
e. An hour meter with a totalizing mechanism of not less than 9,999 hours.
f. Panel instruments shall have night lighting provisions.

3.14.2 Generator and motors. Electrically powered machine shall be furnished with a diesel-engine-driven generator of sufficient capacity to perform all electrical functions. A separate engine-driven generator may be used for supplying power to the vibrator. The generator and electrical motors shall conform to NEMA MG-1.

3.14.3 Main control panel cabinet. A weather- and dust-proof main control panel cabinet, located on the operating platform, shall be provided. The control panel shall be provided with pushbutton, dial, knob, or lever controls, plainly marked to identify function and use for the centralized control of all operations performed by the machine. The control panel shall be formed of sheet metal and shall be so located on the operating platform to allow unobstructed view of the operating area. The control panel shall be provided with lights. The lights shall be of sufficient size and quantity to illuminate all controls on the panel. When specified (see 6.2), night work lighting shall be provided.

3.14.4 Power transmission. Transmission of power shall be accomplished by mechanical, electrical, pneumatic, or hydraulic means. The operation of the spreading mechanism shall be independent of the traction. When a mechanical transmission is furnished, it shall be of the selective gear type, with not less than two traction speeds in both forward and reverse. The transmission shall be fully enclosed, with gears running in oil, and all shafts mounted on antifriction bearings. All operating levers shall be grouped on or near the main control panel cabinet on the operating platform within easy reach of the operator, and lever positions shall be plainly marked.

3.15 Crawler tracks. The machine shall be provided with crawler tracks. The crawler tracks shall withstand the loads imposed by operation of the machine. Crawler treads shall run on steel rollers and shall have provision for adjusting the tension of the treads.

3.16 Slip-forms. Slip-forms shall be provided to form the edges of the pavement slab. Forms shall be of sufficient length, in relation to the paving speed, that the concrete will remain stable and rigid at the edges by the time the forms have passed. Means shall be provided to maintain alinement and rigidity of the slip-forms. Slip-forms furnished shall allow placing of concrete slabs with the thicknesses specified herein. Means shall be provided to allow placing of concrete slabs with straight sidewalls and sidewalls having a horizontal trapazoidal keyway, 1-inch deep, 2 inches wide at the bottom, and 3 inches wide at the surface of the sidewall. Means shall be provided to insert tie rods at the centerline of the slab at preset intervals.

3.17 Subgrader. When specified (see 6.2), the type I machine shall be furnished with a subgrader attachment capable of fine grading the subbase and

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

removing the excess material from the 25-foot width to be paved. The subgrader attachment shall be controlled by the preset guide wire specified in 3.10. Variation of the subgrader shall not exceed 1/3 inch in 10 feet.

3.18 Electromagnetic interference characteristics. When specified (see 6.2), the equipment shall conform to the electromagnetic characteristic requirements and test limits of SAE J551.

3.19 Fungus resistance. When specified (see 6.2), electrical components and circuit elements, including terminal and circuit connections, shall be coated with varnish conforming to MIL-V-173, except that:

a. Components and elements inherently inert to fungi or in hermetically sealed enclosures need not be coated.
b. Current-carrying contact surfaces, such as relay contact points, shall not be coated.

3.20 Drives.

3.20.1 V-belt drives. V-belt drives shall be in accordance with ANSI B15.1, and shall have provisions for adjustment.

3.20.2 Chain drives. Chain drives shall be installed with adequate idlers and shall have provisions for adjustment. A mechanical means of lubrication shall be provided for lubricating chains traveling over 350 linear fpm.

3.21 Lifting and tiedown attachments. When specified (see 6.2), the component units of the machine shall be equipped with lifting and tiedown attachments. Lifting and tiedown attachments shall conform to MIL-STD-209, type III. Attachments shall be indicated by a transportation plate. Tying down attachments may be identified by stenciling or other suitable marking on the component units. Tying down marking shall clearly indicate that the attachments are intended for tying down of the component units on the carrier when shipped.

3.22 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. The color of the finish coat shall be as specified (see 6.2). Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. When specified (see 6.2), cleaning, treatment, and painting shall be in accordance with MIL-T-704, type A.

3.23 Data plates.

3.23.1 Instruction plates. The machine shall be equipped with instruction plates suitably located, describing any special or important procedures to be

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

followed in operating and servicing the equipment. Plates shall be of a material which will last and remain legible for the life of the equipment, and shall be securely affixed thereto with nonferrous screws or bolts of not less than 1/8-inch diameter.

3.23.2 Identification plate. An identification plate will be furnished by the contracting officer for each machine. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose, and securely affix a plate to each machine in a conspicuous place with brass screws or bolts not less than 1/8 inch in diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

3.24 Special maintenance tools. Such special tools as are required for field maintenance and operation of the equipment shall be packed in the toolbox and shipped with the equipment. Special tools are defined as those not normally included in mechanic's tool kit, but which are designed specifically for a certain purpose on a specific piece of equipment. Means shall be provided to carry those tools and accessories required to operate the unit. Toolboxes, when furnished to hold tools and accessories, shall be made of sheet steel 0.0747-inch (US revised standard gage No. 14) nominal thickness.

3.25 Lubrication. Means for lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. All parts requiring lubrication shall be lubricated as specified in section 5. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 pounds per square inch or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

3.26 Workmanship.

3.26.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.26.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.26.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.26.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.26.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one machine when a first article is required (see 3.2 and 6.2). This inspection shall include the examination of 4.3, the tests of 4.4, and, when specified, the preproduction pack inspection of 4.7 (see 4.7 and 6.2). The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.5, and the packaging inspection of 4.7.

4.3 Examination. Each machine shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

4.4 First article tests. The first article shall be subjected to the tests specified in 4.4.1 through 4.4.5 and, when specified, to the tests in 4.4.6, 4.4.7, and 4.6. Failure to pass any phase of the required tests shall be cause for the Government to refuse acceptance of all machines until corrective action has been taken.

4.4.1 Assembly and operation. The machine shall be completely assembled, serviced, and otherwise prepared for operation on slip-forms spaced for laying the width specified herein. All routine maintenance services shall be performed. All operating components shall be operated. Improper fit of any parts or components, inability of components to respond to controls, or any other evidence of malfunction shall constitute failure.

4.4.1.1 Noise hazard test. With the machine in the operating mode, the noise level shall be measured in accordance with SAE J919 to determine conformance to 3.7.1.

4.4.2 Width and crown adjustments. The type II machine shall be assembled for operation at the 12-foot width and again to the maximum width. After each width change, all operating parts and controls shall be operated to assure that the machine will operate at all widths, and with the capability for crowning adjustment specified herein. Inability of the machine to be adjusted or to operate at all widths and crowns shall constitute failure.

4.4.3 Steering and grade test. The type I machine shall be assembled to operate with the slip-forms at the 25-foot width. The machine shall be operated with a preset guide wire to demonstrate the adequacy of the steering mechanisms, the ability of the machine to negotiate curves having a radius of 300 feet, and be capable of maintaining the intended grade level of paving. Inability of the steering mechanism to function, or of the machine to negotiate the curves shall constitute failure.

4.4.4 Travel and spreading tests. The machine shall be adjusted to operate on slip-forms at the width specified herein with each of the crown adjustment set for trial to determine conformance to 3.8. The machine shall be operated forward and reverse at the maximum travel speed specified in 3.8. The spreading mechanism shall also be operated at the minimum, intermediate, and maximum speeds. Nonconformance to the requirement of 3.8 shall constitute failure of this test.

4.4.5 Existing slab test. The machine shall demonstrate ability to pave against an existing slab and between existing slabs as specified in 3.8.

4.4.6 Measurement of electromagnetic radiation. When electromagnetic radiation suppression is required, to determine conformance to 3.18, electromagnetic radiation shall be measured in accordance with SAE J551. When suppressed to conform to 3.18, the manufacturer may furnish a certification in lieu of the test that the finishing machine meets the requirements, together with a list of the suppression devices installed. The list shall be sufficiently detailed to allow visual determination that the devices are installed.

4.4.7 Subgrader test. When furnished, the subgrader attachment shall be installed and tested to determine conformance to 3.17.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

4.4.8 Production sample. Upon acceptance of the first article, the first article shall remain at the manufacturing facility as a production sample, and shall be the last machine delivered on the contract. The first article shall be reconditioned, including replacement of abnormally worn parts and paint touch-up or repainting, prior to delivery to enable it to be accepted as a contract item. The contractor shall maintain the first article in a serviceable condition for the duration of the contract.

4.5 Production unit tests. Each machine shall be completely assembled, serviced, and operationally tested, under no-load conditions, to verify that all paving controls, travel controls, and hydraulic and electric controls are functioning effectively and responsively.

4.6 Lifting and tying down attachment test. When furnished, lifting and tying down attachments shall be tested to determine conformance to 3.21. The manufacturer may furnish certified engineering calculations in lieu of a test to prove that the lifting and tying down attachments offered meets the requirements set forth in MIL-STD-209.

4.7 Packaging inspection. The inspection of the preservation, packing, and marking shall be in accordance with the requirements of section 4 of MIL-T-3351. The inspection shall consist of the quality conformance inspection; and, when specified (see 6.2), a preproduction pack shall be furnished for examination and test within the time frame required (see 6.2).

5. PACKAGING

5.1 Preservation, packing, and marking. Preservation, packing, and marking shall be in accordance with the requirements of MIL-T-3351 with the level of preservation and the level of packing as specified (see 6.2).

6. NOTES

6.1 Intended use. This specification covers a full tracked, concrete-paving finishing machine for paving roads, airfield runways, and similar projects by using attached self-alined slip-forms to pave concrete slabs 12 to 24 or 25 feet in width in place of the conventional preset form method.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type of machine required (see 1.2).
c. Issue of document required if other than as specified (see 2.1.1).
d. When first article is required for inspection and approval (see 3.2, 4.2.1, and 6.4).
e. Type of vibrator attachments required, if different from that specified (see 3.13).
f. When night work lighting is required (see 3.14.3).
g. When subgrader attachment is required for type I (see 3.17).
h. When conformance to electromagnetic interference characteristics and test limits are required (see 3.18).
i. When fungus resistance is required (see 3.19).
j. When lifting and tying down attachments are required (see 3.21).
k. Color of finish coat (see 3.22).
l. When cleaning, treatment, and painting shall be in accordance with MIL-T-704 (see 3.22).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

m. When a preproduction pack inspection is required and time frame required for submission (see 4.7).
n. Level of preservation and level of packing required (see 5.1).

6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423, Contract Data Requirements List (CDRL) and invokes the provisions of paragraph 7-104.9(n) of the Defense Acquisition Regulations (DAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL (DD Form 1423) incorporated into the contract. When the provisions of DAR 7-104.9(n) are not invoked, the data shall be delivered in accordance with the contract requirements.

6.4 First article. When a first article inspection is required, the item will be tested and should be a first production item consisting of one complete machine unit or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.5 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodians:

Army - ME
Navy - YD

Review activity:

Army - AT

Preparing activity:

Navy - YD

Project No. 3895-0259

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

COMMANDING OFFICER (156)
NAVAL CONSTRUCTION BATTALION CENTER
PORT HUENEME, CA 93043

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. 3895-0259

DOCUMENT IDENTIFIER *(Number)* AND TITLE
MIL-F-82098C - FINISHING MACHINE, CONCRETE-PAVING, SLIP-FORM, FULL TRACKED

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1426 1 OCT 76

Replaces edition of 1 Jan 72 which may be used.

S/N 0102-LF-001-4260

☆ U.S. Government Printing Office: 1976—703-175/3081 2-1

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T06:41Z
Check the source to verify that this is the current version before use.