MILITARY SPECIFICATION

SUBMARINE PIPELINE SEAWARD END ASSEMBLY, SIX-INCH TACTICAL PIPELINE SYSTEM

This specification is approved for use by the USA Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the seaward end assembly of the 6-inch diameter tactical tanker off-loading system which facilitates launching and anchoring the seaward end of the pipeline.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-P-514	- Plates, Identification, Instruction and Marking, Blank.
MIL-F-3541	- Fittings, Lubrication.
MIL-G-3859	- Grease Guns, Hand-Operated, Lever, Push and Screw Type.
MIL-G-18709	- Grease, Ball and Roller Bearing.
MIL-B-26195	- Boxes, Wood-Cleated, Skidded, Load-Bearing Base.

FSC 3835

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRDME-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-130	- Identification Marking of US Military Property.
MIL-STD-209	- Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.
MIL-STD-1186	- Cushioning, Anchoring, Bracing, Blocking, and Waterproofing; with Appropriate Test Methods.
MIL-STD-1472	- Human Engineering Design Criteria for Military Systems, Equipment and Facilities.

DRAWINGS

ME

TA13221E4900	- Submarine Pipeline Seaward End Assembly, 6-Inch Tactical Pipeline System.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

AMERICAN PETROLEUM INSTITUTE (API)

Standard 1104 - Standard for Welding Pipelines and Related Facilities.

(Application for copies should be addressed to the American Petroleum Institute, 1801 K Street, N.W., Washington, DC 20006.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 47th Street, New York, NY 10017.)

AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 N.W. 7th Street, Miami, FL 33125.)

UNIFORM CLASSIFICATION COMMITTEE, AGENT

Uniform Freight Classification.

(Application for copies should be addressed to the Uniform Classification Committee, ATTN: Tariff Publishing Officer, Room 1106, 222 South Riverside Plaza, Chicago, IL 60606.)

NATIONAL MOTOR FREIGHT TRAFFIC ASSOCIATION, INC., AGENT

National Motor Freight Classification.

(Application for copies should be addressed to the American Trucking Associations, Inc., ATTN: Traffic Department, 1616 P Street, NW, Washington, DC 20036.)

3. REQUIREMENTS

3.1 Description. The 6-inch tactical pipeline system seaward end assembly (hereinafter called the PSEA) shall be in accordance with Top Assembly TA13221E4900 and as specified herein.

3.1.2 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the PSEA. Any data (e.g., shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or his designated representative.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

3.2 First article (preproduction model). The contractor shall furnish one or more PSEA(s) as specified (see 6.2), for examination and testing within the time frame specified to prove, prior to starting production, that his production methods will produce PSEAs that comply with the requirements of this specification. Examination and tests shall be as specified in Section 4; and, unless otherwise specified herein, all examinations and tests shall be conducted by the contractor subject to surveillance and approval by the Government. When specified, the Government will conduct any or all of the preproduction examination and tests, as specified by the contracting officer (see 6.2).

3.3 Initial production. When specified by the contracting officer (see 6.2), the contractor shall furnish to the Government one or more PSEAs for inspection as specified in 4.4.

3.4 Material. Material shall be as specified on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification (see 6.8).

3.5 Safety. Nonfunctional sharp edges, projecting points, and excessive length of fastening devices shall be avoided.

3.6 Human factors. The PSEA shall be in accordance with the applicable human factors engineering criteria as specified in MIL-STD-1472.

3.7 Maintainability. Accessibility for ease of maintenance shall be considered when the PSEA is fabricated and assembled. Where feasible, the PSEA shall utilize modules to accomplish repair by replacement.

3.7.1 Maintenance support. Assemblages or support elements such as technical manuals, repair parts, special tools, or lubrication charts, as specified in 6.7 and 6.8 shall be adequate to perform the intended function of assisting or conducting maintenance operations. Repair parts which are used to maintain the test item shall be interchangeable with like parts being replaced.

3.8 Detailing of technical requirements.

3.8.1 Parts and components. Parts and components of the PSEA shall be in accordance with the drawings and specifications specified by TA13221E4900.

3.8.2 Fasteners. Screws and nuts shall be of corrosion-resistant steel and shall have National course threads unless otherwise specified. Torque values shall be in accordance with those given in the Appendix.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

3.9 Lubrication.

3.9.1 Lubricants. The PSEA shall be lubricated with grease in accordance with MIL-G-18709.

3.9.2 Lubrication fittings. Lubrication fittings shall be in accordance with MIL-F-3541, Types I, II, or III. Fittings shall be located in a protected position and shall be accessible to a hand-operated grease gun conforming to MIL-G-3859 with a 10-inch flexible extension. Accessibility to fittings shall be provided without the removal or adjustment of accessories or parts.

3.10 Slinging provisions. Permanently affixed slinging provisions that enable the PSEA to be lifted in its normal travel position shall be provided and shall be in accordance with MIL-STD-209. Slinging provisions may also be used as tiedowns when such provisions conform to MIL-STD-209.

3.11 Tiedown provisions. Permanently affixed tiedown provisions that permit fastening the PSEA to the floor or deck of a transportation medium shall be provided and shall be in accordance with MIL-STD-209. Tiedown provisions may also be used as slinging provisions when such provisions conform to MIL-STD-209.

3.12 Identification marking. The PSEA shall be identified in accordance with MIL-STD-130. The marking shall be applied to the PSEA on plates conforming to MIL-P-514, Type III, Composition C, (GG-P-455, Type I, Grade A, Class 1) material, or as specified on the appropriate drawing. The plates shall be attached by screws, bolts, or rivets in a location where the plate shall be both visible and legible.

3.13 Shipping data plate. A shipping data plate in accordance with MIL-P-514, Type III, Composition C, (GG-P-455, Type I, Grade A, Class 1) material shall be provided. In addition, the plate shall show the silhouette of the PSEA in transport position indicating the center of gravity and the location and capacity of the slinging and tiedown provisions. The plates shall be attached by screws, bolts, or rivets in a location where the plate shall be both visible and legible.

3.14 Instruction plates. When specified, each PSEA shall be equipped with instruction plates or diagrams, including warnings or cautions, describing any special or important procedures to be followed in assembling, operating, or servicing the PSEA. Instruction plates shall be in accordance with MIL-P-514, Type III, Composition C, (GG-P-455, Type I, Grade A, Class 1) material. The plates shall be attached by screws, bolts, or rivets in a location where the plate shall be both visible and legible.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

3.15 Treatment and painting. The portions of the PSEA normally coated or painted shall be cleaned and treated as specified herein. Steel components shall be chemically cleaned and completely coated with an epoxy or acrylic primer. Aluminum surfaces in contact with steel surfaces shall be cleaned and the oxide film removed. Aluminum surfaces around boltholes where the bolt heads and nuts contact the aluminum shall be cleaned and coated with an epoxy or acrylic primer. Coating material and color shall be as specified on the appropriate drawing.

3.16 Assembly of bolted connections between steel and aluminum. The primed contact surfaces of aluminum and steel bolted together shall be covered with a flexible sealer. Screws, washers, and nuts shall be coated with a flexible sealer immediately prior to installation. This provision does not apply to screws, washers, and nuts used to join aluminum parts.

3.17 Government-loaned property. When specified (see 6.2), the property will be loaned by the Government to the contractor for conducting tests, which are specified as tests to be conducted by the contractor.

3.18 Interchangeability. All parts having the same part or drawing number shall be functionally and dimensionally interchangeable. Interchangeable parts are defined as two or more like parts possessing such functional and physical characteristics as to be equivalent in performance and durability, and capable of being exchanged one for the other without alteration of the parts themselves or of adjoining parts, except for adjustment, and without selection for fit or performance.

3.19 Workmanship.

3.19.1 Metal fabrication. Metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the steel, may be employed instead of shearing and sawing. All bends shall be made with controlled means to insure uniformity of size and shape. Precaution shall be taken to avoid overheating. Heated steel shall be allowed to cool slowly. External surfaces shall be free of burrs, sharp edges, and corners, except when sharp edges or corners are required or where they are not detrimental to safety.

3.19.2 Connecting holes and slots. Holes and slots for connecting parts shall be accurately drilled and, when required, machined to the dimensions shown on the drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

3.19.3 Welders and welding.

3.19.3.1 Pipeline seam welders. Before assigning any welder to manual welding of transverse pipe seams (i.e., welding the neck flange to the return bend), the contractor shall provide the contracting officer with certification that the welder has passed qualification tests in accordance with API 1104.

3.19.4 Structural steel welders. Before assigning any welder to manual welding work covered by this specification, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operations to be performed and that such qualification is effective as defined by the particular code:

AWS D1.1, Structural Welding Code, Section 5, Qualification.
ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

Contractors who make only horizontal welds need not qualify welders for "all position welding." Subject to approval by the Government, the contractor's standard welder qualification may be substituted in lieu of the above codes provided that the contractor's procedure is equivalent to the above codes. The contractor shall be responsible for determining that automatic welding equipment operators are capable of producing quality welds in accordance with AWS or ASME codes.

3.19.5 Pipe seam welding. Transverse pipe seams (welding neck flange to return bend) shall be welded by the shielded electric-arc method in accordance with API 1104.

3.19.6 Structural steel welding. All structural steel welding, including anchor-rise grip assemblies and external welding on the submarine pipeline terminal assembly, shall be done by the shielded electric-arc method in accordance with AWS D1.1. The surface of all parts to be welded shall be free from paint, grease, and other foreign matter. Where embrittlement of the joined metal may result, preheating, or annealling or both shall be employed. All welded parts shall be free from cracks and other imperfections that may reduce the effectiveness of the part.

3.20 Functional preformance. The PSEA shall be capable of operation at 150 psi when tested as specified in 4.6.2.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Component and material inspection. The contractor is responsible for insuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications, standards, and drawings, as applicable.

4.1.2 Disassembly inspection. Failure of any examination or test by the preproduction model shall be cause for disassembly, in the presence of a Government representative, of the preproduction model to the extent necessary to determine the cause of the failure. Each disassembled part shall be examined in detail for compliance with this specification and referenced drawings in regard to materials, dimensions, tolerances, and workmanship. Parts not complying with such requirements shall be rejected and shall be cause for rejection of the preproduction model. Reassembly with replacement parts and retesting shall be the responsibility of the contractor.

4.1.3 End Item Final Inspection Requirement (EIFIR). Each PSEA shall be inspected in accordance with the applicable EIFIR. One copy of the EIFIR shall be shipped with each inspected PSEA (see 6.4.1).

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) Preproduction inspection (see 4.3).
(b) Initial production inspection (see 4.4).
(c) Quality conformance inspection (see 4.5).
(d) Inspection of packaging (see 4.8).

4.3 Preproduction inspection.

4.3.1 Examination. The preproduction PSEA shall be examined as specified in 4.6.1. Presence of one or more defects shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

4.3.2 Tests. The preproduction PSEA shall be tested as specified in 4.6.2.1 through 4.6.2.6. Failure of any test shall be cause for performing the disassembly inspection specified in 4.1.2.

4.4 Initial production inspection. When specified (see 3.3), one or more initial production PSEAs will be selected at random by the Government from the PSEAs being produced by production tooling and will be examined for the defects listed in Table I and subjected to the tests marked "X" in Column 3 of Table II to determine conformance to the requirements of this specification. The inspection will be performed by the Government at a site selected by the Government. Acceptance of an initial production PSEA shall not exclude the remaining PSEAs from the quality conformance inspection and acceptance provisions specified in Section 4. In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any or all other tests contained in this specification as part of the initial production test, and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests.

4.4.1 Inspection failure. Failure of an initial production PSEA to meet any requirement specified herein during and as a result of the examination and tests specified in 4.4 shall be cause for rejection of the initial production PSEA and shall be cause for refusal by the Government to continue acceptance of production PSEAs until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on PSEAs previously accepted and produced under the contract. Any deficiencies found as a result of the initial production inspection will be considered prima facie evidence that all PSEAs accepted prior to the completion of initial production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Quality conformance inspection.

4.5.1 Examination. Each PSEA shall be examined for the defects as listed in Table I. Presence of one or more defects shall be cause for rejection.

4.5.2 Tests. Each PSEA shall be subjected to the tests marked "X" in Column 4 of Table II. Failure of any test shall be cause for rejection.

4.6 Inspection schedule.

4.6.1 Examination. Each PSEA shall be examined as specified herein for the defects listed in Table I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

TABLE I. Examination Schedule

Number	Characteristic	Requirement Paragraph
Major		
101	The 6-inch pipeline system seaward end assembly not in accordance with Top Assembly TA13221E4900.	3.1
102	Material not as specified.	3.4
103	Safety not as specified.	3.5
104	Human factors not as specified.	3.6
105	Parts and components not as specified.	3.8.1
106	Fasteners not as specified.	3.8.2
107	Lubricants not as specified.	3.9.1
108	Lubricating fittings not as specified.	3.9.2
109	Slinging provisions not as specified.	3.10
110	Tiedown provisions not as specified.	3.11
111	Shipping data plate not as specified.	3.13
112	Instruction plates not as specified.	3.14
113	Assembly of bolted connections between steel and aluminum not as specified.	3.16
114	Interchangeability not as specified.	3.18
115	Metal fabrication not as specified.	3.19.1
	Connecting holes and slots not machined as specified.	3.19.2
116	Pipeline seam welders not as specified.	3.19.3.1
117	Structural steel welders not as specified.	3.19.4
118	Pipe seam welding not as specified.	3.19.5
119	Structural steel welding not as specified.	3.19.6
Minor		
201	Identification marking not as specified.	3.12
202	Treatment and painting not as specified.	3.15
203	Workmanship not as specified.	3.19

4.6.2 Tests.

4.6.2.1 Test conditions. Unless otherwise specified in a test, tests shall be performed without shelter and at the environmental conditions existing at the place of test. The PSEA shall operate as specified herein without maintenance other than the contractor's recommended normal scheduled maintenance as established by a maintenance schedule prepared and submitted by the contractor prior to test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

4.6.2.2 Test schedule.

TABLE II. Test Schedule

Preproduction						
Pneumatic Components	PSEA	Initial Production	Quality Conformance	Test	Test Paragraph	Requirement Paragraph
1	2	3	4	5	6	7
X	X	X	X	Test conditions.	4.6.2.1	-
-	X	X	X	Tiedown provisions.	4.6.2.3	3.11
-	X	X	X	Slinging provisions.	4.6.2.4	3.10
-	X	X	X	Welds.	4.6.2.5	3.19
X	X	X	X	Functional performance.	4.6.2.7	3.20
X	X	X	X	Maintenance evaluation.	4.6.2.6	3.7
-	-	-	X	Inspection comparison.	4.7	-

4.6.2.3 Tiedown provisions.

4.6.2.3.1 Test procedure. With the PSEA anchored by means other than the tiedown being tested, apply the static loads specified in MIL-STD-209 to each provision. Measure the dimensions of the tiedowns.

4.6.2.3.2 Failure criteria. Weld failure, permanent deformation of the PSEA or its tiedowns, breakage of the tiedowns, or nonconformance to MIL-STD-209 shall constitute failure of this test.

4.6.2.4 Slinging provisions.

4.6.2.4.1 Test procedure.

(a) Lift the PSEA and hold it in suspension in its normal travel position. Determine the forward angles of application for each provision. Measure the clearance between each sling and the PSEA. Measure the eye openings and clearance dimensions of the provisions.

(b) Restrain the PSEA by anchoring the main frame and subject each slinging provision to a force of 2-1/2 times the load it carried when suspended. This force shall be applied in the direction as determined in (a) above. An acceptable alternate method of test shall be to lift the PSEA as in (a) above, and add weights to the PSEA until the force on each provision is 2-1/2 times the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

initial force. Hold the PSEA under either of the above loading conditions for not less than 90 seconds. Observe for evidence of weld cracks or permanent deformation of the PSEA and the slinging provisions. Measure as in (a) above.

4.6.2.4.2 Failure criteria. Weld failure, permanent deformation of the PSEA or any slinging provision, or nonconformance to MIL-STD-209 shall constitute failure of this test.

4.6.2.5 Weld test. When specified, welds shall be subjected to radiographic and proof and service load tests conducted by the Government to insure a quality item.

4.6.2.5.1 Failure criteria. Missing or defective welds shall constitute failure of this test (see 3.19.5 and 3.19.6).

4.6.2.6 Maintainability.

4.6.2.6.1 Maintenance support evaluation. Maintenance operations required during preproduction and initial production of the PSEA shall be accomplished to determine conformance to 3.8.4 and recorded.

4.6.2.6.2 Maintenance ratio. The maintenance ratio shall be computed during preproduction and initial production testing of the PSEA.

4.6.2.7 Functional performance. The PSEA shall be completely assembled, lubricated, and tested in accordance with 4.6.2.7.1.

4.6.2.7.1 Test procedures.

(a) Remove all blind flanges. Place a wood obstruction between the check valve clapper and the clapper seat.
(b) Install a blind flange with a water inlet fitting on the lower pipe opening (the opening which exposes the check valve clapper).
(c) Fill the assembly with water. Close the lower butterfly valve as water begins to escape. Gradually close the upper butterfly valve in a manner so that the assembly will be void of air.
(d) Apply 150 psi water pressure for 15 minutes. Leakage of more than 1/4 pint of water by either valve constitutes failure.
(e) Dry the inside of the assembly.
(f) Close the two lower pipe openings (the opening which exposes the check valve and the adjoining opening) with blind flanges and suitable gaskets. Close the remaining opening with a blind flange fitted with an air inlet fitting. Open the butterfly valves.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

(g) From a safe distance or from behind a barricade, pressurize the assembly to 150 psi with air. Reduce the pressure to 75 psi and soap all welds and bolted connections. Any observable leaks constitutes failure.

(h) Anchor the assembly by the lower flanged pipe opening in a manner which will not cause the pipe to deform. Apply a horizontal pull of 10,000 pounds to the tow frame. Damage or permanent deformation constitutes failure.

(i) Close the lower butterfly valve. Attach a 6-inch hose or pipe to the lower flanged opening. The hose or pipe shall terminate with an open end between 10 and 15 feet above the check valve.

(j) Force water through the upper most flanged opening at a rate between 50 and 100 gpm. Simultaneously interrupt the flow of water and open the lower butterfly valve. Failure of the check valve to function constitutes failure. Repeat three times.

4.6.2.7.2 Failure criteria. Failure of the PSEA to meet any of the specified test criteria shall constitute failure of this test.

4.7 Inspection comparison. The Government may select PSEAs at any time during the contract production period and subject these PSEAs to the examination listed in Table I and the tests marked "X" in Column 4 of Table II to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on PSEAs selected at random from those which have been accepted by the Government and will not include the previously inspected preproduction model and initial production PSEA. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison, and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

4.7.1 Inspection failure. Failure of an inspection comparison PSEA to meet any requirement specified herein during and as a result of the examination and tests specified in 4.7 shall be cause for rejection of the inspection comparison PSEA and shall be cause for refusal by the Government to continue acceptance of production PSEAs until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on PSEAs previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparison will be considered prima facie evidence that all PSEAs accepted prior to the completion of inspection comparison are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

4.8 Inspection of packaging.

4.8.1 Quality conformance inspection of pack.

4.8.1.1 Unit of product. For the purpose of inspection. a completed pack prepared for shipment shall be considered a unit of product.

4.8.1.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105.

4.8.1.3 Examination. Samples selected in accordance with 4.8.1.2 shall be examined for the following defects. AQL shall be 2.5 percent defective.

120. Openings into the piping assembly not closed as specified.
121. Towing frame not detached and fasteners bagged and secured as specified.
122. Skidded box not as specified.
123. Piping assembly not secured to the base by bolting as specified.
124. Marking illegible, incorrect, incomplete, or missing.

5. PACKAGING

5.1 Packing. Packing shall be Level A or Commercial as specified (see 6.2).

5.1.1 Level A. All openings into the piping assembly shall be closed using the flange covers provided. The towing frame shall be detached from the piping assembly. The fasteners shall be placed in a bag and the bag shall be secured to the towing frame. Each seaward end pipeline assembly shall be packed in a close-fitting box conforming to MIL-B-26195, Type II, Style C, class optional. The piping assembly shall be bolted to the base of the box using the holes provided in the skid frame. The towing frame shall be placed on edge on the base and shall be cushioned, blocked, and secured to the piping assembly and the base of the box. Cushioning, blocking, and anchoring shall be in accordance with MIL-STD-1186.

5.1.2 Commercial. All openings into the piping assembly shall be closed using the flange covers provided. Each seaward end pipeline assembly shall be packed to assure carrier acceptance and delivery to destination, without damage, at the lowest ratings of the carrier in compliance with Uniform Freight Classification rules or National Motor Freight Classification rules.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

5.2 Marking.

5.2.1 Military packaging. Marking shall be in accordance with MIL-STD-129.

5.2.2 Commercial packaging. The marking shall reflect as a minimum, the item name, National Stock Number, quantity, contract number, and appropriate address markings. The marking shall be applied with a waterproof material, be legible, and shall provide a definite contrast.

6. NOTES

6.1 Intended use. The tactical pipeline system seaward end assembly (PSEA) is intended for use as the seaward end terminal for the 6-inch pipeline and is part of an air transportable tactical tanker mooring and offloading pipeline system for across-the-beach delivery of bulk fuel.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Time frame required for submission of preproduction model, and number of PSEAs required (see 3.2).
(c) When the Government will conduct any or all of the preproduction model examination and tests. When the Government will conduct some but not all of the preproduction examination and tests, the contracting officer should specify which examination and tests will be conducted by the Government and which examination and tests shall be conducted by the contractor (see 3.2).
(d) When initial production inspection is required and the number of PSEAs to be furnished (see 3.3).
(e) When instruction plates are required. When instruction plates are required, the contracting officer should specify the information to be included on the plate (see 3.14).
(f) When Government-loaned property is required (see 3.17). When Government-loaned property is specified, the contracting officer should specify the description, identification, and quantity of the property to be loaned.
(g) When weld tests are required (see 4.6.2.5).
(h) Degree of packing required (see 5.1).

6.3 Preproduction model. Any changes or deviations of production PSEAs from the approved preproduction model during production will be subject to the approval of the contracting officer. Approval of the preproduction model will not relieve the contractor of his obligation to furnish PSEAs conforming to this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

6.4 Definitions. The following definitions shall apply throughout this specification.

6.4.1 End Item Final Inspection Requirement (EIFIR). An EIFIR is a checklist of quality characteristics prepared by the Government which the contractor must following during his final inspection of the completed end item to verify complete and functional conformance to contract requirements prior to submission for final acceptance (see 4.1.3).

6.5 Government-loaned property. The contracting officer should arrange to loan the property specified in 3.17 when applicable (see 6.2).

6.6 Data requirements. The contracting officer should include requirements for such data as technical publications, instructional materials, illustrated parts lists, and contractor's maintenance and operation manual to be furnished with each PSEA.

6.7 Provisioning. The contracting officer should include provisioning requirements for repair parts and maintenance tools as necessary (including any special tools) and instructions regarding shipment of PSEAs.

6.8 Recycled material. It is encouraged that recycled material be used when practical as long as it meets the requirements of the specification (see 3.4).

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 3835-A050

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

APPENDIX

A.1 Torque Data

Size Nut or Screw	Torque (Ft.-Lb.)	Size Nut or Screw	Torque (Ft.-Lb.)	Size Nut or Screw	Torque (Ft.-Lb.)
1/4 - 20	7-9	7/16 - 20	57-61	3/4 - 10	240-250
1/4 - 28	8-10	1/2 - 13	71-75	3/4 - 16	290-300
5/16 - 18	13-17	1/2 - 20	83-93	7/8 - 9	410-420
5/16 - 24	15-19	9/16 - 12	90-100	7/8 - 14	475-485
3/8 - 16	30-35	9/16 - 18	107-117	1 - 8	580-590
3/8 - 24	35-39	5/8 - 11	137-147	1 - 14	685-695
7/16 - 14	46-50	5/8 - 18	168-178		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

DOCUMENT IDENTIFIER *(Number)* AND TITLE MIL-S-52936(ME) Submarine Pipeline Seaward End Assembly, Six-Inch Tactical Pipeline System

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1 OCT 76 1426 EDITION OF 1 JAN 72 WILL BE USED UNTIL EXHAUSTED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:40Z
Check the source to verify that this is the current version before use.