MIL-F-45437D (AR)
AMENDMENT 2
24 May 1983
SUPERSEDING
AMENDMENT 1
17 April 1979

MILITARY SPECIFICATION

FUZES, HAND GRENADE, M213 and M215
PARTS FOR, LOADING, ASSEMBLING AND PACKING

This amendment forms a part of Military Specification MIL-F-45437D(PA), dated 23 April 1976, and is approved for use by the US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

* 2.1: Add the following to immediately precede Section 3 "REQUIREMENTS":

"U. S. ARMY MATERIEL DEVELOPMENT AND READINESS COMMAND

DARCOM R 385-25 - Radiation Protection.

(Application for copies of this regulation should be addressed to Commander, U. S. Army Materiel Development and Readiness Command, 5001 Eisenhower Ave., ATTN: DRCSF-P, Alexandria, VA 22333.)"

PAGE 4

* 3.7.4: Add paragraph 3.7.4 to follow 3.7.3.

"3.7.4 Moisture content. The moisture content of the delay composition shall not exceed 0.04% throughout assembly of the fuze."

PAGE 20

4.4.2.10: Add Major Defect 106:

"106 Moisture content of delay composition - - - -
4.4.3.11.4 3.7.4 4.4.3.11.4"

FSC 1330

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

PAGE 32

4.4.3.11.4: Add paragraph 4.4.3.11.4 to follow 4.4.3.11.3.

"4.4.3.11.4 Moisture content. The contractor shall provide adequate controls to maintain the moisture content of the delay column during all operations of the Fuze assembly. The contractor shall develop and submit a plan to insure that the moisture content is maintained within the specified limits, including records to be kept and made available to the government upon request. Changes to the approved process will require approval of the design Agency in order to insure that the change will not degrade the fuze function."

PAGE 33

* 4.4.4.1 and 4.4.4.2: The following paragraphs shall be added to follow 4.4.4:

"4.4.4.1 Automatic inspection equipment. All automatic test and inspection equipment, when utilized by the Contractor, shall be subjected to periodic verification and calibration check during production. All standards or test samples required for such calibration/verification shall be furnished by the equipment manufacturer as part of the equipment. Procedures for verification shall include, as a minimum: frequency, method of verification, and the method of retrieval of item produced between verification/calibration. These procedures shall be included in the operation/calibration procedures as required by the above paragraph. In addition, the equipment shall be subjected to periodic maintenance by the manufacturer or other qualified personnel, as approved by the Contracting Officer, and in accordance with approved maintenance procedures."

"4.4.4.2 Radiation-emitting equipment. Inspection equipment employing x-rays or containing radioisotopic material, when utilized by the contractor, shall comply with all safety regulations specified in DARCOM R 385-25 and display the required safety tag. The equipment shall be tamperproof, completely self-contained, with all controls locked to production personnel and accessible only to supervisory personnel. Unless otherwise specified, preventive maintenance and verification shall be performed not less than once every six (6) months. Maintenance and verification shall be performed only by the equipment manufacturer or other qualified personnel, as approved by the Contracting Officer. Records shall be kept of all maintenance performed. In addition, maintenance information shall be affixed to the inspection equipment (label or tag)."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

* 4.5.5, line 14: Insert the following sentence after "retest":

"Fuze assemblies subject to retest shall be maintained in a humidity-controlled area in order to insure compliance with requirements of 3.7.4."

The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1330-A192)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.