MILITARY SPECIFICATION

FUZES, HAND GRENADE, M213 and M215
PARTS FOR, LOADING, ASSEMBLING AND PACKING

This amendment forms a part of Military Specification MIL-F-45437D(PA), dated 23 April 1976, and is approved for use within the US Army Armament Munitions and Chemical Command, and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1: Add the following to immediately precede Section 3 "REQUIREMENTS":

"U. S. ARMY MATERIEL DEVELOPMENT AND READINESS COMMAND

DARCOM R 385-25 - Radiation Protection.

(Application for copies of this regulation should be addressed to Commander, U. S. Army Materiel Development and Readiness Command, 5001 Eisenhower Ave., ATTN: DRCSF-P, Alexandria, VA 22333.)"

* 3.4.1: Delete "less than three (3.0) seconds" and substitute "less than four (4.0) seconds".

* 3.4.2: Delete "more than five (5) seconds and substitute "more than five and one tenth (5.1) seconds".

* 3.4.4: Add new paragraph:

"3.4.4 Long delay. Fuzes that function in more than five and one tenth (5.1) seconds but less than 10.0 seconds shall be noted as long delay devices."

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

PAGE 4

3.7.4: Add paragraph 3.7.4 to follow 3.7.3.

"3.7.4 Moisture content. The moisture content of the delay composition shall not exceed 0.04% throughout assembly of the fuze."

* 3.10: Add new paragraph:

"3.10 Delay column process inspection. The contractor shall assure adequate process control exists at the delay column assembly by testing samples in accordance with the sampling plan and procedures noted in 4.4.3.14."

* 3.11: Add new paragraph:

"3.11 Critical defects material handling. An analysis of critical defect material handling shall be made in accordance with MIL-A-48078 and 4.4.3.15."

* 3.12: Add new paragraph:

"3.12 Adhesives, sealants and lubricants. If adhesives, sealants or lubricants are required or permitted by the drawings, a process control drawing is required in accordance with MIL-A-48078 and 4.4.3.16."

* TABLE I, First article inspection. Add to the Fuze Assembly Inspection:

"Adhesives, sealants and lubricants tear down, 10 samples, 3.12, 4.4.3.16."

PAGE 20

4.4.2.10: Add Major Defect 106:

"106 Moisture content of delay composition - 4.4.3.11.4 3.7.4 4.4.3.11.4"

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

* 4.4.3.2: Delete in its entirety and substitute:

"4.4.3.2 Functioning (see 3.4). the fuzes shall be observed for any failure to comply with the requirements as classed in Table II when tested as specified in 4.5.1.

TABLE II

Defect		Classification
Premature delay failure	(see 3.4.1)	Critical
Excessive delay failure	(see 3.4.3)	Critical
"Hung" striker failure	(see 3.4)	Critical
Normal delay failure	(see 3.4.2)	Major
Dud	(see 3.4)	Major
Long delay failure	(see 3.4.4)	Major

A sample of 800 fuze assemblies shall be taken from each lot and divided into two equally sized groups. One group shall be subjected to the static functioning test as specified in 4.5.2.1 and the other group to the dynamic functioning test as specified in 4.5.2.2. The lot shall be rejected if any of the following test results occur:

a. A critical defective is found (see Table II).

b. If four (4) or more fuzes dud or function low order (see 6.8).

c. If six (6) or more long delay failures occur in either group, or is the combined number of long delay failures in both groups equals or exceeds ten (10)."

* 4.4.3.2.1: Delete in its entirety.

* 4.4.3.2.2: Delete in its entirety.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

PAGE 32

4.4.3.11.4: Add paragraph 4.4.3.11.4 to follow 4.4.3.11.3.

"4.4.3.11.4 Moisture content. The contractor shall provide adequate controls to maintain the moisture content of the delay column during all operations of the Fuze assembly. The contractor shall develop and submit a plan to insure that the moisture content is maintained within the specified limits, including records to be kept and made available to the government upon request. Changes to the approved process will require approval of the design Agency in order to insure that the change will not degrade the fuze function."

PAGE 33

* 4.4.3.14: Add new paragraph:

"4.4.3.14 Delay column process inspection. The contractor shall randomly select nine (9) samples form each hour's production quantity that has undergone delay column consolidation. In addition, the contractor shall add to his sample the last unit produced during that hour's production. These ten (10) samples shall be statically fired for determination of that hour's production to comply with the requirements of paragraph 3.4. The production quantity shall be classed defective as noted by:

a. If one (1) or more samples fail to comply with the premature delay requirements of paragraph 3.4.1 - Critical defect.

b. If two (2) or more samples fail to comply with the long delay requirements of paragraph 3.4.4 - Major defect.

c. If one (1) or more samples fail to comply with the excessive delay requirement of paragraph 3.4.3 - Critical defect.

Testing shall be in accordance with paragraph 4.5.9."

* 4.4.3.15: Add new paragraph:

"4.4.3.15 Critical defect material handling (see 3.11). The contractor shall maintain controls for all critical defects as specified in paragraph 3.2, Amendment 4 of MIL-A-48078."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

* 4.4.3.16: Add new paragraph:

"4.4.3.16 Adhesives, sealants and lubricants (see 3.12). The contractor shall maintain documents and controls as specified in paragraph 3.3, Amendment 4 of MIL-A-48078."

PAGE 33

4.4.4.1 and 4.4.4.2: The following paragraphs shall be added to follow 4.4.4:

"4.4.4.1 Automatic inspection equipment. All automatic test and inspection equipment, when utilized by the Contractor, shall be subjected to periodic verification and calibration check during production. All standards or test samples required for such calibration/verification shall be furnished by the equipment manufacturer as part of the equipment. Procedures for verification shall include, as a minimum: frequency, method of verification, and the method of retrieval of item produced between verification/calibration. These procedures shall be included in the operation/calibration procedures as required by the above paragraph. In addition, the equipment shall be subjected to periodic maintenance by the manufacturer or other qualified personnel, as approved by the Contracting Officer, and in accordance with approved maintenance procedures."

"4.4.4.2 Radiation-emitting equipment. Inspection equipment employing x-rays or containing radioisotopic material, when utilized by the contractor, shall comply with all safety regulations specified in DARCOM R 385-25 and display the required safety tag. The equipment shall be tamperproof, completely self-contained, with all controls locked to production personnel and accessible only to supervisory personnel. Unless otherwise specified, preventive maintenance and verification shall be performed not less than once every six (6) months. Maintenance and verification shall be performed only by the equipment manufacturer or other qualified personnel, as approved by the Contracting Officer. Records shall be kept of all maintenance performed. In addition, maintenance information shall be affixed to the inspection equipment (label or tag)."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.

PAGE 34

4.5.5, line 14: Insert the following sentence after "retest":

"Fuze assemblies subject to retest shall be maintained in a humidity-controlled area in order to insure compliance with requirements of 3.7.4."

The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

PAGE 35

* 4.5.11: Add new paragraph:

"4.5.11 Delay column process inspection static firing. The delay column assembly after consolidation shall be placed in a fixture and tested for delay time as specified in 3.4. The firing times shall be recorded for review by the Government and inclusion into the contractor's process control."

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1330-A310)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T02:59Z
Check the source to verify that this is the current version before use.