MILITARY SPECIFICATION
DUMMY PLUG, TEST, ATOMIC WEAPON: T-4087.

1. SCOPE

1.1 This specification covers requirements, quality assurance provisions, and the preparation for delivery criteria for one type of dummy connector assembly entitled as Dummy Connector Assemblies; T-4087, T-4087-4, T-4087-9, T-4087-10, T-4087-11, T-4087-13, T-4087-14, T-4087-15, T-4087-16 and T-4087-17 which are used with the Honest John warhead section.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-810	- Environmental Test Methods.
MIL-STD-1168	- Lot Numbering of Ammunition.
MIL-STD-1460	- Soldering of Electrical Connections and Printed Wiring Assemblies, Procedure For.

DRAWINGS

ORDNANCE CORPS

8800540	- Bag, Packing, Ammunition, for Dummy Connector or Dummy Plug.
8800736	- Dummy Connector Assembly, T-4087-4.
8806600	- Bag, Packing for Repair Parts.
8808362	- Container, Packing, Ammunition, for Domestic (CONUS) Shipments of Special Weapons Items, Packing and Marking.
8813598	- Dummy Connector Assembly, T-4087-10.
8813601	- Dummy Connector Assembly, T-4087-16.
8813602	- Dummy Connector Assembly, T-4087-13.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

8813603 - Dummy Connector Assembly, T-4087-17.
8813604 - Dummy Connector Assembly, T-4087-15.
8813605 - Dummy Connector Assembly, T-4087-14.
8821464 - Dummy Connector Assembly, T-4087-3.
8831045 - Dummy Connector Assembly, T-4087-9.
8831046 - Dummy Connector Assembly, T-4087-11.
EL-8842547 - Equipment List.

(Copies of specifications, standards, drawings, and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The dummy connector assemblies shall comply with all requirements specified on the drawing (dwg) 8800736, 8813598, 8813601, 8813602, 8813603, 8813604, 8813605, 8821464, 8831045, 8831046, with all requirements specified herein, and with the requirements of all applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Mating assembly. The dummy connector assemblies shall be capable of being fully mated and unmated to a receptacle by hand, without use of tools. Testing shall be as specified in 4.4.1.

3.5 Continuity. The direct current resistance of each circuit of the dummy connector assemblies shall not exceed the value specified for the respective circuit in Tables II through XI when tested as specified in 4.4.2.

Table I
T-4087-3 Ordnance No. 8821464
Continuity Test

From	To	Switch Position	Maximum Resistance Ohms
P1-A	P1-D	Y1	0.14
P1-B	P1-D	Y2	0.14
P1-C	P1-D	Y3	0.14
P1-G	P1-H	Note 1	0.05
P1-G	P1-M	Note 1	0.05
P1-G	P1-S	Note 1	0.05
P1-G	P1-T	Note 1	0.05
P1-G	P1-X	Note 1	0.05
P1-G	P1-c	Note 1	0.05

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

P1-G	P1-i	Note 1	0.05
P1-K	P1-L	Note 1	0.05
P1-V	P1-W	Note 1	0.05
P1-d	P1-j	Note 1	0.05

Note: Switch position has no effect on these terminals.

Table II
T-4087-4, Ordnance No. 8300736
Continuity Test

From	To	Switch Position	Maximum Resistance Ohms
P1-2	P1-4	Go	0.14
P1-6	P1-7	No-go	0.14

Table III
T-4087-9, Ordnance No. 8831045
Continuity Test

From	To	Switch Position	Maximum Resistance Ohms
P1-D	P1-S	Note 1	0.05
P1-I	P1-a	Note 1	0.05
P1-b	P1-g	Y1	0.14
P1-k	P1-g	Y2	0.14
P1-j	P1-g	Y3	0.14
P1-H	P1-C	Note 1	0.05
P1-G	P1-Y	Note 1	0.05
P1-L	P1-F	Note 1	0.05
P1-c	P1-K	Note 1	0.05
P1-K	P1-B	Note 1	0.05
P1-B	P1-C	Note 1	0.05
P1-C	P1-T	Note 1	0.05
P1-T	P1-N	Note 1	0.05

Note: Switch position has no effect on these terminals.

Table IV
T-4087-10, Ordnance No. 8813598
Continuity Test

From	To	Switch Position	Maximum Resistance Ohms
P1-A	P1-T	Note 1	0.05
P1-C	P1-D	Note 1	0.05
P1-C	P1-E	Note 1	0.05
P1-C	P1-H	Note 1	0.05
P1-C	P1-J	Note 1	0.05
P1-C	P1-U	Note 1	0.05
P1-C	P1-W	Note 1	0.05
P1-C	P1-a	Note 1	0.05

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

P1-C	P1-b	Note 1	0.05
P1-F	P1-$\overline{V}$	Note 1	0.05
P1-P	P1-L	Y1	0.14
P1-P	P1-M	Y2	0.14
P1-P	P1-N	Y3	0.14

Note 1: Switch position has no effect on these terminals.

Table V
T-4087-11, Ordnance No. 8831046
Continuity Test

From	To	Maximum Resistance Ohms
P1-A	P1-E	0.05
P1-B	P1-D	0.05
P1-C	P1-Y	0.05
P1-D	P1-F	0.05
P1-H	P1-K	0.05
P1-J	P1-L	0.05
P1-K	P1-M	0.05
P1-L	P1-N	0.05
P1-P	P1-S	0.05
P1-R	P1-T	0.05
P1-T	P1-V	0.05
P1-U	P1-W	0.05
P1-X	P1-Z	0.05
P1-AA	P1-CC	0.05
P1-BB	P1-DD	0.05

Table VI
T-4087-13, Ordnance No. 8813602
Continuity Test

From	To	Maximum Resistance Ohms
P1-1	P1-2	0.05
P1-2	P1-14	0.05
P1-3	P1-4	0.05
P1-4	P1-7	0.05
P1-5	P1-6	0.05
P1-8	P1-9	0.05
P1-10	P1-11	0.05
P1-12	P1-13	0.05
P1-13	P1-25	0.05
P1-15	P1-16	0.05
P1-17	P1-18	0.05
P1-18	P1-19	0.05
P1-21	P1-22	0.05
P1-22	P1-23	0.05
P1-23	P1-24	0.05

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Table VII
T-4087-14, Ordnance No. 8813605
Continuity Test

From	To	Switch Position	Maximum Resistance Ohms
P1-A	P1-B	Air	0.14
P1-B	P1-C	Impact	0.14
P1-E	P1-F	Air	0.14
P1-H	P1-J	Air	0.14
P1-K	P1-L	Note 1	0.05

Note: Switch position has no effect on these terminals.

Table VIII
T-4087-15, Ordnance No. 8813604
Continuity Test

From	To	Maximum Resistance, Ohms
P1-1	P1-2	0.05
P1-2	P1-11	0.05
P1-3	P1-21	0.05
P1-6	P1-25	0.05
P1-7	P1-8	0.05
P1-8	P1-27	0.05
P1-11	P1-29	0.05
P1-13	P1-14	0.05
P1-13	P1-32	0.05
P1-17	P1-35	0.05
P1-18	P1-19	0.05
P1-19	P1-37	0.05
P1-21	P1-22	0.05
P1-26	P1-9	0.05
P1-9	P1-28	0.05
P1-29	P1-30	0.05
P1-31	P1-33	0.05
P1-15	P1-33	0.05
P1-35	P1-36	0.05

Table IX
T-4087-16, Ordnance No. 8813601
Continuity Test

From	To	Maximum Resistance, Ohms
P1-1	P1-2	0.05
P1-3	P1-4	0.05
P1-5	P1-6	0.05
P1-7	P1-8	0.05

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Table X
T-4087-17, Ordnance No. 8813603
Continuity Test

From	To	Maximum Resistance, Ohms
P1-1	P1-8	0.05
P1-2	P1-9	0.05
P1-9	P1-11	0.05
P1-12	P1-14	0.05
P1-14	P1-15	0.05

3.6 Insulation resistnace. The insulation resistance of each terminal to all other terminals listed for the respective dummy connector assemblies in Tables XI through XX shall be greater than 20 megohms when subjected to 500 ± 50 volts direct current (vdc) when tested as specified in 4.4.3.

Table XI
T-4087-3, Ordnance No. 8821464
Insulation Resistance Test
Switch In "Y1" Position

Terminal	Terminal
P1-A	P1-V
P1-B	P1-d
P1-C	P1-Note 1
P1-G	Ground Note 2
P1-K	

Note 1 Unused terminals E,F,J,N,P,R,U,Y,Z,a,b,e,f,g,h,k,m, n,p,q,r,s, and t shall be connected together for this test and tested as one terminal.
2 Test Fixture Ground, Dummy connector shell shall be at ground potential.

Table XII
T-4087-4, Ordnance No. 8800736
Insulation Resistance Test
Switch in "No-G0-C" Position

Terminal	Terminal
P1-1	P1-9
P1-2	P1-10
P1-3	P1-11
P1-4	P1-12
P1-5	P1-13
P1-6	P1-14

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

P1-7	P1-15
P1-8	Ground (Note 1)

Note 1. Test Fixture Ground, Connector Shell shall be at ground potential.

Table XIII
T-4087-9, Ordnance No. 8831045
Insulation Resistance Test
Switch in "Y1" Position

Terminal	Terminal
P1-B	P1-I
P1-C	P1-b
P1-D	P1-j
P1-F	P1-k
P1-G	P1-Note 1
	Ground Note 2

Note 1. Unused terminals A,E,J,M,P,R,U,V,W,X,Z,d,e,f, and h shall be connected together for this test and tested as one terminal.
2. Test Fixture Ground Dummy connector shell shall be at ground potential.

Table XIV
T-4087-10, Ordnance No. 8813598
Insulation Resistance Test
Switch in "Y1" Position

Terminal	Terminal
P1-A	P1-N
P1-C	P1-P
P1-F	P1-Note 1
P1-M	Ground Note 2

Note 1. Unused terminals: B,G,K,R,S,X,Y,Z and c shall be connected together for this test and tested as one terminal.
2. Test Fixture Ground. Connector shell shall be at ground potential.

Table XV
T-4087-11, Ordnance No. 8831046
Insulation Resistance Test

Terminal	Terminal
P1-A	P1-R
P1-B	P1-U

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

P1-C	P1-X
P1-H	P1-AA
P1-J	P1-BB
P1-P	P1-Note 1

Note 1. Connector polarizing pins shall be at test fixture ground potential, which shall also be common ground potential.

Table XVI
T-4087-13, Ordnance No. 8813602
Insulation Resistance Test

Terminal	Terminal
P1-1	P1-15
P1-3	P1-17
P1-5	P1-20
P1-8	P1-21
P1-10	Ground Note 1
P1-12	

Note 1. Test Fixture Ground, Connector Shell shall be at ground potential.

Table XVII
T-4087-14, Ordnance No. 8813605
Insulation Resistance Test
Switch in "Air" Position

Terminals
P1-A
P1-C
P1-E
P1-H
P1-K
P1-Note 1
Ground-Note 2

Note 1. Unused terminals D and G shall be connected together for this test and tested as one terminal.
2. Test Fixture Ground. Dummy connector shell shall be at ground potential.

Table XVIII
T-4087-15, Ordnance No. 8813604
Insulation Resistance Test

Terminal	Terminal
P1-1	P1-15

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

P1-3	P1-17
P1-6	P1-18
P1-7	P1-Note 1
P1-9	Ground-Note 2
P1-13	

Note 1. Unused terminals 4,5,10,12,16,20,23,24 and 34 shall be connected together for this test and tested as one terminal.
2. Test Fixture Ground, Connector shell shall be at ground potential.

Table XIX
T-4087-16, Ordnance No. 8813601
Insulation Resistance Test

Terminal
P1-1
P1-3
P1-5
P1-7
P1-Note 1
Ground-Note 2

Note 1. Unused terminals, 9,10,11,12,13,14 and 15 shall be connected together for this test and tested as one terminal.
2. Dummy connector shell shall be at ground potential.

Table XX
T-4087-17, Ordnance No. 8813603
Insulation Resistance Test

Terminal
P1-1
P1-2
P1-12
P1-Note 1
Ground-Note 2

Note 1. Unused terminals 3,4,5,6,7,10 and 13 shall be connected together for this test and tested as one terminal.
2. Test Fixture Ground, Connector shell shall be at ground potential.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

3.7 Environmental testing. The dummy connector assemblies shall comply with MIL-STD-810, visual inspection and failure criteria, section 3. The dummy connector assemblies shall also comply with 3.4, 3.5 and 3.6 before and after each environmental test. Testing shall be as specified in 4.4.4. Tests shall be conducted in the order specified.

3.7.1 Low temperature. The dummy connector assemblies shall withstand a low temperature of -65 + 5°F without evidence of cracking, peeling or any other damage and within 20 minutes of removal from test chamber, shall comply with 3.4, 3.5 and 3.6 when tested as specified in 4.4.4.1.

3.7.2 High temperature. The dummy connector assemblies shall withstand a high temperature of +160 + 5°F without evidence of cracking, peeling or any other damage and while at this temperature, shall comply with 3.4, 3.5 and 3.6 when tested as specified in 4.4.4.2.

3.7.3 Humidity. The dummy connector assemblies shall withstand exposure to a relative humidity of 95 + 5 percent at temperatures cycling from 80 + 5°F to 160 + 5°F to 80 + 5°F without evidence of peeling, swelling or any other damage when tested as specified in 4.4.4.3. Upon completion of this test the dummy connector assemblies shall comply with 3.4, 3.5 and 3.6.

3.8 Soldering. All soldering shall comply with the requirements specified in MIL-STD-1460.

3.9 Workmanship.

3.9.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.9.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.9.3 Burrs. Parts shall be free from burrs.

3.9.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.9.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agent.

3.9.6 Electrical. Cable assemblies and wires shall be dressed in such a manner as to prevent pinching or chafing of the wire insulation. Ends of wires shall be free from burrs, sharp edges, or points. All parts shall be free from flux, chips, dirt, grease, rust or foreign material.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 5 complete assemblies (see dwg 8800736, 8813598, 8813601, 8813602, 8813603, 8813604, 8813605, 8821464, 8831045 and 8831046) for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in Table XXI. Tests shall be conducted in order specified in Table XXI.

Table XXI
First article inspection and tests

Inspection or Test	Dest	Non Dest
1. Classification of characteristics (see 4.3.2.1)		X
2. Mating assembly (see 3.4)		X
3. Continuity (see 3.5)		X
4. Insulation resistance (see 3.6)		X
5. Low temperature (see 3.7.1)		X
6. High temperature (see 3.7.2)		X
7. Humidity (see 3.7.3)	X	

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Quality conformance inspection.

4.3.1 Lot formation.

4.3.1.1 Production lot. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

4.3.1.2 Inspection lot. A lot or batch and its formation, size, and presentation is described in MIL-STD-105, Section 5. Accordingly, a lot shall mean an inspection lot and a batch shall mean an inspection batch for the purpose of this specification. The manner in which each inspection lot or batch is to be presented and identified by the contractor, shall be designated or approved by the Government representative.

4.3.2 Product inspection examination. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table (see Table XXII and Table XXIII), and inspected for all characteristics in the applicable classification. Any characteristics in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Table XXII
Major Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-72	all	140-141	124	256-259	177	541-549	230
73	72	142	125	260-262	178	550-559	231
74	73	143-144	126	263-265	179	560-569	232
75	74	145	127	266-268	180	570-579	233
76	75	146-147	128	269-271	181	580-590	234
77	76	148-149	129	272-275	182	591-601	235
78	77	150	130	276-278	183	602-613	236
79	78	151-152	131	279-282	184	614-625	237
80	79	153-154	132	283-285	185	626-637	238
81-82	80	155-156	133	286-289	186	638-649	239
83	81	157	134	290-293	187	650-662	240
84	82	158-159	135	294-296	188	663-676	241
85	83	160-161	136	297-300	189	677-690	242
86	84	162-163	137	301-304	190	691-704	243
87	85	164-165	138	305-308	191	705-719	244
88-89	86	166-167	139	309-312	192	720-735	245
90	87	168	140	313-316	193	736-751	246
91	88	169-170	141	317-320	194	752-768	247
92	89	171-172	142	321-324	195	769-785	248
93	90	173-174	143	325-329	196	786-804	249
94-95	91	175-176	144	330-333	197	805-823	250
96	92	177-178	145	334-338	198	824-842	251
97	93	179-180	146	339-342	199	843-863	252
98	94	181-182	147	343-347	200	864-884	253
99-100	95	183-184	148	348-352	201	885-907	254
101	96	185-187	149	353-356	202	908-930	255
102	97	188-189	150	357-361	203	931-955	256
103	98	190-191	151	362-366	204	956-981	257
104-105	99	192-193	152	367-372	205	982-1008	258
106	100	194-195	153	373-377	206	1009-1036	259
107	101	196-197	154	378-382	207	1037-1066	260
108-109	102	198-200	155	383-388	208	1067-1098	261
110	103	201-202	156	389-393	209	1099-1131	262
111	104	203-204	157	394-399	210	1132-1166	263
112-113	105	205-207	158	400-405	211	1167-1204	264
114	106	208-209	159	406-411	212	1205-1243	265
115	107	210-212	160	412-417	213	1244-1285	266
116-117	108	213-214	161	418-424	214	1286-1330	267
118	109	215-217	162	425-430	215	1331-1378	268
119	110	218-219	163	431-437	216	1379-1429	269
120-121	111	220-222	164	438-443	217	1430-1483	270
122	112	223-224	165	444-450	218	1484-1542	271
123-124	113	225-227	166	451-457	219	1543-1605	272
125	114	228-230	167	458-465	220	1606-1673	273
126-127	115	231-232	168	466-472	221	1674-1747	274
128	116	233-235	169	473-480	222	1748-1827	275
129-130	117	236-238	170	481-488	223	1828-1914	276
131	118	239-241	171	489-496	224	1915-2010	277
132-133	119	242-243	172	497-504	225	2011-2115	278
134	120	244-246	173	505-513	226	2116-2232	279
135-136	121	247-249	174	514-521	227	2233-2361	280
137	122	250-252	175	522-530	228	over 2361	298
138-139	123	253-255	176	531-540	229		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Table XXIII
Minor Characteristics

Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size	Lot Size	Sample Size
1-16	all	28-29	23	52-56	31	132-156	39
17	16	30-31	24	57-62	32	157-191	40
18	17	32-34	25	63-69	33	192-244	41
19-20	18	35-36	26	70-76	34	245-334	42
21	19	37-40	27	77-86	35	335-519	43
22-23	20	41-43	28	87-97	36	520-1120	44
24-25	21	44-47	29	98-112	37	over 1120	45
26-27	22	48-51	30	113-131	38		

4.3.2.1 Classification of characteristics (see 3.2). Critical, major and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 Dummy connector assemblies; T-4087-3, T-4087-4, T-4087-9, T-4087-10, T-4087-11, T-4087-13, T-4087-14, T-4087-15, T-4087-16 and T-4087-17 prior to potting. (See dwgs 8821464, 8800736, 8831045, 8813598, 8831046, 8813602, 8813605, 8813604, 8813601 and 8813603 respectively, as applicable.

Categories	Characteristics	Method of Inspection
Critical:	None defined.	
Major:		
101.	Improper depth of "female" contact spring (T-4087-10 only)	Gage
102.	Improper connector	Visual
103.	Improper soldering (see 3.8)	Visual
104.	Any pin missing	Visual
105.	Deformation of connector sufficient to impair mating	Visual
106.	Permanently damaged terminal(s) (gouged, nicked, or flattened)	Visual
*107.	Height of pins as applicable (pins of the same diameter must all appear to be within 1/16 inch in height relative to the adjacent pins)	Visual

*In the event pins do not appear to be within 1/16 inch in height relative to the adjacent pins, a gage (see 4.3.4.1) shall kbe used to determine that variation from the normal height. Reject any pin that varies by more than 0.063 inch maximum from the normal pin height of the individual connector. The normal height of the individual connector pins shall be determined by calculating the average height from measurements taken of pins adjacent to the pin that appears to be defective. The forward

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

edge of the connector shell shall be utilized as the reference surface for all measurements of pin heights.

**108.	Depth of sockets as applicable (female sockets of the same diameter must all appear to be within 1/16 inch in depth relative to the adjacent sockets)	Visual
109.	Evidence of poor workmanship (see 3.9)	Visual
110.	Any component missing, loose, or damaged	Visual/Manual
111.	Objective evidence relating to material missing or improper (see 3.1)	Visual

Minor: None defined.

**In the event socket inserts do not appear to be within 1/16 inch in depth relative to adjacent sockets, a gage (see 4.3.4.1) shall be used to determine that variation from the normal depth. Reject any insert that varies by more than 0.063 inch maximum from the normal socket depth of the individual connector. The normal depth of the individual connector sockets shall be determined by calculating the average depth from measurements taken of sockets adjacent to the socket that appears to be defective. The forward edge of the connector shell shall be utilized as a reference surface for all measurements of socket depths.

4.3.2.1.2 Dummy connector assemblies: T-4087-3, T-4087-4, T-4087-9, T-4087-10, T-4087-11, T-4087-13, T-4087-14, T-4087-15, T-4087-16, and T-4087-17. (See dwgs 8821464, 8800736, 8831045, 8813598, 8831046, 8813602, 8813605, 8813604, 8813601, and 8813603 respectively, as applicable).

Categories		Characteristics	Method of Inspection
Critical:	None defined.		
Major:			
	101.	Portion of connector broken away (minor chips, scratches, burrs, or gouges which do not affect mating are not objectionable)	Visual
	102.	Evidence of poor workmanship (see 3.9)	Visual
	103.	Any component missing, loose, or damaged	Visual/Manual
	104.	Objective evidence relating to material missing or improper (see 3.1)	Visual
Minor:			
	201.	Marking missing, mislocated or incorrect	Visual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

202. Improper alignment of switch knob with switch points.....Visual

4.3.2.1.3 Bag, packing for repair parts (see dwg 8806600) and bag, packing, ammo., for dummy connector or dummy plug (see dwg 8800540).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
	101. Wrong size bag	Visual
	102. Bag not sealed	Visual
	103. Air in bag not minimized before sealing	Visual
	104. Marking missing, mislocated or incorrect	Visual
	105. Evidence of poor workmanship (see 3.9)	Visual
Minor: None defined.		

4.3.2.1.4 Container, packing, (see dwg 8808362).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
	101. Marking improper, illegible, smeared, missing or in wrong position	Visual
	102. Incorrect or insufficient cushioning material	Visual
	103. Evidence of poor workmanship (see 3.9)	Visual
	104. Contents loose	Manual
Minor: None defined.		

4.3.3 Testing. All tests shall be performed. Tests shall be performed in the order specified below:

	Test	Test Classification
a.	Mating assembly	Major
b.	Continuity	Major
c.	Insulation resistance	Major
d.	Low temperature	Major
e.	High temperature	Major
f.	Humidity	Major

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

Of these tests, f is considered destructive and samples so tested shall not be returned to the lot. Destructive samples are over and above the deliverable quantity of items required by the contract.

4.3.3.1 Mating assembly, continuity and insulation resistance. Each dummy connector in the lot shall be tested in accordance with 4.4.1, 4.4.2 and 4.4.3. If any item fails to comply with 3.4, 3.5 and 3.6, the item shall be rejected and removed from the lot.

4.3.3.2 Low temperature, high temperature and humidity. A sample shall be selected at random in accordance with Table XXIV. The sample shall be tested in accordance with 4.4.4.1, 4.4.4.2 and 4.4.4.3. If any item fails to comply with 3.7.1, 3.7.2 and 3.7.3, the lot shall be rejected.

Table XXIV

Lot Size	Sample Size	
	Temperature	Humidity
2-15	1	1
16-50	2	1
51-150	4	1
151-500	6	2
501-3200	10	3

NOTE: For destructive testing.
Lot Size Required = Number Required to be Delivered + Sample Size.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL) (see EL-8842547). When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment and obtain approval prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired (see 6.3).
b. The code "CD" is listed in the "Part or Identifying Number" column on the ELP(see 6.1.2).

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on ELs. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

4.4 Test methods The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

4.4.1 Mating assembly. The dummy connector assemblies shall be mated to a suitable matching receptacle. Care must be exercised to avoid bending connector pins.

4.4.2 Continuity. The circuit resistance shall be measured by means of a suitable low electrical resistance measuring instrument which has been connected to the terminals of the dummy connector assemblies as specified.

4.4.3 Insulation resistance. An insulation resistance tester, capable of supplying the required voltage and with which a resistance in megohms con be obtained, shall be used to measure the resistance. The current shall be limited to a maximum of 5 milliamperes to protect human life.

4.4.4 Environmental testing (see 3.7).

4.4.4.1 Low temperature. The dummy connector assembly shall be placed within the test chamber and the chamber cooled to and maintained at a temperature of -65° ± 5°F for a period of 3 hours or until stabilization (see 6.4), whichever is longer. At the conclusion of this exposure period, the connector shall be maintained at this temperature and inspected in accordance with 4.4.1, 4.4.2 and 4.4.3.

4.4.4.2 High temperature. The dummy connector assembly mated to its mating connector shall be placed within the test chamber. The internal temperature of the chamber shall then be raised to 160 ± 5°F. The connector shall be exposed to this temperature for a period of 3 hours or until stabilization (see 6.4), whichever is longer. A relative humidity of not more than 15 percent shall be maintained in the test chamber throughout the exposure period. At the conclusion of this exposure period, the connector shall be maintained at this temperature and inspected in accordance with 4.4.1, 4.4.2 and 4.4.3.

4.4.4.3 Humidity. The assembly shall be placed in the test chamber mounted to simulate the installed conditions. The chamber temperature shall be at 80 ± 20°F. During the first 2-hour period, the temperature shall be gradually raised to 160 ± 5°F. The temperature of 160 ± 5°F shall be maintained during the next 6-hour period. During the following 16-hour period the temperature in the chamber shall be gradually reduced to 80 ± 20°F, which completed one cycle. The relative humidity throughout the cycle shall be 95 ± 5 percent. The test shall consist of ten such cycles for a total of 240 hours. Upon completion of the tenth cycle, the assembly shall be removed immediately from the test chamber and excessive moisture removed by blowing dry, filtered air over the unit for a period of 5 minutes, maximum. The assembly shall then be tested as specified in 4.4.1, 4.4.2 and 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1 Level A. The dummy connector assembly shall be packaged in accordance with dwgs 8800540, 8808362 or 8806600 as applicable using the specified moisture barrier.

5.1.2 Level C. The dummy connector assembly shall be packaged in accordance with dwgs 8800540, 8808362 or 8806600 as applicable except that the moisture barrier may be omitted.

5.2 Packing.

5.2.1 Level A and C. The dummy connector assembly shall be packed in accordance with dwgs 8800540, 8808362 or 8806600 as applicable.

5.3 Marking. Marking shall be as specified in accordance with dwgs 8800540, 8808362 and 8806600 as applicable.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

6.1.1 Procurement requirements.

a. Title, number, and date of this specification.
b. Production or Repair Parts.
c. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

6.1.2 Contract data requirements (see 4.3.4.1). Data specified in 4.3.4.1 will be delivered as identified on a numbered DDpForm 1664 when specified on a DD Form 1423 incorporated in the contract.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment (see 4.3.4.1). The contractor shall obtain approval from the Commander, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SARPA-QA-N-I.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

6.5 Supersession data. This specification supersedes the requirements of Purchase description PA-PD-1688 Rev 1 dated 14 April 1964.

Custodian:
Army - PA

Preparing activity:
Army - PA

Project No. 1190-A068

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:22Z
Check the source to verify that this is the current version before use.