MILITARY SPECIFICATION

MINE, ANTI-TANK, METAL PARTS ASSEMBLY FOR M56 MINE

This specification is approved for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 This specification covers the inspection and test of the metal parts of the M56 mine body metal assembly.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition, General Specification For

FEDERAL

FED-STD-151 - Metals; Test Methods

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168- Lot Numbering of Ammunition
MIL-STD-1169- Packaging, Packing and Marking for Shipment for Inert Ammunition Components

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

MIL-STD-1235- Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

U.S. ARMY PICATINNY ARSENAL

PRODUCT DRAWING

9281613 - Mine, Anti-Tank Metal Parts Assembly

(Copies of specifications, standards, and drawings required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the Contracting Officer).

3. REQUIREMENTS

3.1 Material. - Materials shall be in accordance with the applicable drawings and specifications.

3.2 Assembly. - The assembly shall comply with all requirements specified on Drawing (dwg.) 9281613 and all associated drawings and with all requirements specified in applicable specifications.

3.3 Mine Body Assembly

3.3.1 Chamber Gage. - The assembly shall conform to all the outside maximum dimensions when measured simultaneously as specified in 4.4.11.1.

3.3.2 Switch Housing Bond Strength. - The switch housing shall not separate or cause leaking when it is pushed outward with a force of one hundred and twenty plus ten (120 + 10) pounds.

3.3.3 Fuze Well Bond Strength. - The fuze well shall not separate or cause leaking when it is pushed outward with a force of five thousand plus one thousand (5000 + 1000) pounds.

3.3.4 Leakage. - The assembly shall not show evidence of leakage when subjected to pressure of fifteen plus one pounds per square inch gage (15.0 + 1.0 p.s.i.g.).

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

3.4 Mine, Metal Parts Assembly

3.4.1 Bore Rider Function. - The bore rider shall fully extend when the bore rider clip is removed.

3.4.2 Overrun Switch Functioning. - The overrun switch shall not function when a point load of twelve minus one (12-1) pounds is centrally applied to the pressure plate. The overrun switch shall function under a point load greater than twelve (12) pounds but less than twenty-five (25) pounds.

3.4.3 Leakage. - The assembly shall not leak when subjected to a minimum internal pressure of one and twenty-five hundreds (1.25) p.s.i.g.

3.5 Workmanship. - All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning agent or method used shall not be injurious to any part, nor shall the part be contaminated by the cleaning agents.

3.6 Submission of Results of Contractor-conducted Examinations and Tests. - The contractor shall forward copies of the results as required by the contract. Results shall be submitted within thirty (30) days at the completion of each lot tested (see 6.4).

3.7 First Article Inspection. - This specification makes provisions for first article inspection. Requirement for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and ser-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

vices conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of Product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted.

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agents authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First Article Inspection

4.2.1 Submission.-Prior to the start of regular production the contractor shall submit a first article sample (see 6.1c) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2 and 4.2.3. The first article sample shall consist of:

a. Twenty-five (25) sets of all components.
b. Twenty-five (25) sets of all subassemblies
c. Twenty-five (25) mine body assemblies.

Included in the first article sample shall be at least three (3) items from each cavity used to produce a cast part and so identi-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

fied as to permit tracing each item to the cavity in which it was cast. All parts shall have been produced by the contractor or furnished by a supplier and shall have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials including packaging and packing shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample, including a certificate of conformance for materials. A sample containing known defects will not be submitted unless specifically authorized by the Confracting Officer. A first article sample, or portion thereof, as directed by the Contracting Officer, shall be submitted whenever there is a lapse in production for a period in excess of 90 days or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government.

4.2.2 Inspections to be performed. - Assemblies and components will be subjected by the Government to the examinations and tests as follows:

a) All components, sub-assemblies and assemblies shall be inspected in accordance with 4.3.2.1 through 4.3.2.22.

b) Twenty-five (25) plunger springs shall be tested for the spring rate in accordance with 4.4.1.

c) Twenty-five (25) fin springs shall be tested for torque test in accordance with 4.4.2.

d) Twenty-five (25) pressure plate springs shall be tested for the spring rate in accordance with 4.4.3.

e) Twenty-five (25) end fins shall be tested for the hardness requirements in accordance with 4.4.4.

f) Twenty-five (25) end fins shall be tested for the rotation test in accordance with 4.4.5.

g) Twenty-five (25) side fins shall be tested for the hardness requirements in accordance with 4.4.6.

h) Twenty-five (25) side fins shall be tested for the rotation test in accordance with 4.4.7.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T19:21Z
Check the source to verify that this is the current version before use.

i) Twenty-five (25) bore rider assemblies shall be tested for the pull test requirements in accordance with 4.4.8.

j) Twenty-five (25) bore rider springs shall be tested for the spring rate requirements in accordance with 4.4.9.

k) Twenty-five (25) pressure plate and retainer assemblies shall be tested for leakage in accordance with 4.4.10.

l) Twenty-five (25) mine body assemblies shall be tested in the sequence shown for the following:

(1) Chamber gaging in accordance with 4.4.11.1
(2) Leakage test in accordance with 4.4.11.4
(3) Hardness in accordance with 4.4.11.5.

m) Three (3) mine body assemblies shall be tested in the sequence shown for the following:

(1) Mine body to switch housing bond strength. (see 4.4.11.2)
(2) Mine body to fuze well bond strength. (see 4.4.11.3)

n) Twenty-five (25) fuze wells shall be tested for the hardness requirements in accordance with 4.4.12.

p) Twenty-five (25) mine metal parts assemblies shall be tested in the sequence shown for the following tests.

(1) Bore rider function in accordance with 4.4.13.1
(2) Overrun switch function in accordance with 4.4.13.2
(3) Leakage testing in accordance with 4.4.13.3

q) Twenty-five (25) overrun flex cable assemblies shall be tested for the continuity resistance requirements in accordance with 4.4.14.1. The cable assemblies shall then be tested for the insulation resistance requirements in accordance with 4.4.14.2.

r) Twenty-five (25) plunger assemblies shall be tested for the torque test in accordance with 4.4.15.

4.2.3 Rejection. - If item fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an inert component or subassembly to comply with any of the stated requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168.

4.3.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

4.3.2.1 Plate, Pressure (see dwg. 9287593 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Outside contour	Gage	01001
102.	Flatness	Gage	01002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	01003

4.3.2.2 Spring, fin (see dwg. 9281615 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Helix angle in wrong direction.	Visual	03001
Minor:	AQL 1.5 percent		
201.	Spring angle	Gage	03002
202.	Length of wire lead, minimum (min)	Gage	03003
203.	Evidence of poor workmanship (see 3.5)	Visual	03004

4.3.2.3 Fin, End (see dwg. 9281618 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Length, maximum (max)	Gage	05001
102.	Straightness	Gage	05002

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

103.	Stop angle	Gage	05003
Minor:	AQL 1.0 percent		
201.	Width, max.	Gage	05004
202.	Evidence of poor workmanship (see 3.5)	Visual	05005

4.3.2.4 Fin, Side (see dwg. 9281619 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Width, max.	Gage	06001
102.	Straightness	Gage	06002
103.	Stop angle	Gage	06003
Minor:	AQL 1.0 percent		
201.	Length, max.	Gage	06004
202.	Evidence of poor workmanship (see 3.5)	Visual	06005

4.3.2.5 Bore rider assembly (see dwg. 9281620 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Length, max.	Gage	07001
102.	Deformed, missing or misaligned parts	Visual	07002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	07003

4.3.2.6 Rider, bore (see dwg. 9281623 covering a detail of dwg. 9281613).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Overall length	Gage	08001
102.	Distance to groove	Gage	08002
103.	Groove width	Gage	08003
104.	Groove diameter	Gage	08004
Minor:	AQL 1.0 percent		
201.	Distance to spring stop	Gage	08005
202.	Evidence of poor workmanship (see 3.5)	Visual	08006

4.3.2.7 Plunger (see dwg. 9281627 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Outside diameter, max.	Gage	10001
102.	Thread pitch diameter	Gage	10002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	10003

4.3.2.8 Pressure Plate and Retainer Assembly (see dwg. 9281628 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Rubber loose or peeling	Visual/ Manual	11001
102.	Rubber thickness	Gage	11002
103.	Assembly damaged or distorted	Visual	11003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

104.	Overall height	Gage	11004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	11005

4.3.2.9 Retainer (see dwg. 9281629 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Location of mounting holes	Gage	12001
102.	Location of rod hinges	Gage	12002
Minor:	AQL 2.5 percent		
201.	Length, max.	Gage	12003
202.	Width, max.	Gage	12004
203.	Height, max.	Gage	12005
204.	Pressure plate opening contour	Gage	12006
205.	Evidence of poor workmanship (see 3.5)	Visual	12007

4.3.2.10 Mine body assembly (see dwg. 9281630 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Height of switch housing, max. .	Gage	13001
102.	Alignment of flex cable slot ...	Gage	13002
103.	Switch housing staked improperly	Visual	13003
104.	Booster well staked improperly .	Visual	13004
105.	Depth of fuze well in mine body	Gage	13005
106.	Pitch diameter of filler hole thread	Gage	13006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

107.	Finish coating missing or incomplete on interior surfaces ..	Visual	13007
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	13008

4.3.2.11 Housing, switch (see dwg. 9281631 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Large outside diameter	Gage	14001
102.	Plunger assembly hole diameter	Gage	14002
103.	Width of lever slot	Gage	14003
104.	Location of lever slot	Gage	14004
Minor:	AQL 2.5 percent		
201.	Location of plunger assembly hole	Gage	14005
202.	Depth of plunger assembly hole .	Gage	14006
203.	Overall height	Gage	14007
204.	Location of switch plunger hole	Gage	14008
205.	Evidence of poor workmanship (see 3.5)	Visual	14009

4.3.2.12 Body, mine (see dwg. 9281632 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Curved wall thickness at 3 points, min.	Gage	15001
102.	Cavity opening, min.	Gage	15002
103.	Inside radius	Gage	15003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

104.	Position of inside radius	Gage	15004
105.	Overall length	Gage	15005
106.	Location of switch housing mounting hole	Gage	15006
107.	Switch housing mounting hole diameter	Gage	15007
108.	Location of switch housing cavity hole	Gage	15008
109.	Location of switch housing mounting hole	Gage	15009
110.	Cavity top surface parallelism .	Gage	15010
111.	Depth of switch housing diameter	Gage	15011
Minor:	AQL 2.5 percent		
201.	Depth of flexcable slot, min. ..	Gage	15012
202.	Width of flex cable slot, min. .	Gage	15013
203.	Location of spring holes	Gage	15014
204.	Location of pressure plate surface	Gage	15015
205.	Height of curved section, max.	Gage	15016
206.	Location of flexcable hole	Gage	15017
207.	Depth of pressure plate spring holes	Gage	15018
208.	Evidence of poor workmanship (see 3.5)	Visual	15019

4.3.2.13 Well, fuze (see dwg. 9281633 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.5 percent		
101.	Height, max.	Gage	16001
102.	Bore rider hole diameter	Gage	16002
103.	Location of bore rider holes ...	Gage	16003
104.	Location of cover plate mounting holes	Gage	16004
105.	Location of fuze cutout	Gage	16005
106.	Contour of fuze cutout (maximum material dimensions)	Gage	16006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

107.	Diameter of booster cup stop hole, min.	Gage	16007
108.	Booster cup thru hole diameter .	Gage	16008
109.	Depth of booster cup stop hole, min.	Gage	16009
110.	Location of rivet cavities ...	Gage	16010
111.	Maximum material dimensions of fuze cutout depth	Gage	16011
112.	Surface finish of bore rider hole	Gage	16012
Minor:	AQL 2.5 percent		
201.	Bore rider stop hole diameter ..	Gage	16013
202.	Pitch diameter of cover plate mounting holes	Gage	16014
203.	Location of booster cup thru hole	Gage	16015
204.	Location of booster cup stop hole	Gage	16016
205.	Location of flex cable hole	Gage	16017
206.	Evidence of poor workmanship (see 3.5)	Visual	16018

4.3.2.14 Switch and flex cable assembly over-run (see dwg. 9281634 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Assembly damaged or distorted ..	Visual	17001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	17002

4.3.2.15 Cover assembly (see dwg. 9281635 covering a detail of 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Threads damaged or covered with paint or adhesive	Visual/ Gage	18001
102.	Holes blocked by gasket	Visual	18002
Minor:	AQL 1.5 percent		
201.	Gasket loose	Manual	18003
202.	Paint coating incomplete or damaged	Visual	18004
203.	Evidence of poor workmanship (see 3.5)	Visual	18005

4.3.2.16 Cover, Fuze (see dwg. 9281636 covering a detail of dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Outside contour	Gage	19001
102.	Location of mounting holes	Gage	19002
103.	Location of battery hole	Gage	19003
104.	Battery holes thread pitch diameter	Gage	19004
105.	Battery plug extension height .	Gage	19005
Minor:	AQL 1.5 percent		
201.	Diameter of mounting holes, min.	Gage	19006
202.	Plate thickness	Gage	19007
203.	Evidence of poor workmanship (see 3.5)	Visual	19008

4.3.2.17 Mine, anti-tank metal parts assembly - Prior to pressure plate and fin assemblies (see dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Major:	AQL 0.65 percent		
101.	Flex cable assembly broken, displaced or lifting	Visual	20001
102.	Pins damaged or bent	Visual	20002
103.	Plunger assembly not secure ..	Visual/ Manual	20003
104.	Bore rider assembly bent or misaligned	Visual/ Manual	20004
105.	Part missing	Visual	20005
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	20006

4.3.2.18 Mine, anti-tank metal parts assembly after pressure plate and fin assembly (see dwg. 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.0 percent		
101.	Alignment of retainer plate ...	Gage	21001
102.	Retainer plate screw(s) missing	Gage	21001
103.	Fins do not spring open freely.	Manual	21003
104.	Bore rider safety clip not in place	Visual	21004
105.	Pitch diameter of filler hole thread	Gage	21005
106.	Finish damaged	Gage	21006
107.	Parts missing or damaged	Visual	21007
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	21008

4.3.2.19 Flex Cable Assembly, Over-run (see dwg. 9282571 covering a detail of 9281613).

Categories	Defects	Method of Inspection	Code No.

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Distance between switch holes and fuze pins	Gage	22001
102.	Pins and mounting plate damaged or distorted	Visual	22002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.5)	Visual	22003

4.3.2.20 Plug, closing (see dwg. 9283058 covering a detail of 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Pitch diameter of threads	Gage	23001
102.	Paint on threads	Gage	23002
Minor:	AQL 1.0 percent		
201.	Slots distorted or damaged	Visual	23003
202.	Evidence of poor workmanship (see 3.5)	Visual	23004

4.3.2.21 Battery cap assembly (see dwg. 9287590 covering a detail of 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Pitch diameter of thread	Gage	24001
102.	Paint on threads	Visual	24002
103.	Length of thread	Gage	24003
104.	Terminal not staked	Visual/ Manual	24004

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.0 percent		
201.	Overall length	Gage	24005
202.	Evidence of poor workmanship (see 3.5)	Visual	24006

4.3.2.22 Well, booster (see dwg. 9287608 covering a detail of 9281613).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Inside diameter of cup	Gage	25001
102.	Depth of inside of cup, min. ...	Gage	25002
Minor:	AQL 1.0 percent		
201.	Diameter of stop diameter, max..	Gage	25003
202.	Evidence of poor workmanship (see 3.5)	Visual	25004

4.3.3 TESTING

4.3.3.1 Spring, Plunger, Spring Rate (see dwg. 9281614) - Major defect - Code No. 02001. - Thirty-two (32) springs shall be randomly selected from each lot and tested for the specified requirements in accordance with 4.4.1. The lot shall be rejected if two (2) or more springs are classed defective (Non-destructive test).

4.3.3.2 Fin Spring Torque Test (see dwg. 9281615) - Major Defect - Code No. 03005. - Thirty-two (32) springs shall be randomly selected from each heat treat batch and tested for the specified requirements in accordance with 4.4.2. The lot shall be rejected if two (2) or more springs are classed defective (Non-destructive test).

4.3.3.3 Spring, Pressure Plate Spring Rate (see dwg. 9281616) - Major Defect - Code No. 04001. - Thirty-two (32) springs shall be randomly selected from each heat treat batch and tested for the specified requirement in accordance with 4.4.3. The lot shall be rejected if two (2) or more springs are classed defective (non-destructive test).

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the currentversion before use.

4.3.3.4 End Fin Hardness Test (see dwg. 9281618) - Major Defect - Code No. 05006. - Thirty-two (32) fins shall be randomly selected from each heat treat batch and tested for the specified requirement in accordance with 4.4.4. The lot shall be rejected if one (1) or more fins are classed defective. (non-destructive test).

4.3.3.5 End Fin Rotation Test (see dwg. 9281618) - Major Defect - Code No. 05007. - Two hundred (200) fins shall be randomly selected from each lot and tested for the specified requirements in accordance with 4.4.5. The lot shall be rejected if three (3) or more fins are classed defective (Non-destructive test).

4.3.3.6 Side Fin Hardness Test (see dwg. 9281619) - Major Defect - Code No. 06006. - Thirty-two (32) fins shall be randomly selected from each heat treat batch and tested for the specified requirement in accordance with 4.4.6. The lot shall be rejected if one (1) or more fins are classed defective (non-destructive test).

4.3.3.7 Side Fin Rotation Test (see dwg. 9281619) - Major Defect - Code No. 06007. - Two hundred (200) fins shall be randomly selected from each lot and tested for the specified requirements in accordance with 4.4.7. The lot shall be rejected if three (3) or more fins are classed defective. (Non-destructive test)

4.3.3.8 Bore Rider Assembly Pull Test (see dwg. 9281620) - Major Defect - Code No. 07004. - Thirty-two (32) assemblies shall be randomly selected from each lot and tested for the specified requirements in accordance with 4.4.8. The lot shall be rejected if one (1) or more assemblies are classed defective. (Non-destructive test).

4.3.3.9 Spring, Bore Rider, Spring Rate (see dwg. 9281624) - Major Defect - Code No. 09001. - Thirty-two (32) springs shall be randomly selected from each lot and tested in accordance with 4.4.9. The lot shall be rejected if two (2) or more springs are classed defective (Non-destructive test).

4.3.3.10 Pressure Plate and Retainer Assembly Air Pressure Test (see dwg. 9281628) - Major Defect - Code No. 11006. - Two hundred (200) pressure plate and retainer assemblies shall be randomly selected from each vulcanizing lot and tested for the specified requirements in accordance with 4.4.10. The lot shall be rejected if two (2) or more assemblies are classed defective. (Non-destructive test)

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the current version before use.

4.3.3.11 Mine Body Assembly (dwg. 9281630)

4.3.3.11.1 Chamber Gaging (see 3.3.1) - Major Defect - Code No. 13009. This test shall be performed 100 percent on the mine body assembly minus the switch housing in accordance with 4.4.11.1. Any mine body classed defective shall be removed from the lot. (Non-destructive test).

4.3.3.11.2 Mine Body to Switch Housing Bond Strength. (see 3.3.2) - Major Defect - Code No. 13010. Three (3) assemblies shall be randomly selected from each lot and tested in accordance with 4.4.11.2. The lot shall be rejected if one (1) or more assemblies are classed defective. (Destructive test)

4.3.3.11.3 Mine Body to Fuze Well Strength (see 3.3.3) - Major Defect - Code No. 13011. - The three (3) assemblies from 4.3.3.11.2 shall be used as the test samples and tested in accordance with 4.4.11.3. The lot shall be rejected if one (1) or more assemblies are classed defective (Destructive test)

4.3.3.11.4 Leak Test (see 3.3.4) - Major Defect - Code No. 13012. - The lot shall be tested 100 percent for the specified requirement in accordance with 4.4.11.4. Any assembly classed defective shall be removed from the lot. (Non-destructive test)

4.3.3.11.5 Hardness - (see dwg. 9281630) - Major Defect - Code No. 13013. - Ten (10) assemblies shall be randomly selected from each lot and tested in accordance with 4.4.11.5. The lot shall be rejected if one (1) or more assemblies are classed defective (Non-destructive test).

4.3.3.12 Fuze Well Hardness (see dwg. 9281633) - Major Defect - Code No. 16019. - Ten (10) fuze wells shall be randomly selected from each lot and tested in accordance with 4.4.12. The lot shall be rejected if one (1) or more fuze wells are classed defective (Non-destructive test).

4.3.3.13 Mine Metal Parts Assembly

4.3.3.13.1 Bore Rider Function (see 3.4.1) - Major Defect - Code No. 21009. - Two hundred (200) assemblies shall be randomly selected from each lot and tested for the requirement in accordance with 4.4.13.1. The lot shall be rejected if one (1) or more samples are classed defective. (Non-destructive test).

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the current version before use.

4.4.2 Fin Spring Torque Test. - The spring shall be mounted in an approved fixture to prevent it from rotating. The loads shall then be applied and the displacements measured against the specified angles per specified applied torque. The spring shall not break or crack during the application of the forces and the spring shall return to within ten (10) percent of the original position. Any spring failing to comply with all of the specified requirements shall be classed defective.

4.4.3 The spring wire diameter and the free length shall be measured prior to applying a compressive force. The spring height shall then be measured after it is compressed by applying the specified force. Any spring failing to comply with all of the specified requirements shall be classed defective.

4.4.4 End Fin Hardness Test. - The paint shall be removed from three (3) areas equally spaced across the face of the sample fin. These areas shall then be tested for the specified hardness requirement in accordance with FED-STD-151, Test Method 243.1. Any fin failing to comply with all of the specified requirements shall be classed defective.

4.4.5 End Fin Rotation Test. - The fin and rod specified shall be mated together and the fin shall be free to rotate manually around the rod. Any fin failing to comply with all of the specified requirements shall be classed defective.

4.4.6 Side Fin Hardness Test. - The paint shall be removed from three (3) areas equally spaced across the face of the fin. These areas shall then be tested for the specified hardness requirement in accordance with FED-STD-151, Test Method 243.1. Any fin failing to comply with all of the specified requirements shall be classed defective.

4.4.7 Side Fin Rotation Test. - The fin and rod specified shall be mated together and the fin shall be free to rotate manually around the rod. Any fin failing to comply with all of the specified requirements shall be classed defective.

4.4.8 Bore Rider Assembly Pull Test. - The bore rider assembly shall be held in a fixture and the stop shall be pulled with the specified force. The assembly shall be classed defective if the bore rider comes off of the assembly.

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

4.4.9 The spring wire diameter and the free length shall be measured prior to applying a compressive force. The spring height shall then be measured after it is compressed by applying the specified force. Any spring failing to comply with all of the specified requirements shall be classed defective.

4.4.10 Pressure Plate and Retainer Assembly Air Pressure Test. - The assembly shall be locked into an approved fixture and not show evidence of any leakage when the specified air pressure is applied into the equipment. Any assembly failing to comply with the applicable requirements shall be classed defective.

4.4.11 Mine Body Assembly

4.4.11.1 Chamber Gage Inspection. - The mine body shall have all of its maximum outside dimensions measured simultaneously in an approved chamber gage. Any mine body failing to comply with all of the requirements shall be classed defective.

4.4.11.2 Switch Housing to Mine Body Bond Strength. - The mine body shall be securely fastened in an approved fixture and the specified load applied to the switch housing from the inside of the explosive cavity in a uniform and axial direction. Any item failing to comply with the specified requirement shall be classed defective.

4.4.11.3 Mine Body to Fuze Well Strength. - The filler end shall be removed from the body assembly and the remaining section shall be secured in an approved fixture. The specified force shall be applied equally with an approved fixture pushing on the entire back surface of the fuze well. The rate of travel of the fixture shall be a maximum of one (1) inch per minute. The sample shall be classed defective if it fails to comply with all of the specified requirements.

4.4.11.4 Leak Test. - The mine body assemblies shall then be installed in an approved leak test fixture and submerged in water for twenty (20) seconds, with the explosive cavity pressurized as specified. The explosive cavity shall indicate no leaks. Any mine failing to comply with the specified requirement shall be classed defective.

4.4.11.5 Hardness Test. - Hardness tests shall be performed on three (3) equally spaced points on the curved surface of the body in accordance with Test Method 242.1 of FED-STD-151. Any assembly failing to comply with the applicable drawing requirements shall be classed defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

4.4.12 Fuze Well Hardness Test. - Hardness tests shall be performed on three (3) equally spaced points on the curved surface of the sample, and three (3) equally spaced points on the flat surface of the fuze housing. Testing shall be in accordance with Test Method 242.1 of FED-STD-151. Any fuze well failing to comply with the applicable drawing requirements shall be classed defective.

4.4.13 Mine Metal Parts Assembly

4.4.13.1 Bore Rider Function. - The Bore Rider function shall be tested by placing the Mine Assembly in a suitable holding fixture and manually removing the bore rider clip to allow free movement of the bore rider. With clip removed, bore rider shall extend immediately to where the bore rider stop touches the bore rider bushing. Any sample that fails to comply with all of the requirements shall be classed defective.

4.4.13.2 Over-run Switch Function Test. - The test sample shall be positioned in an approved fixture and the specified load shall be gradually applied to the pressure plate with a .125 ± .020 spherical tip and within ± .25 inch of the plate's geometric center. An ohmmeter shall be placed between the switch common (C) and normally closed (NC) and another ohmmeter between the switch common (C) and normally open (NO) terminal at flex cable pin locations. The meter reading across C and NO must not exceed 2 ohms and across C and NC must indicate an open circuit when the load as specified is applied. The pressure plate loading shall continue to be gradually applied up to the load specified until the ohmmeter reading across C and NO indicates an open circuit and across C and NC does not exceed 2 ohms. The load shall then be removed and the readings as specified for the non-function test shall apply. Mines failing to comply with all the specified requirements shall be classed defective.

4.4.13.3 Leakage Test. - The mine body shall be pressurized and submerged in water for the required time, and observed for evidence of leaks at the switch housing and fuze well. The assembly shall be classed defective if the assembly shows leakage at any bonded section.

4.4.14 Flex Cable Assembly Overrun

4.4.14.1 Continuity Resistance. - The cable assemby shall be measured for the specified resistance using a digital readout

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the currentversion before use.

milliohmmeter. Any cable assembly that has resistance in excess of the specified maximum value shall be classed defective.

4.4.14.2 Insulation Resistance. - The cable assembly shall be measured for the specified insulation resistance by applying five hundred plus fifty volts direct current (500 + 50 v.d.c.) between one cable trace and all the other traces tied together (that are not part of the single trace under test). A microammeter shall measure any leakage current resulting from the 500 v.d.c. potential. The cable shall be classed defective if the leakage current exceeds two (2) microamperes. After the one trace is tested for insulation resistance, with respect to the rest of the cable, the other points (traces) shall be tested in a similar manner to measure their insulation with respect to the other traces. If any measurement exceeds the 2 microamperes at 500 v.d.c., it too, shall be classed defective.

4.4.15 Plunger Assembly Torque Test. - The assembly shall be mounted in an approved fixture and the torque specified shall be gradually applied. The assembly shall be monitored for any rotational movement as the torque is applied. Any assembly having any movement shall be classed defective.

5. PREPRATIONS FOR DELIVERY

5.1 Preservation and Packaging.

5.1.1 Level C. - The Mine, Anti-tank Metal Parts Assembly shall be packaged in accordance with MIL-STD-1169.

5.2 Packing

5.2.1 Level C. - The Mine, Anti-tank Metal Parts Assembly shall be packed for shipment in accordance with MIL-STD-1169.

5.3 Marking. - Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping. - When Mine, Anti-tank Metal Parts Assemblies of more than one lot are shipped together each lot shall be kept separate and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards. - Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. They should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4. Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.
b. A source control drawing or a specification control drawing as defined in MIL-STD-100.
c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detailed design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the

Source: https://assist.dla.mil -- Downloaded: 202640-22T19:21Z
Check the source to verify that this is the current version before use.

general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of Designs for Approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SARPA-QA-A-M, Dover, New Jersey 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List (DD Form 1423) or in the contract. The contractor must include in his submission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 Submission of Results of Contractor Conducted Examinations and Tests (see 3.6). - The contractor shall send his results to:

Commander
Picatinny Arsenal
ATTN: SARPA-QA-A-M
Dover, New Jersey 07801

Custodian:
Army-PA

Preparing Activity:
Army-PA

Project No. 1345-A043

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY
PICATINNY ARSENAL
DOVER, NEW JERSEY 07801

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314



COMMANDER
Picatinny Arsenal
ATTN: SARPA-QA-A
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-22T19:21Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:21Z
Check the source to verify that this is the current version before use.