MILITARY SPECIFICATION
CHARGE, DEMOLITION, H.E., LINEAR, M58, W/FUZE AND CHARGE, DEMOLITION, INERT, LINEAR, M68, W/INERT FUZE, FOR LVTE7 ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the assembling and packing ior one type of mine clearing device designated as Charge, Demolition, H.E., Linear, M58, W/Fuze, and Charge, Demolition, Inert, Linear, M68, W/Inert Fuze, for LVTE7.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for

STANDARDS

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

9275940 - Charge, Demolition, H.E., Linear, M58, W/Fuze, and Charge, Demolition, Inert, Linear, M68, W/Inert Fuze.

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET-9275940 - Equipment Tabulation

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Demolition charge.-The demolition charge shall comply with all requirements specified on Drawing (dwg.) 9275940 and with all requirements specified in applicable specifications.

3.3 Continuity of shorted circuit.-The resistance of the shorted electrical circuit shall be not more than two-tenths of an ohm when measured at the anchor end and not more than one ohm when measured at the fuze end. The test shall be performed as specified in 4.3.1.

3.4 Workmanship.-All parts shall be fabricated and finished in a thorough workmanlike manner. They shall be clean and free of burrs, sharp edges, unblended radii, surface defects, chips, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few slight scratches. All required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

in the specification where such inspections are deemed necessary to assure supplies and services confrom to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items in the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 Inspection provisions

4.2.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and the same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of the inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each lot shall contain:

a. Linear charges from not more than one lot produced by one manufacturer.

4.2.2 Examination.-The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.2.1) of the components or assemblies designated in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.2.4.

4.2.2.1 Rocket harness connector (see dwg. 8845259 covering a detail of dwg. 9275940).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Diameter of large hole	Gage	01001
102.	Width of large slot, min	Gage	01002
103.	Depth of large slot, min	Gage	01003
Minor:	AQL 1.50 percent		
201.	Missing operation	Visual	01004
202.	Protective coating missing or inadequate	Visual	01005
203.	Evidence of poor workmanship (see 3.4)	Visual	01006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

4.2.2.2 Charge with fuze, prior to assembling charge (see dwg. 9275940).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical: None defined			
Major:	AQL 0.40 percent		
101.	Arresting cable not flat	Visual	02001
102.	Arresting cable improperly faked	Visual	02002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	02003

4.2.2.3 Charge, with fuze, after assembly of charge (see dwg. 9275940).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined			
Major:	AQL 0.65 percent		
101.	Linear charge improper type	Visual	03001
102.	Faking of first layer improper	Visual	03002
103.	Layer not reverse faked	Visual	03003
104.	Insufficient slack at fuze connector or arresting cable assembly	Manaul	03004
Minor:	AQL 1.50 percent		
201.	Spare parts bag not stapled to cover	Visual	03005
202.	Component missing	Visual	03006
203.	Evidence of poor workmanship (see 3.4)	Visual	03007

4.2.2.4 Demolition charge, prior to assembling cover (see dwg. 9275940).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Warning stencil on container cover or back missing or illegible	Visual	04001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Fuze missing or improper type	Visual	04002
Minor:	AQL 1.00 percent		
201.	Fuze insecure	Manual	04003
202.	Evidence of poor workmanship (see 3.4)	Visual	04004

4.2.2.5 Charge, with fuze (see dwg. 9275940).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Cover fastener inoperable	Manual	05001
Minor:	AQL 1.50 percent		
201.	Cover fastener not tight	Manual	05002
202.	Marking color incorrect	Visual	05003
203.	Marking missing, misleading or unidentifiable	Visual	05004
204.	Evidence of poor workmanship (see 3.4)	Visual	05005

4.2.2.6 Charge, with fuze, strapped (see dwg. 9275940).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 percent		
201.	Strapping loose, broken or improperly applied	Visual-Manual	06001
202.	Destination marking missing, misleading or unidentifiable	Visual	06002

4.2.3 Testing

4.2.3.1 Continuity of shorted circuit (see 3.3) - Major defect, Code No. 07001.-This test shall be performed one-hundred percent on the electrical circuit of the arresting cable assembly. Any assembly which fails to comply with the applicable requirement

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

shall be classed defective and removed from the lot. The test shall be performed as specified in 4.3.1 using equipment in accordance with 4.2.4.

4.2.4 The inspection equipment required to perform the examinations and tests prescribed in this section is identified by Equipment Tabulation ET-9275940 (see 6.3).

4.3 Test methods and procedures

4.3.1 Continuity of shorted circuit.-The resistance of the shorted electrical circuit of the arresting cable assembly shall be measured across the terminals at both the anchor end and the fuze end. Observation shall be made to determine compliance with the applicable requirement. Test equipment shall be in accordance with 4.2.4.

5. PREPARATION FOR DELIVERY

5.1 Packing

5.1.1 Level A, B or C.-Packing shall be in accordance with drawing 9275940.

5.2 Marking.-Marking shall be in accordance with 9275940.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five-digit code numbers assigned to the inspection herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. These code numbers shall be listed on drawings of equipment designs submitted by the contractor.

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers on the Equipment Lists referenced on the Equipment Tabulation. Design responsibility for all other inspection equipment is assigned to the contractor. Equipment to be designed by the contractor is designated "CD". The

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100 which establishes the criteria which a detail design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public.) Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five-digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of designs for approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SMUPA-QA-A-M, Dover, New Jersey, 07801 in accordance with the stipulations, time frame and distribution specified in the Contract Data Requirements List

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.

(DD Form 1423) or in the contract. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

Custodian:
Army-MU

Preparing Activity:
Army-MU

Project Number: 1375-A-018

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:13Z
Check the source to verify that this is the current version before use.