MIL-C-3776A
4 APRIL 1960
SUPERSEDING
MIL-C-3776
20 JUNE 1952

MILITARY SPECIFICATION

CABLE LASHING MACHINE LC-231( )/FT

This specification has been approved by the Department of Defense and is mandatory for use by the Departments of the Army, the Navy, and the Air Force.

1. SCOPE

1.1 This specification covers a cable lashing machine designated Cable Lashing Machine LC-231( )/FT which consists of a cylindrical, aluminum-alloy frame fitted with grooved, rubber-tired carriage and steel traction wheels geared to a rotating drum containing (2) lashing wire bobbins.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

FEDERAL

PPP-B-621 — Boxes, Wood, Nailed and Lock-Cover.

PPP-T-76 — Tape, Pressure sensitive, Adhesive, Paper, Water-Resistant.

PPP-P-291 — Paperboard, Wrapping, with Cushioning Value.

PPP-B-601 — Boxes, Wood, Cleated-Plywood.

PPP-B-636 — Boxes, Fiber.

PPP-B-585 — Boxes, Wood, Wirebound.

PPP-B-591 — Boxes, Fiberboard, Wood Cleated.

MILITARY

MIL-P-116 — Preservation, Methods of.

MIL-B-117 — Bags, Interior, Packaging.

MIL-L-3503 — Lubricating oil, preservative, light.

MIL-C-10377 — Boxes, Wood, Cleated, Veneer, Paper Overlaid.

MIL-M-13231 — Marking of Electronic Items.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Tables of Inspection by Attributes.

FSC 3895

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

MIL-STD-129 — Marking for Shipment and Storage.

MIL-STD-130 — Identification Marking of U. S. Military Property.

MIL-STD-170 — Moisture Resistance Test Cycle for Ground Signal Equipment.

(Copies of specifications, standards, drawings and publications required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

Consolidated classification committee.

Uniform Freight Classification
Consolidated Freight Classification

(Application for copies should be addressed to the Consolidated Classification Committee, 202 Union Station, Chicago 6, Ill.)

American Trucking Association, Inc.

National Motor Freight Classification

(Application for copies should be addressed to the National Classification Board, 1424 Sixteenth Street, N. W., Washington 6, D. C.).

3. REQUIREMENTS

3.1 Preproduction samples. The contractor shall furnish preproduction samples for approval, as required by the invitation for bids and contract.

3.1.1 *Manufacture.* Preproduction samples shall be made and assembled by tools and methods that, as far as practicable, are the same as those which will be used for quantity production of the equipment.

3.1.2 *Compliance with specified requirements.* Preproduction samples shall be accompanied by a statement that they meet specified requirements for the equipment. Approval of preproduction samples shall not be construed as a waiver of any specified requirement. Any changes or deviations of production units from the preproduction model shall be subject to the approval of the contracting officer.

3.1.3 *Disapproval.* When any samples are disapproved, the contractor will be required to submit additional samples until satisfactory samples have been submitted. Such modified samples shall be accompanied by a description of the changes which have been incorporated in the new samples in order to correct the faults of the rejected samples.

3.1.4 *Reference standards.* After preproduction samples have been approved and returned to the contractor's plant, they shall be kept intact and under the control of the Government inspector until released by him. They shall be used as reference standards to resolve any differences of opinion regarding interpretation of specified requirements.

3.1.5 *Marking and shipping.* Samples shall be marked and shipped by the contractor as specified (see 6.2).

3.2 Procurement model. A procurement model of the item on contract will be available for inspection by prospective bidders and will be lent to the contractor. Unless otherwise specified herein or in the invitation for bids, the item on contract shall conform to the following:

3.2.1 *Construction.* Physical construction of the item on contract shall conform to the procurement model.

3.2.2 *Features.* The item on contract shall incorporate all features of the procurement model.

3.2.3 *Design requirements.* The unit shall incorporate a high strength aluminum alloy cast frame, stainless steel bearing plates, direct gear drive and sealed-for-life

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

precision ball bearings. The total weight of the cable lashing machine, less the two (2) lashing wire bobbins, shall not exceed thirty five (35) pounds.

3.2.4 *Performance.* In case of conflict between specified performance characteristics specified herein and the performance of the procurement model, the former shall govern.

3.3 Service conditions. The equipment shall meet the following service conditions:

3.3.1 *Equipment nonoperating.* The equipment shall comply with the operational requirements of 3.3.2 after subjection to any of the following nonoperating conditions successively or in combinations likely encountered during worldwide short-term storage and transit:

(a) Temperature. Exposure in range of +160°F. to —80°F.; however, exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 24 hours at any one time.

(b) *Relative humidity.* Relative humidity up to 97 percent, for an indefinite period of time; and exposure at 100 percent relative humidity, with condensation, for 4 hours.

3.3.2 *Equipment operating.* The equipment shall meet the performance requirements of this specification while subjected to any of the following conditions successively or in combinations likely to be encountered during worldwide operations:

(a) *Temperature.* Ambient temperature in the range of +132°F. to —25°F. (The 132°F. temperature includes effect of sun-load. Exposure at the high temperature extreme not to exceed 4 hours and at the low temperature extreme not to exceed 72 hours.)

(b) *Relative humidity.* Relative humidity up to 97 percent; and exposure at 100 percent humidity with condensation, for 4 hours.

3.4 Carrying case. The unit shall be provided with a carrying case fitted to support the machine and hold it securely in transit. The case shall have a snug-fitting cover and be provided with a latch and handle, and shall conform to the case provided with the procurement model.

3.5 Marking.

3.5.1 *General.* Marking shall conform to Specification MIL–M–13231 or MIL–STD–130.

3.5.2 *Visibility.* Wherever practicable, parts and assemblies shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.5.2 *Serial number.* The cable lasher shall be serial numbered.

3.6 Ruggedness and reliability. All parts and details of construction shall have the maximum of ruggedness and reliability under all operating conditions. The equipment shall be so constructed that it will withstand long periods of service and repeated rough handling in transportation, with a minimum of damage.

3.7 Technical literature, tools, and running spare parts. Technical literature, tools, and running spare parts shall be furnished as specified in the contract. (See 6.2). Running spare parts shall be identical to corresponding parts in the items furnished on the order.

3.8 Standard parts. AN and MIL standard parts shall be used whenever they are suitable for the purpose and shall be identified by their part numbers. Commercial, utility parts such as screws, bolts, nuts, cotter pins etc., may be used provided they have suitable

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

properties and are replaceable by the AN and MIL part numbers and the part numbers are referenced on the drawings and in the parts listed. In applications for which no suitable corresponding AN and MIL part is in effect on the date of invitation for bids, commercial parts may be used provided they conform to the requirements of this specification.

3.9 Interchangeability. All parts having the same manufacturer's part number shall be directly and completely interchangeable with one another with respect to installation and performance.

3.10 Workmanship. The item shall be manufactured and assembled in accordance with the applicable portions of the following paragraph herein: (see 4.5).

3.1.1 Manufacture

3.2.1 Construction

3.2.2 Features

3.2.3 Design

3.4 Carrying Case

3.5 Marking

3.5.1 General

3.5.2 Visibility

3.6 Ruggedness

3.7 Technical literature, tools, and running spare parts.

4. QUALITY ASSURANCE PROVISIONS

4.1 Contractor responsibility. Unless otherwise specified herein the supplier is responsible for the performance of all inspection requirements prior to submission for Government inspection and acceptance. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order.

4.2 Classification of inspection. Inspection shall be classified as follow:

(a) Preproduction inspection (see 4.3).
(b) Acceptance inspection. (see 4.4).
(c) Acceptance inspection of preparation for delivery. (see 4.10).

4.3 Preproduction inspection. This inspection will be performed by the contractor unless otherwise specified in the contract. It shall consist of the preproduction inspection specified in Table I and the Group A and B inspection specified in Tables II and III respectively. (see 6.2).

TABLE I. *Preproduction inspection*

Inspection	Requirement paragraph	Inspection paragraph
Equipment nonoperating	3.3.1	4.7 thru 4.9
Equipment operating	3.3.2	4.7 thru 4.9

4.4 Acceptance inspection of items before preparation for delivery. The contractor shall perform the inspection specified by (a) and (b) below, to demonstrate compliance with specified requirements. However, this does not relieve the contractor of his responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The government will review and evaluate the contractor's procedures and examine the contractor's inspection records. In addition, the Government—at its discretion—may perform all or any part of the inspection specified in (a), to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specified procurement inspection. Also see (6.4)).

(a) Acceptance inspection shall consist of group A and group B inspec-

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

tion as specified in (4.4.1 and 4.4.2).

(b) Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection.

4.4.1 *Group A inspection.* The inspection (including sampling) shall conform to Table II and Standard MIL–STD–105. Unless otherwise specified, normal inspection shall be used at the start of the contract. Group A inspection shall be performed in any order which is satisfactory to the Government.

TABLE II. *Group A Inspection*

Inspection	Requirement paragraph	Inspection paragraph	AQL	
			Major	Minor
Visual and mechanical**	3.8	4.5 thru 4.5.12	1.5 dphu*	4.0 dphu*

* Defects per hundred units.
** All mechanical defects found during the mechanical tests 4.5.1 thru 4.5.12 are considered major.

4.4.2 *Group B inspection.* This inspection (including sampling) shall conform to table III and the Appendix to Standard MIL–STD–105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. Acceptable Quality Level (AQL) shall be of 10.0% defective with inspection level L–6 for normal and tightened inspection and L–4 for reduced inspection. The reduced inspection procedure shall be R–1. Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with 4.4.3 and the requirements of Standard MIL–STD–105 for disposition of rejected product.

TABLE III. *Group B inspection*

Inspection	Requirement paragraph	Test paragraph	AQL
Performance ..	3.2.4	4.5	10.0% *

* All defects considered major.

4.4.3 *Disposition of nonconforming product.* When defective sample units of failed inspection lots are submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.5 Visual and mechanical inspection. The machines shall be visually and mechanically inspected to determine compliance with 3.8. Mechanical inspection shall include the following examinations and tests:

4.5.1 When the strand-riding unit of each lasher is held against rotation, and the front cable lifter is closed, the drum shall revolve smoothly without binding or excessive friction when turned by hand. There shall not be more than (.025) of an inch play between the drum and the strand riding unit. When this play is taken up by the moving drum as far as possible to the rear of the lasher, all radial and thrust bearing rollers shall revolve when the drum is turned.

4.5.2 The drum locking pin of each lasher shall operate freely, and when engaged, the slot in the drum shall align within $\frac{1}{32}$ of an inch with the slots in the strand-riding unit.

4.5.3 The strand tensioning roller assembly of each lasher shall operate freely. When a ($\frac{9}{32}$) inch diameter drill rod simulating strand is placed in the lasher with the front cable lifter closed and the roller engaged, the drum shall rotate continuously as the rod is pulled from the rear of the lasher and not more than (15) inch length of rod shall pull out for (1) revolution of

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

the drum. When a ($1\frac{3}{32}$) inch diameter drill rod is placed in the lasher, it shall be possible to engage the roller and move the locking lever to the closed position.

4.5.4 The four snubbing pulleys mounted on the drum of each lasher shall be assembled so that their inner flanges are not more than ($\frac{1}{64}$) inch over flush of the drum surfaces, nor more than ($\frac{1}{32}$) inch under flush.

4.5.5 The front and rear cable lifters of each lasher shall lock securely in the closed position and shall open with finger pressure on their latches. They shall not move from the completely open position under the action of gravity.

4.5.6 When each lasher is placed on a $\frac{9}{32}$-inch diameter rod, simulating strand, with the strand tensioning roller engaged and the front cable lifter closed, the brake shall not permit more than $\frac{1}{8}$-inch movement of the lasher when a force of 30 pounds parallel to the rod and directed toward the rear of the lasher is applied to the lasher.

4.5.7 The brake of each lasher shall clear the periphery of the rear strand drive wheel by at least $\frac{1}{32}$ inch when the front cable lifter is opened, and, also, with the front lifter closed, when the pulling plate is rotated downward against the stops.

4.5.8 The grooves of the strand drive wheels and rear strand roller of each lasher shall be so aligned that when $1\frac{3}{32}$-inch diameter drill rod is placed in them and the side play taken up at the rear roller, the clearance between the rod and the sides of the slot in the front of the lasher shall not be less than $\frac{1}{32}$ inch.

4.5.9 The adjusting screw for the vertical cable rollers of each lasher shall turn through its complete travel, when operated with the fingers. However, the torque required to turn the screw shall not be less than 2 pound inches.

4.5.10 It shall be possible to place a $5\frac{9}{16}$ inch outside diameter by two (2) inch inside diameter by $1\frac{3}{4}$ inch thick rubber disc, of the same composition as the strand drive wheels, in the coil recesses of each lasher, and readily close and lock the coil covers in place.

4.5.11 The gears of all lashers shall be securely pinned to their shafts with steel taper pins. All bolts, nuts, screws, and pins shall be set up tight. All lock washers and cotter pins shall be assembled so as to securely lock the parts in place.

4.5.12 When lashing wire is placed in either of the coil recesses and the cover closed and locked in place, wire from the center of the coil shall pull smoothly through the throat in the cover without binding. When the wire is threaded around the snubbing pulleys it shall pull smoothly off the pulleys and there shall be no abrading of the wire at the crossover point or rubbing of the wire against any part of the lasher at any point along its path. When the lasher is placed on a $\frac{9}{32}$ inch diameter rod, simulating strand, and the wire brought around the pulleys and terminated on the rod 8 inches behind the rear cable lifter, the wire shall clear the rear of the lasher throughout the complete rotation of the drum.

4.6 **Operational inspection.** Samples submitted per 3.1 shall be loaded with lashing wire and used to lash cable to messenger wire strung to poles for a distance of not less than 10 feet.

4.6.1 The machine shall be stopped and drag line slacked at least three times on the upgrade for the purpose of checking the promptness with which the reverse brake comes into action. This should occur immediately so that no slack appears in the lashing wire, although a light lessening of tension in the last turns without an accompanying total loss of contact shall not be considered as brake failure.

4.6.2 The pitch of the lashing (the dis-

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

tance between turns) shall be measured and compared with the establishment pitch of the model (3.2) operated on the same messenger and cable. The pitch shall not vary more than 10 percent, plus or minus, from that of the model.

4.6.3 During the progress of this test, the cable guides shall be inspected to insure that they properly position the cable against the messenger strand. Any failure to support or center the cable shall be the subject of corrective action.

4.6.4 The overall operation shall be carefully checked for ease of operation, freedom from vibration, maintenance of proper tension, and functioning of gate and rotation locks. Any departure from the operation of the model shall be noted and appropriate corrective action taken.

4.7 **High temperature.** The equipment shall be maintained for 4 hours in a chamber at an ambient temperature of +160°F. The temperature shall then be lowered to +132° F. and stabilized for 4 hours. The equipment shall then be subjected to the tests of paragraph 4.6.

4.8 **Low temperature.** The equipment shall be maintained for 4 hours in a chamber at an ambient temperature of —80°F. The temperature shall then be raised to —25°F. and stabilized for 4 hours. The equipment shall then be subjected to the tests of paragraph 4.6.

4.9 **Relative humidity.** The equipment shall be tested as follows:

Test Method

(a) Dry at +130°F. ±5°F. for 12 hours.

(b) Condition at +77°F. ±5°F. and 40 to 50 percent relative humidity for 24 hours.

(c) Perform test of paragraph 4.6.

(d) Subject to continuous cycling for one 48 hours cycle. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Standard MIL–STD–170(SigC). The test specified in paragraph 4.6 shall be made during the periods shown on the standard and shall comply with paragraph 4.6.

4.10 **Acceptance inspection of preparation for delivery.** The contractor shall perform the inspection specified by 4.7.1 and 4.7.2 to demonstrate compliance with specified requirements. However, this does not relieve the contractor of responsibility for performing any additional inspection which is necessary to control the quality of the product and to assure compliance with all specification requirements. The Government will review and evaluate the contractor's inspection procedures and examine the contractor's inspection records. In addition, the Government—at its descretion—may perform all or any part of the inspection specified in 4.10.1 and 4.10.2 to verify the contractor's compliance with specified requirements. (The amount of such verification inspection will depend on the extent to which the contractor's inspection procedures and records insure that the equipment on contract meets the specified procurment inspection. Also see 6.4).

4.10.1 *Preservation and packaging.* Inspection of preservation and packaging shall be as specified in Specification MIL–P–116. Classification of defects shall be as shown in Table III.

TABLE III

Major

1. Use of improper or defective material.
2. Quantity in unit package not as specified.
3. Incorrect packaging method applied.
4. Cushioning or padding omitted.
5. Cushioning inadequate for the physical and mechanical protection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

6. Unsealed, punctured, or improperly sealed barrier bag, or envelope.
7. Stock number omitted, incorrect or illegible.
8. Nomenclature omitted, incorrect, or illegible.
9. Marking of quantity of items in package omitted, incorrect or illegible.
10. Different stock numbered items in the same unit package.

Minor

1. Item not properly blocked or braced within the unit package to prevent movement.
2. Packaging material damaged.
3. Conforming wraps are not snugfitting and contain voids.
4. Any item of marking information other than 7 thru 9 omitted, incorrect, or illegible.

4.10.2 ***Packing and marking of exterior containers.*** Packing and marking of exterior containers shall be given visual inspection for the defects listed below and to determine conformance with the approved process sheets furnished by the contractor as required by the contract. This inspection shall conform to the appendix to Standard MIL–STD–105. Inspection level L-8 shall be used for normal inspection and L–6 for reduced inspection. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R–1. The AQL for major defects shall be four percent and the AQL for minor defects shall be ten percent. Classification of defects shall be as shown in table IV.

TABLE IV

Major

1. Use of improper or defective material.
2. Quantity in pack not as specified.
3. Box closure not as specified.
4. Type, grade, class, and style of the shipping container not as specified.
5. Strapping omitted.
6. Strapping inadequate or incorrectly applied.
7. Items not adequately blocked, braced or cushioned within the shipping container to prevent movement or damage.
8. Shipping documents or packing list omitted.
9. Stock number omitted, incorrect, or illegible.
10. Nomenclature omitted, incorrect, or illegible.
11. Marking of quantity of items in pack omitted, incorrect, or illegible.
12. Destination marking omitted, incorrect, or illegible.
13. Service designation (color marking) omitted.
14. Specified special marking and labeling such as MAP labels, shipment digit markings, etc., omitted, incorrect, or illegible.
15. Overseas code marking omitted, incorrect, or illegible.

Minor

1. Unsealed carton.
2. Defective taping or sealing of carton.
3. Any other box defect which may be considered minor by definition of Standard MIL–STD–105.
4. Any item of required marking information other than 9 thru 15 listed under major defects omitted, incorrect, or illegible.

4.10.2.1 *Inspection lot.* A lot for visual inspection of the pack shall be all completed packs which are identical and will be submitted for acceptance at one time.

4.10.2.2 *Disposition of nonconforming product.* Disposition of nonconforming product (sample units and inspection lots) shall be in accordance with the requirements of Standard MIL–STD–105 for disposition of rejected product. When submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is submitted and shall become the property of the Government.

4.11 Navy department inspection. For naval purchases, the general inspection pro-

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

cedures shall be in accordance with the General Specifications for inspection of Material.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 *Level A.* Cable Lashing Machine, LC–231( )/FT shall be preserved, packaged and tested in accordance with the procedures specified for the designated methods as prescribed in Specification MIL–P–116 and as described herein.

5.1.1.1 *Technical manual.* Each technical manual shall be packaged Method IC–3 as follows: Inclose each technical manual within a close-fitting, type I, class b, bag, conforming to Specification MIL–B–117. Heat seal the bag to effect closure.

5.1.1.2 *Accessories, tools and spare parts.* Accessories, tools and spare parts, determined in quantity and number from the bid request or contract, shall be packaged in accordance with the applicable provisions of Specification MIL–P–116.

5.1.1.3 *Stowage within transit case.* Stow and secure accessories and the lashing machine within the case. As required, fill all voids with pads fabricated of single face, flexible, corrugated, fiberboard, type III, forming to Specification PPP–P–291. Close the case and secure all fastenings. Prior to storage, unpainted ferrous metal surfaces of the Cable Lashing Machine shall be coated with P–8 light preservative oil conforming to Military Specification MIL–L–3503.

5.1.1.4 *Case with contents.* Each case with contents shall be packaged Method IC–5 as follows: Cushion each case on all surfaces with cells or pads, or both, fabricated of double faced corrugated fiberboard, and designed to absorb the shock of impact encountered in handling and transit. Cells and pads shall have dry bursting strength and water resistant qualities equal to the box in which they will be used. Place the cushioned case within a close-fitting, regular, slotted style, corrugated, fiber, box, class 2, W5c, conforming to Specification PPP–B–636. Box closure shall be effected by the application of water resistant, pressure sensitive, tape, conforming to Specification PPP–T–76, to all seams, corners and joints.

5.1.2 *Level C.* Cable Lashing Machine, LC–231( )/FT, shall be packaged in accordance with commercial practice, and in a manner that will afford protection against corrosion, deterioration and physical damage, during direct shipment to the first receiving activity.

5.2 Packing.

5.2.1 *Level A.* Cable Lashing Machine, LC–231( )/FT, shall be packed for shipment, one each, within a close-fitting overseas class or type, wood, wirebound, box; a fiberboard wood cleated box; or a wood cleated plywood box; a wood, nailed and lock corner box; a fiber box, or a wood cleated, veneer paper overlaid box, conforming to Specification PPP–B–585, PPP–B–591, PPP–B–601, PPP–B–621, PPP–B–636 or MIL–B–10377. Place the technical manual (see 5.1.1.1) between the contents and lid of the box. Box closure and strapping shall be in conformance with the applicable box specification or appendix thereto.

5.2.2 *Level B.* Cable Lashing Machine, LC–231( )/FT, shall be packed for shipment as specified in 5.2.1, except boxes shall be domestic class or type. No strapping required.

5.2.3 *Level C.* Cable Lashing Machine, LC–231( )/FT, shall be packed for shipment in a manner conforming to the requirements of Uniform Freight Classification No. 4 and Consolidated Freight Classification Rules 21 for rail shipment, National Motor Freight Classification No. A-3 and No. 14 for truck shipment, and the regulations of other carriers, as applicable to the mode of transportation employed at the lowest transportation rate.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

5.3 Marking. Interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL–STD–129.

6. NOTES

6.1 Intended use. This machine is designed to lash lead-covered telephone cable to steel messenger cable on pole line construction of communication circuits. It can accommodate from 5/16 inch to 7/16 inch diameter messenger and up to 1 5/8 inch cable. It can also be used to lash other forms of communication wire or cable not more than 1 5/8 inch diameter. The machine is provided with 2 bobbins each designed for a capacity of 1200 feet of .045 diameter lashing wire.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification and any amendment thereto.

(b) Level of packaging and level of packing required for shipment. (Level A, level B or level C).

(c) Preproduction inspection.

1. Marking and shipping of sample. (See 3.1.5.)
2. Place of final inspection, if other than contractor's plant.

(d) Technical literature required. (See 3.7).

(e) Quantity of tools and running spares required. (3.7.)

(f) Whether marking shall conform to MIL–M–13231 or MIL–STD–130, or both. (See 3.5.1).

6.3 Nomenclature. The parentheses in the nomenclature, will be deleted or replaced by a letter identifying the particular design; for example LC–231/FT. The contractor should apply for nomenclature in accordance with the applicable clause in the contract.

6.4 Verification inspection. Verification by the Government will be limited to the amount deemed necessary to determine compliance with the contract and will be limited in severity to the definitive quality assurance provisions established in this specification and the contract. The amount of varification inspection by the Government will be adjusted to make utilization of the contractor's quality control system and the quality history of the product, and will normally be identified by the categories listed below:

(a) *Type A.* The total of that inspection set forth in the Quality Assurance Provisions of this specification or the contract. Included in the category is that amount of inspection referred to as normal and tightened inspection by Military Standard MIL–STD–105.

(b) *Type B.* That inspection set forth in the Quality Assurance Provisions of this specification or the contract reduced in amount under the reduced inspection provisions of Military Standard MIL–STD–105.

(c) *Type C.* A reduced inspection procedure resulting in a material reduction in the amount of inspection set forth in the Quality Assurance Provision of this specification. The amount of inspection is less than that provided for the type B and is based upon a consistently acceptable product resulting from a planned quality control system voluntarily employed by the contractor in the production of this product.

6.5 Commercial equivalent. This machine is the commercial equivalent of the Bell Telephone System type C Cable Lashing Machine.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.

Notice. When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Custodians:
Army—Signal Corps
Navy—Bureau of Yards and Docks
Air Force—Memphis Air Force Depot

Preparing activity:
Army—Signal Corps

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:28Z
Check the source to verify that this is the current version before use.