MIL-M-46310A(MU)
8 September 1969
SUPERSEDING
MIL-M-46310(Ord)
28 April 1961

MILITARY SPECIFICATION

MOUNT, TELESCOPE: M137

1. SCOPE

1.1 This specification covers performance requirements, quality assurance provisions, and packaging data relative to a telescope mount designed primarily to provide adjustments in pitch and to compensate for angles of cant for indirect fire (see 6.1).

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

Military

MIL-F-13926	Fire Control Materiel: General Specification Governing the Manufacture and Inspection of
MIL-P-14232	Parts, Equipment and Tools for Army Materiel, Packaging and Packing of
MIL-I-45607	Inspection Equipment, Supply and Maintenance of

STANDARDS

Military

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-109	Quality Assurance Terms and Definitions
MIL-STD-130	Identification Marking of U.S. Military Property
MIL-STD-202	Test Methods for Electronic and Electrical Component Parts

DRAWINGS

U.S. Army, Frankford Arsenal

F8587295	Mount, Telescope: M137

PACKAGING DATA SHEET

8587295	Packaging of Mount, Telescope: M137

FSC 1240

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, dr: ngs, and packaging data sheets required by suppliers in connection with ecific procurement functions should be obtained from the procuring act.vity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Fabrication.- The mount shall be manufactured in accordance with Drawing F8587295 and drawings pertaining thereto.

3.2 General specification.- The contractor shall be responsible for adherence to the following requirements of MIL-F-13926:

(a) Order of precedence
(b) Dimensions and tolerances
(c) Inorganic protective surface finishes
(d) Part identification and marking
(e) Electrical
(f) Workmanship

3.3 Environmental.

3.3.1 Operating temperature.- The mount shall meet the applicable requirements of 3.4.3 to 3.4.6.1 inclusive while exposed and thermally stabilized at ambient temperatures of +60°Fahrenheit (F) to +90°F. The mount shall then meet the requirements of 3.4.5 at +150° and -40°F, subsequent to which the mount shall meet the requirements of 3.3.2.

3.3.2 Vibration.- The mount positioned and supported in its using position shall be vibrated at a constant frequency of 30 cycles per second with an amplitude of 1/16 inch (1/8 inch total excursion) for a period of 5 minutes plus or minus 15 seconds. Subsequent to vibration, there shall be no evidence of damage or physical failure and the mount shall meet the requirements of 3.4.

3.3.3 Sealing (counter box area).- The counter box area of the mount shall be capable of sustaining an interim pressure of 2.0 ± .2 psi for a period of 2 hours (minimum) without loss of pressure in excess of 0.2 psi.

3.3.4 Rain test.- The mount shall meet the requirements of Procedure I of the rain test of MIL-F-13926.

3.3.5 Purging.- The counter box area of the mount shall be purged with dry nitrogen supplied at a pressure of 2 ± .2 psi until the dew point of the emergent gas is no higher than -25°F. Purging apertures shall be quickly and positively closed to minimize intermingling of external atmosphere upon disconnecting of purging equipment.

3.4 Performance.

3.4.1 Orientation.- The mount shall be positioned and orientated as follows:

(a) The flat mounting surface of the mounting bracket vertical within 10 seconds

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

(b) The locating keyway horizontal within 10 seconds

(c) The elevation and correction counters set at zero

(d) The quadrant seat shall be parallel to the plane of the locating key surface "X" shown on Drawing F8587295 within .2 mil

(e) The top locating surface of the telescope support housing shall be parallel in all planes to surface "X" of the keyway within 0.5 mil

(f) The elevation and cross level vial bubble shall be centered within the width of a graduation line

(g) The level vials shall be illuminated for a minimum of five minutes (utilizing 24 volts) prior to readings and shall remain illuminated during all testing, except during vibration

(h) The centerline passing through the two locating pins on the top surface of the telescope support housing shall be perpendicular to the vertical locating surface of the mounting bracket within 0.5 mil

3.4.2 Movement.

3.4.2.1 Elevation travel.- The mount shall travel through an excursion of at least 1333 mils in elevation and 89 mils in depression from the position established in 3.4.1 when the correction counter is set at zero.

3.4.2.2 Correction counter.- The correction counter shall travel through an excursion of plus and minus 9 mils.

3.4.2.3 Cross level travel.- The cross level knob shall move the mount through a minimum angle of 20 degrees to the right and 20 degrees to the left from the position established in 3.4.1.

3.4.3 Mount rigidity.- With the mount positioned as in 3.4.1, apply a 20 pound load at the right side of the telescope mounting flange in line with the locating pins. Release the load and record the movement. Apply the same load at the left side of the telescope mounting flange in line with the locating pins. Release the load and record the movement. The total movement as indicated by the two readings shall not exceed the values of Table I.

TABLE I

MOVEMENT RIGIDITY

ELEVATION (in mils)	CANT (in degrees)	TOTAL MOVEMENT (in mils)
0	0	.25
800	0	.75
1100	0	1.75
1333	0	3.50

3.4.4 Accuracy.- With the mount positioned in accordance with 3.4.1, the following conditions shall be met.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

3.4.4.1 Plumb travel.- With the cross level vial bubble centered, the line of sight shall not deviate from a plumb line by more than 0.5 mil when the elevation knob is actuated through its full range of movement.

3.4.4.2 Elevation error.- Elevation error shall not exceed 0.5 mil excluding backlash as read in 200 mil increments between zero and 1200 mils.

3.4.4.3 Backlash.

3.4.4.3.1 Elevation mechanism.- Backlash in the elevation mechanism shall not exceed 0.5 mil.

3.4.4.3.2 Cross level mechanism.- Backlash in the cross level mechanism shall not exceed 0.5 mil.

3.4.4.4 Correction counter.- The correction counter shall be checked at plus and minus readings of 2, 5 and 9 mils. The angle of the gunners quadrant seat shall correspond to the correction values within 0.2 mil when the elevation counter is reset to zero reading.

3.4.4.5 Counter alignment.- Variation in the alignment of the numbers in the counter shall not exceed one sixteenth inch (1/16").

3.4.4.6 Correction counter operation.- Plus values of 5 and 9 mils put on the correction counter shall subtract an equal number of mils from the elevation counter. Minus values of 5 and 9 mils put on the correction counter shall add an equal number of mils to the elevation counter.

3.4.5 Operating torques.- The maximum operating torques shall not exceed the values in Table II at temperatures indicated therein.

TABLE II

	At Standard Ambient Temperature of +60°F to +90°F and at +150°F	at -40°F
Cross Level Knob	4 lb-inch min. to 12 lb-inch max.	25 lb-inch max.
Elevation Knob	4 lb-inch min. to 14 lb-inch max.	25 lb-inch max.
Elevation Correction Knob	2 lb-inch min. to 4 lb-inch max.	8 lb-inch max.
Rheostat	1 lb-inch max.	3 lb-inch

3.4.6 Correction.

3.4.6.1 Cant correction.- The mount shall make left and right cant correction in accordance with the values in Table III. The elevation

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

counter shall read within plus or minus 0.5 mil of the elevation angle of the quadrant seat.

TABLE III

CANT CORRECTION

QUADRANT ELEVATION (in mils)	CANT ANGLE (in mils)	CORRECTION (in mils)	TOLERANCE (in mils)
500	177.8	96.1	0.5
800	177.8	180.5	1.0
1000	177.8	271.9	2.0

3.4.7 Electrical.

3.4.7.1 Illumination.- The bulbs for the level vials and counters when energized with 24 volts shall provide sufficient illumination for the level vial markings and counter numbers to be clearly defined when observed in a darkened area.

3.4.7.2 Insulation resistance.- Insulation resistance shall not be less than 10 megohms when subjected to a direct potential of 100 Vdc ± 10% for a 2 minute period.

3.4.7.3 Continuity.- The continuity of the wiring shall be checked for conformance with applicable wiring and continuity drawing requirements.

3.5 Identification marking.- Identification marking unless otherwise specified, shall be in accordance with MIL-STD-130.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.- Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 General provisions.- The component and subassembly inspection requirements of MIL-F-13926 form a part of the Quality Assurance Provisions of this specification. Definitions of inspection terms shall be as listed in MIL-STD-109.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

4.2 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the contract. The sample for first article approval tests shall consist of three (3) mounts plus 3 each of all items covered by SQAPs. The sample shall be manufactured in the same manner, using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing, shall be obtained from the same source of supply as used in regular production.

4.2.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials.

4.2.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection.

4.3 Inspection provisions.

4.3.1 Submission of product.- Unless otherwise specified by the contracting officer, inspection lot size, lot formation and presentation of lots shall be in accordance with "Submission of Product" provisions of MIL-STD-105.

4.3.2 Examination and tests.

4.3.2.1 Components and subassemblies.- All components and subassemblies shall be inspected in accordance with the inspection provisions contained in Supplementary Quality Assurance Provisions (SQAP) listed in the Technical Data Package (TDP). In the absence of SQAPs, the applicable Quality Assurance Provisions of MIL-F-13926 shall apply.

4.3.2.2 Final acceptance inspection.- Subsequent to first article approval, examination and tests related to Section 3 herein shall be performed on a single defect (individual characteristic) basis in accordance with MIL-STD-105 and the sampling plans specified in Table IV herein. Examination and tests for Packaging, Packing and Marking shall be in accordance with MIL-P-14232 and Section 5 herein. The tabulated classification of defects in Table IV shall constitute the minimum inspection to be performed by the supplier after first article approval and prior to Government acceptance or rejection by item or lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

TABLE IV - CLASSIFICATION OF DEFECTS

Use Inspection Level II Sampling Plan Table IIA of MIL-STD-105.

CLASS	REQUIREMENT	TEST PROCEDURE
CRITICAL: 100%		
1. Sealing	3.3.3	4.6.1.2
2. Rain	3.3.4	4.6.1.3
3. Purging	3.3.5	4.6.1.4
4. Insulation resistance	3.4.7.2	4.6.2.16
MAJOR: 1.5% Defective		
101. Orientation	3.4.1 (a) to (h)	4.6.2.1
102. Vibration	3.3.2	4.6.2.2
103. Post vibration	3.3.2	4.6.2.3
104. Elevation travel	3.4.2.1	4.6.2.4
105. Correction counter	3.4.2.2	4.6.2.10
106. Cross level travel	3.4.2.3	4.6.2.9
107. Rigidity	3.4.3.	4.6.2.7
108. Plumb travel	3.4.4.1	4.6.2.5
109. Elevation error	3.4.4.2	4.6.2.6
110. Elevation backlash	3.4.4.3.1	4.6.2.6
111. Cross leveling backlash	3.4.4.3.2	4.6.2.9
112. Correction counter	3.4.4.4	4.6.2.12
113. Correction counter operation	3.4.4.6	4.6.2.13
114. Operating torques	3.4.5	4.6.2.14
115. Cant correction	3.4.6.1	4.6.2.8
116. Illumination	3.4.7.1	4.6.2.15
117. Continuity	3.4.7.3	4.6.2.17
118. Identification	3.5	4.6.2.18
MINOR: 2.5% Defective		
201. Counter alignment	3.4.4.5	4.6.2.11

4.3.3 Acceptance and rejection.- Rejected lots shall be screened for all defective characteristics. Removal or correction of defective units and resubmittance of rejected lots shall be in accordance with "Acceptance and Rejection" as specified in MIL-STD-105.

4.4 Special sampling for environmental testing.

4.4.1 Samples shall be selected at random from lots listed under inspection level S-3 Table I of MIL-STD-105. Acceptance or rejection of the lot shall be in accordance with AQL 2.5 of Table II-A of MIL-STD-105. The control samples shall have met all the requirements and tests outlined in Table IV prior to being subjected to the following examination and test:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

NO.	CHARACTERISTIC	PER DWG OR SPEC	INSPECTION METHOD
301.	Temperature (operating)	3.3.1	4.6.1.1
302.	Torque	3.4.5	4.6.1.1

4.4.2 Failure of sample.- Should any one item of a special sampling fail to meet the specified test requirements, acceptance of the represented inspection lot will be suspended by the Government until necessary corrections have been made by the contractor and the resubmitted samples have been approved (see 4.3.3).

4.5 Inspection equipment.- Except as otherwise provided for by the contract, the contractor shall supply and maintain inspection equipment in accordance with the applicable requirements of MIL-I-45607.

4.5.1 Government furnished inspection equipment.- Where the contract provides for Government furnished test equipment, supply and maintenance of test equipment shall be in accordance with the applicable requirements specified in MIL-I-45607.

4.5.2 Contractor furnished inspection equipment.

4.5.2.1 Government design.- Unless otherwise specified in the contract, all inspection equipment specified by drawing number in specifications or SQAP forming a part of the contract shall be supplied by the contractor in accordance with technical data listed in the List of Inspection Documents when provided with the technical data package (TDP).

4.5.2.2 Contractor design.- The contractor shall design and supply inspection equipment compatible with the "Test Methods and Procedures" specified in 4.6 of this specification and with the component inspection procedures specified in "Examination" and "Test Facilities" requirements of MIL-F-13926. Since tolerance of test equipment is normally considered to be within 10% of the product tolerance for which it is intended, this inherent error in the test equipment design must be considered as part of the prescribed product tolerance limit. Thus, concept, construction, materials, dimensions and tolerances used in the design of test equipment shall be so selected and controlled as to insure that the test equipment will reliably indicate acceptability of a product which does not exceed 90% of the prescribed tolerance limit, and permit positive rejection when nonconforming. Construction shall be such as to facilitate routine calibration of test equipment.

4.5.2.3 Device to test performance.- Test equipment used to perform acceptance inspection shall be equal to or exceed the accuracies depicted on drawing F11730831.

4.6 Test methods and procedures.

4.6.1 Environmental test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

4.6.1.1 The temperature test shall be performed as outlined in Procedure II of MIL-F-13926; however, the temperature specified in 3.3.1 shall be used. When thermally stabilized at the specified temperature, the mount shall meet the performance requirements outlined in 3.3.1.

4.6.1.2 Sealing (counter box area).- The counter box portion of the mount shall be pressurized internally to the psi value specified in 3.3.3 with dry nitrogen for the length of time specified in 3.3.3. While under pressure, the counter box area shall meet the requirements specified in 3.4.2. Dry nitrogen used in this test shall have a dew point of at least -25°F. Accuracy of the test equipment used on this test shall be equal to or exceed the accuracies depicted on Drawing F8665556.

4.6.1.3 Rain test.- Prior to performing the rain test outlined in Procedure I of MIL-F-13926, each mount shall be inspected to assure conformance to the insulation resistance specified in 3.4.7.2, when tested as outlined in 4.6.2.16. After completing the insulation resistance test, the mount shall then be subjected to the rain test outlined in Procedure I of MIL-F-13926. After completion of the rain test, objectionable water penetration shall be determined by repeating the insulation resistance test outlined in 4.6.2.16. There shall be no change between this reading and the preliminary insulation resistance reading.

4.6.1.4 Purging.- The counter box area of the mount shall be flushed with dry nitrogen gas to conform to the requirements of 3.3.4. A dew point tester (standard shop type test equipment) shall be used to measure the nitrogen dew point for conformance with 3.3.4. Purging to be performed at standard ambient temperature and prior to performing temperature test. Pressure of nitrogen remaining within the counter box area to be between .25 and .5 psi.

4.6.2 Performance testing.

4.6.2.1 Orientation.- To assure proper orientation, the mount and test fixtures and targets shall be oriented within the limits outlined under set-up instructions specified on Drawing F11730831.

4.6.2.2 Vibration.- Remove the adapter (F11730831) from the mount and remove the mount from the test fixture and without disturbing any of the knob settings, vibrate the mount in accordance with Test Procedure IV of MIL-F-13926; however, the time duration, frequency and amplitude shall be as outlined in 3.3.2. After vibration, visually inspect the mount for damaged or broken components. Do not rotate the knobs.

4.6.2.3 Post vibration.- Reassemble the mount and adapter (F11730831) to the fixture and observe coincidence between the optical line of sight and the intersecting point of the target representing the viewing telescope's optical axis. They must remain within the limits of 3.4.1 after adjusting the mount to a level and cross level position as indicated by the level and cross level vials. Read the error, if any, from the target.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

4.6.2.4 Elevation travel.- With the mount and fixture positioned as outlined in 4.6.2.1, rotate the mount's elevation knob to reflect maximum elevation. Note the reading on the elevation counter. Set this reading into Inspection Aid (Gunner's Quadrant) A8658940. Position the inspection aid on the quadrant seat assembly and by means of the fixture elevation handwheel, relevel the inspection aid. Observe the elevation level bubble of the mount with respect to the quadrant level vial. Both must indicate level within the limits outlined in 3.4.2.1. Repeat this procedure in the opposite direction. Any non-compatibility in level vial bubble position shall be measured by means of the quadrant.

4.6.2.5 Plumb travel.- With the mount and fixture set as outlined in 4.6.2.1, this test is made by sighting through viewing telescope F5549108 and observing coincidence between the telescope's optical axis and the intersecting point of target centerlines while simultaneously rotating the mount in elevation and the test fixture an equal amount in the opposite direction. The optical line of sight shall not deviate from the intersecting point by more than the limits outlined in 3.4.4.1 as measured by target mil blocks. During this total travel the cross level vial shall remain level within the limits of 3.4.4.1.

4.6.2.6 Elevation error and backlash.- With the fixture and mount positioned as outlined in 4.6.2.1, insert an elevation reading into the mount. Use the elevation counter as the recording mechanism. Insert this selected reading into the inspection aid and position the inspection aid on the quadrant seat assembly and by means of the fixture elevation handwheel relevel the quadrant level vial, do not override this level position. Observe coincidence between both level vial bubbles. Any non-compatibility between level vial bubble positions shall be measured by means of the quadrant. This difference, if any, shall not exceed the limits outlined in 3.4.4.2. Note this reading. Continue to rotate the elevation knob approximately one revolution beyond this point of coincidence. Return the knob to reposition the elevation level vial bubble to indicate level. Note the elevation counter reading. The difference, if any, in elevation reading is concidered backlash and must be within the limits outlined in 3.4.4.3.1.

4.6.2.7 Mount rigidity.- With the fixture positioned as outlined in 4.5.2.3, position the mount as specified in 3.4.1 with the level vial bubbles centered. Check rigidity by gradually applying and releasing the pressure specified in 3.4.3 at the top left side of the telescope support as specified in 3.4.3. Take the reading on the test target and record the movement. Repeat this procedure gradually applying and releasing the specified pressure at the top right side of the telescope support. Take the reading on the test target and record the movement. The total movement shall be within the allowable maximum deviation specified in Table I of 3.4.3. The same procedure shall be followed as the simulated gun trunnion (cross leveling fixture) is moved from the "0" position to the 1333 mil elevation position to conform to the requirements of Table I. The maximum movement at the various settings shall not exceed the mil values specified in Table I.

4.6.2.8 Cant correction.- With the mount and fixture positioned as outlined in 4.6.2.1, rotate the auxiliary telescope's line of sight 1600 mils and engage the locating pin in the proper locating hole indicated in the set-up instructions F11730831. The line of sight shall coincide with

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

the vertical target line with the limits outlined in 3.4.6.1. Elevation angle of the quadrant seat shall coincide with the elevation reading shown on the elevation counter within the limits of 3.4.6.1. Elevate and cant the fixture to selected set of values (Table III) and set the mount off an equal amount in the opposite direction. The telescope's line of sight shall coincide with the target vertical centerline within the limits outlined in 3.4.6.1.

4.6.2.9 Cross level travel and backlash.- With the mount positioned on the fixture as outlined in 4.6.2.1 and with the auxiliary telescope's sighting device assembled to the mount, rotate the cant mechanism to full extent of travel. Place the inspection aid over the appropriate set of pads of the sighting device and read the cant angle. This reading must be equal to or exceed the minimum requirement outlined in 3.4.2.3. Repeat this procedure at the opposite extreme setting. Return the cross leveling mechanism somewhere between zero and maximum angle and scribe a line on the casting and cross leveling knob and obtain a cross level angle reading using the inspection aid, record this reading. Continue to rotate the cross leveling knob one revolution beyond the index mark and return to the index mark. Exercise care not to override this point of coincidence and record this reading using the inspection aid. The difference, if any, is considered backlash and must conform to the limits outlined in 3.4.4.3.2.

4.6.2.10 Correction counter.- Rotate the correction counter knob to indicate that the maximum correction range is within the limits of 3.4.2.2.

4.6.2.11 Counter alignment.- Actuate the elevation knob through its complete travel range. During this travel make a minimum of 2 stops each side of zero elevation, and by standard measuring equipment, determine if digit alignment is within the limits outliend in 3.4.4.5.

4.6.2.12 Correction counter.- With the mount and fixture set as outlined in 4.6.2.1, rotate the correction counter to the minimum setting specified in 3.4.4.4. Return the elevation counter to zero. By means of the fixture, level the elevation level vial of the mount. Do not override this level position. Place the inspection aid on the quadrant seat assembly and set the inspection aid level vial to indicate level. Read the angle on the inspection aid. This reading to be identical to the correction counter reading within the limits of 3.4.4.4. Repeat this procedure at the setting specified in 3.4.4.4 each side of zero correction.

4.6.2.13 Correction counter operation.- This test may be performed in conjunction with the previous test. Visually determine that when a negative correction is inserted in the mount, the elevation counter reading increases an equal amount. Also, determine that when a positive correction is inserted in the mount, the elevation counter reading decreases an equal amount. Using the test procedure outlined in 4.6.2.1, determine that the inserted correction factors are recorded on the elevation counter as specified in 3.4.4.6.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

4.6.2.14 Torques.- All torque readings specified in 3.4.5 shall be measured using standard torque wrench and appropriate adapters. All readings to conform to the values specified in 3.4.5 for the temperature specified.

4.6.2.15 Illumination.- Illumination to be inspected in a dark area after connecting a 24 Vdc power source to determine conformance with 3.4.7.1.

4.6.2.16 Insulation resistance.- Use test condition "A" of Method 302 of MIL-STD-202, however, the duration of testing shall be as specified in 3.4.7.2. The measured resistance shall not be less than megohm value specified in 3.4.7.2.

4.6.2.17 Continuity.- Using standard shop type continuity checker, determine if continuity conforms with 3.4.7.3.

4.6.2.18 Identification marking.- All markings shall be visually inspected for conformance with appropriate test procedures to assure conformance with 3.5.

5. PREPARATION FOR DELIVERY

5.1 Packaging, packing and marking.- Packaging, packing and marking shall be in accordance with Packaging Data Sheet 8587295. The level of protection shall be as specified in the procurement document.

6. NOTES

6.1 Intended use.- The Telescope Mount: M137 is primarily intended to support the Panoramic Telescope: M115 in the 175mm Self-Propelled Gun, M107 and the 8 inch Self-Propelled Howitzer, M110. The mount provides cant correction and elevation adjustments for the panoramic telescope.

6.2 Ordering data.- Procurement documents should specify the following:

(a) Title, number and date of this specification
(b) Selection of an applicable level of preservation packaging and packing
(c) Applicable stock number

6.3 Design information.- Information regarding specific design not covered or referenced by this specification may be obtained from the procuring activity upon specific request of the contractor.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1240-A177

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS
ENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY CARD

FIRST CLASS PERMIT NO. 12062 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE ARMY

COMMANDER
US ARMY ARMAMENT RESEARCH & DEVELOPMENT
COMMAND
ATTN: DRDAR-TST-S
DOVER. NEW JERSEY 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

[ ] DIRECT GOVERNMENT CONTRACT [ ] SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

[ ] YES [ ] NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:30Z
Check the source to verify that this is the current version before use.