INCH-POUND

MIL-R-0052105E(ME)
20 October 1994
USED-IN-LIEU-OF
MIL-R-52105D
1 April 1988

MILITARY SPECIFICATION

RAMP, RAFT

This specification is approved for use by the USA Mobility Technology Center - Belvoir based upon currently available technical information but it has not been approved for promulgation as a coordinated revision of MIL-R-52105D. It is subject to modification. However, pending its promulgation as a coordinated military specification, it may be used in acquisition.

1. SCOPE

1.1 Scope. This specification covers a raft ramp which is a component of the M4T6 military floating bridge.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DoDISS) and supplement thereto, cited in the solicitation (see 6.2).

SPECIFICATIONS

FEDERAL

PPP-B-601	- Boxes, Wood, Cleated-Plywood.
PPP-B-621	- Boxes, Wood, Nailed and Lock Corner.
PPP-B-636	- Box, Shipping, Fiberboard.

MILITARY

MIL-T-704	- Treatment and Painting of Materiel.
MIL-C-16173	- Corrosion Preventive Compound, Solvent Cutback, Cold-Application.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US ARMY MOBILITY TECHNOLOGY CENTER - BELVOIR, ATTN AMSTA RBES, 10115 GRIDLEY RD STE 128, FT BELVOIR VA 22060-5843 by using the Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 5420

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	- Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	- Marking for Shipment and Storage.
MIL-STD-889	- Dissimilar Metals.

2.1.2 Other Government drawings and publications. The following other Government drawings and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues shall be those in effect on the date of the solicitation.

DRAWINGS

ME

TA13208E9891	- Ramp, Raft.

QUALITY ASSURANCE PAMPHLETS

P715-109	- Inspection Equipment for Ramp, Raft.

(Copies of drawings required by contractors in connection with specific acquisition functions should be obtained from: USA MOBILITY TECHNOLOGY CENTER - BELVOIR, ATTN AMSTA RBBS, 10115 GRIDLEY RD, STE 128, FT BELVOIR VA 22060-5843.)

2.2 Non-Government publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DoDISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DoDISS are the issues of the documents cited in the solicitation (see 6.2).

AMERICAN SOCIETY FOR TESTING AND MATERIAL (ASTM)

D 3951 - Standard Practice for Commercial Packaging.
D 3953 - Strapping, Flat Steel and Scales.
D 4675 - Selection and Use of Flat Strapping Materials.

(Application for copies should be addressed to: AMERCN SCTY FOR TEST & MTRLS, 1916 RACE STRET, PHILADELPHIA PA 19103.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Section IX, Welding Qualifications.

(Application for copies should be addressed to: AMERCN SCTY OF MECHL ENGRS, 345 E 47TH STRET, NEW YORK NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

AMERICAN WELDING SOCIETY (AWS)

A5.1 - Mild Steel Covered Arc-Welding Electrodes.
A5.10 - Aluminum and Aluminum-Alloy Welding Rods and Bare Electrodes.
A5.18 - Mild Steel Electrodes for Gas Metal-Arc Welding.
D1.1 - Structural Welding Code, Steel.
D1.2 - Structural Welding Code, Aluminum.

(Application for copies should be addressed to: AMERCN WELD SCTY, 550 NW LEJEUNE RD, PO BOX 351040, MIAMI FL 33135.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein (except for associated detail specifications, specification sheets or MS standards), the text of this document shall take precedence. Nothing in this specification, however, shall supersede applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The raft ramp shall be as shown on TA13208E9891 and as specified herein.

3.1.1 Drawings. The drawings forming a part of this specification are end product drawings. No deviation from the prescribed dimensions or tolerances is permissible without prior approval of the contracting officer. Where tolerances could cumulatively result in incorrect fits, the contractor shall provide tolerances within those prescribed on the drawings to insure correct fit, assembly, and operation of the (nomenclature). Any data (e.g. shop drawings, layouts, flow sheets, processing procedures, etc.) prepared by the contractor or obtained from a vendor to support fabrication and manufacture of the production item shall be made available, upon request, for inspection by the contracting officer or the designated representative.

3.2 First article. Unless otherwise specified (see 6.2), a sample shall be subjected to first article inspection (see 4.3 and 6.3).

3.3 Material. Material shall be as specified herein and as shown on the applicable drawings. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification.

3.3.1 Material deterioration prevention and control. The raft ramp shall be fabricated from compatible materials, inherently corrosion resistant or treated to provide protection against the various forms of corrosion and deterioration that may be encountered in any of the applicable operating and storage environments to which the raft ramp may be exposed.

3.3.1.1 Dissimilar metals. Dissimilar metals shall not be used in intimate contact with each other unless protected against galvanic corrosion. Dissimilar metals and methods of protection are defined and detailed in MIL-STD-889.

3.3.2 Recovered materials. For the purpose of this requirement, recovered materials are those materials which have been collected from solid waste and reprocessed to become a source of raw materials, as distinguished from virgin raw materials. The components, pieces and parts incorporated in the raft ramp may be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

newly fabricated from recovered materials to the maximum extent practicable, provided the raft ramp produced meets all other requirements of this specification. Used, rebuilt or remanufactured components, pieces and parts shall not be incorporated in the raft ramp.

3.4 Welding electrodes.

3.4.1 For steel. Welding electrodes for steel shall conform to AWS A5.1 or A5.18, classification E60 or E70 series, size as required.

3.4.2 For aluminum. Welding electrodes for aluminum shall conform to AWS A5.10, classification ER4043, size as required.

3.5 Identification marking. The raft ramp shall be metal-die stamped as shown on the applicable drawing. Die stamping shall be legible after painting.

3.6 Treatment and painting. The raft ramp, except pins and bridge pin retainers, shall be cleaned, treated, and painted in accordance with MIL-T-704, type B. The pins and bridge pin retainers shall be coated with corrosion-preventive compound conforming to MIL-C-16173, grade 1. Contact surfaces, regardless of whether such contact is between similar or dissimilar metals, shall be cleaned, treated, and painted prior to assembly.

3.7 Stenciling. The nomenclature, national stock number, weight, and cube shall be stenciled on each raft ramp. The letters "NET WT" shall precede the numerals in the weight and the letters "CU" shall precede the cubic displacement. Markings shall be Gothic-type capitals and Arabic numerals 3/4 inch high. Stenciling shall conform to MIL-T-704.

3.8 Government-loaned property. Unless otherwise specified (see 6.2), the following property in the quantities indicated will be loaned by the Government (see 6.7):

Item	Description	Identification	Quantity
1	Inspection Equipment for Ramp, Raft	Quality Assurance Pamphlet, P715-109	1

3.9 Workmanship.

3.9.1 Steel fabrication. Steel may be cut by shearing, sawing, or flame cutting. Burned surfaces or flame-cut material shall be ground or machined to remove cooling checks. All bends shall be made by use of metal dies or fixtures to insure uniformity in size and shape. All burrs shall be removed.

3.9.2 Aluminum fabrication. Aluminum used in the fabrication of the component shall be free from kinks and sharp bends. Straightening of material shall be done by methods that will not cause injury to the metal. Surfaces and edges of all finished members shall be smooth and free from kinks, bends, and winds. All bends of a major character shall be made with metal dies or fixtures to insure uniformity of size and shape. Sharp instruments shall not be used for marking bend lines. Aluminum shall not be cut by methods using heat. Aluminum less than

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

3/8 inch thick may be cut by shearing; aluminum 3/8 inch thick and over shall be cut by routing or by high-speed saws. Shearing and sawing shall be done neatly and accurately.

3.9.3 Riveting. Rivet holes shall be drilled to the diameter specified on the applicable drawing or subpunched 1/8 inch smaller and reamed to the specified diameter. Holes for contersunk rivet heads shall be of such a depth and angle that heads shall fill the hole without projecting or recessing. The rivets may be driven hot or cold. Hot rivets shall be heated uniformly throughout their length and driven while at a light cherry-red color. Rivets shall be free from slag or scale when driven. Heads of driven rivets shall be uniform in shape, concentric with rivet shank axis and shall have full bearing on the surfaces of the joined members. Caulking or re-driving of rivet heads shall not be permitted. Rivets with a head deficient in size, not uniform in shape, off center, loose, or burned shall be considered defective. Defective rivets shall be removed without injury to the joined metal. Where it is practicable, rivets shall be driven by direct-action rivet machines. In lieu of direct-action rivet machines, pneumatic rivet hammers may be used. Excessive air-driving pressures or overdriving of rivets resulting in damage to the joined members shall not be permitted.

3.9.4 Welders and welding.

3.9.4.1 Welders. Before assigning any welder or automatic welder equipment operator to welding work covered by this specification, the contractor shall obtain certification that the welder or operator has passed qualification tests as prescribed by one of the following listed codes for the materials joined and the type of welding operation to be performed and that such qualification is effective as defined by the particular code: AWS D1.2 - Structural Welding Code, Steel, AWS D1.2 - Structural Welding Code, Aluminum, and ASME Boiler and Pressure Vessel Code, Section IX, Welding Qualification.

In the event of evidence of poor welds, the Government reserves the right to require retesting of any welder or operator. The test results shall be made available for review by the contracting officer or the contracting officer's representative.

3.9.4.2 Welding. The surfaces of parts to be welded shall be free from scale, paint, grease, rust, oxide, and other foreign matter. Welding shall be done by the shielded metal-arc or gas-metal-arc (MIG) process and shall conform to the provisions of the American Welding Society Publications, AWS D1.1 - Structural Welding Code - Steel or AWS D1.2 Structural Welding Code - Aluminum. All welded parts shall be free from cracks and other discontinuities that may reduce the effectiveness of the part. Work shall be positioned for flat welding when practicable. Before welding over previously deposited weld metal, all traces of slag shall be removed and the deposit and adjoining base metal shall be wire brushed clean.

3.9.4.2.1 Steel welding. Where embrittlement of the joined metal may result, preheating and annealing or both shall be employed.

3.9.4.2.2 Aluminum welding. Aluminum members to be welded may be preheated for welding to a temperature of not more than 400 °F. Top and bottom extrusions shall be butt-welded by the automatic-machine methods. The weld shall be made at a uniform rate in one pass and shall be backed up for its entire length. Complete

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

and uniform penetration and fusion of the metals shall be obtained on all welds. Skips and blow-through holes in the automatic-machine-made welds may be corrected by manual welding if the sum of the length of each skip and blow- through holes is not more than 2 percent of the total length of the weld and if the length of any skip or blow-through holes is not more than 1 inch. The ends of skips and the total length of blow holes shall be chipped to parent metal before welding. Aluminum welds may be ground, filed, wire brushed, or chipped but shall not be hammered.

3.9.5 Interchangeability. Raft ramps shall be fabricated to be duplicates within the tolerances specified and shall be interchangeable.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order and unless disapproved by the Government, the contractor's own or any other facilities suitable for the performance of the inspection requirements specified herein may be used. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of assuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to acceptance of defective material.

4.1.2 Component and material inspection. The contractor is responsible for ensuring that components and materials used are manufactured, examined, and tested in accordance with referenced specifications and standards.

4.1.3 Parts and components. Parts and components detailed on the drawings shall be inspected in accordance with the quality assurance provisions (QAP) shown on the drawings. The drawings specify the characteristics requiring QAP inspection, the sampling plan, and the basis for acceptance and rejection (see 6.5 and 6.6).

4.2 Classification of inspection. Inspection shall be classified as follows:

a. First article inspection (see 4.3).
b. Quality conformance inspection (see 4.4).
c. Inspection of packaging (see 4.6).

4.3 First article inspection.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

4.3.1 Examination. The first article raft ramp shall be examined in accordance with 4.4.2.1 and for the defects specified in 4.5.1. Presence of one or more defects shall be cause for rejection.

4.4 Quality conformance inspection.

4.4.1 Sampling. Sampling for examination and test shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when zero defects are found and rejected when one or more defects are found.

4.4.2 Examination.

4.4.2.1 Individual. Each raft ramp shall be inspected for conformance to the dimensions covered by the quality assurance provisions (QAP) shown on the drawings under "Major - 100 percent inspection", unless otherwise specified (see 6.2). Government-loaned inspection equipment (see 3.8) shall be used in accordance with Quality Assurance Pamphlet P715-109 to inspect those dimensions marked "Major - 100 percent inspection". Nonconformance to any of these dimensions shall constitute failure of this examination and shall be cause for rejection.

4.4.2.2 Samples. Samples selected in accordance with 4.4.1 shall be examined for the defects specified in 4.5.1.

4.5 Inspection procedure.

4.5.1 Examination. The raft ramp or component, as applicable, shall be examined for the following defects:

101.	All dimensions designated major on the QAP other than those under 100 percent inspection not as specified.	100
102.	Material not as specified.	
103.	Components missing or not as specified.	
104.	Workmanship not as specified.	
105.	Weld defects such as flux inclusions, spatter, undercutting, porosity, incorrect size, or lack of fusions with parent metal.	
106.	Riveting not as specified.	
107.	Materials not resistant to corrosion and deterioration, or treated to be resistant to corrosion and deterioration for the applicable storage and operating environments.	
108.	Dissimilar metals as defined in MIL-STD-889 are not effectively insulated from each other.	
109.	Used, rebuilt or remanufactured components, pieces, or parts incorporated in the ramp raft.	
110.	Welding electrodes for steel and aluminum not as specified.	
111.	Welders certification not as specified.	
112.	All dimensions not designated major on the QAP not as specified.	
113.	Identification marking incorrect, missing, or illegible.	
114.	Treatment and painting not as specified.	
115.	Stenciling not as specified.	

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

4.6 Inspection of packaging.

4.6.1 First article pack inspection.

4.6.1.1 Examination. Examine the first article pack of bundled raft ramps for the defects specified in 4.6.2.3. Presence of one or more defects shall be cause for rejection.

4.6.2 Quality conformance inspection of pack.

4.6.2.1 Unit of product. For the purpose of inspection, a completed pack of bundled raft ramps or boxed components prepared for shipment shall be considered a unit of product.

4.6.2.2 Sampling. Sampling for examination shall be in accordance with MIL-STD-105. Sample size shall be determined by using MIL-STD-105, table I and table IIa. A lot shall be accepted when 0 defects are found and rejected when 1 or more defect is found.

4.6.2.3 Examination. Samples selected in accordance with 4.6.2.2 shall be examined for the following defects. Presence of one or more defect shall be cause for rejection as a clause for the first article test.

116. Ramps not bundled and components procured separately, not packed in a box as specified for level A or B.
117. Strapping on bundles and boxes not as specified for level A or B.
118. Gross weight of wood boxes exceeds 200 pounds for level A or B.
119. Gross weight or size of fiberboard boxes exceeds the limitation of the box specification for level B.
120. Marking missing, illegible, incorrect, or incomplete for level A, level B or commercial.

5. PACKAGING

5.1 First article pack. The contractor shall furnish a first article pack of the bundled raft ramps for examination within the time frame specified (see 6.2) to prove prior to starting production packing that the applied packing and marking comply with the packaging requirements of this specification. Examination shall be as specified in section 4 and shall be subject to surveillance and approval by the Government (see 6.4).

5.2 Packing. Packing shall be level A, B, or commercial as specified (see 6.2).

5.2.1 Level A. Complete raft ramps, with pins secured as applicable, shall be bundled in quantities of two. The top ramp of the bundle shall be inverted with the ends of the ramps alternated to form a compact bundle. The ramps forming each bundle shall be secured together with flat steel strapping conforming to ASTM D 3953, type I, finish B, grade 1, heavy coating, size 1-1/4 inch by 0.035 inch, placed through the tubing and around the end of the opposite ramp. Wood blocking shall be provided where necessary to prevent damage to the ramps and the straps.

5.2.1.1 Components. When the vertical or horizontal pins are procured separately from the raft ramp, the items shall be packed, like items only, in

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

close-fitting boxes conforming to PPP-B-621, class 2, style optional, or PPP-B-601, overseas type, style optional. The gross weight of each box shall not exceed 200 pounds and the boxes shall be closed and strapped in accordance with the appendix to the applicable box specification except that strapping shall be flat and the finish shall be "B".

5.2.2 Level B. Complete raft ramps, with pins secured as applicable, shall be bundled as specified for level A in 5.2.1, except strapping may be finish A.

5.2.2.1 Components. When components are procured separately, they shall be packed as specified in 5.2.1.1 for level A except that boxes shall be domestic class or type and the strapping may be finish "A". As an alternate, a fiber-board box conforming to PPP-B-636, grade V3c, V11c, V13c or V15c, may be used as the shipping container when the cube and gross weight for the total quantity of a single component to be shipped to a single destination does not exceed the cube and gross weight limitations specified therein for the applicable grade of fiberboard utilized. Like items only shall be packed in either the wood box or the fiberboard box.

5.2.3 Commercial. Each complete raft ramp, with pins secured as applicable, and components which are procured separately, shall be packed in accordance with ASTM D 3951.

5.3 Marking.

5.3.1 Military. In addition to any special or identification markings required by the contract or purchase order (see 6.2), all boxes, bundles and, as applicable, all loose ramps, shall be marked in accordance with MIL-STD-129.

5.3.2 Commercial. All boxes, bundles, and loose ramps shall be marked in accordance with ASTM D 3951.

6. NOTES
(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The raft ramp is intended for use at the end of the deck of the raft to facilitate the loading or unloading of vehicles.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of the DoDISS to be cited in the solicitation, and, if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. Time frame required for submission of first article model (see 3.2).
d. When Government-loaned property is not required (see 3.8).
e. When the Government-loaned inspection equipment will not be used for inspection of dimensions (see 4.4.2.1).
f. Time frame required for submission of the first article pack (see 5.1).
g. Degree of packing required (see 5.2).
h. Any special marking (see 5.3).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

6.3 First article. When a first article inspection is required, the item(s) should be a preproduction model. The first article should consist of one or more units. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examinations, approval of the first article test results and disposition of the first articles. Invitation for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product which has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so in the solicitation.

6.4 First article pack. Any changes or deviations of production packs from the approved first article pack will be subject to the approval of the contracting officer. Approval of the first article pack will not relieve the contractor's obligation to pack, and mark the bundled raft ramps and boxed components in accordance with this specification.

6.5 Quality assurance provisions (QAP). The contracting officer should require the contractor to maintain records of all QAP inspections.

6.6 Definitions.

6.6.1. Quality assurance provisions (QAP). A QAP is a contractual requirement that supplements section 4 of the specification. QAP indicates the minimum requirements which must be inspected on the product drawings to verify the design objectives of the product and assure interchangeability of repair parts.

6.7 Government-loaned property. The contracting officer should arrange to lend the property specified in 3.8 when applicable.

6.8 Subject term (key words) listing.

Raft
Ramp
Ramp, raft

6.9 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A163

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

RECOMMEND A CHANGE:	1. DOCUMENT NUMBER MIL-R-0052105E(ME)	2. DOCUMENT DATE (YYMMDD) 941020

3. DOCUMENT TITLE
RAMP RAFT

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (if applicable) (2) DSN	7. DATE SUBMITTED

8. PREPARING ACTIVITY

a. NAME Carolyn B. Johnson	b. TELEPHONE (Include Area Code) (1) Commercial (703) 704-3468	(2) DSN 654-3468
c. ADDRESS (Include Zip Code) USA MOBILITY TECHNOLOGY BELVOIR CTR ATTN AMSTA-RBE 10115 GRIDLEY RD STE 228 FT BELVOIR VA 22060-5849	IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT: DEFNS QLTY & STDZN OFC 5203 LEESBURG PIKE STE 1403 FLS CHURCH VA 22041-3466 Telephone (703) 756-2340	DSN 289-2340

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:07Z
Check the source to verify that this is the current version before use.