MILITARY SPECIFICATION
RECEIVER, CONTROL; SUBASSEMBLY

1. SCOPE

1.1 This specification covers special requirements, quality assurance provisions, and the preparation for delivery criteria for one type of Control Receiver used for training on the Atomic Demolition Charge.

2. APPLICABLE DOCUMENTS

2.1 The following documents, of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-S-60902(MU) - Soldering Electrical Connections for Nuclear Weapons Systems, Procedure for.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1169(MU) - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.

DRAWINGS

ORDNANCE CORPS

8808362 - Packing and Marking for Storage and Shipments.
8852449 - Control Receiver Subassembly.
8852450 - Chasis Control Receiver.
8852468 - Potentiometer.
8852508 - Clamp Control Receiver.
8852531 - End Plate, R.H., Control Receiver.
8880602 - Marking and Sealing for Unit Packages.
9240970 - Carton, Packing, Ammunition for Control Receiver Subassembly.
ET-8852449 - Equipment Tabulation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

(Copies of specifications, standards, drawings, and publication required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Materials. The contractor shall furnish objective evidence (see 6.2) that the material complies with the specifications listed on the applicable drawing.

3.2 Assembly. The receiver subassembly shall comply with all requirements specified on Drawing (dwg.) 8852449, with all requirements specified herein, and with the requirements of applicable specifications to the extent specified on the drawing and herein.

3.3 First article testing. Requirements for the submission of first article samples by the contractor shall be as specified in the contract (see 4.2).

3.4 Serialization. The contractor shall assign serial numbers as required by drawings. The contractor may select any number which complies with the drawing requirement. These numbers shall not be duplicated.

3.5 Low temperature. The control receiver subassembly shall withstand a temperature of -30 ± 1 degrees centigrade (^{o}C) and maintain drawing requirements while at this temperature. After completion of the test, there shall be no evidence of swelling, peeling, cracking, distortion or other deterioration and the item shall comply with drawing requirements. Testing shall be in accordance with 4.4.1.

3.6 High temperature. The control receiver subassembly shall withstand a temperature of +60 ± 1°C and maintain drawing requirements while at this temperature. After completion of the test, there shall be no evidence of swelling, peeling, cracking, distortion or other deterioration, and the item shall comply with drawing requirements. Testing shall be in accordance with 4.4.2.

3.7 Workmanship.

3.7.1 Plastic and metal characteristics. All components shall be free from cracks, splits, cold flow, shrinkage, cold shuts, inclusions, porosity, or any similar characteristic.

3.7.2 Threads. Threads shall be full and undamaged for the entire minimum length or depth as required on the applicable drawing.

3.7.3 Burrs. Parts shall be free from burrs.

3.7.4 Foreign matter. Parts shall be free from chips, dirt, grease, rust, corrosion, or any embedded foreign material.

3.7.5 Cleaning. The cleaning method shall not be injurious to any of the parts, nor shall the parts be contaminated by the cleaning agents.

3.7.6 Electrical. Cable assemblies and wires shall be dressed in such a manner as to prevent pinching or chafing of the wire insulation. Ends of wires shall be free from burrs, sharp edges, or points. All parts shall be free from flux, chips, dirt, grease, rust or **foreign** material.

4. QUALITY ASSURANCE PROVISIONS.

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article inspection.

4.2.1 Quantity to be submitted. When the contract requires first article inspection, the contractor shall submit 1 complete assembly (see dwg. 8852449), for first article testing to the testing facility designated in the invitation for bids or request for proposal.

4.2.2 Inspection and testing to be performed. The first article inspection sample shall be subjected to the inspections and tests specified in table I. Tests need not be conducted in order specified in table I.

Table I

First article inspections and tests

Examination or test	Contractor's inspection permissible before submission	Assembly	Parts
1. Classification of characteristics (see 4.3.2.1)	X	X	X
2. Low temperature (see 3.5)	X	X	
3. High temperature (see 3.6)	X	X	

4.2.3 Inspection equipment. The inspection and testing specified in 4.2.2 shall be accomplished by using the gages and test equipment specified in 4.3.4.1.

4.2.4 Rejection. If any item fails to comply with any of the applicable requirements, the first article sample shall be rejected.

4.3 Product acceptance inspection.

4.3.1 Lot formation. A lot shall consist of parts and assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification and same specification revision. Drawing, specification and process changes not affecting safety, performance, storage, or interchangeability, as determined by the Government, shall not necessitate changing the lot interfix number. The criteria and procedures for the assignment of lot numbers shall be in accordance with MIL-STD-1168.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

4.3.1.1 Inspection lot. An inspection lot shall be the quantity of parts, subassemblies, or assemblies from the same lot, which are submitted to inspection for Government acceptance.

4.3.2 Product inspection examination. Critical characteristics shall require 100 percent inspection of all items in the inspection lot. A sample shall be selected at random from each inspection lot in accordance with the applicable major or minor characteristic table and inspected for all characteristics in the applicable classification. Any characteristic in the sample found to be defective shall reject the inspection lot. Sequence for the inspection of characteristics in each classification need not be followed as long as all characteristic inspections are performed.

Major characteristic table II

Lot size	Sample size
1- 155	100% inspection
156- 200	155
201- 250	175
251- 300	190
301- 350	200
351- 400	210
401- 450	220
451- 500	225
501- 550	230
551- 600	235
601- 650	240
651- 700	243
701- 750	247
751- 800	250
801- 900	254
901-1000	258
1001-1100	261
1101-1200	264
1201-1300	266
1301-1400	268
1401-1500	270
1501-1600	272

Minor characteristic table III

Lot size	Sample size
1- 25	100% inspection
26- 30	25
31- 35	26
36- 40	27
41- 45	28
46- 50	29
51- 55	30
56- 60	31
61- 65	32
66- 70	33
71- 75	34
76- 85	35
86- 95	36
96- 110	37
111- 130	38
131- 156	39
157- 190	40
191- 240	41
241- 340	42
341- 520	43
521-1120	44
1121 and over	45

4.3.2.1 Classification of characteristics. Critical, major, and minor characteristics are defined in MIL-STD-105. Inspection shall be conducted as follows:

4.3.2.1.1 End Plate, R.H., Control, Receiver (see dwg 8852531).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
101.	Location of potentiometer mounting holes	Gage
102.	Diameter of potentiometer mounting holes	Gage

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Minor: None defined.

4.3.2.1.2 End Plate L.H. Control Receiver (see dwg 8852530).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
101.	Total width	*Measure
102.	Length to angular cut	*Measure
103.	Angle of angular cut	Gage
104.	Location of holes	Gage
105.	Material (see 3.1)	Visual

*Measure with suitable scale.

Minor:		
201.	Workmanship (see 3.7)	Visual/Manual

4.3.2.1.3 Chasis Control Receiver (see dwg 8852450) Potentiometer (see dwg 8852468).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
101.	Objective evidence (see 6.2) available for part in accordance with dwg 8852450	Visual

Minor: None defined.

4.3.2.1.4 Clamp Control Receiver (see dwg 8852508).

Categories	Characteristics	Method of Inspection
Critical: None defined.		
Major:		
101.	Contour of formed portion	Gage
102.	Material (see 3.1)	Visual
Minor:		
201.	Workmanship (see 3.7)	Visual/Manual

4.3.2.1.5 Control Receiver Subassembly (see dwg 8852449).

Categories	Characteristics	Method of Inspection

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

Critical: None defined.

Major:
101. Soldering in accordance with MIL-S-60902(MU).....Visual/Manual
102. No nicked wires or loose parts.....Visual/Manual
103. Proper insulation where required.....Visual
104. Workmanship (see 3.7).....Visual/Manual

Minor: None defined.

4.3.2.1.6 Preparation for delivery (see section 5.1).

Categories	Characteristics	Method of Inspection

Critical: None defined.

Major:
101. Packaging, packing and marking in accordance with MIL-STD-1169(MU).....Visual

Minor: None defined.

4.3.2.1.7 Carton, Packing, Ammunition for Control Receiver Subassembly (see dwg 9240970 and 5.2).

Categories	Characteristics	Method of Inspection

Critical: None defined.

Major:
101. Item wrapped.....Visual
102. Item tight in carton.....Manual
103. Carton sealed in accordance with dwg 8880602.....Visual
104. Materials (see 3.1).....Visual
105. Marking.....Visual

Minor: None defined.

4.3.2.1.8 Packing and Marking for Storage and Shipments (see dwg 8808362 and section 5.2).

Categories	Characteristics	Method of Inspection

Critical: None defined.

Major:
101. Gross load weight, max.....*Measure
102. Contents tight in package.....Manual

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

103. Correctly packed.....Visual/Manual
104. Package material (see 3.1).....Visual

*Determine weight with a suitable scale.

Minor:
201. Marking.....Visual
202. Workmanship.....Visual/Manual

4.3.3 Testing. All the tests shall be performed. Tests do not have to be performed in the order specified.

Test	Classification
a. Input impedance	Major
b. Input sensitivity	Major
c. Frequency	Major
d. Frequency stability	Major
e. Selectivity	Major
f. Spurious response	Major

None of these tests are considered destructive and samples so tested may be returned to the lot.

4.3.3.1 Input impedance, input sensitivity, frequency, frequency stability, selectivity, and spurious response. Each control receiver subassembly shall be tested for input impedance, input sensitivity, frequency, frequency stability, selectivity, and spurious response in accordance with 4.4.3. If any control receiver subassembly fails to comply with drawing requirements, the subassembly shall be rejected and removed from the lot.

4.3.4 Acceptance inspection equipment.

4.3.4.1 Critical and major characteristics and tests. Inspection and testing shall be performed with the acceptance inspection equipment, operating instructions, and calibration instructions specified on the Equipment Lists (EL). EL's for assemblies are listed on the Equipment Tabulation, ET-8852449. When either of the conditions listed below exist, the contractor shall design required equipment or specify suitable commercial equipment. The contractor shall obtain approval of such designs operating instructions, and special calibration instructions as specified in 6.3 prior to use on the contract.

a. Any deviation from equipment or procedures specified on the EL is desired.

b. The code "CD" is listed in the "Part or Identifying Number" column on the EL.

4.3.4.2 Minor characteristics and tests. Acceptance inspection equipment for minor characteristics is not specified on EL's. The acceptance inspection equipment, operating instructions and calibration instructions used by the contractor for minor classification inspection shall be approved by the Government representative authorized by the procuring agency.

4.4 Test methods. The tolerances specified herein are absolute with no allowance for test equipment inaccuracy. The tolerances used by the manufacturer shall be equal to the absolute tolerances less the accuracy tolerances of the test equipment used.

Source: https://assist.dla.mil - Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

4.4.1 Low temperature (see 3.5). Place the item in the conditioning chamber and lower the temperature to -30 ± 1°C. After the temperature stabilizes (see 6.4), the item shall be exposed to the temperature for 4 hours minimum (min). While at this temperature, the item shall comply with drawing requirements for frequency stability. At the end of the 4 hour period, the item shall be removed from the chamber and allowed to return to ambient temperature +80 ± 20°Fahrenheit (F) without the use of forced heating.

4.4.2 High temperature (see 3.6). Place the item into the conditioning chamber and raise the temperature to +60 ± 1°C. After the temperature stabilizes (see 6.4), the item shall be exposed to the temperature for 4 hours min. While at this temperature, the item shall comply with drawing requirements for frequency stability. At the end of the 4 hour period, the item shall be removed from the chamber and allowed to return to ambient temperature +80 ± 20°F without the use of forced cooling.

4.4.3 Input impedance, input sensitivity, frequency, frequency stability, selectivity, and spurious response (see 4.3.3.1). The item shall be tested on approved equipment in accordance with instructions in the applicable equipment list.

5. PREPARATION FOR DELIVERY

5.1 Production control receiver subassemblies.

5.1.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.1.1.1 Level A. The subassembly shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.1.1.2 Level C. The subassembly shall be preserved and packaged in accordance with instructions contained in MIL-STD-1169(MU).

5.1.2 Packing.

5.1.2.1 Levels A and C. The subassembly shall be packed in accordance with the applicable instructions contained in MIL-STD-1169(MU).

5.1.3 Marking. Marking shall be in accordance with MIL-STD-1169(MU).

5.2 Repair part control receiver subassembly.

5.2.1 Preservation and packaging. Preservation and packaging shall be level A or C as specified (see 6.1).

5.2.1.1 Level A. The subassembly shall be packaged in accordance with dwgs 9240970 and 8808362 using the specified moisture barrier.

5.2.1.2 Level C. The subassembly shall be packaged in accordance with dwgs 9240970 and 8808362 except that the moisture barrier may be omitted.

5.2.2 Packing.

5.2.2.1 Level A and C. The subassembly shall be packed in accordance with dwgs 9240970 and 8808362.

5.2.3 Marking. Marking shall be as specified in accordance with dwgs 9240970 and 8808362, as applicable.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

a. Title, number, and date of this specification.

b. Selection of applicable level of packaging and packing required (see 5.1 and 5.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

6.2 Objective evidence. Records of contractor quality control and inspections which can be verified.

6.3 Acceptance inspection equipment. The contractor shall obtain approval of equipment designs, operating instructions, and calibration instructions from the Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SMUPA-NR4.

6.4 Temperature stabilization. The temperature is considered stabilized when the greatest peaks (both highest and lowest) continually observed over 5 minutes min. do not exceed the nominal temperature plus tolerance specified.

Custodian:
Army - MU

Preparing activity:
Army - MU

Project No. 1190-A048

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

MIL-R-50283(MU) Receiver, Control; Subassembly

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426 REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE ARMY

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-NR
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:19Z
Check the source to verify that this is the current version before use.