INCH-POUND

A-A-58062
15 June 1996

COMMERCIAL ITEM DESCRIPTION

Closed Circuit Impact (lusher and Screening Plant

This commercial item description covers a complete trailer(s) mounted closed circuit impact crusher and screening plant (crusher/plant). The crusher/plant shall be capable of crushing quarried rock, sand and gravel, dolomite limestone, traprock and construction rubble consisting of steel reinforced concrete, brick, block and asphalt. The Crusher/plant shall have a design rated capacity of 100 to 250 tons per hour depending on specific products being made and conditions. The crusher/plant shall be a horizontal shaft impactor of sufficient size to accept and crush stones as large as 48 inches in diameter. The overall production quantity of the crusher/plant shall be 100 to 250 tons per hour for materials having a physical property of MOH's hardness scale up to 7. NSN 3820-00-060-1841.

PRODUCT	SIZE	TONS PER HOUR (TPH)
a. Rock/Sand/Gravel	1 1/2" minus	250 TPH
b. Recycle Reinforced Concrete	1 1/2" minus	150 to 200 TPH
c. Recycle Asphalt	5/8" minus	100 to 125 TPH

Salient characteristics:

A. Feed Hopper and Vibrating Grizzly Feeder. The crusher/plant shall be fed by means of a vibrating type grizzly feeder, V-belt driven by a variable speed electric motor. The feeder shall include a receiving hopper, a grizzly section consisting of stationary bars, and a bypass chute with a flop gate to allow desired routing of the frees. The feed hopper and vibrating feeder shall have a common support structure which allows for removal as an individual unit.

Beneficial comments, recommendations, additions, deletions, clarifications, etc. and any data which may improve this document should be sent to: WR-ALC/LVRE, 225 , Ocmulgee Ct, Robins AFB, GA 31098-1647.

AMSC N/A FSC 3820

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.

B. Grizzly Fines Discharge Conveyor. The grizzly fines conveyor shall be crusher/plant mounted and have a minimum 18 inch width. It shall be reversible to discharge material to either side of the unit. Conveyor components shall include head pulley assembly, a tail pulley assembly with screw type takeups, antifriction rollers, rollers spaced on 48 inch maximum centers, full length skirtboards, 2-ply minimum standard commercial belting and V-belt driven by an electric motor.

C. Crusher. The crusher shall be a horizontal shaft impact type. The rotor shall be of solid steel construction and V-belt driven by the units diesel engine. The musher shall have a hinged housing hydraulically operated for access to the rotor and curtains. The crusher shall have a minimum of two independent, adjustable impact curtains, one serving as the primary and the other as the secondary. The primary curtain shall be a solid reversible casting with wrench-type adjustment. The secondary curtain shall be fabricated with replaceable liners and be hydraulically shim adjusted. The crusher feed opening shall e a minimum of 4 feet wide by 3 feet high. The crusher shall be mounted over a gathering hopper with replaceable steel liners.

D. Crusher Discharge Conveyor. The musher discharge conveyor shall be crusher/plant mounted and be a minimum of 42 inches in width. Conveyor components shall include lagged head pulley assembly, self cleaning tail pulley assembly with screw type take-ups, troughing rollers spaced on 48 inch maximum centers and antifriction return roller. Also to be included is an impact rail assembly in the loading area with impact absorbing replaceable rails, 2 ply minimum standard commercial belting, V-belt driven by an electric motor. An electromagnet shall be provided to remove any ferrous metal before the material is discharged onto the screen.

E. Couble Deck Vibrating Screen. The vibrating screen shall be 5’ x 16 inclined, double deck, to include an eccentric shaft assembly, comer support springs and be V-belt driven by an electric motor. The screen shall have the means to divert the sized material to the proper conveyor/hopper. The screen cloth for the following sized products shall be provided:

1. 2"
2. 1 3/4"
3. 1 1/2"
4. 1 1/4"
5. 1"
6. 3/4"
7. 1/2"
8. 3/8"

Source: https://assist.dla.mil -- Downloaded: 202610-26T10:00Z
Check the source to verify that this is the current version before use.

F. Closed Circuit Return Conveyor. The return conveyor shall be plant mounted and be a minimum of 24 inches in width. Conveyor components shall include head pulley assembly, tail pulley assembly with screws type take-ups, troughing rollers spaced on 48-inch maximum centers, return rollers, full length skirtboards, 2 ply minimum standard commercial belting and V-belt driven by an electric motor.

G. Folding and Revesible Side Discharge Conveyor. The side discharge coveyor shall be crusher/plant mounted with a minimum width of 24 inches. Conveyor components shall include a head shaft assembly, tail pulley assembly with screw type take-ups, a gathering hopper, troughing rollers spaced on 48 inch maximum centers, return rollers, 2 ply minimum standard commercial belting and V-belt driven by an electric motor.

H. Front Discharge Conveyor. The front discharge conveyor shall be crusher/plant mounted and be a minimum of 42 inches in width. Conveyor components shall include lagged head pulley assembly with screw type take-ups, self cleaning tail pulley assembly, troughing rollers, spaced on 48 inches maximum centers, return rollers, 2 ply minimum standard commercial belting and V-belt driven by an electric motor.

I. Radial Stacking Conveyor. Included are three 30” by 60’ portable radial stackers each powered by an electric motor (minimum 15 hp), pre-wired for plug in to the control panel, hydraulically adjustable 19’3“ discharge height, gathering hoppers, swivel wheels for conversion from towing to radial configuration and anchor pivot plates.

J. Power Unit. The power unit shall be plant mounted and consist of a diesel engine rated at a minimum of 325 horsepower (hp) continuous at 1899 RPM, which shall directly drive both the crusher and a 460 volt, 3 phase, 60 cycle, 100 KW rated generator. The diesel engine shall supply the necessary power required to operate both the crusher and 100 KW generator simultaneously at full design rating. The engine shall operate satisfactorily on grade JP-4 and JP-5 fuel conforming to MIL-T-5624 under emergency, short duration conditions and on grade JP-8 fuel conforming to MIL-T-83133 under normal conditions. The generator shall be sufficient in size to run all plant mounted electric motors plus three additional minimum 15 HP motors for the radial stackers. The diesel engine shall be equipped with but not limited to, hood and sides, heavy duty dry type air cleaners, muffler and vertical exhaust stack, instruments including tachometer, hourmeter, temperature gauge, oil pressure gauge and voltmeter, alternator and voltage regulator, 24 volt electric starting system including batteries, box and cables, 200 gallon minimum fuel capacity, low oil pressure. high temperature and high RPM safety devices. a governor and a sufficient size clutch for engaging arid disengaging the crusher. The engine shall have a run and idle speed only. The generator shall supply 460 volts to the central control panel during operation.

Source: https://assist.dla.mil -- Downloaded: 2026l0-26T10:00Z
Check the source to verify that this is the currentversion before use.

K. Control Panel. The control panel shall be plant mounted and conform to BEMA 4 enclosures. It shall provide a main circuit breaker that will disconnect the entire plant load from the electrical power source circuit and also provide circuit breakers for each electrical branch circuit. The control panel shall be provided with the necessary circuit receptacles mounted on the side of the enclosure for receiving electrical connections from the auxiliary equipment. All power receptacles shall have spring loaded covers. A motor controller, operated by a momentary contact start, and maintained contact stop pushbuttons, shall be provided for each electric motor and be mounted in a remote pendant station located at the operator level. The remote station shall include an emergency panic button. These pushbuttons shall be wired in sequence of plant operation and carry a maximum of 115 volts. An emergency panic button, which controls tripping of the main circuit breaker, shall be installed in the control panel door and be easily accessible from ground level.

L. Operator and Service Platforms. An operator's platform, complete with railings, ladder and non-skid flooring, shall be provided. In addition to the operator's platform, service type platforms shall be located in the impact crusher and power unit areas to facilitate maintenance and service. Ladders shall provide access to service type platforms where applicable.

M. Guards. All V-belt drives shall be provided guards. The power unit drive guards, shall have a hinged door in front of each drive sheave to facilitate maintenance and service.

N. Electric Mortors. All electric motors shall by polyphase induction motors and of the totally enclosed fan cooled configuration. The rated horsepower of each electric motor shall be equal to or greater than the horsepower requirement of the driven equipment, under all operating conditions including full rated capacity. The electric motors shall be suitable for operation on 460 volt, 60 hertz, 3 phase, CA power supply.

O. Electromagnetic Separator. A standard commercial self cleaning belt magnet to remove rebar and metal from crushed concrete at the crusher discharge conveyor to eliminate metal rebar and other objects from entering the double deck vibrating screens. The self cleaning belt shall be clad with stainless steel plates with intermittent cleats.

P. Hydraulic Lift/Leveling System. A DC powered hydraulic lift/leveling system shall be provided.

Q. Semi-Trailer Mounting. The crusher/plant shall be semi-hailer mounted. All tires on the semi-trailer shall be the same tubeless type, rim size, tire size and ply rating. Rim and tire ratings shall conform to the Tire and Rim Association recommendations for the type and size of tires furnished for the load supported. The trailer brakes shall be full air type

Source: https://assist.dla.mil -- Downloaded: 2026l0-26T10:00Z
Check the source to verify that this is the currentversion before use.

with air controls. The front of the trailer shall reequipped with a fifth wheel plate ad pin that will hook up to commercial fifth wheel heights of 48 to 51 inches. The semi-trailer shall be equipped with one set of two 24-volt hydraulically operated leveling jacks.

R. Maintrenance Kit. A maintenance kit consisting of filter elements, O-rings and other parts required for the first maintenance service at 50 operating hours shall be provided. This kit shall be noted separately in the (1) parts book, (2) operator's manual and (3) service manual. The maintenance kit shall be used as an Air Force War Readiness Supplies Kit (WRSK) for field operations.

S. Manuals. Each crusher/plant shall be provided with two copies each of (1) parts book, (2) operator's manual and (3) service manual.

T. Spare Parts Kit. The supplier of the crusher/plant shall furnish a spare parts kit that will ensure operability for a minimum period of 300 hours. A list of the parts furnished in the spare parts kits shall be submitted for review at the time of bid submission for completeness, cost and approval. Spare parts kit list shall be included in the parts manual.

U. Repair and Maintenance Parts. The following repair and maintenance parts shall be furnished with the crusher/plant.

a. Two sets blow bars with pin.
b. One each different type conveyor belt hinge pin.
c. Two sets of V-belts for diesel power unit and conveyors if required.
d. Two each conveyor belts for the crusher discharge, return, side discharge and front discharge.
e. One each different horse power electric motor.
f. Two each different type idlers.
g. Six each all types rollers.
h. Three each solenoid switch.
i. One each different type belt field repair kit.
j. One each screen cloth for the following sizes of product.
    1. 2"
    2. 1 3/4"
    3. 1 1/2"
    4. 1 1/4"
    5. 1"
    6. 3/4"
    7. 1/2"
    8. 3/8"
k. One each feeder drive sheave.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.

l. One each different applicable starter.
m. Three each different size fuse.
n. Twelve each screen rail bolts.
o. Twelve each screen rail wedges.
p. Four each air, oil, fuel, water and hydraulic fuel filters.

v. Standardized Metal Container Option. The size and number of containers used shall be predicated on the type, quantity and size of materials packed. Commercially available container options are as follows:

l. Three standard sized containers shall be provided for the repair and maintenance parts, one size shall be 90” by 72” with a maximum allowable weight of 4000 pounds, the second size shall be 45” by 72” with a maximum allowable weight of 4000 pounds, and the third size shall be 45” by 36” with a maximum allowable weight of 2000 pounds. Height of each container can vary, however, if a standard height can be determined which generally matches up with all requirements, it shall be used exclusively.

2. A single commercial 10’ by 20’ sea-hind-van container.

All containers shall meet the following requirements:

a. Shall have a forklift and lifting lugs capability (lifting lug capability is not required if option 1 is chosen).
b. Shall be capable of repelling blowing rain when sorted outside.
c. Shall be provided with vertical dividers to support and separate.
d. Shall be provided with removable shelving supported on vertical dividers.
e. Shall be stackable three containers high.
f. Top shall be hinged or lift-off design, one piece or multiple pieces.
g. Container shall be given an ID number, listed in parts manual and be provided with an inventory list of equipment and/or material packed in a container. Also enclosed shall be technical written material concerning the packed equipment and its application, if applicable.
h. Shall be primed and painted inside, color shall be the same as the crusher/plant.

w. Lubricaiton Plate. A lubrication plate showing the following information shall be securely attached to each crusher/plant.

a. Point of application
b. Service interval
c. Type of lubricant
d. viscosity of lubricant

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.

x. Cleaning, Painting, Plating Anodic Films and Chemical Treatment. Cleaning, painting, plating, anodic films, and chemical treatments shall be in accordance with the manufacturer's standard commercial practice.

Y. Paint. The outer surface of the crusher/plant and any interior compartments shall be primed and painted in accordance with the manufacture's standard commercial practice. The paint color shall be olive drab green. The crusher/plant shall be rust proofed/undercoated in accordance with the manufacture's standard commercial practice.

Z. Safety. All rotating or reciprocating parts, and all parts subject to high operational temperature that are of such a nature or are located as to be hazardous to personnel, shall be guarded of insulated to eliminate the hazard. Ladders, steps and handrails shall be provided so entrance and exit are unhampered and nonhazardous. All brake pads and braking material shall be made from asbestos free compounds if commercially available. The crushing/plant shall conform to all Federal Laws and Regulations concerning noise, air pollution and other health and safety regulations which are in effect for this type of equipment at the time of contract award.

AA. Operational Environment. The crusher/plant, as specified, shall be capable of travel and full operation in temperatures from minus 20 to 120 degrees Fahrenheit at sea level and in temperatures from 0 to 120 degrees Fahrenheit at altitudes up to 8000 feet above sea level.

BB. Dust Suppression system. The manufacturer's standard commercial dust suppression system shall be provided and should include as a minimum a spray bar withwith brass nozzles and a glove shut of valve at the transition between the feed hopper and the crusher.

CC. Identificatyion Plate. An identification plate, permanently marked in accordance with MIL-STD-130, shall be securely attached to the vehicle in a readily accessible location. The identification plate shall contain the following information:

NOMENCLATURE

MANUFACTURER'S MODEL NUMBER

MANUFACTURER'S SERIAL NUMBER

MANUFACTURER'S NAME

MANUFACTURER'S ADDRESS

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.

MANUFACTURER'S SERVICE PHONE NUMBER

DATE OF MANUFACTURE

CONTRACT NUMBER

NATIONAL STOCK NUMBER

REGISTRATION NUMBER

DD. The crusher/plant furnished must be the latest model as of the date of award (with minor modifications, as that term is defined in DoD FAR Supplement 252.211-7012, Paragraph K-85 of the solicitation) of an established product previously produced and sold in substantial commercial quantities (exceeding the criteria at FAR 15.804-39 (f) (2) (ii) (A)) for at least three years immediately preceding the issuance date of the solicitation. The crusher/plant furnished or earlier models of it, absent minor modifications, shall have routine] y been supported with spare/repair parts which were produced or sold in the normal course of business. At the time of delivery, the contractor shall furnish the Administrative Contracting Officer with verification of compliance with these requirements.

NOTE TO OFFERORS: Offerors shall provide, as part of their proposals, the following information on the item (or its earlier models) being offered as a commercial item:

(1) Total sales to the U.S. Government or to contractors for U.S. Government use during the three years immediately preceding the issuance date of the solicitation.

(2) Total sales of the item to the general public during the three years immediately preceding the issuance date of the solicitation.

(3) Length of time the item has been sold in the commercial market place.

(4) Points of contact and phone numbers of customers to which the item has been sold in the commercial market place.

(5) Other pertinent information necessary to determine That the item is an established commercial item.

Contractor certification. The contractor shall certify that the product offered meets the salient characteristics of this description and conforms to the producers' own drawings. specifications, standards, and quality assurance practices. The Government reserves the

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.

right to require proof of such conformance prior to first delivery and thereafter as may be otherwise provided for under the provisions of the contact.

Regulatory requirements.

Recovered materials. The offeror/contractor is encouraged to use recovered materials in accordance with Public Law 94-580, as amended, and as implemented by Federal . Acquisition Regulation Subpart 23.4 to the maximum extent practical.

Preservation, packaging, packing, labeling, and marking. Unless otherwise specified, preservation, packaging, and packing shall be to a degree of protection to preclude damage to containers and/or contents thereof under normal shipping conditions, handling, etc., involving shipment from the supply source to the receiving activity, plus reshipment from receiving activity, and shall conform to applicable carrier's rules and regulations. Intermediate and exterior package quantities, labeling, and marking shall be as specified in the contract and/or order.

Custodian:
AIR FORCE -99

Preparing Activity:
AIR FORCE -84

Project number 3820-0003

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:00Z
Check the source to verify that this is the current version before use.