MIL-G-15840C
AMENDMENT 3
30 September 1976

SUPERSEDING
AMENDMENT 2
28 JULY 1976

MILITARY SPECIFICATION

GARBAGE DISPOSAL MACHINES, COMMERCIAL AND HOUSEHOLD

This amendment forms a part of Military Specification MIL-G-15840C dated 15 March 1963, and is approved for use by all Departments and Agencies of the Department of Defense.

Page 1

Paragraph 1.2, Type I, Class 2, under "Capacity", remove: "1,000 pounds per hr-1¼", and add: "1,000 pounds per hr-1½".

Page 2

Remove note in parenthesis at end of paragraph 2.1 which begins as follows: "Copies of specifications, standards, ...".

After MIL-STD-130 . . . .", add: "MIL-STD-882 System Safety Program For Systems and Associated Subsystems and Equipment: Requirements for

(Copies of specifications, standards, drawings, and publications required by suppliers, in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)"

Page 4

Paragraph 3.9 Safety. Add: Following the last sentence which ends: " . . . . or properly guarded." "All equipment furnished under this specification shall be analyzed for Category III and Category IV hazards as defined in MIL-STD-882. Any hazard so identified shall be brought to the attention of the procuring agency with recommended action for satisfying safety requirements. Action order of precedence shall be as specified in MIL-STD-882, para 5.6. Safety devices shall include, but shall not be limited to, devices to prevent accidental contact with parts that would present electrical hazard and guards for belts, pulleys, chains, gears, guideways and sprockets. All guards shall be designed to allow access to the shielded parts."

FSC 4540

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T08:05Z
Check the source to verify that this is the current version before use.

Page 5

Add: New Sub-Paragraph:

"3.13.4 Automatic reverse control. The machine shall be equipped with an automatic reverse control which automatically reverses the action in the event of clog up. The reverse action of the mechanism shall clear the lines in such a manner that the machine will again be operable."

Page 6

Add: New Sub-Paragraph:

"4.5.3.3 Automatic reverse control test. The machine shall be tested to determine compliance with paragraph 3.13.4."

Custodians:
Air Force - 99
Navy - YD
Army - ME

Preparing Activity:
Air Force - 99

Project Number:
4540-0058

Source: https://assist.dla.mil -- Downloaded: 2026-10-18T08:05Z
Check the source to verify that this is the current version before use.