MILITARY SPECIFICATION

TEST SET, ELECTRICAL, M40
PARTS FOR, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the parts, assembling and packing for one type of test set designated as Test Set, Electrical, M40.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

PPP-B-636 - Boxes, Fiber

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1345

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

DRAWINGS

U.S. ARMY MUNITIONS COMMAND

8800950 - Test Set, Electrical Circuit, M40

PUBLICATIONS

U.S. ARMY MUNITIONS COMMAND

ET - 8800950 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in comection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Materials, parts and assemblies shall be In accordance with applicable drawings and specifications.

3.2 Test sets.-The test sets shall comply with all requirements specified on drawing 8800950 and with all requirements specified in applicable specifications.

3.3 Five foot drop.-Test sets shall show no evidence of cracking or separating after being subjected to the five foot drop test and shall function satisfactorily when tested as specified in 4.4.4.

3.4 Wiring.-The distance between any portion of the bulb circuit and any portion of the resistor circuit shall be not less than 1/8 inch.

3.5 Functioning

3.5.1 Test set.-The test set (see dwg. 8800950) shall function satisfactorily as evidence by a flash of the lamp with the output terminals connected to a dummy load, and by no flash of the lamp with the output terminals open when tested as specified in 4.4.2.

3.5.2 Test set (lamp).-The test set (see dwg. 8800950) shall function satisfactorily and shall not blow out when tested as specified in 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

3.6 Functioning of lamp.-The lamp (see dwg. 9275725) shall function satisfactorily and shall not blow out when connected in series with a fifteen (15) ohm resistor and tested as specified in 4.4.8.

3.7 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, crazes, unblended radii, porosity, warpage, burn marks, checks, chipped edges, blisters, excess flash, dirt, grease, rust, salt deposits, visible raised cement seams, solder splash, corrosion products, and other defects and foreign matter which would affect their serviceability. The cleaning method used shall not be injurious to any part norshall the parts be contaminated by the cleaning agent. All required markings shall be neat and sharply defined.

3.8 First article inspection.-This specification makes provisions for first article Inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specifted In the contract or order, the supplier may use hts own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth In the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of Items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.

b. Drawing and specification number and date, together with identification and date of changes thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

c. A statement that all material purchased by the contractor meets requirements, when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.
d. Number of items In the lot.
e. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agentts authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-Prior to the start of' regular production, the contractor shall submit a first article sample (see 6.lc) to a Government approved facility as designated by the contracting officer for evaluation in accordance with the provisions of 4*2.2. The first article sample shall consist of component parts, sub-assemblies and assemblies which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing components, shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that It conforms to the requirements of the contract and he shall submit a record of this inspection with the sample, including certificates of conformance of materials. A sample containing known defects shall not be submitted unless specifically authorized by the contracting officer. A first article sample, or portion thereof, as directed by the contracting officer shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing or specification such as to significantly affect product uniformity as determined by the Government. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit an additional sample or portion therecsf of items for first article inspection. Until that phase of the first article sample consisting of parts, and test sets is accepted, the contractor is in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:19Z
Check the source to verify that this is the current version before use.

4.2.2 First article inspection provisions.

4.2.2.1 Component parts and subassemblies.

4.2.2.1.1 Submission.-Twenty-five (25) complete sets of parts (i.e. 25 each of every component parts and subassembly, including at least three (3) items from each cavity used to produce plastic parts and so identified as to permit tracing each item to the cavity in which it was molded).

4.2.2.1.2 Inspections to be performed.-The parts and sub-assemblies will be subjected by the Government to any or all of the applicable examinations and tests specified in 4.3.2, 4.3.3 and 4.3.5 of this specification and any or all of the requirements of the applicable drawings.

4.2.2.1.3 Rejection.-If any component or subassembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component or subassembly to comply with any of the stated requirements.

4.2.2.2 Test set assemblies

4.2.2.2,1 Submission.-Thirty (30) test sets completely packaged and sealed as required by the applicable drawings.

4.2.2.2.2 Inspections to be performed.-The thirty (30) test sets shall be subjected to the following tests in the sequence indicated in addition to the inspections specified in 4.3.2.9:

a. Functioning (see 3.5.1) in accordance with 4,4.2.
b. Functioning (see 3.5.2) in accordance with 4.4.3.
c. Five foot drop test (see 3.3) in accordance with 4.4.4.

4.2.2.2.3 Rejection.-If any test set fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of the test set to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term “inspection lot” as used in this specification is defined as an essentially homogeneous collection of units of protiuct from which a representative

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchange process, using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified In MIL-STD-105. Changes to the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procdure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of test sets shall contain parts from not more than one lot interfix number from one manufacturer.

4.3.2 Examination. -The examinations listed in the following subparagraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designed in the applicable paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL?s designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable subparagraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor’s inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Connector assembly, male (see dwg. 8800911 covering a detail of dwg. 8800950).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Component improperly assembled, damaged, loose or missing	Visual	01002
102.	Clip ends not secure	Manual	01003
103.	Clip base not flat or not seated	Visual	01004
104.	Presence of rubber or other foreign material on contacts	Visual	01007
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	01006

4.3.2.2 Connector, female (see dwg. 8837107 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Component improperly assembled,		02003
102.	Presence of rubber or other foreign material on contacts	Visual	02004
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	02005

4.3.2.3 Case (see dwg. 9211698 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Crack or poor weld line	Visual	03001
102.	Alignment of mating surfaces over maximum (max)	Visual	03002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

Minor: AQL 0.65 percent

201.	Evidence of poor workmanship (see 3.7)	Visual	03004

4.3.2.4 prong (see dwg. 9212136 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Length	Gage	04001
102.	Prong end length	Gage	04002
103.	Prong end diameter	Gage	04003
104.	Diameter "A"	Gage	04005
105.	Knurl missing or inadequate	Visual	04007
Minor:	AQL 1.5 percent		
201.	Hole "A" depth	Gage	04008
202.	Body length	Gage	04004
203.	Diameter "B"	Gage	04006
204.	Evidence of poor workmanship (see 3.7)	Visual	04009

4.3.2.5 Contact, female prior to pinch (see dwg. 9212137 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Length	Gage	05001
102.	Front hole diameter	Gage	05002
103.	Diameter "A"	Gage	05004
104.	Slot length	Gage	05006
105.	Entrance radius missing	Visual	05007
106.	Knurl missing or inadequate	Visual	05008
Minor:	AQL 2.5 percent		
201.	Front hole depth	Gage	05009
202.	Hole "A" depth	Gage	05010
203.	Body length	Gage	05003
204.	Diameter "B"	Gage	05005
205.	Evidence of poor workmanship (see 3.7)	Visual	050011

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

4.3.2.6 Contact, female (see dwg. 9212137 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Front hole diameter	Gage	06001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	06002

4.3.2.7 Case and connector assembly (see dwg. 921-2138 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Component improperly assembled, damaged, loose or missing	Visual	07001
102.	Wiring too close (see 3.4)	Visual	07002
103.	Solder or crimp incorrect (as applicable)	Visual	07003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	07004

4.3.2.8 Bulb and vial assembly (see dwg. 9212139 covering a detail of dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Component improperly assembled, damaged, loose or missing	Visual	08001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	08002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

4.3.2.9 Test set, M40 (see dwg. 8800950).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Component improperly assembled, damaged, loose, or missing	Visual	09001
102.	Evidence of insufficient potting (not flush)	Visual	09003
Minor:	AQL 1.0 percent		
2010	Marking misleading or unidentifiable	Visual	09004
202.	Evidence of poor workmanship (see 3.7)	Visual	09005

4.3.2.10 Carton, sealed (see section 5).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed	Visual	10001
102.	Sealing strip incomplete, badly wrinkled, or not in full contact with surface around entire carton	Visual	10002
Minor:	AQL 1.0 percent		
201.	Contents move when carton is shaken	Manual	10003
202.	Marking misleading or unidentifiable	Visual	10004

4.3.3 Testing

4.3.3.1 Resistance of resistor - Major defect - Code No. 11001 (see dwg, 9207841). Fifty (50) resistors shall be selected from each lot for test. The lot shall be rejected if any resistor fails to comply with the requirements. The test shall be performed as specified in 4.4.1 using test equipment in accordance with 4.3.4. (non-destructive)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

4.3.3.2 Functioning of test set - Major defect - Code No. 11002 (see 3.5.1).-This test shall be performed 100 percent. Any test set which falls to comply with the requirements shall be classed defective and removed from the lot. The test shall be performed as specified in 4.4.2 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.3 Functioning of test set (lamp) - Major defect - Code No. 11008 (see 3.5.2).-One hundred and twenty five (125) test sets shall be selected at random from each lot for test. The lot shall be rejected if two (2) or more lamps fails to comply with the requirements. The test shall be performed as specified in 4.4.3 using test equipment in accordance with 4.3.4. (Non-destructive).

4.3.3.4 Five foot drop - Major defect - Code No. 11003 (see 3.3).-Fifty (50) test sets shall be selected from each lot for test. The lot shall be rejected if any test set fails to comply with the requirements. The test shall be performed as specified in 4.4.4 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.5 Load test - Major defect - Code No. 11OO4 (male connector dwg. 8800925) - Code No. 11005 (female connector dwg. 8837107).-Fifty (50) connectors of each type shall be selected from each lot for test. The lot shall be rejected if any connector fails to comply with the requirements. The test shall be performed as specified in 4.4.5 using test equipment in accordance with 4.3.4. (Non-destructive)

4.3.3.6 Pull test of crimped prong and contact connections Major defect - Code No. 11oo6 (see dwg. 9212138).-A sample of at least 5 of each prong and each contact shall be crimped with a one-foot length of the appropriate gauge of solid copper wire and tested as specified in 4.4.6 to qualify new or adjusted crimping equipment for use in production or as a control of the equipment during production. Testing for control of crimping equipment during production shall be performed on the above quantity of samples from each crimping machine beginning with the samples crimped at the start of regular production and at the end of each continuous production run of four hours or less~ If any defective crimp is found when testing is performed for control of the equipment, the equipment producing the defective crimp shall be removed from production. Further, that portion of production since the last control check shall be returned to

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:19Z
Check the source to verify that this is the current version before use.

the contractor for testing, according to MIL-STD-105, Code Letter G, AQL 1.5 percent. All equipments formerly removed from production because of some fault may, after correction, be returned to production providing they pass the qualification test above. The contractor may request a change of testing frequency providing he presents objective evidence to the Contracting Officer to substantiate the request. Test equipment shall be in accordance with 4.3.4. (Destructive Test)

4.3.3.7 Resistance of lamp - Major defect - Code No. 11007 (see dwg. 9275725).-One hundred and twenty-five (125) lamps shall be selected from each lot for test. The lot shall be rejected if two or more lamps fail to comply with the requirements. The test shall be performed as specified in 4.4.7 using test equipment in accordance with 4.3.4. (Non-Destructive)

4.3.3.8 Functioning of lamp - Major Defect - Code No. 11009 (see 3.6).-Eighty (80) lamps shall be selected at random from each lot of lamps for this test. The lot of lamps shall be rejected if one or more lamps fail to comply with the requirements. The test shall be performed as specified in 4.4.8 using test equipment in accordance with 4.3.4. (Destructive Test)

4.3.4 Inspection equipment.-Equipment Tabulation Number ET-8800950 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to docurnentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, c~nstruction, sur~e.y and Nhenever in~peckion equipment drawings are netied.

4.3.5 Dimensional control of molded parts.-In place of the normal samplin~ and inspections associated with the Classification of Defects, and after a curing time for the parts has been approved (see Note 1) a sample of three (3) parts (as molded) from each cavity shall be fully inspected dimensionally to qualify a new or reworded cavity for use in production. The molded parts shall carry the individual cavity identification. As a control of each cavity during production, the above quantity of parts from each cavity shall be inspected for at least the defects listed

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

in paragraphs 4.3.5.1 through 4.3.5.3 after continuous production of each 5,000 parts or at the end of each week, whichever occurs first. Of the three (3) samples, one (1) sample shall be the last part produced. If any defective parts are found during qualification of the cavity, the cavity producing the defective part will not be used in production. If any defective parts are found when inspection is performed for the control of the cavity, the cavity producing the defective part shall be removed from production. Further, that portion of production since the last control check shall be returned to the contractor for inspection for each separate type of defect according to MIL-STD-105, using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. All cavities removed from production because of some fault, may after reworking, be returned to production providing they pass the qualification test above. The contractor may request a change of inspection frequency providing he presents objective evidence to the contracting officer to substantiate the request. Contractor design of gages and test equipment required to perform the inspections listed herein shall be forwarded to Commanding Officer, Picatinny Arsenal, Dover, New Jersey 07801, ATTN: SMUPA-QA-A-M for approval prior to manufacture of equipment. The following subparagraphs identify those items and minimum inspections subject to the requirements of tl~is paragraph.

NOTE 1.-In establishing a curing time, dimensionally check ten (10) parts from each cavity at periodic intervals (e.g. every 30, 60, etc. mins.) until dimensional stability is attained. The curing time will be from the time the part comes out of the mold until dimensional stability is attained. The inspection data used in determing the curing time shall be sent to Picatinny Arsenal, Dover, New Jersey, 07801, ATTd: SMUPA-QA-A-M. If any new change in material, cycle time, a reworked cavity, or a new cavity is used, a new curing time shall be established and approved.

4.3.5.1 Connector, Male (see dwg. 8800925 covering a detail of dwg. 8800950).

Major Defect	Method of Inspection	Code No.
101. Prong c-to-c distance	Gage	12001
102. Cap does not fit securely	Manual	12002
103. Depth to prong tips	Gage	12003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

4.3.5.2 Connector, Female (see dwg. 8837107 covering a detail of dwg. 8800950).

Major Defect		Method of Inspection	Code No.
101.	Depth to contact tops	Gage	13004
102.	Contact c-to-c distance	Gage	13001
103.	Front hole entrance diameter of contacts	Gage	13002
104.	Cap does not fit securely	Manual	13003

4.3.5.3 Case (see dwg. 9211698 covering a detail of dwg. 8800950).

Major Defect		Method of Inspection	Code No.
101.	Evidence of mold wear or shifting	Visual	14001
102.	Counterbore diameter under-size	Gage	14002
103.	Marking misleading or unidentifiable	Visual	14003

4.4 Test methods and procedures

4.4.1 Resistance.-The resistance of the resistor shall be measured using an ohmeter. Observation shall be made for compliance with the applicable drawing requirements.

4.4.2 Functioning.-The test set shall be connected to a pulse generator and functioned at the 12 mini-watt-second energy position. The lamp shall be observed for compliance with the applicable requirement.

4.4.3 Functioning of test set (lamp).-The test set shall be connected to a pulse generator and functioned at the twenty-seven (27) milliwatt second energy level for ten (10) consecutive pulses. The lamp shall be observed for compliance with the specified requirement.

4.4.4 Five-foot drop.-The test set shall be examined for any evidence of cracking or separation of parts after being dropped from a height of 5 plus or minus 0.25 feet onto a 2-inch-thick pine plank. The test set shall then be functioned in accordance with 4.4.2 and checked for compliance with the specified requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

4.4.5 Load test of male and female connectors.-With the connector held securely in a tensile testing machine, the required force shall be applied at the crimping end of each prong and contact separately with a speed of head travel of 1 inch per minute maximum. Observation shall be made for compliance with the specified requirements.

4.4.6 Pull test of crimped prong and contact connections.- The prong and contact connections shall be placed in a tensile testing machine and sufficient force applied to pull the wire out of the sample or break the wire. The test shall be conducted with a speed of head travel of 1 inch per minute maximum. observation shall be made for compliance with the specified requirements.

4.4.7 Resistance of the lamp.-The resistance of the lamp shall be measured using an ohmeter. Observation shall be made for compliance with the applicable drawing requirement.

4.4.8 Functioning of lamps. -The lamps shall be tested prior to assembly in the test set. The test lamp shall be connected in series to a fifteen (15) ohm resistor, plus or minus 10 percent, then connected to a pulse generator and functioned at the twenty-seven (27) milliwatt second energy level for one hundred (100) consecutive pulses. The lamp shall be observed for compliance with the specified require~ent. Lamps subjected to this test shall not be returned to the lot.

5. PREPARATION FOR DELIVERY

5.1 Packing

5.1.1 Level C.-Sixty (60) test sets shall be packed in a fiber box conforming to PPP-B-636, Type CF, Class Domestic, Variety SW, Grade 200, Style RSC complete with a fiberboard liner and plain fiberboard pads constructed of the same test and fiberboard as the box. The liner shall be inserted around the inside surfaces of the box and a plain pad placed on the bottom of the box. The test sets shall be positioned in the box, electrical receptacle end down, in a 6 by 5 arrangement; 30 sets per layer; 2 layers per box. A plain pad shall be placed between layers and one or more pads on top of contents, as required, to insure a tight pack. Fiber box size shall be approximately 9-1/8 by 8-1/4 by 7-1/2 inches depth, inside dimensions. Liner shall be approximately 34-1/4 inches long by 7-1/2 Inches wide scored as required to fit flush against the interior side and end walls of the box. Plain pads shall be approximately 8-7/8 by 8 inches. Box shall be closed and sealed in accordance with instruction contained in the appendix of the box specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

5.2 Palletization.-Boxes may be palletized at the shippers option. Palletization shall conform to MIL-STD-1169 instructions for Level C shipment.

5.3 Marking.-Marking of boxes and pallet loads shall comply with MIL-STD-1169 requirements.

5.4 Shipping.-When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.
c. Provisions for submission of first article samples

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are of two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers on the Equipment Lists referenced on the Equipment Tabulation. Design responsibility for all other inspection equipment is assigned to the contractor. Equipment to be designed by the contractor is designated “CD”. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

b. A source control drawing or a specification control drawing as defined in MIL-STD-1OO.

c. An envelope drawing, as defined In MIL-STD-1OO, which establishes the criteria which a detail design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the con-- tractor proposed to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public). Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commerical equipment shall be fully described by catalog listings or other means which provide suf- ficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per M1L-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, “Inspection Equipment Design” for guidance. The specification number and the applicable five- dlgit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of destgns for approval.-Contractor designs shall be approved by the Government prior to fabricating or pro- curing the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SMUPA-QA-A-M, Dover, New Jersey, 07801 in accordance with the stipulations, time frame and distribution specified in the contract Data Requirements List (DD Form 1423) or in the contract. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1345-A-004

Source: https://assist.dla.mil -- Downloaded: 202640-22T05:19Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 22-R255

INSTRUCTIONS: This sheet is to be filled out by personnel, either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments and suggestions submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or serve to amend contractual requirements.

SPECIFICATION

ORGANIZATION

CITY AND STATE

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO *(If "yes", in what way?)*

4 REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity - Optional)*

DATE

DD FORM 1 JAN 66 1426

REPLACES EDITION OF 1 OCT 64 WHICH MAY BE USED.

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:19Z
Check the source to verify that this is the current version before use.

FOLD

Department of the Army
Headquarters, Picatinny Arsenal
Dover, New Jersey 07801

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY

OFFICIAL BUSINESS

Commanding Officer
Picatinny Arsenal
ATTN: SMUPA-QA-A
Dover, New Jersey 07801

FOLD

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:19Z
Check the source to verify that this is the current version before use.