MILITARY SPECIFICATION

TEST SET, ELECTRICAL, M40
PARTS FOR, ASSEMBLING AND PACKING

This Amendment forms a part of Military Specification MIL-T-46238E(AR), dated 22 January 1973, and is approved for use by the US Army Armament, Munitions and Chemical. Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 2

2.1 Add to drawings the following:

9201429 - Sinusoidal Pulser
9201431 - M40 Test Set Operating Instructions
9~01434 - Sinusoidal Pulser with Four Levels Calibration Procedures

2.1 Wiete from PUBLICATIONS the following:

ET - 8800950 - Equipment Tabulation

PAGE 10

4.3.2.9 ueiete Major Defect 102 and substitute as foilows:

102	Evidence of insufficient potting (not more than .125 inch below flush)....Gage		0900

4.3.2.9 Change AQL 1.0 percent to read 1.50 percent

4.3.2.9 Add minor defect 203 as follows:

203	Gap greater than .015, or foam does exude between case halves	Gage/ Visual	09006

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:19Z
Check the source to verify that this is the current version before use.

PAGE 11

4.3.3.2 Delete from last sentence:

"using test equipment in accordance with 4.3.4”

4.3.3.3 Delete from last sentence:

“usinq test equipment in accordance with 4.3.4”

PAGE 12

4.3.4 Delete in its entirety and substitute as follows:

“4.3.4 Inspection equipment. Inspection equipment required to perform the inspection prescribed in this specification is identified i.n the Examination (4.3.2 and 4.3.5) and Test Method (4.4) paragraphs herein. See 6.3 for details concerning responsibilities for inspection equipment design and approval."

4.3.4.1 Delete in its entirety.

PAGE 14

4.4.2 Add last sentence as follows:

“Test shall be conducted using the equipment and procedures specified on dwg. 9201429, 9201431, and 9201434.”

PAGE 15

* 5* Delete in its entirety and subsitute:

“5. PACKAGING

5.1 Packaging.

?5.1.1 Level A. Test sets and all packaging material sha?l be thoroughly clean and dry before packaging. sixty (60) test sets shall be packed in a fiber box conforming to PPP-B-636, Type CF, Class Domestic, Variety SW, Grade 200, Style RSC complete with a fiberboard liner and plain fiberboard pads constructed of the same test and fiberboard as the box. The liner shall be inserted around the inside surfaces of the box and a plain pad placed on the bottom of the box. The test sets shall be positioned in the box, electrical. receptacle end

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

down, in a 6 by 5 arrangement; 30 sets per layer; 2 layers per box . A plain pad shall be placed between layers and one or more pads on top of contents, as required, to insure a tight pack. Advisory fiber box size shall be approximately 9-1/8 by 8-1/4 by 7-1/2 inches depth, inside dimensions. Liner shall be approximately 34-1/4 inches long by 7-1/2 inches wide scored as required to fit flush against the interior side and end walls of the box. Plain pads shall be aproximately 8-7/8 by 8 inches. Box shall be closed and sealed in accordance with instruction contained in the appendix of the box specification. Blunt all corners of the box and insert into a barrier bag conforming to Type I, Class E, Specification MIL-B-117. Exhaust excess air from bag and seal in accordance with manufacturer's instructions.

5.1.2 Level B. Same as Level A.

5.1.3 Level C. Sixty (60) test sets shall be packed as in 5.1.1 except the blunting of the corners and placing into a barrier bag is not required.

5.2 Packing.

5.2.1 Level A. Two (2) boxes, sealed in barrier bags, from 5.1.1 (total 120 test sets) shall be packed into a wood box. The wood box shall conform to either a Class 2, Style 4, Grade A, Specification PPP-B-62L box or a Type I, Class 1, Grade A, Specification MIL-B-2427 box. Filler material conforming to MIL-F-50449 shall be positioned between the barrier bags and wood box on all surfaces. Additional fillers shall be placed around and on top of the contents to insure tight packing. Close and securely strap the box in accordance with the instructions contained in the appendix to the appropriate specification.

5.2.2 Level B. Same as Level A.

5.2.3 Level C. Fiberboard boxes, from 5.1.3 containing 60 test sets, may be overpacked in a consolidation container at the contractor's option. The packing shall comply with the requirements of ASTM-D-3951.

5.3 Palletization.

5.3.1 Level A. Palletization of the packed wood boxes from 5.2.1 shall be in accordance with Level A of MIL-STD-1169.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

5+3.2 Level B. Same as Level A.

5.3.3 Level C. palletization of the boxes from 5.1.2 or the consolidation Container from 5.2.2 shall be at the contz~ctor's option. The palletization shall meet all commercial requirements for CONUS shipment and storage.

5.4 Marking.

5.4.1 Level. A. The marking of the boxes and palletized configuration shall comply with the Level A requirements of MIL-STD-129.

5,4.2 Level B. Same as Level A.

5,4.3 Level C. The marking of the boxes and palletized load shall comply with the requirements of ASTM-D-3951.

5.5 Shipping. When component parts from more than one lot are shipped as a carload, each lot shall be kept separate and the division between lots clearly indicated."

PAGE 16

6.2 Delete second sentence in its entirety.

PAGES 16 and 1;

6.3, 6.3.1, 6.3.2-, 6.3.3, 6.3.4 and 6.3.5: Delete in their entirety and substitute as follows:

"6.3 Inspection equipment design"s. Inspection equipment designs are of two.types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers under the "Method of Inspection" headings in Section 4, Design responsibility for all other inspection equipment is assigned to the contractor. The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6,3.3 should he elect to do so."

"6.3.1 SIE designs. SIE designs may consist of any of the following:

Source: https://assist.dla.mil -- Downloaded: 2026t0-22T05:19Z
Check the source to verify that this is the currentversion before use.

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-1OO, which establishes the criteria which a detail design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein."

"6.3.2 Contractor Designs. Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which i.s cataloged and available for purchase by the general public.) Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures, Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-10000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five-digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.

* 6.3.3: Delete in its entirety and substitute the follow~ng.:

"6.3.3 Submission of designs for app~oval. Contractor designs shall be approved by the Government prior to fabricating OK procuring the equipment. Designs shall be submitted for approval to Army Armament, Munitions and Chemical Command, ATTN: AMSMC-QAT-I(D), Dover, New Jersey 07801-5001 in accordance with the sti.pulations~ time fcame and distribution specified in the Contract Data Requirements hist (DD Form 1423) or in the contract. The contractor must include in his submission of designs a listing of any and all Government SIE designs which will be utilized. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of desi~rks. AMCCOM design review will normally be accomplished within one month after receipt."

The margins of this amendment are marked with an asterisk or vertical lines to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever far any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1345 -A336)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:19Z
Check the source to verify that this is the current version before use.