[NOT MEASUREMENT SENSITIVE]
A-A-52617
July 25, 1996
SUPERSEDING
MIL-T-62324B(AT)
16 September 1991

COMMERCIAL ITEM DESCRIPTION

TRAILER, VAN: MOBILE HEARING TEST CENTER

The General Services Administration has authorized the use of this commercial item description (CID) for all federal agencies.

1. SCOPE. This CID covers a van type trailer containing facilities for conducting hearing tests, fitting of hearing protective devices, record keeping, and also includes an orientation area. The trailer is intended for nontactical use by the Government at various installations

2. SALIENT CHARACTERISTICS

2.1 Standard vehicle and accessories. The vehicle, components, assemblies, and accessories shall be standard or optional items which meet or exceed the requirements of this CID.

2.2 Tiedown loops. Four tiedown loops shall be provided for securing the fully equipped trailer in high wind areas and on piers. The tiedown loops shall be mounted to the main frame of the trailer and shall be located on each side, at the front and rear of the trailer. Each tiedown loop shall be a hardened steel, 3 inch (in.) loop of 0.500 in. diameter cross-section.

2.3 Rustproofing. The vehicle shall be rustproofed in accordance with the accepted commercial standard practice. The trailers shall be fabricated from compatible materials providing corrosion protection and coating adherence equal to or exceeding that provided by hot-dip galvanized 1010 steel, with coating thickness in accordance with ASTM A123 (or minimum coating thickness of 0.75 mil on pre-galvanized sheet 0.063 in. or less), with zinc phosphate pre-treatment. A proposed alternate design shall be compared to a galvanized sample (as described above) using

Beneficial comments, recommendations, additions, deletions, clarifications, etc. and any data which may improve this document should be sent to: U.S. Army Tank-automotive and Armaments Command, ATTN: AMSTA-TR-E/BLUE, Warren, MI 48397-5000.

AMSC N/A FSC 2330

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

ASTM D522 Mandrel Bend Test followed by the Accelerated Corrosion Test GM 9540P Method B 120 cycles, or until prior failure of one of the items with defects such as extensive corrosion at scribe or significant penetration of base material.

2.4 General design.

2.4.1 Gross weight. The gross weight shall consist of the weight of the chassis and body with all attachments, accessories, equipment and a full compliment of water. The gross weight of the trailer shall be not more than 8500 pounds (lb).

2.4.2 Weight distribution. With the longitudinal axis of the trailer horizontal and with the trailer resting on a level solid surface, the center of gravity of the trailer shall be forward of the axles. The load imposed on the hitch by the gross weight of the trailer shall be not more than 1000 lb. The rated capacity of the axle, suspension and tires shall be at least equal to the load imposed at the ground by the gross weight of the trailer.

2.4.3 Accessibility. The design of the vehicle and optional equipment shall permit access for routine servicing and shall permit access for replacement and adjustment of component parts and accessories with minimal disturbance of other components and systems.

2.4.4 Dissimilar metals. All dissimilar metals used in intimate contact shall be insulated from one another to prevent galvanic or electrolytic action.

2.4.5 Prohibited materials. Asbestos materials shall not be used in any form in any part of the vehicle. No item, part, or assembly shall contain radioactive materials in which the specific activity is greater than 0.002 microcuries per gram or activity per item equals or exceeds 0.01 microcouries.

2.4.6 Leakage. The trailer shall not leak when subjected to a fresh water spray at a minimum rate of 2 in. per hour at an angle between 30 to 45 degrees from the vertical. The water shall be directed against all sides and the roof of the trailer simultaneously and shall continue for not less than 15 minutes.

2.5 Performance. Vehicle performance as specified in 2.5.1 shall be met by the trailer when fully equipped with all attachments and accessories, completely serviced, and towed by a towing vehicle for a distance of not less than 100 miles. At least 20 percent of this distance shall be over unimproved roads and the other 80 percent of this distance shall be over improved roads.

2.5.1 Towing speed and trailing ability. The trailer shall follow the towing vehicle over dry, level, smooth, prepared, hard-surfaced roads at sustained speeds up to 60 miles per hour (mph), and over dry, unimproved and gravel roads at speeds up to 20 mph.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

2.5.2 Turning ability. When coupled to a towing vehicle operating in its minimum turning circle, the trailer shall follow without cramping. The trailer shall be capable of moving through an angle of not less than 60 degrees in relation to a 102 in. wide towing vehicle without interference between vehicles. The angle shall be measured between the longitudinal axis of the trailer and the longitudinal axis of the towing vehicle at the lunette.

2.5.3 Parking brakes. Manually applied parking brakes shall be furnished. The parking brakes shall hold the trailer on a dry, hard-surfaced grade of not less than 30 percent when uncoupled from the towing vehicle, resting on the trailer's running gear and landing leg, and headed up and down the incline. The parking brake lever shall have sufficient moment arm to require not more than 30 lb of effort for application and release. Provisions shall be made for slack adjustment.

2.6 Dimensions. The trailer, uncoupled from the towing vehicle, resting on its landing leg, on level ground, and with the platform level, shall conform to the dimensions specified in table I.


TABLE I. Dimensions.

Dimension	Inches
Overall length, maximum	369
Overall width, maximum	93
Overall height, maximum	104
Van body interior length, minimum	310
Van body interior width, minimum	86
Van body interior height, minimum	76
Ground clearance, minimum	12

2.7 Drawbar and coupling device. The trailer shall be equipped with a drawbar of the "A" frame type. Unless otherwise specified, the drawbar shall be equipped with a standard ball hitch assembly, complete with mating ball for installation on the towing vehicle. The hitch shall conform to class 4 of SAE J684. The hitch coupling shall be 2.313 in. When specified (see 6.2), anti-sway bar(s) shall be provided. When specified (see 6.2), the coupling device shall be an offset-ring drawbar lunette coupler conforming to A-A-52464, Type III, and figure 1 and shall provide a 4 in. vertical range of adjustment. The hitch assembly or lunette ring shall be capable of supporting not less than 1000 lb.

2.8 Landing leg. The trailer shall have a retractable landing leg with a substantial ground bearing plate, with cranking handle permanently installed. The vertical range of adjustment of the landing leg shall be not less than 14 in. The landing leg and related parts shall withstand, without permanent deformation, the combined static and dynamic forces due to the proportion of the gross weight imposed, and impacts during coupling and uncoupling operations. When placed into travel position, the landing leg shall remain positively locked to provide not less than 12 in. ground clearance in the course of normal towing operations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.



NOTE: Unless otherwise specified, the dimensions are in inches. DO NOT SCALE.

FIGURE 1. Lunette - coupler, drawbar, ring.

2.9 Safety chains. The trailer shall be equipped with two safety chains. The chains shall conform to SAE J684. A grab hook shall be provided on the free end of each chain.

2.10 Stabilizing jacks. Four permanently installed stabilizing jacks shall be provided to permit four point stabilization of the trailer. The jacks shall be capable of leveling the trailer when used in conjunction with wheel blocks and hydraulic jack. The wheel blocks and hydraulic jack shall be furnished. Each stabilizing jack shall be provided with a ground bearing plate not less than 7.50 in. in diameter or 7.50 in. square. Jacks shall be retractable for maximum road clearance. The stabilizing jacks and wheel blocks shall enable the van floor to be leveled to within ± 1 percent of horizontal with the trailer parked on a 5 percent slope.

2.10.1 Level indicator. An exterior level indicator, showing both side to side and front to back degree of level, shall be provided.

2.11 Suspension. The suspension system shall have a rated capacity at least equal to the load imposed at the ground by the gross weight of the trailer, distributed as specified in 2.4.2. When specified (see 6.2), manufacturer's heavy duty suspension system shall be furnished. The heavy duty suspension system shall have a rated capacity equal to the load imposed at the ground by the gross weight of the trailer, plus at least 10 percent.

2.12 Wheels, rims, tires and tubes. Except when tube-type tires are specified in acquisition documents, multi-piece rims shall not be furnished. When specified (see 6.2), disc type wheels shall be furnished.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

2.12.1 Tires. Unless otherwise specified (see 6.2), tires shall be tubeless type with highway tread. Unless otherwise specified (see 6.2), low profile or standard profile tires may be furnished. Tires shall be of rated capacity at least equal to the load imposed on each tire, measured at each wheel at the ground, by the gross weight of the trailer, distributed as specified in 2.4.2. Tires shall conform to Tire and Rim Association recommendations for the type and size furnished.

2.12.2 Inner tubes. When tube-type tires are furnished, inner tubes shall be of heavy duty type. Tire flaps shall be provided for tube-type tires.

2.12.3 Spare wheel and tire assembly. When specified (see 6.2), a functional spare tire shall be furnished and shall be mounted on a carrier and installed in a readily accessible location. The carrier shall enable the safe removal and installation of the spare tire assembly from and to the vehicle and carrier without personnel positioning themselves or any part of their body under the spare tire assembly. The spare tire shall be the same as the tires in use on the vehicle.

2.13 Service brakes. The trailer shall be equipped with a 12 volt (V) electric brake system and shall include an automatic breakaway feature. The system shall include a manual controller kit for mounting on the dash of the towing vehicle, a controller kit for synchronizing the trailer electric brakes with the brakes of the towing vehicle, and an emergency breakaway kit. Kits shall be complete with all necessary parts and installation instructions. Unless otherwise specified, the synchronizing controller shall be for use with hydraulic brake equipped towing vehicles. When specified (see 6.2), the synchronizing controller shall be for use with air brake equipped towing vehicles. All components of the braking system shall be installed in such a manner as to provide adequate road clearance when traveling over uneven or rough terrain, including objects liable to strike and cause damage to the brake system components. No part of the braking system shall extend below the bottom of wheel rims.

2.14 Wheel chocks. When specified (see 6.2), four wheel chocks shall be provided. Wheel chocks shall be secured to the trailer with corrosion resistant chains or cables. Provisions for stowage with the chains or cables attached shall be provided.

2.15 Electrical system. Unless otherwise specified, the primary electrical system shall be wired for 120 V, 60 Hertz (Hz), alternating current (ac) single-phase power. Two 25 foot (ft), 120 V entrance cords, each rated at not less than 25 amperes (A), shall connect to the electrical distribution panel. All circuits shall be protected by ground-fault interrupter type circuit breakers. The main electrical circuits shall be designed for load balance during full heat and full air conditioning loads. When specified (see 6.2), the primary electrical system shall be wired for 100 V, 50 Hz, ac single-phase power. Two 25 ft, 100 V, entrance cords rated at not less than 35 A shall connect to an electrical distribution panel. Heating, lighting, air conditioning and other electrical components shall be rated for use from the primary electrical system of 100 V,

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

50 Hz power. On both systems, primary alternating current power shall be converted to 12 volts direct current (Vdc) nominal voltage. All interior wiring shall be color coded, using mechanically crimped and solder-dipped connections. The lighting shall not fade and the air conditioning units shall perform satisfactorily during the phase-in operation of the air conditioners.

2.15.1 Lighting. The electrical lighting system shall be 12 Vdc. Lights and reflectors shall not be mounted on rub rails (unless recessed and fully protected) or on vehicle bumpers. All interior room lighting shall be incandescent and provide a minimum of 15 foot-candles in the test chamber and seating area, and a minimum of 50 foot-candles at the table top of all working consoles. The brake lights shall override the four-way emergency flasher or the two systems shall be independent of each other.

2.15.2 Electrical receptacle. A trailer electrical receptacle with a spring-loaded cover assembly shall be installed on the forward end of the drawbar or a permanently installed electrical intervehicular lighting cable shall be furnished. The receptacle shall conform to ANSI/SAE J560, with conductors connected and color-coded as specified in ANSI/SAE J560.

2.15.3 Lighting cable. A seven-conductor lighting cable, with a cable plug at one end for a permanently installed cable and with a cable plug at both ends when an electrical receptacle is furnished, shall be provided. The cable shall conform to SAE J1067. Each plug shall conform to ANSI/SAE J560 and shall be equipped with a grip for withdrawing from connector sockets. The cable shall extend from the point of attachment on the trailer to at least three feet beyond the trailer hitch coupling centerline, when the cable is fully extended. Stowage provisions having an anti-theft feature and means of hanging the cable with the plugs pointing downward shall be provided.

2.15.4 Brake wiring. Electric brakes shall be wired to the auxiliary circuit of the ANSI/SAE J560 seven-conductor electrical connector. All wiring shall be properly mounted and secured with clamps. Wiring shall be heavy wall thermoplastic insulated cable and shall be enclosed in conduit, except where flexing occurs.

2.15.5 Battery. A 12 V battery shall be provided for the trailer emergency breakaway function. The battery shall be mounted in a protective compartment that is accessible from the trailer exterior. The battery compartment door shall be secured with a cylinder lock.

2.16 Bumper. A rear bumper shall be furnished. The sides of the vehicle shall be provided with bumpers and door retaining devices to prevent damage and to hold the exterior doors in the full open position, if desired.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

2.17 Tools. When specified (see 6.2), each vehicle shall be furnished with tools required for exchanging a mounted tire assembly with the spare assembly, and shall include at least a jack, jack handle, and wheel nut wrench. The jack shall be of such closed height as to permit its location under the axle, or other satisfactory lift point, at any wheel with tire flat. The jack, without blocking, shall be capable of raising any wheel of the loaded vehicle to a height adequate to permit removal and replacement of the wheel and tire assembly.

2.18 Carpeting. The floor shall be covered with industrial grade 100 percent nylon carpet or equivalent.

2.19 Doors. Two exterior doors shall be installed on the curb side. The door latches shall be freezer type, with adjustable positive-latching mechanisms, interior panic-bar releases and cylinder locks. Fold-away steps shall be provided under each door. Steps shall be capable of withstanding repeated loads of up to 250 lb. One door shall provide entrance and exit to the orientation area, and the other to the audiometer console area. Each door shall provide a clear opening of not less than 26 in. in width and 64 in. in height.

2.20 Windows. All exterior windows shall be safety glass. All joints and seams shall be weatherproof. One window shall be located in the rear of the body in the bathroom area, and shall be not less than 29 in. wide and 19 in. high. One window shall be located in the front of the body in the orientation area, and shall be not less than 40 in. wide and 21 in. high.


2.21 Heating system. A heating system shall be supplied and shall be capable of maintaining the inside body temperature at a minimum of 72 degrees Fahrenheit (°F), with no occupants, midway between the floor and ceiling in 0°F outside ambient temperature. Thermostat controls shall be recessed as flush as practicable with the surface of each heater assembly.

2.22 Air conditioning system. A central air conditioning system shall be provided and shall be capable of maintaining the inside of the vehicle body at an evenly circulated cooling temperature of 74°F maximum in 100°F ambient temperature. The noise level of the air conditioning system, when operating in the high cool mode, shall not exceed values listed in 2.25.2. Inside temperature may be determined either with the number of occupants required or with the use of a simulated heat load for sensible cooling.

2.23 Interior arrangement and furnishings. The interior of the van body shall consist of four rooms as follows:

a. Orientation.
b. Test chamber.
c. Console area.
d. Bathroom.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.



NOTE: All dimensions given are interior, in inches, and are the minimum acceptable.

Figure 2. Interior arrangement.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

The interior floor plan and furnishings shall be as shown in figure 2 and as specified herein. The layout of the interior shall permit efficient flow of personnel, and shall permit orientation and fitting of hearing protective devices to four individuals while another four are being tested. The interior shall feature ample storage space, four microprocessor audiometers with jack panels to connect audiometers with earphones and response button, and direct communication to the four testing areas inside the test chamber with earphones and response buttons. Cabinet doors shall be lightweight, warp-free, roll tambour construction. Storage cabinets shall be as large as practicable without interfering with the work space.

2.23.1 Orientation area. An orientation desk, not less than 78 in. in length and 28 in. wide, shall be provided. A desk top shall be provided for the manual audiometers. The manual audiometer desk top shall be not less than 28 in. long and 18 in. wide. Two lounges, complete with cushioned seats and backs, shall be provided with storage underneath. Overhead storage cabinets shall be provided. The frontal height of the storage cabinets, from the ceiling to the bottom edge, shall be not less than 9 in. The upper rear portion of the storage cabinets shall be shaped to the wall-to-ceiling contour. Storage cabinets, not less than 72 in. in length, shall be provided over the orientation desk. Storage cabinets not less than 18 in. in length shall be provided over the manual audiometer desk. Storage cabinets shall be provided over the transverse lounge and shall extend the full width of the front wall. Storage cabinets shall be provided with an appropriate number of doors not less than 7 in. high.

2.23.2 Test chamber. The floor of the test chamber shall be an acoustical floatation design completely isolated from the subfloor, shell, and chassis. The test chamber doors shall be the same design as the walls with seals to minimize sound leakage. The door latches shall be freezer-type, with adjustable, positive latching mechanism and interior panic-bar releases. Each test chamber door shall be not less than 26 in. wide and 68 in. high. The test chamber windows shall consist of three 12 in. square panels of impact-resistant, noise barrier material with a slotted window mounting channel and shall be located in the doors to provide visibility into the test chamber. Windows shall also be located in the test chamber above each of the two manual audiometer stations and shall be provided with removable curtains. A foldable curtain shall be installed longitudinally inside the test chamber so that it can be fully extended or retracted. Two room dividers shall be installed transversely, one on each side wall of the test chamber, equidistant between the front and rear walls of the chamber. Each room divider shall be full height from floor to ceiling and not less than 29 in. wide. Four cushioned seats, with storage underneath, shall be provided. Each seat shall be not less than 12 in. wide and 28 in. long.

2.23.3 Console area. An audiometer console desk shall be provided and shall consist of a desk top with legs or with an enclosed storage cabinet with doors underneath. The console desk shall be the full length between the test chamber and bathroom partitions and shall be not less than 28 in. wide. A manual audiometer desk top as specified in 2.23.1 shall be provided. Overhead

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

storage cabinets as specified in 2.23.1 shall be provided and shall extend the full length between the test chamber and bathroom partitions over the audiometer console desk. Overhead storage cabinets not less than 18 in. long shall be provided over the manual audiometer desk.

2.23.4 Bathroom area. A full height and width partition shall be provided between the bathroom area and the console area and shall be transversely located between the van body side walls. A sliding door not less than 21 in. wide and 70 in. high shall be provided in this partition as an entrance door to the bathroom area. The bathroom area shall be provided with a half-bath assembly. The half-bath assembly shall consist of a one-piece vanity top and lavatory. The lavatory cabinet shall be constructed as in 2.23. A 30 gallon (gal) potable water tank shall be installed to provide fresh water to the lavatory and the toilet. Waste water from the toilet shall drain into a 12 gal sewage holding tank and lavatory waste water shall drain into a separate 10 gal waste tank. A mechanical seal flush-type toilet shall be installed. Hot water shall be provided to the system by a 120 V (100 V when specified) electric water heater. The capacity of the hot water tank shall be not less than 6 gal. The bathroom area shall be provided with two full height, open-type, partitioned closets. Each closet shall be provided with a door not less than 16.50 in. wide and 70 in. high. The in-place water supply system and water heater with connections shall withstand a pump pressure of not less than 40 pounds per square inch (psi) and not more than 50 psi for a period of not less than 30 minutes with no evidence of leakage and no additional air or water being required to maintain the pressure. The drainage system shall not leak when the sink is filled with water and the main drain outlet is capped for not less than 30 minutes.

2.24 Instrumentation. Appropriate jacks and wiring shall be furnished. A two-way intercom system shall be provided between the two manual consoles or desks for technician communication, permitting manual hearing testing of two subjects simultaneously. The intercom system shall produce no audible hum or other sound when not in use.

2.25 Test chamber acoustical performance. The acoustical attenuation of the audiometric testing van shall be in accordance with ANSI/ASA S3.1. The noise source shall be a continuous broadband pink-noise spectrum.

2.25.1 Exterior to interior noise level. The difference between the 1/3 octave band levels measured outside the van and inside the test chamber, in the area normally occupied during the test by the subject's head, shall be not less than the values specified in table II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

TABLE II. Exterior to interior noise level.

1/3 octave band center frequency (Hz)	Attenuation (decibels (dB)), minimum
250	40
500	55
1000	60
2000	70
4000	80
8000	80

2.25.2 Ambient noise level. The ambient noise level inside the test chamber area shall not exceed the values specified in table III with the heating and air conditioning systems operating on high mode.

TABLE III. Ambient noise level.

Octave band center frequency (Hz)	Octave band level (dB), maximum
500	21.5
1000	29.5
2000	34.5
4000	39.0
8000	41.0

2.25.3 Orientation area to test chamber noise level. The difference between the 1/3 octave band levels measured outside the test chamber and inside the test chamber, in the area normally occupied during the test by the subject's head, shall be not less than the values specified in table IV.

TABLE IV. Orientation area to test chamber noise level.

1/3 octave band center frequency (Hz)	Attenuation (dB), minimum
250	30
500	45
1000	50
2000	50

3. REGULATORY REQUIREMENTS

3.1 Safety standards. The vehicle and all furnished accessories shall comply with all federal safety standards and regulations in effect on the date of manufacture.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

3.2 Recovered materials. The offeror/contractor is encouraged to use recovered materials to the maximum extent practicable, in accordance with paragraph 23.403 of the Federal Acquisition Regulation (FAR).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. The contractor is responsible for the performance of all inspections and tests.

4.2 Product conformance. The products provided shall meet the salient characteristics of this commercial item description, conform to the producer's own drawings, specifications, standards, and quality assurance practices, and be the same product offered for sale in the commercial market. The Government reserves the right to require proof of such conformance.

5. PACKAGING. Preservation, packing, and marking shall be as specified in the contract or order (see 6.2).

6. NOTES

(This section contains information of a general or explanatory nature which may be helpful, but is not mandatory.)

6.1 Addresses for obtaining copies of referenced documents.

6.1.1 Copies of A-A-52464, "Coupler Drawbar, Ring: Light Duty, 60,000 LB GVW; Offset (Taper Shank), 60,000 LB GVW; and Heavy Duty 120,000 LB GVW", may be obtained from the Defense Printing Service Detachment Office, 700 Robbins Avenue, Bldg. 4D (Customer Service), Philadelphia, PA 19111-5094.

6.1.2 Copies of ANSI/ASA S3.1, "Maximum Permissible Ambient Noise Levels for Audiometric Test Rooms (DoD Adopted)", and ANSI/SAE J560, "Seven Conductor Electrical Connector for Truck-Trailer Jumper Cable, Standard (DoD Adopted)", may be obtained from the American National Standards Institute, 11 West 42nd Street, New York, NY 10036.

6.1.3 Copies of ASTM A123, "Standard Specification for Zinc (Hot-Dip Galvanized) Coatings for Iron and Steel Products (AASHTO M111) (DoD Adopted)" and ASTM D522, "Standard Test Methods for Mandrel Bend Test of Attached Organic Coatings (DoD Adopted)", may be obtained from the American Society for Testing and Materials, 100 Barr Harbor Drive, W. Conshohocken, PA 19428-2959.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

6.1.4 Copies of GM 9540P, “Accelerated Corrosion Test”, may be obtained from General Motors Corp., c/o Global Engineering, 15 Inverness Way, Englewood, CO 80112.)

6.1.5 Copies of SAE J684, “Trailer Couplings, Hitches, and Safety Chains - Automotive Type, Standard”, and SAE J1067, “Seven Conductor Jacketed Cable for Truck Trailer Connections, Standard (DoD Adopted)”, may be obtained from the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.

6.1.6 Copies of the Tire and Rim Association Yearbook may be obtained from the Tire and Rim Association, Inc., 175 Montrose West Avenue, Suite 150, Copley, OH 44321.

6.2 Ordering data. Acquisition documents must specify the following:

a. Title, number, and date of this CID.
b. Issue of the Department of Defense Index of Specifications and Standards (DODISS) to be cited in the solicitation, and if required, the specific issue of individual documents referenced.
c. Anti-sway bar(s), if required.
d. A lunette coupling device, if required in lieu of ball hitch.
e. A heavy duty suspension system, if required.
f. Disc type wheels, if required.
g. Tube-type tire, if required .
h. Low profile tires, if required.
i. A spare wheel and tire assembly, if required.
j. An air brake synchronizing controller for electric brakes, if required in lieu of a hydraulic brake synchronizing controller.
k. Wheel chocks, if required.
l. Primary electrical system 100 V, 50 Hz, if required.
m. Tools, if required.
n. Packaging requirements.

6.3 Cross-reference. Van trailers conforming to this CID are interchangeable/substitutable with van trailers conforming to MIL-T-62324B(AT), dated 16 September 1991.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.

MILITARY ACTIVITY:

Custodian:
Army - AT

CIVILIAN AGENCY COORDINATING ACTIVITY:
GSA-FSS

Preparing Activity:
Army - AT

(Project 2330-0220)

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T09:14Z
Check the source to verify that this is the current version before use.