MILITARY SPECIFICATION

TRANSPORTER: WELDED HULL,

FOR

MOBILE FLOATING ASSAULT BRIDGE/FERRY

This amendment forms a part of Military Specification MIL-T-52703A(ME), dated 18 November 1974.

PAGE 1

2.1, under SPECIFICATIONS, FEDERAL, add:

"L-P-378	- Plastic Sheet and Strip, Thin Gauge, Polyolefin.
PPP-C-850	- Cushioning Material, Polystyrene, Expanded, Resilient (for Packaging Uses).
TT-E-522	- Enamel, Phenolic, Outside."

Delete and substitute:

"QQ-S-781	- Strapping, Steel, and Seals."

PAGE 2

2.1, under SPECIFICATIONS, MILITARY, add:

"MIL-E-52798	- Enamel, Alkyd, Camouflage."

PAGE 3

2.1, under Drawings, ME, add:

"D13217E8500	- Blocking and Tie Down for Rail Transportation of MAB.
D13207E4614	- Blocking and Tie Down for Rail Transportation of MAB Hull."

PAGE 7

3.6, line 8, delete "in 4.6.2.34." and substitute "in 4.6.2.33 and 4.6.2.34."

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

PAGE 20

3.36, line 9, after "lusterless." add:

"Finish coat shall be forest green conforming to TT-E-522 modified to meet color, reflectance, gloss, sheen, and pigmentation of MIL-E-52798."

PAGE 23

3.41.6, at end of paragraph, add:

"To assure that all welding variables have been addressed the welding procedures shall include provisions for a daily on the job aluminum weldbreak test by each production welder during each work shift. The procedure shall require that the welder construct the 'weldbreak' specimen using the same materials, alloys, and thicknesses, with the same weld type and size, and cleaned, prepared and welded in accordance with the applicable procedures and techniques developed for the end item weldment being welded at the time the break test is required. The procedures shall also include the steps to be followed for breaking the specimens and examination of the fractured parts to determine the weld quality. The procedures shall also describe the corrective action to be taken in the event that the specimen test demonstrates weld quality that is not acceptable, including disposition of component welding accomplished by the welder since the last acceptable weldbreak test."

PAGE 25

4.1, delete and substitute:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

PAGE 26

4.2(e), delete "preparation for delivery" and substitute "packaging".

PAGE 27

4.3.3, lines 2 and 3, delete: "due to incorrect workmanship, materials, dimensions, or tolerances;".

Source: https://assist.dla.mil -- Downloaded: 20260-22T21:30Z
Check the source to verify that this is the current version before use.

4.4.1, lines 2 and 3, delete: "due to incorrect workmanship, materials, dimensions, or tolerances".

PAGE 49

4.6.2.33, at end of paragraph, add:

"Occurrence of seven or fewer reliability failures (see definition in 4.6.2.34) or attaining a 57 hour MTBF (Point estimate) shall constitute conformance to the reliability requirement of 3.6 assuming testing of two transporters. If only one transporter is tested, the number of failures allowable is three or fewer."

PAGE 50

4.6.2.34, at end of paragraph, add:

"Occurrence of 20 or fewer reliability failures or attaining a 57 hour MTBF (Point estimate) shall constitute conformance to the reliability requirements of 3.6 assuming testing of two transporters. If only one transporter is tested, the number of failures allowable is 10." Failures determined to be pattern failures must be corrected regardless of whether demonstrated MTBF is accepted or not."

PAGE 52

4.8, delete "preparation for delivery" and substitute "packaging".

PAGE 53

Table VI, defect 168, delete "Consolidated packaging" and substitute "Consolidation".

PAGE 54

5., delete "PREPARATION FOR DELIVERY" and substitute "PACKAGING".

5.1, lines 1 and 5, delete in two places, "Level C" and substitute "Commercial".

5.2, line 4, delete: "packaging,".

5.3, line 1, delete in two places, "packaging" and substitute "consolidation"; line 2, delete "C" and substitute "Commercial".

5.3.1.2, lines 3 and 4, delete: "and packaging".

PAGE 56

5.3.1.10, line 5, delete "The electrolyte shall be packaged and" and substitute "When included, packed electrolyte shall be "; line 6, delete "Type I, Class B" and substitute "Class 1, Type I, Finish A, size as appropriate".

Source: https://assist.dla.mil -- Downloaded: 20260-22T21:30Z
Check the source to verify that this is the current version before use.

PAGE 57

5.3.1.20, line 1, delete "Consolidated packaging" and substitute "Consolidation"; line 9, after "cab", delete the period and add: "but not in areas where water might collect."

PAGE 58

5.3.1.23, line 6, delete "Grade B, CD with exterior glue." and substitute "Grade B (CD interior with exterior glue)."; lines 11 and 12, place period after "cab" and delete "with tape as specified herein."

5.3.1.24, line 5, delete entire second sentence and substitute:

"The superstructure spline assembly shall be tightly covered with black plastic film conforming to L-P-378, Type I, Class 1, 5 mils minimum thickness, which shall be secured in place with tape conforming to PPP-T-60, Type IV."

5.3.1.25, delete entire paragraph and substitute:

"5.3.1.25 Rear control station. The entire upper surface of the rear station control panel shall be protected with 2-inch-thick pad of cushioning material conforming to PPP-C-850, Type I, Class 1 or 2, which shall be secured to the control pedestal with the waterproof tape specified herein. The cushion pad shall be cut out or otherwise arranged to fit around the control levers; the pad may consist of more than one piece. The entire rear control station pedestal shall be covered with plastic barrier as specified in 5.3.1.24. The barrier shall extend below the rung assemblies and shall be secured with waterproof tape which shall encircle the control pedestal and overlap itself at least 2 inches. The barrier shall be snug enough around the pedestal to reduce the possibility of wind induced damage."

PAGE 59

5.3.1.26, line 2, delete "Grade B, CD with exterior glue" and substitute "Grade B (CD interior with exterior glue)."; line 2, delete in its entirety the sentence beginning "One inch of waterproof . . . . . ."; line 5, delete "Type I, Class B" and substitute "Class 1, Type I, Finish B 3/4 X 0.031 inch minimum,"; line 9, delete the last sentence entirely.

5.3.2, line 1, delete "Level C." and substitute "Commercial."

5.4, line 2, delete "do not require packing for shipment" and substitute "are such that packing is not required."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

5.5, line 2, delete: "A Guide for the"; line 3, after "shall be" add: "in accordance with"; line 4, delete: "(ref. only)."

5.6, line 2, delete "packages" and substitute "packaged items"; line 3, add at end of sentence: "for Level A."

Add new sentence to paragraph as follows:

"For Commercial, marking shall be that required for Level A except that it may be applied by any legible method, using waterproof materials."

PAGE 61

6.2, item(m), delete: "and packaging".

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A302

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:30Z
Check the source to verify that this is the current version before use.