ADVANCE COPY

DESTROY THIS COPY WHEN PRINTED
COPIES OF THE SPECIFICATION ARE AVAILABLE

MIL-B-60301A(MU)
8 May 1967
SUPERSEDING
MIL-B-60301(MU)
16 August 1966

MILITARY SPECIFICATION

BOMB, SUBASSEMBLIES, METAL

(BLU-17/B)

1. SCOPE

1.1 This specification covers the inert subassemblies for the BLU-17B bomb.

2. APPLICABLE DOCUMENTS

2.1 Government documents. The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-B-7883	-	Brazing of Steels, Copper, Copper Alloys, Nickel Alloys, Aluminum and Aluminum Alloys.

STANDARDS

MILITARY

MIL-STD-105	-	Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-129	-	Marking for Shipment and Storage.

FSC 1325

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

DRAWINGS

US ARMY MUNITIONS COMMAND

DL13-20-84 - Body, Bomb, Assembly.

(All drawings referenced in this specification are listed on the above Edgewood Arsenal drawing.)

PUBLICATIONS

EDGEWOOD ARSENAL INSTRUCTION MANUAL

136-300-40 - Instruction Manual for the Installation, Operation and Maintenance of Tester, Air Leakage, Q48.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

UNIFORM CLASSIFICATION COMMITTEE

Uniform Freight Classification Ratings, Rules and Regulations.

(Application for copies of these freight classification rules should be addressed to the Uniform Classification Committee, 202 Union Station, Chicago, Illinois 60606.)

3. REQUIREMENTS

3.1 Materials. All materials cited on Drawing DL13-20-84 or on the subsidiary drawings shall conform to the specifications listed thereon, or to the specific characteristics set forth on the drawings.

3.2 Brazing. The body cap assembly and the burster well assembly shall be brazed in accordance with type III of MIL-B-7883 and tested as specified in 4.3.4.1.

3.3 Assembly. Both subassemblies of the bomb shall conform to their respective drawings.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

3.4 Leakage. When tested as specified in 4.3.4.2, neither assembly shall leak while each is subjected to an internal air pressure of 45 ± 5 pounds per square inch gage (psig) for a period of 35 ± 5 seconds.

3.5 Preproduction. Prior to the start of regular production, a preproduction sample of subassemblies shall be produced, examined and tested in accordance with this specification.

3.6 Workmanship. The subassemblies of the bomb shall be free from damage such as dents, cracks or deformations and foreign matter such as oil, grease, oxide scale and residue from brazing, which would affect their intended use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.

4.1.1 Supplier's responsibility. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.2 Objective evidence. The supplier shall provide objective evidence acceptable to the contracting officer that the requirements of 3.1, 3.2, and section 5 for which specific inspection has not been provided in this specification have been satisfied.

4.2 Preproduction.

4.2.1 Lot. Two hundred each body and cap assemblies and burster well assemblies shall be produced from the same materials, methods, equipment, processes and procedures as will be used during regular production. Any change in the above criteria will require a new preproduction quantity.

4.2.2 Sampling. Twenty-five each assemblies shall be randomly taken from the preproduction lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

4.2.3 Inspection. Sample assemblies shall be examined and tested in accordance with the classification of defects and with MIL-STD-105. The AQL is not applicable.

4.2.4 Acceptance/rejection criteria. The subassemblies shall comply with 4.2.3 to be acceptable. The supplier shall obtain written approval from the contracting officer prior to proceeding with regular production.

4.3 Regular production.

4.3.1 Lotting. A lot shall consist of the like subassemblies produced by one manufacturer, at one plant, from the same materials and under essentially the same manufacturing conditions. The bodies (Dwg C13-20-86) shall be subjected to the same mechanical process to produce the same work hardening condition during one period of time.

4.3.2 Sampling for examination and nondestructive tests. Sampling shall be conducted in accordance with MIL-STD-105.

4.3.3 Inspection.

4.3.3.1 For examination and nondestructive tests. Sample subassemblies shall be examined and tested in accordance with the classification of defects and with MIL-STD-105.

4.3.3.2 For critical defects. Each subassembly shall be inspected for its critical characteristic listed in the classification of defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

4.3.3.3 Classification of defects.

(a) Body and cap assembly (Dwg D13-20-84).

Categories	Defects	Acceptance standards
Critical:		
1	Leakage	4.3.4.2
Major:	AQL 0.65 percent defective	
101	Brazing	4.3.4.1
	AQL 1.0 percent defective	
102	Overall length incorrect	
103	Press-fit diameter or taper incorrect	
104	Machine finish (16-32) incorrect	
105	Body diameter incorrect	
106	Workmanship (3.6)	
Minor:	AQL 2.5 percent defective	
201	Corrosion preventive missing	

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

(b) Well, burster assembly (Dwg C13-20-82).

Categories	Defects	Acceptance standards
Critical:		
1	Leakage	4.3.4.2
Major:	AQL 0.65 percent defective	
101	Brazing	4.3.4.1
	AQL 1.0 percent defective	
102	Thread incorrect	
103	Press-fit diameter and taper incorrect	
104	Machine finish (16-32) incorrect	
105	Eccentricity excessive	
106	Workmanship (3.6)	
Minor:	AQL 2.5 percent defective	
201	Radius (press-fit surface) missing	
202	Corrosion preventive missing	
203	Overall length incorrect	

4.3.4 Tests.

4.3.4.1 Brazing. Brazing shall be tested in accordance with the applicable test of MIL-B-7883.

4.3.4.2 Leakage. The body and cap assembly and the burster well assembly leakage shall be determined separately using Tester, Air Leakage, Q48.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging, level C. Subassemblies shall be cleaned, dried, preserved and packaged to provide adequate protection from the supply source to the first receiving activity for immediate use or for storage under controlled humidity conditions.

5.2 Packing, level C. Subassemblies packaged as specified in 5.1 shall be packed in a manner to insure carrier acceptance and safe delivery at the first domestic destination. Containers shall be in accordance with the Uniform Freight Classification rules, or regulations of other carriers applicable to the mode of transportation.

5.3 Marking. In addition to any special marking required by the contract or order, unit packages and shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Ordering data. Procurement documents should specify the following:

(a) Title, number and date of this specification.
(b) Preproduction.

(1) Time allowed for supplier's submission of samples for Government test and evaluation after award of contract.
(2) Name and address of test facility and shipping instructions when testing is performed by the Government.
(3) Time required for the Government to notify the supplier whether to proceed with production.

Custodian:

Army - MU

Preparing activity:

Army - MU (EA)

Project No. 1325-A193

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T00:26Z
Check the source to verify that this is the current version before use.