MIL-S-3723B
28 AUGUST 1957

SUPERSEDING
MIL-S-003723A (Sig C)
24 OCTOBER 1955
MIL-S-3723
28 MARCH 1952

MILITARY SPECIFICATION

SWITCHBOARD, PATCHING, COMMUNICATION (TELEGRAPH SWITCHBOARD SB-6( )/GG)

This specification has been approved by the Department of Defense and is mandatory for use by the Departments of the Army, the Navy and the Air Force.

1. SCOPE

1.1 This specification covers one type of military switchboard for field use, as a jack patching unit for interconnecting local d.c. lines, loops or extensions and teletypewriter sets or equipments, designated as Telegraph Switchboard SB-6 ( )/GG. (See 6.3.)

2. APPLICABLE DOCUMENTS

2.1 The following specifications, standards, and drawings, of the issue in effect on date of invitation for bids, form a part of this specification:

SPECIFICATIONS

FEDERAL

T-T-871 — Twine; Cotton, Wrapping.

QQ-S-571 — Solder (Tin, Tin-Lead, Lead-Silver).

UU-T-111 — Tape; Paper, Gummed (Sealing and Securing).

LLL-F 291 — Fiberboard; Corrugated, Single Face (Flexible).

PPP-B-601 — Boxes, Wood, Cleated Plywood.

PPP-B-621 — Boxes, Wood, Nailed and Lock-Corner.

PPP-B-636 — Boxes, Fiber

PPP-T-60 — Tape, Pressure Sensitive Adhesive, for Packaging and Sealing.

MILITARY

JAN-P-108 — Packaging and Packing for Overseas Shipment — Boxes, Fiberboard (V-Board and W-Board) Exterior and Interior.

MIL-P-116 — Preservation, Methods of.

MIL-B-117 — Bags, Interior Packaging.

JAN-T-152 — Treatment, Moisture- and Fungus-Resistant of Communications, Electronic, and Associated Electrical Equipment; General Process for.

MIL-L-10547 — Liners, Case, Waterproof.

MIL-N-13231 — Marking of Electronic Items.

MIL-F-14072 — Finishes for Ground Signal Equipment.

FSC 5805

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:20Z
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Table for Inspection by Attributes.

MIL-STD-109 — Inspection Terms and Definitions.

MIL-STD-129 — Marking for Shipment and Storage.

MIL-STD-169 — Extreme-Temperature Cycle.

MIL-STD-170 — Moisture Resistance Test Cycle for Ground Signal Equipment.

MIL-STD-252 — Wired Equipment, Classification of Visual and Mechanical Defects for.

DRAWINGS

SIGNAL CORPS

SC-C-33073 — Form to be Used for Pilot Pack Process Sheet.

SC-A-46406 — Classification of Defects for Visual Inspection of Preparation for Delivery.

SC-D-47601 — Telegraph Switchboard SB-6( ) GG Drawing and Data List.

(Copies of specifications, standards, and drawings required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer. Both the title and number or symbol should be stipulated when requesting copies.)

2.2 Other publications. The following documents form a part of this specification. Unless otherwise indicated, the issue in effect on date of invitation for bids shall apply.

National Motor Freight Classification, Rules and Container Specifications for Truck Shipments.

(Application for copies should be addressed to the American Trucking Association, 1424 Sixteenth Street, N.W., Washington 6, D.C.)

Uniform Freight Classification, Ratings, Rules, and Regulations.

(Application for copies should be addressed to the Association of American Railroads, 202 Chicago Union Station, Chicago 6, Ill.

3. REQUIREMENTS

3.1 Construction. Telegraph Switchboard SB-6( )/GG shall be constructed in accordance with the drawings on Drawing and Data List SC-D-47601 and shall meet the requirements of this specification. In case of conflict between the drawings and the specifications, the specification shall govern.

3.2 Preproduction samples.

3.2.1 *Quantities.* Two preproduction samples of Telegraph Switchboard SB-6( )/GG shall be furnished for Government inspection and approval.

3.2.2 *Compliance with specified requirements.*

3.2.2.1 Preproduction samples shall meet specified requirements, shall be made and assembled by tools and methods that will be used for quantity, production, and shall be accompanied by a statement to that effect.

3.2.2.2 Approval of preproduction samples shall not be construed as a waiver of any specified requirement. After being released to the contractor (see 3.2.4), preproduction samples to be offered as units on contract shall be refabricated by the contractor if necessary to meet specified requirements.

3.2.2.3 When deviation from 3.2.2.1 is unavoidable, the preproduction samples may be submitted for approval provided that the accompanying statement describes in detail each nonconforming feature, reason therefor, and manner in which it will be corrected in production of equipment on contract.

3.2.3 *Test data.* The production samples shall be accompanied by test data showing compliance with specified performance. The test data shall comprise an engineering report giving test procedure, observations and other

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:20Z
Check the source to verify that this is the current version before use.

data, calculations, test results, and essential details of the testing equipment (manufacturer's model, serial number, date of calibration, etc.).

3.2.4 *Reference standards.* After preproduction samples have been approved and returned to the contractor's plant, they shall be kept intact in custody of the Government inspector until released by him. They shall be used as reference standards to resolve any differences of opinion regarding interpretation of requirements.

3.3 Plastic material and parts. Where not machined, plastic material and parts shall have the original smooth or polished surfaces. Surfaces that have been sawed, cut, punched, or otherwise machined shall be as smooth as practicable in accordance with good manufacturing practice for the intended application.

3.4 **Soldering.**

3.4.1 *Solder.* Solder used for electrical connections shall be composition Sn60 conforming to Specification QQ-S-571.

3.4.2 *Flux and cleaning agents.* No acid or acid salts shall be used in preparation for or during soldering; however, exception is permitted for preliminary tinning of electrical connections and for tinning or soldering of mechanical joints not used to complete electrical circuits, but in no case shall acid or acid salts be used where they can come in contact with insulation material. Where acid or acid salts are used, as permitted above, they shall be completely neutralized and removed immediately after use. Flux for soldering of electrical connections shall be rosin, rosin and alcohol, or rosin and turpentine.

3.4.3 *Process.* There shall be no sharp points or rough surfaces resulting from insufficient heating. The solder shall feather out to a thin edge, indicating proper flowing and wetting action, and shall not be crystallized, overheated, or underheated. The minimum necessary amount of flux and solder shall be used for electrical connections. Any means employed to remove an unavoidable excess of flux shall not incur the risk of loose particles of flux, brush bristles, or other foreign material remaining in the equipment; flux being spread over a larger area; or damage to the equipment. Insulation material that has been subjected to heating during the soldering operation shall be undamaged and parts fastened thereto shall not have become loosened.

3.5 Cleaning. Metal parts, after fabrication, shall be cleaned in accordance with good commercial practice, or as specified in an applicable document. Cleaning processes shall have no deleterious effect on the equipment. Corrosive material shall be removed completely before parts are assembled into the equipment. After assembly, components shall be cleaned thoroughly and shall be free from particles of solder, flux, and other foreign material. If necessary, such cleaning shall also be performed before final assembly of components.

3.6 Tropicalization.

3.6.1 *Treatment of assembled equipment.* Assembled equipment shall be treated in accordance with Specification JAN-T-152 unless both of the following conditions are met:

(*a*) Each component part and subassembly meets one of the following:

(1) It is furnished under an individual, detailed Government document (specification, standard, drawing, etc.) which is applicable on contract.

(2) It does not incorporate any material listed in 3.6.3 unless the material has been given the treatment specified herein or a treatment approved by the contracting officer.

(3) It does not comply with (1) or (2) above but its use has been approved by the contracting officer for the particular application.

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:20Z
Check the source to verify that this is the current version before use.

(*b*) The finish of the interior of the equipment meets the requirements of Specification MIL–F–14072.

3.6.2 *Treatment of materials.*

3.6.2.1 *Treating materials.* Treating materials containing a mercury-bearing fungicide shall not be used. The contractor shall determine that the treating material is compatible with the material or surface to be treated. Selection of treating materials shall be such that any increase in flammability of treated material is held to the practical minimum.

3.6.2.2 *Toxicity.* Treatment of materials shall cause no skin irritation or other injury to personnel handling the treated material either during fabrication of the equipment or when carrying, operating, or maintaining the equipment, or in use of the finished items when used for the purpose intended.

3.6.2.3 *Flexibility.* Treatment shall not affect flexibility of treated materials, to the extent that the equipment may fail to meet specified requirements when subjected to specified service conditions.

3.6.2.4 *Statement of treatment.* The contractor shall submit, to the contracting officer for approval, a statement describing in detail the materials to be treated and the treating materials and processes that he proposes to use. When assembled equipment is treated in accordance with Specification JAN–T–152, the above statement shall be incorporated in the statement of treatment required by that specification.

3.6.3 *Materials not resistant to moisture and fungi.* The following materials are considered not resistant to moisture and fungi:

(*a*) Cellulose, regenerated.

(*b*) Cotton.

(*c*) Cork.

(*d*) Felt, hair or wool.

(*e*) Jute.

(*f*) Leather.

(*g*) Linen.

(*h*) Paper, paperboard, cardboard, organic fiberboard, vulcanized fiber, etc.

(*i*) Thermosetting plastic materials using cotton, linen, or wood-flour as a filler or base.

3.7 **Service conditions.** The equipments shall meet the following service conditions:

3.7.1 *Equipment operating.* The equipment shall meet the requirements of this specification under any probable combination of the following:

(*a*) *Temperature.* Any ambient temperature in the range of —65° F. to +160° F.

(*b*) *Elevation.* Any elevation up to 10,000 feet above sea level.

(*c*) *Relative humidity.* Relative humidity up to 97 percent, and exposure at 100 percent relative humidity, with condensation, for 4 hours.

3.7.2 *Equipment nonoperating.* The equipment shall meet the requirements of 3.7.1 after subjection to any one or more of the following nonoperating conditions:

(*a*) *Temperature.* Continuous exposure for 72 hours at +160° F. and 72 hours at —80° F., at any orientation. (See 4.8.1)

(*b*) *Elevation.* Elevations up to 50,000 feet above sea level.

(*c*) *Relative humidity* Relative humidity up to 97 percent, for an indefinite period of time; and exposure at 100 percent relative humidity, with condensation, for 4 hours. (See 4.8.2.)

(*d*) *Vibration.* No mechanical resonance below 55 cycles per second. (See 4.8.3.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:20Z
Check the source to verify that this is the current version before use.

3.8 **Interchangeability.** Corresponding units and replaceable assemblies, subassemblies, and parts on contract shall be physically and functionally interchangeable as complete items without modification thereof or of other articles with which the items are used. When dimensions, ratings, characteristics, etc., are not specified, the manufacturer's design limits shall be used to determine compliance with the foregoing. If the contractor is in doubt as to whether a particular assembly, subassembly, or part is to be considered replaceable, the contracting officer shall be consulted.

3.9 **Marking.**

3.9.1 *General.* Marking shall conform to Specification MIL-M-13231.

3.9.2 *Visibility.* Whenever practicable, parts, and assemblies shall be so mounted that their identification markings will be readily visible with minimum disassembly of the equipment.

3.9.3 *Serial numbers.* Serial numbers under Specification MIL-M-13231 are required.

3.10 **Preconditioning.** The equipment shall be capable of meeting the inspection of section 4, without subsequent processing, after subjection to the bounce preconditioning of 4.4.

3.11 **Workmanship.** The equipment shall be manufactured and assembled in a thoroughly workmanlike manner, in accordance with the applicable portions of the following paragraphs herein:

3.3 Plastic materials and parts
3.4.2 Flux and cleaning agents for soldering
3.4.3 Process for soldering
3.5 Cleaning

4. QUALITY ASSURANCE PROVISIONS

4.1 **Inspection, general.**

4.1.1 *Definitions.* Standard MIL-STD-109 applies for definitions of inspection terms used herein.

4.1.2 *Classification of inspection.* Inspection shall be classified as follows:

(*a*) Preproduction inspection of equipment.

(*b*) Preproduction inspection of preparation for delivery. (See section 5.)

(*c*) Acceptance inspection of equipment.

(*d*) Acceptance inspection of preparation for delivery.

4.2 **Preproduction inspection.**

4.2.1 *Preproduction inspection of equipment.* This inspection shall consist of the group A inspection and nondestructive group B inspection specified in tables II and III respectively, and the preproduction inspection specified in table I. Other nondestructive inspection on preproduction samples may be performed to determine compliance with specified requirements.

TABLE I. *Preproduction Inspection*

Inspection	Requirement Paragraph	Test Paragraph
Temperature test for equipment	3.7	4.8.1
Moisture-resistance test for equipment	3.7	4.8.2
Vibration	3.7	4.8.3

4.2.2 *Preproduction inspection of preparation for delivery.* This inspection shall consist of the group B inspection specified in table III and the rough handling test specified in 4.11.

4.3 **Acceptance inspection.**

4.3.1 *Acceptance inspection of equipment.* This inspection shall include group A and group B inspection as specified in 4.3.1.1 through 4.3.1.2. Group B inspection shall normally be performed on inspection lots that have passed group A inspection and on samples selected from units that have been subjected to and met the group A inspection. Each unit which will be subjected to group A

Source: https://assist.dla.mil -- Downloaded: 202610-16T21:20Z
Check the source to verify that this is the currentversion before use.

or B inspection shall be preconditioned after final assembly. (See 3.10.)

4.3.1.1 *Group A inspection of equipment.* This inspection (including sampling) shall conform to table II and Standard MIL-STD-105. It shall be performed in any order which is satisfactory to the Government Inspector.

TABLE II. *Group A Inspection of Equipment*

Inspection	Test Paragraph	AQL		
		Major	Minor	Control
Visual and mechanical inspection.	4.5	1%	4%	25 dphu
Dielectric	4.6	1%	4%	.....
Continuity	4.7	1%	4%	.....

4.3.1.2 *Group B inspection of equipment.* This inspection (including sampling) shall conform to table III and to the appendix to Standard MIL-STD-105. Unless otherwise specified herein, normal inspection shall be used at the start of the contract. The reduced inspection procedure shall be R-1.

4.3.1.2.1 *Group B sampling plans.* The group B sampling plans, as listed in table III, shall be as follows:

Group B plan	*AQL*	*Inspection level for normal inspection*	*Inspection level for reduced inspection*
B-1	4.0%	L-8	L-6
B-2	6.5%	L-7	L-5
B-3	10.0%	L-6	L-4
B-4	15.0%	L-5	L-3

4.3.1.2.2 *Order of inspection within group B.* Group B inspection shall be performed in any order which is satisfactory to the Government inspector.

4.3.1.2.3 *Procedure in case of failure.* If an inspection lot is rejected the contractor shall immediately investigate the cause of failure and shall report to the Government inspector the results thereof and details of the corrective action taken. If the contractor and the Government inspector cannot agree on the effectiveness of the corrective action, the matter shall be referred to the contracting officer for resolution.

TABLE III. *Group B Inspection of Preparation for Delivery*

Inspection	Requirement Paragraph	Inspection Paragraph	AQL
Packaging:			
Visual inspection, minor.		4.9	10%
Visual inspection, major.		4.9	4%
Heat seal	5.4	4.9	
Waterproofness	5.4	4.10	
Packing:			
Visual inspection, minor.		4.10	10%
Visual inspection, major.	.....	4.9	4%

4.3.2 *Disposition of nonconforming product.* Disposition of rejected lots and defective sample units shall be in accordance with Standard MIL-STD-105. When submitted for acceptance, such product shall be suitably tagged or identified by equivalent means to indicate the cause of failure and means employed to correct the fault. The required information shall be presented to the Government when the product is resubmitted and shall become the property of the Government.

4.4 **Bounce preconditioning.** The equipment shall be placed in its normal operating position on the table of the Package Tester as made by L. A. B. Corporation, Summit, N. J., or equal. The package tester, shafts in phase, shall have a speed such that it is just possible to insert a $\frac{1}{32}$-inch-thick strip of material under one corner or edge of the equipment to a distance of 3 inches as the equipment bounces. The equipment shall be subjected to this preconditioning for 1 minute. After bounce preconditioning, the equipment shall not be repaired, alined, cleaned or otherwise changed prior to subjection to acceptance inspection.

Source: https://assist.dla.mil -- Downloaded: 202610-16T21:20Z
Check the source to verify that this is the currentversion before use.

4.5 **Visual ad mechanical inspection.** Parts and equipment shall be examined for the defects listed in Standard MIL–STD–252. Particular attention shall be given to the following:

(*a*) Completeness.

(*b*) Construction of cable assembly.

(*c*) Inspection of soldered joints.

(*d*) Finishes.

(*e*) Circuit label and nameplate.

(*f*) Fit and operation of jacks.

4.6 **Dielectric test.** The dielectric strength of all circuits on each equipment shall be tested to withstand 400 volts dc or peak ac of the same value for 10 seconds between wiring and adjacent nonconductors and grounds.

4.7 **Continuity test.** The continuity test shall be made on all electrical circuits. This test shall be made with the switching in each combination of operating positions.

4.8 **Service condition tests.**

4.8.1 *Temperature test for equipment.* The equipment shall be subjected to the temperature cycle shown on Standard MIL–STD–169. The dielectric test specified in 4.6 shall be applied at steps 1, 4, 9, and 10, and the equipment when tested shall meet full specification requirements.

4.8.2 *Moisture-resistance test for equipment.*

4.8.2.1 *Test conditions.*

(*a*) Do not move equipment from the humidity chamber for measurements.

(*b*) Start measurements not more than 5 minutes after power is applied to the equipment. Complete measurements as rapidly as possible. Do not leave power on after measurements have been completed.

4.8.2.2 *Test method.*

(*a*) Dry at 130° ±5° F. for 24 hours.

(*b*) Condition at 77° ±5° F. and 40 to 50 percent relative humidity for 24 hours.

(*c*) Subject to continuous cycling for five 48-hour cycles. Temperature, relative humidity, and period of time for each portion of the cycle shall conform to Standard MIL–STD–170. The dielectric test specified in 4.6 shall be made during the periods shown on the standard.

(*d*) After cycling has been completed, condition the equipment for 24 hours at 77° ± 5° F. and 40 to 60 percent relative humidity. Adjust for optimum performance, using only those means provided by the equipment. No repair or replacement of parts shall be made. After adjustment, the equipment shall meet full specification requirements.

4.8.2.3 *Performance.* Measurements made during test, and specified performance during cycling, shall meet fully specified performance.

4.8.3 *Vibration test.* The equipment shall be tested for resonant frequencies below 55 cycles per second, to determine compliance with 3.7.2, as follows:

(*a*) The equipment shall be fastened in its normal mounting position on a vibration table that can be controlled within 10 percent of the specified amplitude. Equipment shock mounts, if any, shall be blocked. The vibration table shall provide approximately sinusoidal vibration.

(*b*) The equipment shall be vibrated successively in three mutually perpendicular directions that are parallel respectively to the edges of the equipment, over a frequency

Source: https://assist.dla.mil -- Downloaded: 202610-16T21:20Z
Check the source to verify that this is the currentversion before use.

range of 10 to 55 cycles per second, in 1-cycle per second steps. The total excursion shall be constant at $\frac{1}{64}$ inch.

(c) Mechanical resonance, if any, shall be determined visually by means of a Strobotac, as made by the General Radio Corporation, Cambridge, Mass., or equal, or by energizing the equipment and detecting mechanical vibration through electrical output indications.

4.9 **Visual inspection of preparation for delivery.** Packages and shipping containers shall be examined for the defects listed in Drawing SC-A-46406, as applicable, and to determine conformance with the approved process sheet specified in 5.5.

4.10 **Package tests.** Package tests shall be as follows:

(a) Packaging method IC-3; waterproofness and heat seal.

(b) Packaging method IC-5; water spray. (These packages need not be subjected to the water spray test when it will be performed as part of the rough handling test of the pack.) (See 4.11.)

(c) Packaging method III; none.

4.11 **Rough handling (pilot pack only).** Each complete pack (of the pilot pack, as prepared for shipment) shall be subjected to the rough handling test followed by the water spray test, as specified in Specification MIL-P-116. Packs shall be opened after testing and the packages and the items therein examined for damage. These items shall then be subjected to such operational tests as are necessary to determine freedom from malfunction.

5. PREPARATION FOR DELIVERY

5.1 **Preservation and packaging.**

5.1.1 *Level A.* Telegraph Switchboard SB-6( )/GG shall be preserved and packaged in accordance with the procedures specified for the designated methods as prescribed in Specification MIL-P-116 and described in the following paragraphs:

5.1.1.1 *Technical manual.* Each technical manual shall be packaged method IC-3, as follows: Inclose each technical manual within a close-fitting, type I, class b bag, conforming to Specification MIL-B-117. Heat seal to effect closure.

5.1.1.2 *Cord CX-106/GR.* Each cord shall be packaged method III as follows: Wind each cord into a coil of proportionate dimensions and tie in one place with cotton twine, 6-ply, type II, conforming to Specification T-T-871.

5.1.1.3 *Dummy plug.* No packaging required.

5.1.1.4 *Consolidated package.* Consolidate the items specified in 5.1.1.2 and 5.1.1.3 together within a wrap of two thicknesses of type II, single-face, flexible corrugated fiberboard, conforming to Specification LLL-F-291. Secure the cushioning with class 2, gummed paper tape, conforming to Specification UU-T-111.

5.1.1.5 *Telegraph Switchboard SB-6( )/GG.* Each switchboard shall be packaged method IC-5, as follows: place one each switchboard together with the consolidated package specified in 5.1.1.4 and the technical manual, packaged as specified in 5.1.1.1 within a close-fitting, regular slotted style, fiberboard box, conforming to W6c of Specification PPP-B-636, type 1, class 3. Box closure shall be in accordance with the appendix of the box specification. In addition, seal all seams and joints with waterproof, pressure-sensitive tape, type III, class 1, olive drab, conforming to Specification PPP-T-60.

5.1.2 *Level C.* Telegraph Switchboard SB-6( )/GG shall be packaged in accordance

Source: https://assist.dla.mil -- Downloaded: 202610-16T21:20Z
Check the source to verify that this is the currentversion before use.

with commercial practice and in a manner that will afford protection against corrosion, deterioration and physical damage, during direct shipment to the first receiving activity.

5.2 **Packing.**

5.2.1 *Level A.* Place a quantity of Telegraph Switchboards SB-6( )/GG within a style 4, nailed wood box, conforming to class 2 of Specification PPP-B-601, type 1, PPP-B-621, or PPP-B-636, type 1, class 3. The gross weight in fiber containers shall conform to the specification. Fabricate the box to fit contents snugly. The approximate gross weight of shipping containers shall not exceed 150 pounds. Box closure shall be in accordance with the box specification. Sealed case liners conforming to MIL-L-10547 shall be provided for PPP-B-601 and PPP-B-621 containers.

5.2.1.1 *Metal strapping.* Shipping containers shall be strapped in conformance with the requirements of the appendix of the container specification only for direct shipment to ports.

5.2.2 *Level B.* Telegraph Switchboard SB-6( )/GG shall be packed for shipment as specified in 6.2.1, except that the style 4, nailed wood box shall conform to Specification PPP-B-601, Type III, class 1 of Specification PPP-B-621, or PPP-B-636, type 1, class 1, and the approximate gross weight of shipping containers shall not exceed 200 pounds.

5.2.3 *Level C.* Telegraph Switchboard SB-6( )/GG shall be packed for shipment in a manner conforming to the requirements of Uniform Freight Classification for rail shipment, National Motor Freight Classification for truck shipment, Parcel Post Regulations and the regulations of other carriers as applicable to the mode of transportation employed, at the lowest transportation rate.

5.3 **Marking.** Interior packages and exterior shipping containers shall be marked in accordance with the applicable provisions of Standard MIL-STD-129.

5.4 **Package testing.** Packages prepared as specified in 5.1.1. shall be required to pass the applicable tests in section 4.

5.5 **Pilot pack.** Unless otherwise specified in the invitation for bid or contract, a pilot pack shall be furnished for Government inspection and approval. A pilot pack shall consist of all preservation, packaging, packing and marking for delivery for the complete equipment on contract or order. A Pilot Pack Process Sheet, using the format shown on Drawing SC-C-33073 shall be prepared by the Contractor and forwarded to the Contracting Officer and shall be accompanied by such drawings, sketches and other data as may be necessary to completely describe the procedure followed in fabricating the pilot pack and to identify the equipment items therein.

6. NOTES

6.1 **Intended use.** Telegraph Switchboard SB-6( )/GG is intended to provide means for easily and quickly changing interconnections of local dc lines, loops or extensions and teletypewriter sets or equipment by use of patching cords. Telegraph Switchboard SB-6( )/GG is also intended for use in case of failure of either the circuits or equipment when it is desired to rearrange a circuit or equipment layout and provides means to assist in making simple tests of associated line facilities.

6.2 **Ordering data.** Procurement documents should specify the following:

(*a*) Title, number, and date of this specification and any amendment thereto.

(*b*) Levels of packaging and packing required for shipment. (Immediate use at first domestic receiving activity, domestic shipment and indefinite storage, or overseas shipment.)

(*c*) Samples required. (See 3.2.)

(*d*) Marking and shipping of samples

Source: https://assist.dla.mil -- Downloaded: 202610-16T21:20Z
Check the source to verify that this is the currentversion before use.

(e) Place of final inspection.

(f) Technical literature required.

(g) Quantity of tools and running spare parts required.

(h) The statement of treatment reference in 3.6 as soon as possible after award of contract. This statement should be submitted to the contracting officer.

(i) A packaging technician from the procuring agency will evaluate the pilot pack. (See 5.5.)

(j) Five copies of the process sheet, specified in 5.5, are required.

6.3 **Nomenclature.** The parentheses in the nomenclature will be deleted or replaced by a letter identifying the particular design, for example: SB–6W/GG. As soon as possible after the award of contract, the contractor should apply to the contracting officer for such information. (See 1.1.)

Notice. When Government drawings, specification, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or any any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Custodians:
Army—Signal Corps
Air Force

Preparing activity:
Signal Corps

Source: https://assist.dla.mil -- Downloaded: 2026-10-16T21:20Z
Check the source to verify that this is the current version before use.