MIL-B-46415B (AR)
5 May 1966
SUPERSEDING
MIL-B-46415A (AR)
3 May 1965

MILITARY SPECIFICATION

BURSTER, PROJECTILE, M35, PARTS FOR LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the parts, loading, assembling and packing for one type of projectile burster designated as Burster, Projectile M35 for use in smoke cartridges for 4.2 inch Mortars.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 - Preservation, Methods of
MIL-A-2550 - Ammunition and Special Weapons; General Specification for
MIL-R-11470 - Radiographic Inspection: Qualification of Equipment, Operators and Procedures
MIL-R-11471 - Radiographic Inspection of Metals
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of

STANDARDS

FEDERAL

Federal Test Method Standard No. 151a - Metals; Test: Methods

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions

FSC: 1315

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

MIL-STD-1167 - Ammunition Data Cards
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

DRAWINGS

ORDNANCE CORPS

8796522 - Marking Diagram and Sealing for Wood Packing Boxes
8797832 - Burster, Projectile, M35 Assembly
8847535 - Carton, Packing Ammunition for Charge Burster, T74 (M35)
8847534 - Box, Packing Ammunition for Charge Burster, T74 (M35)

PUBLICATIONS

ORDNANCE CORPS

ET-8797832 - Equipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Materials shall be in accordance with applicable drawings and specifications.

3.2 Assembly.-The projectile burster shall comply with all requirements specified on Drawing (dwg.) 8797832 and with all requirements specified in applicable specifications.

3.3 Cavitation

3.3.1 End areas.-There shall be no single cavity having a projected length of more than 1/8 inch or a sum total of cavitities of more than 1/64 square inch, in either end in the area extending to one inch from the end. There shall be no cracks or annular rings in the charge in these areas.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

3.3.2 Area between end areas defined above (3.3.1).-There shall be no single cavity having a projected length of more than one inch or a sum total of cavities or more than 3/8 square inch and there shall be no more than three transverse cracks 1/32 inch wide, maximum, in this area.

3.3.3 Porosity.-Porous areas shall be treated as cavities, and shall be subject to the restrictions placed upon cavities, except that 80 percent of the projected length and 80 percent of the projected area shall be considered for acceptance purposes.

3.3.4 Void at end surface.-There shall be no void greater that 1/32 of an inch between charge face at either end and the plane of the tube end.

3.4 Workmanship.-All parts shall be free from burrs, chips, cracks, dirt, grease, rust and other foreign material. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define the terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Certificates of conformance on all material purchased

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection

4.2.1 Submission.-Prior to the start of regular production, the contractor shall submit an initial production sample to a Government approved facility as designated by the contracting officer (see 6.5) for evaluation in accordance with the provisions of 4.2.2. The initial production sample shall consist of 15 consecutively produced complete assemblies (see dwg. 8797832) and 15 burster tubes (see dwg. 8799008) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of analysis for materials.

From each of (5) of the tubes specified above, a full section test specimen shall be prepared and tested in accordance with paragraph 4.3.3.3 and paragraph 4.4.3, the test results only being submitted with the initial production sample. The (15) complete assemblies will be x-rayed in accordance with this specification and individually identified. After being inspected, the x-ray negatives identified as to tube sample shown will be forwarded with the actual assemblies.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

An initial production sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply such as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

4.2.2 Inspections to be performed.-Each assembly and sub-assembly shall be subjected by the Government to any or all of the examinations or tests specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.-If any assembly or sub-assembly fails to comply with any or all of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of any assembly or sub-assembly in the sample to comply with any or all of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot shall contain:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

a. Composition B-4 from not more than one lot from one manufacturer.
b. Parts of one lot interfix number from one manufacturer.

Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

4.3.2 Examination.-Inspection for Critical defects shall be 100 percent. Sampling plans and procedures for Major and Minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with Standard MIL-STD-1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to individual characteristics listed using an AQL of 0.65 percent for each Minor defect and an AQL of 0.40 percent for each Major defect, except where 100 percent inspection is specified. Equipment necessary for the performance of the inspection listed shall be in accordance with 4.3.4.

4.3.2.1 Tube, burster, prior to assembly (see dwg. 8799008 covering a detail of dwg. 8797832).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Total length	Gage	01001
102.	Outside diameter	Gage	01002
103.	Wall thickness, min	Gage	01003
104.	Tube curvature excessive	Gage	01004
Minor:	AQL 1.00 percent		
201.	Interior or exterior surface not completely painted or varnished	Visual	01005
202.	Foreign matter in interior	Visual	01006
203.	Pool of paint	Visual	01007
204.	Evidence of poor workmanship prior to painting (see 3.4)	Visual	01008

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

4.3.2.2 Assembly (see dwg. 8797832)

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 1.00 percent		
101.	Total length, maximum (Max)	Gage	02001
102.	Chamber gage failure	Gage	02002
103.	Ends incompletely sealed	Visual	02003
104.	Crack in tube	Visual	02004
105.	Explosive charge loose or missing, or not completely filling tube, either end	Visual-Manual	02005
Minor:	AQL 1.00 percent		
201.	Coating damaged (bare area except slight scratches)	Visual	02006
202.	Evidence of poor workmanship (see 3.4)	Visual	02007
203.	Marking of nomenclature or lot data incorrect or illegible	Visual	02008

4.3.2.3 Carton, prior to sealing (see dwg. 8847535)

Categories	Defects	Method of Inspection	Code No.
Critical: .None defined.			
Major:	AQL 0.40 percent		
101.	Burster charge missing	Visual	03001
Minor: None defined.			

4.3.2.4 Carton, prior to insering in bag (see dwg. 8847535)

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.40 percent		
101.	Carton damaged so that contents are exposed or liable to become exposed	Visual	04001
102.	Sealing strip incomplete, badly wrinkled, or not in contact with surface for at least 1/2 inch around entire carton	Visual	04002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

Minor:	AQL 1.50 percent		
201.	Contents move when carton is shaken	Visual	04003
202.	Marking misleading, missing or unidentifiable	Visual	04004
203.	Label missing	Visual	04005

4.3.2.5 Carton, in sealed bag (see dwg. 8847535)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Waterproofness destroyed by rip, tear, puncture or separation of seal	Visual	05001
Minor:	AQL 0.65 percent		
201.	Marking misleading, missing or unidentifiable	Visual	05002

4.3.2.6 Sealed wood packing box (see dwg. 8847534)

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Strapping missing, broken or loose	Visual-Manual	06001
102.	Contents exposed	Visual	06002
103.	Board broken or split	Visual	06003
Minor:	AQL 1.50 percent		
201.	Strapping improperly assembled	Visual	06004
202.	Marking misleading, missing or unidentifiable	Visual	06005
203.	Contents loose	Manual	06006

4.3.3 Testing

4.3.3.1 Cavitation (see 3.3).-Cavitation defects are classified as follows:

Critical Code No. 02009

Any cavity, crack or annular ring in excess of that permitted by 3.3.1. Any void in excess of that permitted by 3.3.4.

Source: https://assist.dla.mil - Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

Major Code No. 02010

Cavities or cracks in excess of that permitted by 3.3.2 or 3.3.3.

The sampling plan and procedure for this test for both critical and major defects shall be in accordance with Standard MIL-STD-1235 using a CSP-2 plan having an AQL of 0.25 percent except that when a critical defect is found, 100 percent inspection for i successive defect free units (for both criticals and majors) shall be required immediately instead of continuing on a sample basis. When a major defect is found during the f phase of the plan, inspection shall continue at the same frequency until the homogeneity requirement is fulfilled or 100 percent inspection is required. Appropriate i and f values shall be as specified by the procuring activity. The test shall be performed as specified in 4.4.1.

4.3.3.2 Heat seal test of barrier bag (see dwg. 8847535) - Major defect - Code No. 05003.-The sampling plan for this test shall be in accordance with Standard MIL-STD-105, Code letter H and AQL 0.25 percent. The test shall be performed as specified in 4.4.2.

4.3.3.3 Tensile properties - Major defect - Code No. 01009.-Five (5) burster tubes shall be selected at random from each burster lot. From each one of these tubes (1) full section test specimen shall be prepared in accordance with paragraph 4.4.3. When tested in accordance with paragraph 4.4.3 of this specification, all specimens shall meet the minimum tensile property requirements of Dwg. 8799008.

4.3.4 Inspection Equipment.-Equipment Tabulation Number ET-8797832 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

4.3.4.2 Supply and Maintenance.-Supply and maintenance of the equipment listed in the EL's shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment.-The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures

4.4.1 Determination of cavities.-The sample bursters shall be subjected to x-ray examination. In all exposures, the x-ray beam shall form a 90 degree angle with the longitudinal axis of the projectile. Examination of the x-ray negative shall be made to determine compliance with applicable requirements.

NOTE: Radiographic equipment, operations and procedures shall be qualified in accordance with Specifications MIL-R-11470. In addition the sensitivity of x-ray technique shall be 2.0 percent, and the photographic density of the film used shall be no less than 1.25 as determined in accordance with 4.4.1.1 and 4.4.1.2. In the event an original x-ray picture leaves doubt as to acceptability, the burster shall be re-x-rayed at an angle 90 degrees from that of the original exposure and in the same plane.

4.4.1.1 Check of sensitivity of x-ray technique.-The sensitivity of x-ray technique shall be determined by means of a penetrameter fabricated as specified herein. The penetrameter shall be placed on the side of the burster away from the film (source side). Observation shall be made of the image of the penetrameter on the x-ray film. The sensitivity of x-ray technique shall be considered satisfactory when the image of the penetrameter, including the 2T hole, is sharply defined on the x-ray film. Unless otherwise specified, the penetrameter shall be made of steel having an approximate specific gravity of 7.8. The thickness of the penetrameter shall be based on a combination of both charge and steel thickness and shall be equal to 2.0 percent of the maximum equivalent thickness. The penetrameter shall have a hole, the diameter of which is twice the thickness of the penetrameter. For future details on construction of the penetrameter, see Specification MIL-R-11471. The actual thicknesses may be determined from a radiograph of the metal parts. The penetrameter thickness shall be determined as illustrated in figure 1 of this specification.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

4.4.1.2 Check of photographic density of film.-The photographic density of the film shall be determined on the film in a region of sound charge plus metal corresponding to that portion of the material which is of the greatest combined thickness to be examined on the negative. To judge densities, it is recommended that standards of radiographic densities be used (see 6.4). Comparison of film with standards may be made visually; however, the use of a densitometer is recommended.

4.4.2 Heat seal test of barrier bag.-The test procedure for this test shall be as prescribed in Specification MIL-P-116 for the "Heat Seal Test."

4.4.3 Tensile properties.-Full section tensile test specimens shall be prepared and tensile properties determined in accordance with Federal Test Method Standard No. 151a, Method 211.1.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level C.-The projectile burster shall be preserved and packaged in accordance with dwg. 8847535.

5.2 Packing

5.2.1 Level C.-The projectile burster shall be packed in accordance with dwg. 8847534.

5.3 Marking.-The container shall be marked in accordance with dwg. 8847535. The wood box shall be marked in accordance with dwg. 8847534.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

6.3.1 Equipment lists.-Equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (SMUPA Form 1010) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.6 will be designated in the EL. by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) or their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format relfects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.

6.3.7 Submission of contractor designs.-Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Film density.-"American Standard for Diffuse Transmission Density" published by American Standards Association, 70 East 40th Street, New York, N.Y., has been found satisfactory as a source of information on film densities.

6.5 Submission of initial production samples.-Instructions as to the location for evaluation of initial production shall be obtained from the contracting officer shall advise Picatinny Arsenal, ATTN: SMUPA-NI, Dover, New Jersey, and instructions will be issued accordingly.

Custodian:
Army-AR

Preparing activity:
Army-AR

Project Number: 1315-A465

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:53Z
Check the source to verify that this is the current version before use.