MIL–D–46418B(MU)
27 MARCH 1964

SUPERSEDING
MIL–D–46418A(MU)
10 DECEMBER 1962

MILITARY SPECIFICATION

DELAY ELEMENT, T6E4 AND T5E3 PARTS FOR

1. SCOPE

1.1 This specification covers quality assurance requirements for the metal parts for two types of delay elements designated as Delay Element, T6E4 and T5E3 (see 6.5).

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL–A–2550 —Ammunition and Special Weapons General Specification for
MIL–P–10025—Packing and Marking for Domestic Shipment of Inert Ammunition Components; General Specification for
MIL–I–45208 —Inspection Requirements, General Specification for
MIL–I–45607 —Inspection Equipment, Supply and Maintenance of

STANDARDS

MILITARY

MIL–STD–105 —Sampling Procedures and Tables for Inspection by Attributes.
MIL–STD–109 —Quality Assurance Terms and Definitions.
MIL–STD–1235 —Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8822520—Body Assembly.
8822526—Plug.

PUBLICATIONS

ORDNANCE CORPS

IEL–8872308 —Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 **Material.** Materials shall be in accordance with applicable drawings and specifications.

3.2 **Parts.** The parts shall comply with all requirements specified on Drawings (dwgs.) 8822520 and 8822526 and with all requirements specified in applicable specifications.

3.3 **Workmanship.** All manufacturing and processing shall be correctly performed in a

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.

thorough workmanlike manner. Parts shall be free from burrs, chips, sharp corners where not required, dirt, grease, rust and other foreign matter. The cleaning method shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Contractor quality assurance system.* The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL–I–45208.

4.1.2 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

(b) Number of units of product inspected.

(c) Results obtained for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of analyses on all material procured directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.3 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL–I–45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 Prior to the start of regular production, the contractor shall submit an initial production sample to a Government approved facility as designated by the Contracting Officer (see 6.4) for evaluation in accordance with the provisions of 4.2.2. The initial production sample shall consist of 15 each of each component which have been produced by the contractor or furnished by a supplier and

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.

which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of analysis for materials. An initial production sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 *Inspections to be performed.* The components will be subjected by the Government to any or all of the examinations or tests specified in 4.3.2 of this specification and any or all requirements of the applicable drawings.

4.2.3 *Rejection.* If any component fails to comply with any of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

4.3 **Inspection provisions.**

4.3.1 *Lot formation.* Lot formation shall consist of parts produced by one manufacturer in one unchanged process in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification and process changes not affecting performance, safety or fit, as determined by the Government, shall not be cause for changing the lot interfix number.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105 except that inspection for critical defects shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Body (see dwg. 8822523 covering a detail of dwg. 8822520).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.2)*
Critical: None defined.			
Major:	AQL 1.5 percent		
101.	Thickness of base at bottom of longer cavity	Gage	01001
102.	Height of longer cavity	Gage	01002
103.	Depth of shorter cavity	Gage	01003
104.	Profile and location of cavities at top of element	Gage	01004
105.	Location of primer cavity and flash hole from bottom of longer charge cavity, minimum (min.)	Gage	01005
106.	Concentric position of flash hole with primer cavity	Gage	01006
107.	Diameter of gas relief hole, min.	Gage	01007

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
	108. Diameter of flash hole, min.	Gage	01008
	109. Diameter at bottom of primer cavity, min.	Gage	01009
	110. Distance to bottom of primer cavity	Gage	01010
	111. Distance from body to primer crimping lip, min.	Gage	01011
	112. Distance between primer flash hole and relay flash cavity	Gage	01012
	113. Wall thickness at relay flash cavity, maximum (max.)	Gage	01013
	114. Profile and location of locking pin slot	Gage	01014
	115. Height of spring pin guide shoulder	Gage	01015
	116. Distance from body (primer side) to lock pin slot	Gage	01016
	117. Presence of oil or moisture in pores	Visual	01017
Minor:	AQL 4.0 percent		
	201. Total height	Gage	01018
	202. Total length	Gage	01019
	203. Total thickness	Gage	01020
	204. Distance from body to spring pin guide shoulder	Gage	01021
	205. Location of vent hole	Gage	01022
	206. Diameter of vent hole disc seat, min.	Gage	01023
	207. Height of vent hole disc crimping lip	Gage	01024
	208. Diameter of longer and shorter charge cavities	Gage	01025
	209. Protective finish damaged exposing base metal	Visual	01026
	210. Finish improper	Visual	01027
	211. Chamfer missing at locking pin slot	Visual	01028
	212. Evidence of poor workmanship (see 3.3)	Visual	01029

4.3.2.2 Plug (see dwg. 8822526).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.40 percent		
	101. Length	Gage	02001
	102. Width	Gage	02002
	103. Radius of ends	Gage	02003
	104. Foreign matter	Visual	02004
Minor:	AQL 1.5 percent		
	201. Thickness	Gage	02005
	202. Protective coating damaged exposing base metal	Visual	02006
	203. Evidence of poor workmanship (see 3.3)	Visual	02007

4.3.2.3 Disc (see dwg. 8822524 covering a detail of dwg. 8822520).

Categories	Defects	Method of inspection	Code No.
Critical:	None defined.		
Major:	None defined.		
Minor:	AQL 1.0 percent		
	201. Thickness	Gage	03001
	202. Diameter	Gage	03002

4.3.4 *Inspection equipment.* Index of Inspection Equipment Number IEL 8872308 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whatever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment, and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

5. PREPARATION FOR DELIVERY

5.1 Packing and marking.

5.1.1 *Level C.* The parts shall be packed and marked in accordance with Specification MIL–P–10025.

5.2 Data cards. Data card information shall be prepared for each lot in accordance with Specification MIL–A–2550.

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

6.2 Inspection code numbers. The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "contractor design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5, and 6.3.6 will be designated in the inspection equipment list by the following codes:

CDOF —Contractor's design responsibility on Ordnance format; ORDM–608–12.
CDCF —Contractor's design responsibility on contractor format.
OD —Ordnance design.
ODMU—Ordnance design, mandatory for use.
CE —Commercial equipment.
SCD —Specification control drawing.

6.3.3 *Ordnance designs.* Ordnance designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and nonmandatory. When an In-

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.

spection Equipment List references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with nonmandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawings.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial inspection equipment but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDOF shall comply with the format and requirements of ORDM 608–12, and, in addition, contain the detail and information specified above.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Submission of initial production sample. Instructions as to the location for the evaluation of the initial production sample shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NI, Dover, New Jersey.

6.5 Intended use. It is intended that the items of this specification, when loaded, will be used with Bomb Fuze, M906 (T788E3).

Custodian:
Army—MU

Preparing activity:
Army—MU

Project No. 1375–A709

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T05:54Z
Check the source to verify that this is the current version before use.