|NOT MEASUREMENT|
|SENSITIVE|

MIL-C-28562C(YD)
19 June 1989
SUPERSEDING
MIL-C-28562B(YD)
25 March 1983

MILITARY SPECIFICATION

# CENTRAL MIX PLANT, CONCRETE, MOBILE 100 CUBIC YARDS PER HOUR CAPACITY

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

## 1. SCOPE

1.1 This specification covers a complete central mix concrete plant in a single mobile unit, electric-driven, with automatic controls, capable of producing not less than 100 cubic yards (cu yd) of concrete mix per hour, when accompanied with a mobile mixer unit.

## 2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. The following specifications and standards form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

|Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043-5000, by using the self-addressed Standardation Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter|

AMSC N/A FSC 3895

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

| | | |
|---|---|---|
| TT-P-664 | - | Primer Coating, Synthetic, Rust-inhibiting, Lacquer-Resisting. |
| TT-V-119 | - | Varnish, Spar, Phenolic-resin |
| MMM-A-260 | - | Adhesive, Water-Resistant (for Sealing Waterproofed Paper). |
| PPP-B-1055 | - | Barrier Material, Waterproofed, Flexible. |
| PPP-T-60 | - | Tape, Packaging, Waterproof. |

MILITARY

| | | |
|---|---|---|
| MIL-C-104 | - | Crates, Wood; Lumber and Plywood Sheathed, Nailed and Bolted. |
| MIL-P-116 | - | Preservation, Methods of. |
| MIL-B-121 | - | Barrier Material, Greaseproofed, Waterproofed, Flexible. |
| MIL-V-173 | - | Varnish, Moisture and Fungus Resistant (for Treatment of Communications, Electronic, and Associated Equipment). |
| MIL-C-3600 | - | Compressor, Air and Gas (except Oxygen), Packaging of. |
| MIL-V-13811 | - | Varnish, Waterproofing, Electrical, Ignition. |
| MIL-E-16298 | - | Electric Machines having Rotating Parts and Associated Repair Parts: Packing of. |
| MIL-G-19826 | - | Generator Sets, Diesel Engine, Alternating Current, for Facilities Construction 10 KW through 500 KW. |
| MIL-T-22085 | - | Tape, Pressure Sensitive, Adhesive, Preservation and Sealing. |
| MIL-G-28554 | - | Generator Sets, Mobile Electric Power and Supplemental Equipment, Packaging of. |
| MIL-P-46093 | - | Primer Coating, Synthetic (For Brake Drums). |
| MIL-B-81705 | - | Barrier Materials, Flexible, Electrostatic-Free, Heat Sealable. |

STANDARDS

FEDERAL

| | | |
|---|---|---|
| FED-STD-595 | - | Colors. |



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

MILITARY

| | | |
|---|---|---|
| MIL-STD-129 | - | Marking for Shipment and Storage. |
| MIL-STD-209 | - | Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment. |
| MIL-STD-281 | - | Automobile, Trucks, Truck-tractors and Trailer lollies, Preservation and Packaging of. |
| MIL-STD-2073 | - | DOD Material Procedures for Development and Application of Packaging Requirements. |

(Unless otherwise indicated, copies of federal and military specification, standards, and handbooks are available from the Naval Publications and Forms Center, (ATTN: NPODS), 5801 Tabor Avenue, Philadelphia, PA 19120-5099.)

2.1.2 Other Government documents and publications. The following other Government documents and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

DEPARTMENT OF LABOR (DoL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

DEPARTMENT OF TRANSPORTATION (DoT)

Federal Motor Carrier Safety Regulations.

(Application for copies should be addressed to the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402.)

2.2 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DOD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of the documents not listed in the DODISS are the issues of the documents cited in the solicitation (see 6.2).

CONCRETE PLANT MANUFACTURER'S BUREAU (CPMB)

Concrete Plant Standards.

(Application for copies should be addressed to the Concrete Plant Manufacturer's Bureau, 900 Spring Street, Silver Springs, MD 20910.)



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM D-3953 - Standard Specification for Strapping, Flat Steel and Seals.

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018-3308.)

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 6 - Enclosures for Industrial Controls and Systems.
NEMA MG 1 - Motors and Generators.
NEMA WC 3 - Wire and Cable, Asbestos.
NEMA WC 7 - Asbestos Varnished Cloth and Asbestos Thermoplastic, Insulated.

(Application for copies should be addressed to the National Electrical Manufacturers Association, 2101 L Street, N.W., Washington, DC 20037.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 - National Electrical Code.

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269.)

NATIONAL LUBRICATING GREASE INSTITUTE (NLGI)

NLGI - Lubricating Grease Guide

(Application for copies should be addressed to the National Lubricating Grease Institute, 4635 Wyandotte Street, Kansas City, MO 64112.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE J534 - Lubrication Fittings.
SAE J551 - Performance Levels and Methods of Measurement of Electromagnetic Radiation from Vehicles and Devices (30-1000 Mhz).
SAE J700 - Upper Coupler King Pin - Commercial Trailers and Semitrailers.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

TIRE AND RIM ASSOCIATION, INC. (TRA)

TRA Yearbook.

(Application for copies should be addressed to the Tire and Rim Association, Inc., 3200 West Market Street, Akron, OH 44313.)



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

(Non-Government standards and other publications are normally available from the organizations which prepare or which distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The central mix concrete plant hereinafter called the concrete plant shall consist essentially of an aggregate bin with three compartments; conveyor belts or screw conveyors; a weighing means; a cement bin or silo; control console panel; water delivery; air and hydraulic systems; instruments; delivery conveyors or gravity discharge. All equipment shall be mounted on a single semitrailer chassis frame with kingpin. When specified (see 3.7.4), a mobile tiltable or horizontal shaft concrete mixer with stand, or other elevating means, shall be furnished to supplement the plant. The concrete plant shall be capable of being erected and ready for operation in not more than 16 working hours, and without the use of special tools. The concrete plant shall be capable of being self-erected or erected with the use of not more than one standard commercial truck crane having a maximum capacity of 25 tons. Except as otherwise specified herein, the concrete plant shall conform to the specifications of the CPMB, Concrete Plant Standards. When specified (see 6.2), the manufacturer shall provide a skid-mounted diesel engine-driven generator set (see 3.7.9.3). The generator set shall be fully housed in a weatherproof enclosure.

3.2 First article. When specified in the contract or purchase order, a sample shall be subjected to first article inspection (see 4.2.1, 6.2 and 6.3).

3.3 Safety. All rotating or reciprocating parts that are of such nature or so located as to become a hazard to operating or maintenance personnel shall be enclosed or properly guarded. All concrete plant components shall conform to the applicable safety and health standards and regulations of DoL OSHA.

3.4 Standard commercial product. The concrete plant shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the concrete plant being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements or manufacturer's catalogs, or brochures, and represents the latest production model.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.5 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. Unless otherwise specified, none of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification.

3.6 Performance. The assembled concrete plant shall be rated for not less than 100 cu yd per hour of pavement quality, 1-inch slump concrete, based on a 1-minute mix cycle per batch, utilizing a six-bag mix and 2-1/2 to 3-inch maximum sized aggregate; and not less than 100 cu yd per hour of structural quality, 3-inch slump concrete, utilizing a six-bag mix and 1-1/2-inch maximum sized aggregate, and within 1 percent for cement of the preset requirement. The batching of aggregates and cement shall be synchronized with the demand cycle of the mixer. The concrete plant, including the mixer unit when furnished, shall be capable of being towed cross country over reasonably hard, level to rolling terrain at speeds up to 5 miles per hour (mph) without damage, malfunction, or permanent set. The concrete plant, including the mixer unit, shall be capable of being towed over paved highways at speeds up to 35 mph without damage, malfunction, or permanent set.

3.7 Construction. The equipment shall be designed and constructed to facilitate field maintenance. All adjustments and replaceable accessories shall be readily accessible. Conditions which can be hazardous to personnel or deleterious to equipment shall not be permitted.

3.7.1 Aggregate bin. An aggregate bin having three approximately equal compartments, for sand and two different sizes of aggregates, shall be furnished. Total capacity shall be calculated in accordance with CPMB and be not less than 20 cu yd. The aggregate bin shall be fabricated from sheet steel reinforced with structural steel, with partitions to form the three compartments. The compartment tops shall be of sufficient size to facilitate loading a standard commercial 2-1/2 cu yd front end loader. The interior of the compartments shall be free from obstructions, and the sides shall be sloped from top to bottom, or the lower portion of the sides shall be sloped, to insure free flow of the material and prevent bridging. Each compartment shall be visible to the plant operator. The sand compartment shall be furnished with a moisture sensing device located so as to be visible to the plant operator. The moisture sensing device shall be the direct reading, pen or dial type calibrated to show the percentage of free moisture by weight. A separate conversion chart, table, or dial scale shall be furnished to facilitate converting the amount of free moisture in volume per 100 pounds (lb) of sand. A means shall be provided to weigh the aggregate and shall have a capacity of not less than 20,000 lb and shall be calibrated in increments of 20 lb or less with a weighing tolerance within 2 percent for each aggregate material being weighed.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.7.2 Cement bin. The cement bin, or silo, shall have a capacity of not less than 740 cubic feet (185 barrels) of cement. The cement bin shall be provided with self-loading means, mechanical or pneumatic. Means such as air injection or mechanical vibration shall be provided to insure free flow of the dry cement from the bin. The cement bin, equipped with air vent, shall be provided with a batch hopper sized for the mixer capacity to hold a full batch of cement for mixer provided. A dust collector shall also be provided. A means shall be provided to weigh the cement having a capacity of not less than 3,600 lb and shall be calibrated in increments of not more than 3 lb. The cement bin shall be provided with a content indicator of the high-low type, located so as to be visible to the plant operator.

3.7.3 Batch conveyor or delivery conveyor(s). Material transfer shall be accomplished either by a motor driven batch conveyor of the inclined trough or channeled belt type at least 24 inches in width (with 3-piece trough type idlers or rollers), with a foldable, demountable, retractable discharge head, or by motor driven conveyor(s) for each material being delivered to the batcher. The batch conveyor shall be covered to guard the materials against inclement weather. All troughing idler bearings shall be either of the anti-friction or bronze bearing type with dustproof seals. Idlers shall be designed to insure true running and self-centering of the conveyor belt with the width and running speed of the conveyor belt, so as to assure efficient movement of material, without spillage and pileup at receiving points, when the plant is operating at full capacity. An accessible adjustment for maintaining proper belt tension shall be provided, as well as a cleaning device capable of removing foreign material adhering to the pulley side of the belt. The height of the conveyor(s) discharge head(s) shall be compatible with the charging height of the mixer. A water feeding system with automatic metering controls shall be installed on the conveyor(s), discharge head(s), or on a location directly over the mixer receiving opening for adding the required amount of water to obtain the desired concrete mixtures.

3.7.4 Mixer. When specified (see 6.2), the concrete plant shall be supplemented with a powered tiltable or horizontal shaft type mixer having a capacity rating of not less than 4-1/2 cu yd. Mixer shall be motor driven and compatible with the plant capacity in producing or exceeding the specified production. A system shall be provided on the mixer for loading and unloading the mixer. The mixer shall be equipped with a stand or other means so as to have a discharge height of not less than 13′ 6" above ground level to facilitate unloading into dump trucks without spillage. The liner and the edge of charging and mixing blades shall be fabricated of abrasion-resistant steel. The mixer shall be furnished with a slump meter.

3.7.5 Water system. A water system, consisting of a pump of adequate capacity to supply all demands of the plant, cycling timer, piping, hose, and all the necessary accessories shall be provided with the plant. The required amount of water shall be discharged to the mixer while the mixer is being charged with aggregate. The suction and discharge connections of the pump shall have not less than 3-inch National Taper Pipe Thread. The pump shall have a constant speed motor drive, and automatic start-stop controls.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.7.6 Air system. Air required to operate the plant shall be supplied by compressor(s) of adequate capacity to satisfy all demands. The compressor(s) shall be equipped with an oiler, strainer, relief valve, moisture separator, drain, and receiver with an unloading valve.

3.7.7 Hydraulic system. Hydraulic power required to operate the plant shall have a constant speed motor driven pump of adequate capacity with a relief valve, and automatic start-stop controls to satisfy the operational demands.

3.7.8 Admix dispensing system. An air entraining admix dispensing system shall be provided with the plant. The system shall include pump, meter, piping, and all necessary components for a complete dispensing system.

3.7.9 Electrical system. All electrical equipment and wiring shall conform to NFPA 70.

3.7.9.1 Motors. All motors for driving components of the concrete plant shall be totally enclosed, fan cooled, conforming to NEMA MG 1, and rated for 230/460 volts (V), 3-phase, 60 Hertz (Hz), alternating current. All motors larger than 15 horsepower shall be started from nonreversing reduced voltage starters with under-voltage and overload protection.

3.7.9.2 Power panel. The power panel enclosure shall be NEMA type 3S in accordance with NEMA ICS with doors. The power panel shall contain master switch circuit breakers, motor starters, and all items necessary for 460 V, 3-phase, hookup of the concrete plant. The power plant shall be furnished with two 50-foot, rubber covered, 4-conductor (one conductor for each phase, plus an equipment ground (green) conductor) cable conforming to NEMA WC 3 or WC 7. The cable shall have lugs for connecting to an electrical system. The cables shall have conductive capacity to meet the electrical requirements of the concrete plant. The cables shall be portable power cables, with extra-heavy-duty jacket, rated for 600V. Cables shall be UL approved. The power panel shall have an instruction plate permanently affixed in a conspicuous location. In addition to instructions for connecting and operating the plant, the instruction plate shall show the applicable power supply requirements for the plant, in bold type, as follows:

POWER SUPPLY REQUIRED

460 VOLTS, THREE-PHASE,
INPUT CAPACITY, MAXIMUM _____ KVA (_____ KW)
OPERATING LOAD (AT RATED CAPACITY)_____ KVA (_____ KW)



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.7.9.3 Diesel engine-driven generator set. When required (see 3.1), a diesel engine generator set shall be furnished. The generator set shall comply with MIL-G-19826, and shall have 60 Hz, 460 V current generation. The rated power output of the generator set shall be adequate for the total maximum connected load, including start-up, of the concrete plant and auxiliary electrical equipment, plus 5 percent additional load for area lighting for night operations. The generator set shall be provided with a weatherproof housing. The housing shall protect the generator set for both storage and operation in all weather conditions.

3.7.10 Scales. Scales shall be of the level balance, springless or load cell type. The aggregate scale shall be of the accumulative three-material type, capable of automatically weighing preset amounts of the three materials. The cement scale shall be one material type, capable of weighing a preset amount of cement. Scales shall be equipped with zero interlocks to prevent charging of a new batch, or the next material of the batch, or discharging of the batch until the preset weights are reached.

3.7.11 Control panel and controls. The concrete plant shall be furnished with a dust-and-weather-tight control panel with key-locked door(s) or cover(s). The control panel, or console, shall contain all the necessary controls to enable automatic, as defined by the CPMB, and manual operation of the plant by one operator at the control panel. Automatic batching, mixer(s) charging, water introduction, and mixing time cycle controls shall be provided with manual over-ride controls. The mixer shall be discharged by activation of discharge control at the control panel or at the mixer. An emergency stop control shall be provided to enable complete shutdown. The control panel shall be provided with preset type controls to control the amount of three sizes of aggregate, cement, water, and mixing time per batch of concrete. A digital type batch counter and a water readout (gallons per batch) shall be provided.

3.7.12 Semitrailer units. The concrete plant (and mixer when furnished) shall be separated into two semitrailer units for transportation. The semitrailer units shall be designed to withstand shock loads incumbent with performance requirements specified herein. Each semitrailer unit shall be equipped with full air service brakes controlled from the towing vehicle. Service brakes, lighting, reflectors, and associated equipment shall conform to DoT Motor Carrier Safety Regulations. The kingpin shall conform to SAE J700. Support jacks, legs, or braces shall be provided in sufficient number and location to support the plant semitrailer unit in its operating position when the semi-trailer is unhooked from the towing vehicle. Jacks, legs, and braces shall be retractable or removable to preclude interference with travel capabilities. Axle and suspension ratings shall be at least equal to the imposed load. The plant semitrailer units shall conform to table I.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

TABLE I. Dimensions and clearances.

| | |
|---|---|
| Maximum overall height (feet) | 13-1/2 |
| Maximum overall width (feet) | 12 |
| Maximum length centerline of kingpin to rear (ft) | 65 |
| Kingpin height from ground (inches) | 48 to 52 |
| Centerline of kingpin to front (inches) | 24 to 36 |
| Minimum swing clearance (radius from center of king pin to any portion of semitrailer 6 inches or more below upper fifth wheel plate) (inches) | 82 |
| Angle of departure, not less than (degrees) | 23 |
| Vertical road clearance, except for axle assembly not less than (inches) | 6 |

3.7.13 Tires and rims. The tire and rim ratings shall conform to TRA Yearbook recommendations for the type and size of tires furnished. Tire and rim sizes shall be the same for all wheels. Tires shall be tube of tubeless type with highway tread. Tires shall be or rated capacity at least equal to the load imposed on each tire, measured at each wheel at the ground. Tires shall be not less than 100 level quality and shall be of domestic make. When tube tires are furnished, inner tubes shall be heavy-duty types, and shall be of proper size for the tires furnished. Disc wheels are required.

3.8 Toolbox. A toolbox shall be provided. The toolbox shall be large enough to store all tools required for field service or maintenance, but shall not have external closed dimensions less than 14 inches in length, 6 inches in width, and 6 inches in height. The toolbox shall be of nominal 0.0740-inch (US revised standard gage No. 14) thick steel, with a hinged lid and a lockable fastener to keep the lid secure when vibrated. The toolbox shall be mounted in a protected, accessible location.

3.9 Dissimilar metals. Intimate contact which can be expected to cause galvanic corrosion shall be avoided. When such contact cannot be avoided, an interposing insulating material shall be provided to minimize the corrosive effect.

3.10 Lubrication. Means for lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 pound-force per square inch or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

3.11 Electromagnetic interference characteristics. When specified (see 6.2), the plant and mixer shall conform to electro-magnetic characteristic requirements and test limits of SAE J551.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.12 Fungus resistance. When specified (see 6.2), electrical components and circuit elements, including terminal and circuit connections, shall be coated with varnish conforming to MIL-V-173, except that:

a. Components and elements inherently inert to fungi or in hermetically sealed enclosures need not be coated.
b. Current-carrying contact surfaces, such as relay contact points, shall not be coated.

3.13 Lifting and tiedown attachments. When specified (see 6.2), the plant shall be equipped with lifting and tiedown attachments. Lifting and tie-down attachments shall conform to type II or type III of MIL-STD-209. Lifting devices shall be designed and constructed to preclude the use of spreader bars. A nonferrous transportation plate shall be provided and mechanically attached to the plant. Transportation plates shall be inscribed with a diagram showing the lifting attachments and lifting slings, the capacity of each attachment, and the required length and size of each sling cable. A silhouette of the item furnished showing the center of gravity shall be provided on the transportation plate. Tiedown attachments may be identified by stenciling or other suitable marking. Tiedown markings shall indicate which attachments are intended for the tie down of the plant on the carrier when shipped.

3.14 Instruction plates. The plant shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. Plates shall be of a material which will last and remain legible for the life of the equipment. Plates shall be securely affixed to the equipment with nonferrous screws or bolts of not less than 1/8-inch diameter.

3.15 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.16 Identification plate. The contracting officer will furnish to the Government inspector the required metal identification plates. The contractor will be required to stamp the necessary data in the blank spaces thereon and securely affix said plates in a conspicuous place on each unit, assembly or subassembly, and parts as directed by the Government inspector. Nonferrous screws, rivets, or bolts of not less than 1/8-inch in diameter shall be used to affix the plates. Nomenclature shall be "CENTRAL MIX PLANT, CONCRETE, 100 CUBIC YARDS PER HOUR CAPACITY."

3.17 Servicing and adjusting. Prior to acceptance of the concrete plant by the Government, the contractor shall service and adjust the concrete plant for immediate operational use as required in the operator's manual. The servicing and adjusting shall include at least the following:



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

1. Inflation of all tires.
2. Adjustment of brakes.
3. Proper functioning of all lighting and electrical systems.
4. Wheel alignment.
5. Adjustment of engine to include tune-up when engine generator is furnished.
6. Complete lubrication with grades of lubricants recommended for ambient temperature at the delivery point.
7. Cooling system filled to capacity with a clean solution of equal parts by volume of water and antifreeze (ethylene glycol) when engine generator is furnished.

The concrete plant shall be conspicuously tagged to identify the lubricants and their temperature range.

3.18 Marking. The empty weight of the plant shall be conspicuously marked on each side of the plant by stenciling or other suitable means. Block or stencil type letters not more than 1-inch and not less than 3/4-inch high shall be used.

3.19 Cleaning, treatment, and painting. Surfaces normally painted shall be cleaned, treated, and painted as specified herein. Surfaces to be painted shall be cleaned and dried to ensure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion products, or any other interfering substances. As soon as practicable after cleaning, and before any corrosion product or other coating interfering material can result, the surface shall be prepared or treated to ensure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat of acrylic enamel. The primer shall be applied to a clean, dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. Color of the finish coat shall be Green, N. 14064, conforming to FED-STD-595 "Colors." The end item, allied equipment, and attachments shall be the same color.

3.20 Workmanship.

3.20.1 Metal fabrication. The metal used in fabrication shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the material. Corners shall be square and true. Flame-cutting, using tips suitable for the thickness of the metal, may be used instead of shearing and sawing. All bends shall be made by controlled means to ensure uniformity of size and shape. Precautions shall be taken to avoid overheating and heated metal shall be allowed to cool slowly. External surfaces shall be free from burrs, sharp edges and corners, except when sharp edges or corners are required or where they are not detrimental to safety.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

3.20.2 Bolted connections. Boltholes shall be punched or drilled within manufacturer's design tolerances and shall have the burrs removed. Washers or lockwashers shall be provided, and all bolts, nuts, and screws shall be tight.

3.20.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall completely fill the holes. Rivet heads, when not countersunk or flattened shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.20.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.20.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the castings ability to perform its intended function.

3.21 System of measurement. The dimensions used in this specification are not intended to preclude the use of the metric system of measurement in the fabrication and production of the material, individual parts, and the finished product, provided form, fit, and function requirements are satisfied.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements (examinations and tests) as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in this specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however in quality conformance does not authorize submission of known defective material, either indicated or actual, nor does it commit the Government to accept defective material.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

4.1.2 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on one concrete plant when a first article is required (see 3.2, 6.2 and 6.3). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the tests of 4.4, and the packaging inspection of 4.5. This inspection shall be performed on the samples selected in accordance with 4.3.

4.3 Examination. Each concrete plant shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 Tests. Every unit shall be tested in accordance with 4.4.1. The first article shall be tested in accordance with 4.4.2. Failure to pass any phase of the required tests shall constitute cause for rejection.

4.4.1 Acceptance tests. Each concrete plant shall be erected to function as a complete plant to determine conformance to 3.6. All controls shall be operated a sufficient number of times to determine ease of operation and responsiveness.

4.4.2 First article tests. The following tests shall be performed on the first article when a first article sample is required (see 3.2).



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

4.4.2.1 Road test. Each trailer-mounted unit shall be towed for not less than 5 miles over hard surface rolling terrain, at speeds up to 5 mph with an average speed of not less than 3 mph. Each unit shall be towed for not less than 20 miles over paved roads at speeds up to 35 mph with an average speed of not less than 20 mph.

4.4.2.2 Production test. The assembled plant shall be operated a sufficient period of time to satisfy the contracting officer that the concrete plant is capable of meeting the production performance specified in 3.6.

4.4.2.3 Electromagnetic interference suppression. When specified (see 6.2), the generator set shall be tested in accordance with SAE J551 to meet the requirements of 3.11.

4.4.2.4 Lifting and tying down attachments. When required, the lifting and tying down attachments shall be tested to conform to 3.13.

4.5 Packaging inspection. The preservation, packing, and marking of the item shall be inspected to verify conformance to the requirements of section 5.

5. PACKAGING

5.1 Preservation. Preservation shall be level A or commercial as specified (see 6.2).

5.1.1 Level A. The concrete plant shall be preserved as specified in the following paragraphs.

5.1.1.1 Methods of preservation. Cleaning processes, drying procedures, preservatives, and methods of preservation specified in the following paragraphs are listed in MIL-P-116 and shall conform to the requirements of MIL-P-116 and any applicable specifications.

5.1.1.2 Matchmarking. Parts removed and mating parts on the equipment and attachments shall be matchmarked to facilitate reassembly. Large parts shall be matchmarked by stenciled letters or numerals using lusterless white enamel overcoated with varnish. Small parts and mating parts on the basic unit and attachments shall be matchmarked with weatherproof tags attached to mating parts and locations with wire or twine. Markings shall be applied to the tags with a waterproof material.

5.1.1.3 Cleaning and drying. Prior to the application of preservative compounds or paint, surfaces shall be cleaned by process C-1 and dried by any applicable procedure of MIL-P-116.

5.1.1.4 Unprotected surfaces. Unprotected exterior metal surfaces requiring the application of a contact preservative in accordance with MIL-P-116 and not specifically provided for herein shall be preserved as follows:



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

5.1.1.4.1 Unfinished (not machined) surfaces. Unfinished exterior metal surfaces shall be coated with type P-1 preservative.

5.1.1.4.2 Machined surfaces. Exposed machined surfaces shall be coated with type P-6 or P-11 preservative and wrapped or covered, as applicable, with barrier material conforming to MIL-B-121, type I, grade A, class 2. The material shall be secured in place with waterproof tape.

5.1.1.5 Drive belts and pulleys. Drive belts shall be removed or released from tension. Removed belts shall be preserved method IC-1 or IC-3. Unpainted surfaces shall be coated with primer conforming to TT-P-664 or MIL-P-46093. A weatherproof tag shall be attached in a conspicuous location indicating: "Belts have been (removed or released from tension). (Install or tension) prior to operation." Markings shall be applied to the tags with a waterproof material.

5.1.1.6 Hydraulic systems (except hydraulic brakes or steering systems). The hydraulic fluid supply tanks shall be filled to the operating level with hydraulic fluid required for operation. The pistons shall be retracted as far as practicable into the cylinders and secured. When the pistons cannot be fully retracted, the exposed portions of the piston rods (ramshafts) shall be coated with type P-6 or P-11 preservative and the coated surfaces wrapped or covered with barrier-material conforming to MIL-B-121, type I, grade A, class 2, extending the wraps approximately 2 inches onto the ram cylinders. The wraps shall be secured in place with waterproof tape conforming to PPP-T-60. When the pistons can be fully retracted, any remaining uncoated surfaces of the piston rods shall be coated with type P-1 preservative, with no wrapping required. The hydraulic control valves shall be secured in the neutral position and preserved as specified herein for piston rods. Hoses shall not be disconnected. A weatherproof tag shall be attached to the control lever indicating: THE HYDRAULIC SUPPLY TANK IS FILLED TO THE OPERATING LEVEL WITH FLUID REQUIRED FOR OPERATION. DO NOT DRAIN." Markings shall be applied to the tag with a waterproof material.

5.1.1.7 Air compressor. The air compressor shall be preserved in accordance with the level A requirements of MIL-C-3600.

5.1.1.8 Electrical components.

5.1.1.8.1 Electrical motors. Preserve level A by the alternate method of MIL-E-16298.

5.1.1.8.2 Electrical modules. Circuitry modules, printed circuit boards, and panel boards that are not hermetically sealed should be removed, if possible, and packaged method II. If the complexity of the circuitry will not allow removal, seal area with a waterproof barrier conforming to MIL-B-81705 or tape conforming to MIL-T-22085, type II or PPP-T-60, type IV.

5.1.1.8.3 Electrical components. Openings in sockets, coupling plugs, and switches shall be sealed with waterproof tape.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

5.1.1.8.4 Generator Set. The generator set, when provided (see 3.1) shall be preserved in accordance with the level A requirements of MIL-G-28554.

5.1.1.9 Brakes.

5.1.1.9.1 General. Clean all surfaces as required to remove contaminants. Coat unpainted exterior surfaces of rods, levers, cables, clevises, linkage, and associated parts with type P-1 preservative. Remove brakedrum covers and spray enclosed metallic components with primer TT-P-664. Spray coat brakedrum friction surfaces with a very thin coat (0.5-0.6 mil thick) of primer. Coat friction surfaces of cams, adjusting screws, and anchor pins with type P-6 or P-7 preservative. Back off all brakeshoe adjusters for maximum clearance between brakedrum and brakeshoes. Do not apply coating of any type to contact surfaces of electric brakes. Adjust brakeshoes to provide maximum clearance to drum surfaces and lined surfaces. In a conspicuous location in the operator's compartment, attach a weatherproof warning tag marked, "Brakes preserved. Do not apply brakes when vehicle is being moved. Use tow bar or similar arrangement for moving vehicle. Adjust brakes before placing equipment into operation." Markings shall be applied with waterproof material.

5.1.1.9.2 Air-actuated brake systems. The air-actuated brake systems shall be drained. Interior surfaces of the air-supply tanks shall be fogged with type P-10, grade 30 preservative. Excess preservative oil shall be drained. Threaded openings and the threads of drain plugs shall be coated with P-10. The drain plugs shall be reinstalled. Air line filters shall be drained and closed. The exhaust ports of relay emergency, quick-release, and relay valves not equipped with exhaust check valves shall be closed by inserting caps or plugs as applicable or by sealing the ports with waterproof tape. Attach a waterproof tag to the valves and service lines indicating, "Remove (plugs, caps, or tape) from exhaust ports and valves before operating." Markings shall be applied with a waterproof material.

5.1.1.10 Water system. Interior surfaces of the water system, such as pumps, piping, and valves, shall be coated with type P-21 preservative in a manner to insure thorough coating of all interior parts and surfaces. Excess preservative shall be drained and all openings sealed with caps, plugs, or waterproof tape specified herein.

5.1.1.11 Scales. The component parts of the torque lever assembly of level balance-type scales, such as pivot pins, pivot loops and U-bolts, shall be coated with type P-1 preservative. The loops and pins shall be secured in place with tape conforming to PPP-T-60, type IV. The weighing beams, including poises, weights, and linkage shall be coated with type P-7 or P-10 preservative and where practicable, the coated surfaces and parts covered or wrapped with barrier material conforming to MIL-B-121, type I, grade A, class 2, shall be secured with tape specified herein. The dial glass of springless dial-type scales shall be covered with a fitted piece of 1/4-inch thick exterior grade plywood secured in place with tape specified herein.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

5.1.1.12 Conveyor belts. Metal facings shall be coated with varnish conforming to TT-V-119 or MIL-V-13811. Each belt shall be completely rolled with a tube or piece of round wood placed in each end fold of the belt to prevent sharp bends. Prior to rolling, belt surfaces shall be dusted with powdered talc to prevent surfaces from adhering together. When required, to hold belt in compact roll, strapping conforming to ASTM D 3953 shall be placed around the roll. Suitable protective cushioning shall be placed under the strapping, and the strapping not tensioned so tight as to damage the belting. Each rolled belt shall be wrapped with waterproofed barrier conforming to PPP-B-1055, class E-1 or E-2, with all laps, seams, and folds sealed with adhesive conforming to MMM-A-260.

5.1.1.13 Instruments. The dial glass of instruments not protected by a metal housing shall be covered individually or in groups with a fitted piece of plywood secured with tape conforming to PPP-T-60, type IV or MIL-T-22085, type II.

5.1.1.14 Vehicle bodies. The vehicle body and chassis shall be preserved as specified in MIL-STD-281 for level A (mobile) requirements.

5.1.1.15 Lubrication. Lubricate all grease fittings with type P-11 preservative to include universal joints, chassis suspension and steering linkage, fifth wheels, propeller shaft, and parking brake cable. Wheel bearings requiring a NLGI No. 2 grade grease shall be lubricated with type P-11 preservative. Lubricate control mechanisms, linkage, hinges, fasteners, and all pivot points with P-10.

5.1.1.16 Wheels, axles, bearings, and tires. When wheels are removed, the tires shall be inflated to two-thirds of the specified operating pressure. The wheel nuts shall be replaced on the studs and the exposed threaded surfaces shall be coated with type P-1 preservative. When wheels and hubs are removed from axles or spindles, the interior bearing surfaces of the hubs and the bearings or bearing surfaces of the axles or spindles shall be coated with type P-11 preservative. The coated surfaces of the axles or spindles shall be wrapped and hub openings shall be covered with barrier material conforming to MIL-B-121, type I, grade A, class 2. The barrier material shall be secured in place with tape conforming to PPP-T-60, type IV. Bearings removed from the wheels shall be coated with type P-11 preservative and preserved method IA-8. When wheels are not removed, the tires shall be inflated to 10 pounds above the specified operating pressure and wheel bearings shall be preserved with type P-11 preservative.

5.1.1.17 Pumps and valves. Interior surfaces of pumps and valves shall be coated with type P-10, grade 30 preservative in a manner to insure thorough coatings of all interior parts and surfaces. Excess preservative shall be drained. Where packing rings are not removed from pumps, care shall be exercised to prevent the preservative from coming in contact with the packing



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

material. Packing rings removed shall be preserved in accordance with method IC-1. Openings into the pumps and valves shall be sealed with caps or plugs; tape conforming to MIL-T-22085, type II or PPP-T-60, type IV; or with barrier material conforming to MIL-B-121, type I, grade A, class 2 and secured with tape specified herein.

5.1.1.18 Consolidation. The dash compartment and tool boxes shall be utilized for the consolidation of loose components, tools, and publications. Tool boxes shall be secured to prevent pilferage. The remainder of the components that will not fit in the dash compartment or tool boxes shall be consolidated, along with disassembled components, in woodboxes for the level required from table VII of MIL-STD-2073-1. The contents shall be cushioned, blocked, and braced to prevent movement in accordance with MIL-STD-2073-1. Boxes shall be placed in the cab or secured to the equipment with appropriate strapping. Arrangement and location on the equipment shall be such so as not to increase cubage or interfere with lifting or mobility of the equipment.

5.1.2 Commercial. The equipment shall be preserved in accordance with the contractor's standard practice in a manner to prevent deterioration and damage. The equipment shall be lubricated for operational service as required in the operator's manual.

5.2 Packing. Packing shall be level A, B, or commercial as specified (see 6.2).

5.2.1 Level A.

5.2.1.1 Basic concrete plant (except conveyors). The basic concrete plant shall be prepared for mobile shipment; openings shall be sealed to prevent the entry of free falling water. Large disassembled components that cannot be consolidated, packaged, or secured to the basic plant shall be packed in crates designated for level A from table VII of MIL-STD-2073-1. The contents shall be anchored, blocked, and braced in accordance with MIL-STD-2073-1

5.2.1.2 Portable conveyors. Portable conveyors shall be shipped knocked down to the most practicable extent. The structural components shall be nested, arranged, and secured with bolts or steel strapping, in combination with suitable wood blocking or battens, as required to form nonshifting bundles. The strapping shall be 0.035 by 1-1/4 inch strapping conforming to ASTM D 3953. The strapping shall be stapled to any wood blocking or battens provided. Where it is not practicable to disassemble the equipment to the extent required for suitable bundling, the sections shall be secured to skid bases conforming to the skid-type base of MIL-C-104, style A crates, and shipped as individual assemblies. The electric motors, conveyor belts, bolts, nuts, washers, and any other small components requiring the protection of a container for safe convenient handling shall be packed in containers as specified for disassembled components. Where skid bases are used, consideration shall be given to consolidating and securing any bundled or boxed components on the skid bases.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

5.2.2 Level B. The complete concrete plant shall be packed as specified for Level A, except that components not trailer-mounted shall be packed in containers designated for level B from table VII of MIL-STD-2073.

5.2.3 Commercial. The equipment shall be prepared for shipment in a manner which will insure arrival at destination in a satisfactory condition. Preparation for delivery shall comply with applicable carrier rules and regulations.

5.3 Marking. Marking shall be in accordance with MIL-STD-129.

6. NOTES

(This section contains information of a general or explanatory nature which may be helpful, but is not mandatory.)

6.1 Intended use. This specification covers a central mix concrete plant composed of mobile units to be used either as a concrete mix plant or, when not using the mixer unit, as an aggregate batch plant of 100 cu yd per hour capacity.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When diesel engine-driven generator is required (see 3.1).
d. When first article is required for inspection and approval (see 3.2, 4.2.1, and 6.3).
e. When tiltable or horizontal shaft mixer(s) are required (see 3.7.4).
f. When electromagnetic radiation is to be suppressed (see 3.11 and 4.4.2.3).
g. When fungus resistance is required (see 3.12).
h. When lifting and tying down attachments are required (see 3.13).
i. Level of preservation and level of packing required (see 5.1 and 5.2).

6.3 First article. When a first article inspection is required, the item will be tested and should be a first production item consisting of one complete central mix plant or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.4 Waiver of test. Any or all tests of 4.4 may be waived by the contracting officer provided the contractor furnishes actual test results which were submitted by the contractor and accepted by the Government under a previous contract for an identical item acquired to this specification.



Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

6.5 Subject term (key word) listing.

Concrete mixer, large
Concrete batch plant, movable
Batch plant, aggregate and cement

6.6 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extensiveness of the changes.

Preparing activity:

Navy - YD

Project No. 3895-N268



☆ U.S. GOVERNMENT PRINTING OFFICE: 1989 - 604-033/13441

Source: https://assist.dla.mil -- Downloaded: 2025-10-26T18:10:02
Check the source to verify that this is the current version before use.

# STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

*(See Instructions – Reverse Side)*

| 1. DOCUMENT NUMBER | 2. DOCUMENT TITLE |
|---|---|
| MIL-C-28562C(YD) | Central Mix Plant, Concrete, Mobile 100 Cubic Yards Per Hour Capacity |

**3a. NAME OF SUBMITTING ORGANIZATION**

**b. ADDRESS** *(Street, City, State, ZIP Code)*

**4. TYPE OF ORGANIZATION** *(Mark one)*

- ☐ VENDOR
- ☐ USER
- ☐ MANUFACTURER
- ☐ OTHER *(Specify)*: _____

**5. PROBLEM AREAS**

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

**6. REMARKS**

| 7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional | b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional |
|---|---|
| c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional | 8. DATE OF SUBMISSION *(YYMMDD)* |

DD FORM 82 MAR 1426

PREVIOUS EDITION IS OBSOLETE.

*(TO DETACH THIS FORM, CUT ALONG THIS LINE.)*

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.

**INSTRUCTIONS:** In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

*NOTE:* This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document*(s)* or to amend contractual requirements.

*(Fold along this line)*

*(Fold along this line)*

DEPARTMENT OF THE NAVY

Commanding Officer (Code 156)
Naval Construction Battalion Center
Port Hueneme, CA 93043-5000

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Commanding Officer
Code 156
Naval Construction Battalion Center
Port Hueneme, CA 93043-5000

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:13Z
Check the source to verify that this is the current version before use.