NOT MEASUREMENT SENSITIVE

MIL-T-28571G(NAVY)
20 September 1991
SUPERSEDING
MIL-T-28571F(YD)
14 January 1985

MILITARY SPECIFICATION

TRUCK, FIREFIGHTING, STRUCTURAL, 1,000 GPM, 4 BY 2

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers a diesel-engine-driven, four-wheel, two-rear-wheel drive, 1,000 gallons per minute (gpm) pumping capacity, firefighting truck capable of fighting structural fires.

2. APPLICABLE DOCUMENTS

2.1 Government Documents.

2.1.1 Specifications and Standards. The following specifications and standards form a part of this specification to the extent specified herein. Unless otherwise specified, the issues of these documents are those listed in the issue of the Department of Defense Index of Specifications and Standards (DODISS) and supplement thereto, cited in the solicitation (see 6.2).

Beneficial comments (recommendations, additions, deletions) and any pertinent {data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043-5000, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

AMSC N/A FSC 4210

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

FEDERAL

W-B-131 - Battery, Storage, Vehicular, Ignition, Lighting, and Starting.

MILITARY

MIL-T-704 - Treatment and Painting of Materiel.
MIL-F-24385 - Fire Extinguishing Agent, Aqueous Film Forming Foam (AFFF) Liquid Concentrate, For Fresh & Sea Water.
MIL-I-45208 - Inspection System Requirements.
MIL-V-62038 - Vehicle, Wheeled, Preparation For Shipment And Storage Of.

STANDARDS

FEDERAL

FED-STD-H28 - Screw-Thread Standards for Federal Services.
FED-STD-297 - Rustproofing of Commercial (Nontactical) Vehicles.
FED-STD-595 - Colors.

MILITARY

MIL-STD-889 - Dissimilar Metals.
MIL-STD-1223 - Nontactical Wheeled Vehicles Treatment, Painting, Identification Marking & Data Plate Standards.

(Unless otherwise indicated, copies of federal and military specifications , standards and handbooks are available from Standardization Documents Order Desk, Bldg. 4D, 700 Robbins Avenue, Philadelphia, PA 19111-5094)

2.1.2 Other Government documents, drawings and publications . The following other Government documents, drawings and publications form a part of this specification to the extent specified herein. Unless otherwise specified, the issues are those cited in the solicitation.

ENVIRONMENTAL PROTECTION AGENCY (EPA)

Control of Air Pollution from New Motor Vehicles and New Motor Vehicle Engines: Certification and Test Procedures.
Interstate Motor Carrier Noise Emission Standards.
Motor Vehicle Air Pollution Standards.

(Application for copies should be addressed to the Public Affairs Office, Environmental Protection Agency, Rockville, MD 20852)

DEPARTMENT OF TRANSPORTATION (DoT)

Federal Motor Vehicle Safety Standards and Regulations.
Federal Motor Carrier Safety Regulations.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

(Application for copies should be addressed to the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402)

2.2 Non-Government Publications. The following document(s) form a part of this document to the extent specified herein. Unless otherwise specified, the issues of the documents which are DoD adopted are those listed in the issue of the DODISS cited in the solicitation. Unless otherwise specified, the issues of documents not listed in the DODISS are the issues of the documents which are current on the date of the solicitation (see 6.2).

AMERICAN NATIONAL STANDARDS INSTITUTE, INC. (ANSI)

ANSI B 40.1 - Gauges, Pressure Indicating Dial Type - Elastic Element.

(Application for copies should be addressed to the American National Standards Institute, Inc. , 1430 Broadway, New York, NY 10018.)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 - National Electrical Code.
NFPA 1901 - Automotive Fire Apparatus.
NFPA 1931 - Fire Department Ground Ladders.

(Application for copies should be addressed to the National Fire Protection Association, Batterymarch Park, Quincy, MA 02269)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

SAE Standards and Recommended Practices

SAE J534 - Lubrication.
SAE J537 - Storage Batteries (DoD adopted).
SAE J551 - Performance Levels and Methods of Measurement of Electromagnetic Radiation.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc. , 400 Commonwealth Drive, Warrendale, PA 15096)

STATE OF CALIFORNIA

California Vehicle Code.

(Application for copies should be addressed to the Department of Motor Vehicles, 2570 24th Street, Sacramento, CA 95809)

TIRE AND RIM ASSOCIATION, INC. (TRA)

TRA Yearbook.

(Application for copies should be addressed to the Tire and Rim Association, Inc ., 175 Montrose West Avenue, Coply, OH 44321)

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T13:15Z
Check the source to verify that this is the currentversion before use.

THE EUROPEAN TYRE AND RIM TECHNICAL ORGANISATION (ETRO)

Standard Manual.

(Application for copies of the European Tyre and Technical Organisation publications should be addressed to the European Tyre and Rim Technical Organisation, 32, Avenue Brugmann, 1060 Brussels, Belgium)

(Non-Government standards and other publications are normally available from the organizations that prepare or distribute the documents. These documents also may be available in or through libraries or other informational services.)

2.3 Order of precedence. In the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 Description. The truck shall be 4-wheel/2-axle, 2-rear wheel drive, diesel-engine-driven, with a four (4) door fully enclosed cab, and a chassis having a gross vehicle weight (gvw) rating of not less than 35,000 pounds (lbs). The truck shall be equipped with a 1,000 gpn single-stage pump, mounted amidship and driven by the truck engine, a removable 750-gallon water tank, three transverse hose beds, a main hose bed, operator's control panel for the fire pump, equipment compartments, foam system, and such other equipment and accessories as are specified herein and in compliance with NFPA-1901.

3.2 First article. When specified (see 6.2), the contractor shall furnish a fire truck for first article inspection and approval (see 4.2.1 and 6.4).

3.2.1 inspection system requirements. Quality assurance inspections and tests necessary to substantiate product conformance to contract specifications shall be in accordance with MIL-I-45208.

3.3 standard fire truck. components and accessories. Except as specified in 3.3.1 through 3.3.7, the fire truck, components and accessories shall be standard or optional items which meet or exceed the requirements for this specification. All items shall be as represented and rated in the manufacturer's sales information, including special or mounted equipment. Sales information shall be limited to specifications and technical material, identical to that furnished to the authorized company representative for selection of fire truck models and components. The fire truck, components and accessories to be provided hereunder are standard or optional commercial products for the purpose of this specification. Such items shall be construed as commercial motor vehicle products, and shall comply with all DoT Federal Motor Vehicle Safety Standards and Regulations applicable on the date of manufacture.

3.3.1 Heavy-duty cooling system. A heavy-duty cooling system shall be provided, The heavy-duty cooling system shall be of the pressurized type of sufficient capacity to maintain a cooling liquid temperature of not less than 180 degrees Fahrenheit (°F) and to provide proper cooling without overheating or loss of coolant when operated in an ambient temperature range of -20°F to +125°F

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

during operating conditions of either stationary pumping or mobile performance as specified.

3.3.1.1 Heat exchanger. An auxiliary heat exchanger shall be provided, which shall permit delivery of water from the fire pump to heat exchanger for cooling of the engine liquid coolant without admixture, The heat exchanger may be separate from the radiator. The discharge water from the heat exchanger shall be piped into the suction side of the fire pump. The size of the heat exchanger discharge line shall be large enough to eliminate back pressure on the heat exchanger. The flow of water from the fire pump to the heat exchanger shall be controlled by a valve, with the valve control extended to the fire pump operator's control panel and specifically identified on that panel.

3.3.1.2 Drain valves. Water drain valves shall be installed at the low point of the cooling and heat exchanger systems and at any other points necessary to completely drain the systems. The drain valves shall be of a type that will remain closed under the most severe operating conditions to be encountered by the fire truck. Drain lines shall be furnished and shall discharge to the ground at a point not above the bottom of the chassis frame.

3.3.3 Coolant system and indicators. The coolant system shall include a de-aeration system, a surge tank, or a coolant recovery reservoir of not less than 2-quart capacity. A high coolant temperature or low coolant level alarm buzzer and red indicator warning light shall be provided on the cab dash instrument panel and on the pump operator control panel. A radiator servicing access door shall be provided to allow verification of coolant level. The coolant system shall be filled to capacity with a clean solution of ethylene glycol and water in equal parts by volume. A warning tag shall be securely attached to the radiator filler neck with the information "COOLING SYSTEM FILLED WITH WATER AND ETHYLENE GLYCOL IN EQUAL PARTS BY VOLUME - DO NOT DRAIN

3.3.4 Radio interference suppressors. The fire truck shall be suppressed to limit electromagnetic radiation in accordance with SAE J551. Any body equipment emitting electromagnetic radiation shall be suppressed to the same level as the vehicle chassis. Certification of compliance with SAE J551 shall be provided.

3.3.5 Sound level. The exterior sound level produced by the truck, except for trucks with California destinations, shall not exceed the noise limits established by the EPA. The exterior sound level produced by the trucks destined for California shall not exceed the noise limits established by the California Vehicle Code, Section 27220. The interior sound level shall be in accordance with DoT Federal Motor Carrier Safety Regulations, Section 393.94 and in compliance with NFPA-1901.

3.3.6 Air pollution control. Trucks shall comply with EPA Code of Federal Regulations Governing Control of Air Pollution from New Motor Vehicles and New Motor Vehicle Engines in effect on the date of manufacture. Trucks shall also meet emission requirements at final destination, in addition to EPA standards; i.e. California.

3.3.7 Engine hour meter. An engine hour meter, having a totalizing mechanism of not less than 9,999 hours, shall be furnished for the truck chassis engine to register accurately the number of hours of operating time. The meter shall be of rugged construction to insure continuous trouble-free performance

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

under severe operating conditions. Engine hour meter shall be mounted on the cab instrument panel.

3.4 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.5 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.5.1 Dissimilar metals. Unless protected against electrolytic corrosion, dissimilar metals shall not be used in intimate contact with each other. Dissimilar metals are defined in MIL-STD-889.

3.6 Performance. The fully equipped fire truck, loaded as specified in 3.8.1, shall be capable of the following:

a. The service brakes shall control and hold the truck on a 30 percent longitudinal grade. The service brakes shall be tested with the truck heading up-grade and also heading down-grade.
b. The service brakes shall stop the truck within 35 feet from a speed of 20 miles per hour (mph) on a dry, paved, smooth level surface, free from loose material.
c. The parking brakes shall hold the truck in a parked position on a 30 percent longitudinal grade with the truck heading up-grade and also heading down-grade.
d. The truck shall ascend a grade of not less than 30 percent in both forward and reverse gears.
e. The truck shall accelerate from a standing start to a speed of 35 mph in not more than 30 seconds. The test shall be conducted on a dry, level, paved roadway.
f. The truck shall accelerate from a standing start to a speed of 15 mph in not more than 200 feet on an 8 percent grade. The roadway shall be dry and paved.
g. The truck shall maintain a minimum speed of not less than 60 mph on dry, level, paved roadway.
h. The truck shall be subjected to an endurance road test consisting of not less than 30 miles over paved roads at a maximum speed of not less than 60 mph and not less than 10 miles over graded dirt roads at a maximum speed of not less than 25 mph, There shall be no evidence of body distortion, water leakage, tire and body contact, malfunction of components, or irregular chassis noise, resulting from the test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

3.7 Dimensions. The overall dimensions shall not exceed the following:

Length	360-inches
Width	96-inches
Height	118-inches
Wheelbase	192-inches

3.8 Chassis components.

3.8.1 Weight rating and distribution. The manufacturer's gvw rating for the fire truck chassis furnished shall be not less than 35,000 lb. The total gvw of the complete truck shall not exceed the manufacturer's gvw rating when fully equipped as specified herein, including all specified firefighting equipment, serviced with fuel, water, and lubricants, loaded with 750 gallons of water in the water tank, 100 gallons of foam in the foam tank, a 1,600 lb simulated load uniformly distributed in the main hose bed and a firefighting crew, or equivalent deadweight, in the cab having a combined weight of not less than 800 lbs. weight distribution ratio between the front and rear axles shall be such as to insure positive traction at the rear wheels and positive steering at the front wheels under all operating conditions specified herein. The percentage of gvw at front axle shall be not less than 25 percent of the vehicle in all phases of loading and shall at no time exceed the capacity rating of any of the front axle components. The application of weights to the chassis for the purpose of meeting the gvw distribution requirements between front and rear axle is not acceptable .

3,8.2 Engine The fire truck engine shall be a diesel engine having not less than 300 gross horsepower, with torque and speed characteristics to meet satisfactorily all mobile and pumping performance requirements specified herein. The engine furnished in all trucks shall comply with Federal Regulations, and shall be the same make and model. The diesel engine shall have the necessary constant load and endurance characteristics for long pumping operations. The diesel engine shall be a liquid cooled, compression ignition, two or four cycle engine, with not less than six cylinders. The diesel engine shall achieve self-sustained combustion at the manufacturer's rated idle speed in less than 5 minutes in ambient temperature from -20°F to +125°F. The fire truck shall meet the mobile and pumping performance requirements specified herein utilizing diesel fuel. The engine shall be fitted with the engine manufacturer's standard or recommended fuel filter system. The engine manufacturer's standard "engine start-up" procedure (engine tune-up) shall be applied before delivery of the completed fire truck. The engine coolant system shall be fitted with silicone rubber hoses.

3.8.2.1 Governor. A governor shall be provided that will limit the engine to the maximum full load revolutions per minute (rpm) recommended by the engine manufacture r. The governor shall provide maximum effectiveness under all engine operating conditions and shall not restrict engine power output below governed full load rpm.

3.8.2.2 Power plant heater. When specified (see 6.2), an engine coolant heater shall be provided. The heater shall operate on 110 volt (V) alternating current (at), 60 Hertz (Hz), and shall be wired through a junction block to a single three pronged (male) weatherproof slave receptacle for receiving external power and grounding vehicle. The receptacle shall be located near the engine at

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

the driver's entrance of the cab. A three-wire connecting cable, 25 feet long, and of adequate capacity to supply power to the heater, shall be furnished. The connecting cable shall include a matching female connector at the vehicle end and a standard three pronged male connector at the other end. Electrical apparatus shall conform to DoT Federal Motor Carrier Safety Regulations, Section 393.77. The electrical insulation of the connecting cable shall withstand normal operating stresses in low ambient temperatures (down to -50°F) without cracking or loss of dielectric capacity. All heater lead wires shall be installed without interfering with vehicle component operation and without loose excess wire. Provisions for stowage of the cable shall be provided in the vehicle cab. The heater furnished shall be as follows:

a. The coolant heater shall be installed in the engine block or lower coolant hose. The coolant heater shall be a 2250 watt (W), 19.5 ampere (A), 115V, 60 Hz, ac, heater.

3.8.3 Fuel System. The fuel system shall conform to DoT Federal Motor Carrier Safety Regulations, Sections 393.65, 393.67, and as specified herein.

3.8.3.1 Air cleaner. Manufacturer's dry type air cleaner shall be furnished. The air cleaner shall be accessible and easily removed for replacement.

3.8.3.2 Fuel filter. The fuel system shall be provided with not less than two fuel filters; a primary and secondary design.

3.8.3.3 Fuel tank. The fuel tank shall not be less than 65-gallon capacity. The tank and fill piping shall be placed so as to be protected from mechanical injury. The fuel tank shall not project below the rear axle and shall have a drain plug. The fuel tank filler shall be located for ease in filling, shall not extend outside the body skin, shall have a drain to the ground for any spillage and shall be provided with a spring loaded, polished stainless steel access door, flush with the outer body skin and identified accordingly.

3.8.4 Exhaust svstem. The exhaust system shall comform to DoT Federal Motor Carrier Safety Regulations, Section 393.83. Where necessary, the exhaust pipe shall be insulated and shielded. The muffler and tailpipe shall be aluminized steel. The exhaust system discharge shall be directed away from the fire pump operator's control panel and any body panel, and the muffler shall not project below the truck axles.

3.8.5 Frame. The chassis franc shall provide a rigid platform and shall be of bolted construction. The chassis frame side rail(s) shall be one continuous piece with no notching allowed. The chassis frame material shall be of high strength, 110,000 psi, heat-treated alloy steel of sufficient width, depth, and thickness that will provide the required resistance bending moment to support the intended load, When operating the fully equipped and loaded fire truck under conditions specified herein, the frame shall show no evidence of permanent deformation or distortion.

3.8.6 Electrical equipment. The fire truck shall be provided with a complete starting and lighting system. Electrical equipment, including all truck lights and wiring, shall conform to DoT Federal Motor Carrier Safety Regulations, Sections 393-12, 393.19, 393.20, 393.22, 393,24, 393.25, 393.27

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

through 393.31 and 393.33, except as specified herein. Reflectors shall conform to DoT Federal Motor Carrier Safety Regulations, Section 393.26. Wiring shall be weatherproof, resistant to moisture and fungus, and color coded or numbered for ready identification. Wire identification shall be consistent throughout the truck. Two spare, single pole, 15A breakers shall be furnished for future radio use. The fire truck chassis electrical circuits and the fire truck body electrical circuits shall be separate circuits, The truck body electrical circuits, excluding truck chassis electrical circuits, shall be provided with circuit breaker type overload protection. A master electric module shall be provided. The module shall be located in the instrument panel in the cab. An access door to the master electrical module shall be located in the face of the instrument panel. The master electrical module shall consist of all necessary solenoids, relays , terminal blocks and circuit breakers. All wiring shall be automatic circuit breaker protected, that is numbered or color coded. The inside of the master electrical compartment door shall have both a wiring layout printed on a metal plate and a complete index of all wiring. All electrical equipment shall comply with NFPA-1901.

3.8.6.1 Starting system. The manufacturer's standard starting system shall be provided, complete with a keyless switch and pilot light.

3.8.6.2 Alternator. An alternator shall be furnished complete with a rectifier and regulator. The alternator shall be rated for not less than 160A.

3.8.6.3 A uiliary generator, A 6000 watt (6KW) auxiliary generator shall be installed in the left rear compartment. The generator shall provide single phase 120/240V, 26/13A, 60 cycle power. The following output receptacles shall be provided: Four 120V (2 located on the pump panel and 2 located at the rear tailboard area), one 120V twist lock, and one 240V twist lock. The generator shall be powered by a diesel engine, equipped with a fuel pump and filter, an air cleaner, shutoff valve, and a low-tone muffler. The engine shall be air cooled and equipped with an automatic shut-down system for high temperature and low oil pressure conditions. The engine shall be fueled from the truck's main fuel system and shall have an electric starting system energized from the main battery circuit. The generator start and stop switches shall be located in the cab , at the pump panel and at the generator. Circuitry shall be provided for the telescoping lights at the pump compartment (see para. 3.8.6.5 k). The auxiliary generator system shall comply with the NFPA-1901, and all 120/240 volt components , equipment and installation procedures shall comply with the NFPA-70, National Electrical Code.

3.8.6.4 Battery system. A dual 12V battery system shall be furnished. Each battery in the system shall be 12V, maintenance free, with characteristics listed in W-B-131. Each battery shall be rated in terms of cold cranking power capacity at O°F in accordance with SAE J537. The batteries shall be installed in "banks" and each bank shall have not less than the engine manufacturer's recommendation of cold cranking ampere rating required at O°F for the engine furnished. The battery compartment shall be provided as close as possible to the engine in order to reduce battery cable length for connection. Access shall be provided for ease in service and removal. The battery cables shall be protected by use of grommets where the cables pass through metal bulkheads and shall be covered by a protection boot where the cables are attached under vehicle frame to the electrical switches or connectors. The battery compartments shall be ventilated and treated against acid fumes and spillage.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

The battery compartment shall not be mounted on, or project onto, the side running boards when in the retracted (operating) position. The batteries shall be provided with a polarized receptacle(s) for station charging. The receptacle shall be located near the batteries at the driver's entrance to the cab. The charging receptacle shall be suitably identified. The receptacle shall be of the recessed male type with a spring loaded cover and provided with a matching female plug with protected prongs. The battery compartment cover(s) shall be easily raised/removed, not interfere with the servicing of batteries and not interfere with the. battery terminal connections. Hinged type covers shall be capable of being supported in the open position. Battery circuits and switching systems shall be provided whereby:

a. Either battery or battery bank may be used:

(1) For starting alone.
(2) For starting and lighting,
(3) For operation of priming pump.

b. Both batteries or battery banks may be used simultaneously in starting.

c. A battery master switch shall be provided, adjacent to and readily accessible , to the operator while seated in the driver's seat.

3.8.6.5 Lights. All lights shall be mounted in such a manner as to prevent being obscured by riding personnel or mounted equipment. All metal rims, shells, mounting arms, brackets and bases of all exterior lights shall be chromium plated or stainless steel. Stoplights and taillights shall be flush mounted at the rear of the body. A removable panel shall be installed in the rear compartments to protect the lights and wiring from damage. All warning lights shall operate off a single switch mounted on the cab instrument panel and shall be marked to indicate function. The following additional lighting shall be furnished and shall be provided with overload protection (see 3.8.6) and shall conform to current DoT regulations.

a. Two automotive type, 6-inch sealed beam, roof type spotlights shall be furnished. One spotlight shall be located near each front corner of the cab roof. Controls shall be extended inside the cab for on-off control and movement of lamp housing through a horizontal angle of at least 270°, and a vertical angle of at least 90° above and 35° below horizontal.
b. Two adjustable, sealed beam, hose pickup lights, with weatherproof switches, mounted on rear handrail supports.
c. Two shielded, engine compartment lights, arranged to illuminate both sides of the engine, with switch located on cab dashboard.
d. Two automatic backup lights shall be flush mounted at rear of body. Two rear scene lights, not less than six (6) inches in diameter, shall be provided and controlled by a switch in the cab.
e. Pump compartment light or lights, arranged to provide non-glare illumination of the compartments and enclosed within a protective housing, with switch mounted on pump control panel,
f. Pump control panel lights (see 3.11.3.i).
g. Two 6-inch sealed beam, red alternating flashing warning lights shall be mounted on the rear handrail supports adjacent to the hose pickup

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

lights . The lamps shall have a minimum output rating of 20 candlepower. The lights shall have a combined minimum flash rate of 80 flashes per minute.

h. Two red flashing lights shall be mounted on the front of the truck above the headlights on a horizontal plane through the centerline of the turn signals. The lights shall be sealed beam lamps, 6 inch diameter, and shall have a combined minimum flash rate of 80 flashes per minute.

i. A minimum of four (4) halogen headlamps shall be provided and shall conform to DoT Federal Motor Vehicle Safety Regulations, Section 393.24.

j. Red flashing lights (intersection lights) shall be mounted at the two forward comers of the cab and controlled by a switch in the cab.

k. Two telescoping, 120 volt, 500 watt quartz lights shall be mounted in the area of the pump compartment, powered by the auxiliary generator and controlled by switches in the cab and at the pump panel (see para. 3.8.6.3).

3.8.6.6 Warning light. One 12V cross fire oscillating light bar shall be provided and mounted, with reinforcement at the point of attachment, on the truck cab roof centerline in a position affording 360° visibility. A single control shall be provided for the roof mounted warning light and those warning lights described in 3.8.6.5 g. and h. The control shall be suitably identified. The control shall be provided with a red or green pilot light indicating the "ON" position. The pilot light shall be located in the cab on the instrument panel.

3.8.6.7 Horn. Dual electric horns, controlled by button in steering wheel, shall be furnished. Also , two chrome plated air horns of the studder tone type shall be provided and installed below the front surface of the cab and recessed through the front bumper, one horn on each side of the bumper. The air horns shall be controlled from one floor mounted, foot operated control device located on the fire officer's side of the cab and a lanyard (pull type) control from the inside center of the cab.

3.8.6.8 siren. An electronic siren with an output of not less than 150 watts shall be provided and activated by either firefighter seated in the front seat of the cab. The siren shall include two speakers, each with an output (watts) rating at least equal to the minimum output of the siren. The speakers shall be recessed in the front bumper.

3.8.7 Backup warning device. The fire truck shall be provided with an automatically activated, audible, pulsating, signaling warning device, mechanical or electrical, to caution personnel when fire truck is in reverse gear operation. The backup alarm signal shall be audible at a distance of 15 feet with self-adjusting volume that will maintain a minimum decibel output of 5 decibels above environmental noise.

3.8.8 Automatic transmission . The vehicle shall be provided with an automatic transmission of the fixed. ratio type and shall provide continuous drive . The transmission shall include a hydraulic torque converter and not less than four forward gear ratios. Normal driving range selector position shall provide not less than four gear ratios without movement of the selector. The maximum net input torque capacity of the transmission shall be higher than the

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

maximum net torque delivered by the engine. The transmission shall have a torque converter lockup feature in the two highest forward speeds. A means shall be provided to hold the truck transmission in the gear ratio used for pumping Operations whenever the pump transmission is in the pump position (see 3.10). Any modification to the transmission shall be made or approved by the transmission manufacturer.

3.8.8.1 Torque converter temperature gage A transmission torque converter oil temperature gage shall be furnished. The gage shall be installed on the pump operator's control panel and inside the cab (see 3.11.3), complete with a flashing red light and an audible warning device. The warning light and audible device shall be activated when the converter oil temperature exceeds the transmission manufacturer's recommended safe operating temperatures. The gage and warning light shall be suitably identified.

3.8.9 Drive line components. Drive line components shall have a continuous duty torque capacity of not less than the maximum torque delivered by the engine, as developed through the maximum gear train reduction. The drive line shall be dynamically balanced at a minimum of 500 rpm.

3.8.10 Axles. Axle ratings shall be at least equal to the load imposed on each axle, with the truck loaded to rated gvw. A single speed rear axle shall be furnished. The front axle hubs shall have an oil level view window.

3.8.11 Suspension. The truck's suspension system shall be equipped with components having a rated capacity at least equal to the load imposed on each member, measured at the ground, with the truck loaded to rated gvw. When suspension capacity is rated at the spring pads, unsprung weight shall be deducted. Double action, heavy-duty shock absorbers shall be provided at front wheels .

3.8.12 Wheels. rims. tires and tubes. The truck shall have single front and dual rear wheels. Rim and tire ratings shall conform to TRA/ETRO recommendations . Tires shall be steel belted radial tube or tubeless type with highway tread. All tires shall be of the same size and ply rating (load range). The rated individual tire capacity at 60 mph highway conditions shall be not less than maximum wheel loading imposed with the truck loaded to rated gvw, as cited in 3.8.1. Wheel and tire assemblies shall be dynamically balanced at simulated speeds up to 60 mph, each assembly shall be balanced individually.

3.8.12.1 Inner tubes . For tube tires, inner tubes shall be of heavy-duty type, and shall be of proper size for the tires furnished. Tire flaps shall be provided for tube type tires in accordance with TRA/ETRO recommendations.

3.8.12.2 spare wheel. When specified (see 6.2), a spare wheel or rim without spare tire shall be furnished and stowed in the hose bed for shipment.

3.8.13 Brakes Brakes shall conform to DoT Federal Motor Carrier Safety Regulations, Sections 393.40 through 393.42, 393.43, 393.45 through 393.52 and as specified herein.

3.8.13.1 service brakes. The service brakes shall be four wheel disk, automatic adjusting, air application type. Air filters shall prevent brake system contamination. Brake operation shall not be subject to excessive fading.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

Brakes shall be certified by the component manufacturer for GVW rating of the truck assembly.

3.8.13.1.1 Brake system air compressor. The capacity of the air compressor shall be sufficient for the intended service but shall be not less than 15.5 cubic feet per minute. The air compressor shall be equipped with a governor and the compressor intake shall be properly connected to an air cleaner. An air dryer shall be furnished and installed to remove moisture from the air. The moisture removed from the air by the air drying system shall be disposed of automatically and the moisture collector shall be winterized to prevent freezing.

3.8.13.1.2 Brake system air Storage reservoirs. In conformance with DoT requirements , air storage reservoirs with a buzzer-type low-pressure indicator and a safety relief valve shall be provided. The system shall be of the quick-release buildup valve type with the air compressor connected to a small reservoir which is pressure-relieved into the larger reseroirs when-the minimum pressure is reached for optimum operation of the brake-system. The time required to reach operational pressure from zero pressure shall not exceed 30 seconds. If other than brake air supply requirements are to be supplied from the reservoirs, a priority system shall be instilled to assure that an adequate supply of air is always available to operate the brake system. All wet tanks shall have an auto-moisture ejector.

3.8,13.2 Parking brakes. Parking brakes, conforming to DoT requirements, shall be provided. They shall be so mounted that they can be effective stall times . The operating controls of the parking brakes shall-be independent-mf the operating controls of the service brakes. A warning light in the cab shall indicate when the parking brake is on/applied. The parking brake shall be.. capable of meeting the performance requirements specified in paragraph 3.6.

3.8.13,3 Air brake emergencv system. An emergency brake system shall be furnished. The system shall be capable of being manually applied by the operator seated in the driver's seat. A manual or mechanical means co release the brakes shall be provided when compressed air is not available to release the brakes. The emergency system shall also serve as a parking brake and shall conform to DoT Federal Motor Carrier Safety Regulations, Sections 393.41 and 393.52.

3.8.13.4 Brake System air inlet. An air inlet valve and coupling shall be installed on the pump operator's control panel to allow an external air supply to be connected to the brake system.

3.8.14 Steering mechansm. The truck shall be equipped with a hydraulic power assist steering mechanism. The mechanism shall permit manual steering in the event of failure of the hydraulic system, and shall be properly effective at all truck speeds. The system shall be furnished complete with all necessary piping, valves, and accessories. The steering mechanism shall provide for controlling the direction of the fully loaded truck under all operating conditions . The cramping angle shall be the maximum permitted by the front axle manufacturer.

Source: https://assist.dla.mil -- Downloaded: 2026t0-20T13:15Z
Check the source to verify that this is the currentversion before use.

3.8.15 Front bumper and towing devices. " A heavy duty, full width, front bumper, and two hooks shall be provided at the front of the truck. The bumper shall be polished stainless steel. A stainless steel grab rail, not less than 12 inches long, shall be provided on the cab front not more than 4 inches below the windshield to facilitate personnel stepping up onto the extended bumper. The front bumper shall extend out not less than 18 in. to provide a step at the front of the cab/truck. A trough shall be provided in the center of the bumper for storage of not less than 150 feet of 1-1/2 inch double jacket fire hose. The space between the front bumper and cab shall be decked with heavy gage aluminum diamond plate. The two front tow hooks shall be mounted to the frame or rigid members which are attached to the frame. When access to the two front tow hooks are furnished through the front cab panel, access holes with hinged cover plates shall be provided. Two towing rings or comparable U-bolts, not less than 2-1/2 inch inside diameter, shall be provided at the rear of the truck and mounted directly to the chassis side rails.

3.9 Cab. The truck shall have a four (4) door fully enclosed cab. The cab roof shall have a removable weather-proofed section over the engine area to allow for engine and transmission removal without having to dismantle the cab. The rear outside wall shall be covered with aluminum treadplate. The engine compartment cover shall be insulated against heat and noise and allow for readily accessible engine maintenance, servicing and ventilation.

3.9.1 Cab construction. The cab shall be all aluminum, reinforced, welded construction. The cab interior width dimension shall be not less than 88 inches . With the driver's seat in the rearmost position, cab width shall be measured at the floor on a transverse line through a vertical plane, 6 inches forward of the driver's seat cushion. Aluminum sheet metal used in construction of the cab shall be at least .0.125 inch thick. The cab shall provide unobstructed seating and head room for a minimum of four persons fully clothed in firefighting gear. In the forward section of the cab, seats shall be provided for one passenger and a driver, and in the rear, two jump seats shall be furnished. The passenger seat is to be a jump seat designed to accommodate an air pack as described in 3.9.2. The cab doors shall be ample size for easy access and shall be equipped with roll-down windows and polished stainless steel 6 inch scuff plates at the bottom of each door. The doors shall be provided with locks and with at least the front curbside door equipped with an external key-operated lock. Grab handles shall be provided on each side of the fire truck at each cab door and inside the cab on the inside of the cab doors or at the end of the instrument panel. The outside grab handles shall be of a non-twist and nonslip design, polished stainless steel, and shall be not less than 1-1/4 inch id. A step shall be provided at each cab door and shall have an aluminum, nonslip tread surface. All steps shall sustain a minimum static load of 500 pounds without deformation and shall have skid-resistant surfaces. Each step shall be of maximum width and depth to permit safe entry and exit for firefighters wearing firefighting foot gear. The maximum stepping height of steps and platforms shall not exceed 18 inches with the exception of the ground to first step. Safety glass shall be provided throughout the cab. A dome light shall be provided in the front of the cab and above each jump seat in the rear. Each dome light shall have it's own individual switch. Lights installed in the door well\step area shall be activated when the door is opened along with the front dome light, Rubber boots shall be provided for all floor board openings. Directional reading/map lights, each with their own switch, shall be installed on the forward cab overhead. Dual padded sun visors shall be provided. Sound

Source: https://assist.dla.mil -- Downloaded: 20261O-20T13:15Z
Check the source to verify that this is the currentversion before use.

absorbing headliners and dashboard shall be provided. Cab floors and walkways shall be of heavy gage aluminum diamond plate. A full circular wheel well liner, with fenderette, shall "be furnished to protect against dirt and water entry. A rubber or flexible material mud flap of sufficient size shall be furnished at the rear of each wheel well liner to protect against the splashing entry of dirt and water. The cab compartment shall meet the interior noise criteria of DoT Federal Motor Carrier Safety Regulations, Section 393.94 and NFPA-1901.

3.9.2 Seats. All seats, front and rear, shall be upholstered over deep air foam cushions with first grade black vinyl covering, suitable for fire service. The driver's seat shall be a heavy-duty, four-way, adjustable air ride bucket type . The fire officer, passenger and the two rear facing seats (jump seats) shall be the Ziamatic Quick-Seat type and may be manufactured by the fire truck manufacturer. The fire officer/passenger seat shall not be less than 18 inches wide and at least 34 inches shall be provided for leg and knee room in the space measured from the front of the back rest, at the seat level, to the dash (instrument) panel. Each jump seat shall have a padded lower cushion of suitable width and depth to provide ample seating for firefighters wearing turn out gear and back strapped air packs. The back of each jump seat shall have an air breathing apparatus walk away bracket. The bracket shall provide for mounting of the air breathing apparatus in the upright position. A series of pre-drilled holes shall be provided in jump seat backs for vertical adjustment of walk away brackets. Each jump seat back shall be provided with padded flanges on each side and forward of the breathing apparatus. Retractable seat belts with shoulder straps shall be furnished and installed for the driver and for each seated position provided, and be of sufficient length to accommodate firemen wearing turn out gear. All passenger seats, front and rear, shall be equipped with head restraints. The rearward facing jump seats shall provide additional storage compartment(s) if available In the manufacturer's basic design. Mounting of the two jump seats in the rear section of the cab shall allow for breathing apparatus regulators.

3.9.3 Outside rearview mirrors. Outside reariew mirrors shall be mounted on each side of the cab, Combination (flat and convex) mirrors, secured by a common housing/support, shall be furnished. Each combination mirror shall have at least 50 square inches of flat reflective area and a convex surface having at least 20 square inches of reflective area.

3.9.4 Windshield wipers. Heavy-duty electric operated windshield wipers shall be mounted to facilitate clear vision. The wipers shall be of such capacity and coverage as to cleanse the windshield of rain, snow, ice, and agent when used in conjunction with the defrosting system or windshield washer mechanism. The wipers shall be the vet arm type. The wiper blades shall be of sufficient length to clear at least 75 percent of windshield area. Wiper assemblies shall include features to permit speed control and return of the wiper blades to a retracted position out of the line of vision when not in use.

3.9.5 Windshield washers. Power operated windshield washers, equipped with a minimum of l-gallon capacity plastic container for cleaning fluid, shall be furnished.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

3.9.6 Heater and defroster. The cab shall be equipped with a hot water type heater having fresh air intakes, and discharge outlets to the floor and side door windows, in both front and rear sections, and windshield defroster louvers. The heater shall be equipped with a 12V, electric-motor-driven multi-speed blower, controlled by a dash mounted, three-position switch. The heater shall not be positioned directly in front of any seat where it would interfere with the feet of the firefighters or in the space between the driver and the right side passenger seat.

3.9.6.1 Defrosting, anti-icing, and ventilating. A sufficient defrosting, anti-icing, and ventilating system shall be provided in the cab. This system shall have the capacity to effectively prevent formation of frost on the interior surface of all transparent areas of the cab and to prevent the formation of ice on the exterior of the vehicle windshield. The system shall also maintain clear vision over at least 75 percent of the area of all windows of the cab interior.

3.9.6.2 Controls. Variable controls shall be provided on air blowers and at least a high output setting shall be furnished on the cab heating system controls. Adequate operating instructions shall be provided at the heater system control point. The cab heater and defroster system control shall be mounted on the instrument panel.

3.9.7 Instrument panel. The cab instrument panel shall be complete with all equipment and accessories furnished as standard items by the manufacturer. The following minimum equipment shall be furnished and suitably identified:

a. Indirect panel lights (to illuminate all cab switches, instruments and controls).
b. Keyless starting switch and pilot light.
c. Ammeter.
d. Fuel gage.
e. Oil pressure gage with low pressure light and alarm.
f. Engine temperature gage with high temp. light/alarm.
g. Speedometer with recording odometer.
h. Tachometer.
i. Brake air pressure gage with warning light and alarm.
j. Brake quick buildup gage with warning light and alarm.
k. Plaster warning light control switch.
l. Indicator light for safe pumping mode.
m. Pump and engine hour meter.
n. Transmission temperature gage; high temp. light/alarm.

3.9.7.1 Audio/visual alarms. The following operating conditions shall be alarmed with both audio and visual alarm devices on the pump operator's panel and with individual visual and single audio alarms on the driver's instrument panel:

a. Fuel (less than 1/8 tank).
b. Loss of engine oil pressure.
c. Excessive engine coolant temperature.
d. Excessive pump transfer case temperature.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

3.9.8 Controls and operating mechanisms. All controls and operating mechanisms shall be located for left hand drive. Controls shall be complete and conveniently operable by the driver. Lever controls shall be designed and located to permit easy entrance and exit of operator, to and from driver's compartment. Instruments and controls shall be identified as to their function and installed in a manner to facilitate removal and servicing. Instrument controls and wiring thereto shall be incorporated into modular design panels and shall be removable by quick disconnects for ease of maintenance.

3.10 Fire Pump. The fire pump shall be fitted with a gear drive or chain drive transmission, shall be midship mounted, include provisions for a front suction intake, and driven by the truck engine from the output shaft of the road transmission. The pump transmission system shall provide means for pump and road operation. The pump shift shall be the manufacturer's standard electric or air shift, with a spring loaded cover guard over the control switch or lever. A manual override shall be provided to permit mechanical shifting in the event of electrical or air shift failure. The manual override control shall be located on the pump operator control panel, or within reach of the pump operator, and shall be suitably identified. A means shall be provided to assure that the pump transmission is held in the pump position during pumping operations and that when the pump transmission is in the pump position to cause the chassis transmission to be held in the proper ratio for pumping (see 3.8.8). A single stage pump of the centrifugal type shall be provided. The pump shall conform to NFPA-1901 requirements. An indicator light shall be mounted at the pump operator's panel and on the cab instrument panel, to indicate to the operator the pump control is properly engaged and it is safe to open the throttle and initiate -pumping mode. Controls for changing from road transmission to pump transmission shall be operable from the driver's position and shall be identified as to function. ControLs for single-stage pump operation shall be the manufacturer's standard and shall be operable from the fire pump operator's control panel. The impeller shaft shall be of corrosion-resistant steel. The fire pump shall have the manufacturer's standard cast iron casing. The pump drive, gearing, and housing shall be such that at rated capacity and pressure, the temperature rise in the gear oil will not exceed the maximum temperature recommended by the pump manufacturer for continuous operation in an ambient temperature of 125° F. When required, oil cooling shall be provided by a water jacket or cooling coils in the gear case constructed so as not to be damaged by freezing. All shafts in the pump gear train shall turn in anti-friction bearings, except that the impeller shaft shall be provided with a minimum of two inboard anti-friction bearings and an outboard bearing of either the anti-friction or oil/water lubricated sleeve type, All pump-shaft glands or mechanical seals shall be adequate for service under operating conditions specified herein. The pump shall withstand a hydrostatic pressure of 350 pound-force per square inch (psig) for a period of 10 minutes. Push-pull type drain cocks, accessible at the pump operator's position and arranged so that the open and closed position is clearly indicated, shall be provided to drain the pump and all water carrying lines. Drain cocks shall be of the water service type and shall be equipped with positive stops. Pump drain lines shall be furnished and shall discharge to the ground at a point not above the bottom of the chassis frame. All threaded connections shall conform to FED-STD-H28. The pump, when drafting at a minimum lift of 10 feet through 20 feet of 5-inch suction hose, shall:

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

a. Deliver a minimum of 1,000 gpm at 150 psig net pump pressure at less than the manufacturer's recommended governed speed of the engine.
b. Deliver a minimum of 700 gpm at 200 psig net pump pressure at less than the manufacturer's recommended maximum governed speed of the engine.
c. Deliver a minimum of 500 gpm at 250 psig net pump pressure at less than the manufacturer's recommended maximum governed speed of the engine.
d. The pump, when dry, shall take suction and discharge water within 30 seconds, with a lift of 10 feet through 20 feet of 5-inch suction hose.

The piping and valve arrangement shall be capable of delivering water to the pump at a minimum 500 gpm flow rate, while pumping at 150 psi net pressure.

3.10.1 Priming pump. The priming pump shall be of the rotary type, 12 VDC motor driven, complete with lubricating oil reservoir and necessary valves, operated from the pump control panel. The priming pump shall develop a vacuum of 22 inches of mercury (Hg) at an altitude of 1,000 feet above sea level in not more than 30 seconds.

3.10.2 Suction connections. The fire truck shall be provided with four suction connections. Each suction connection shall be equipped with a removable and accessible strainer. One 5-inch suction connection shall be located at the operator's control panel and one 5-inch connection directly opposite the operator's control panel on the curbside of the truck and one 5-inch connection on the right rear of the truck. One 2-1/2-inch suction connection shall be located on the fire pump operator's control panel. A quarter-turn butterfly type suction valve-shall be installed in the five (5) inch rear suction and controlled by a chrome plated hand wheel at the pump panel. The 5-inch suction connection on the left and right side and the suction valve on the rear of the truck shall provide a seat for suction hose connection hose gaskets and shall be threaded with American National standard hose coupling screw thread (NH). The 2-1/2-inch suction connection shall be gated and shall be a female swivel type with gasket, and equipped with a chromium plated rocker lug plug. The 2-1/2-inch suction connection shall be provided with a 3/4-inch drain valve and push-pull type controls. Valves shall be capable of being locked in any position and handles shall be provided. The valves shall be capable of holding 500 psi in either direction. The valve balls shall be trunnion mounted, corrosion-resistant, nonsticking type. The valve seats shall not require adjustment and shall be capable of holding a vacuum or pressure in either direction. The valve ball and seats shall be replaceable without disturbing the valve piping. The 2-1/2-inch suction valve shall be properly identified as to function and indicate when open or Closed. An adjustable 2-1\2-inch or larger intake pressure relief system shall be permanently installed (per NFPA-1901). Shutoff valves or other means to disable the relief system shall not be permitted.

3.10.3 Discharge connections. The fire truck shall be provided with eleven bronze gated locking type discharge connections. Each discharge connection shall provide a seat for discharge gaskets and shall be threaded with NH threads. Each 2-1/2-inch discharge connection shall be provided with a rocker lug and chromium plated cap with gasket, chained to the valve body. Each discharge connection shall be provided with hose discharge digital flow meters

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

on the fire pump operator's control panel. Two 2-1/2-inch discharge connections shall be located on the fire pump operator's control panel, and two 2-1/2-inch discharge connections shall be located directly opposite on the curbside of the fire truck along with one 5 inch discharge connection. The 5 inch connection shall be piped with a gated 4 inch pipe and controlled by a chrome plated handwheel at the pump operator's control panel. One 2-1/2-inch discharge connection shall be located at the left rear (driver's side) of the truck, below the hose bed. Three l-l\2-inch swivel type discharge connections shall be located in the transverse hose beds (see 3.11.2) and one l-l/2-inch swivel discharge connection shall be located on the front bumper. One discharge connection shall be provided to the monitor (deluge gun) turret with appropriate piping to flow 1,250 gpm. Each discharge valve shall be the pump manufacturer's recommended valves. The valves shall be capable of holding 500 psi in either direction. The valve balls shall be the trunnion mounted, corrosion-resistant, nonsticking type. The valve seats shall not require adjustment and shall be capable of holding a vacuum or pressure in either direction. The valve ball and seats shall be replaceable without disturbing the valve piping. Each discharge connection shall be provided with a drain valve of at least 3/4 inch id for draining hose lines with the pump discharge gates closed. The push-pull type valves shall be of the water service type and shall be equipped with positive stops . Drain valve controls shall be located at the bottom of the control panel directly above the running board. Drain lines shall be concealed behind the pump compartment panels and shall discharge to the ground at a point below the bottom of the chassis frame. Each discharge connection, flow meter and drain(s) shall be identified by a related numbering system as well as function. Five, 30° or 45° downward turn male end discharge gates, shall be provided in lieu of straight connection discharge gates, on the 2-1/2-inch discharge connections. Two l-1/2-inch or larger outlets supplied by at least 2-inch piping and valving for preconnected hose lines-shall be provided at the location of the hose storage area.

3.10.4 Relief valve. An automatic relief valve shall be provided for controlling the pressure from all outlets. The locating of the relief valve control shall be such that adjustment can readily be made by the operator when standing in normal position, without the use of tools, and in full view of the discharge pressure gage. The relief valve shall be of such design that when set 10 psi higher than the pump working pressure, there will not be an increase in pump Pressure greater than 30 psi when discharge lines are shut slowly. The relief valve shall perform satisfactorily when pumping rated capacity at any pump working pressure over 75 psi. A relief valve drain shall be provided and shall be in a readily accessible location. The relief valve drain line shall discharge to the ground at a point not above the bottom of the chassis frame.

3.11 Body The fire truck shall be equipped with a body which shall incorporate a fire pump compartment, fire pump operator's control panel, removable water tank, three transverse hose beds, main hose bed, equipment compartments, rear platform, foam equipment, and firefighting equipment. The body and compartment construction structural members shall be aluminum alloy having not less than 42,000 psi ultimate strength and 35,000 psi yield strength with thickness of not less than 0.125 inch. The body side panels and beavertail shall be integral. The body shall be reinforced at all stress concentration points where equipment and compartments are attached. Wheel well liners, with fenderettes and mud flaps, shall be furnished (front and rear) to protect

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T13:15Z
Check the source to verify that this is the currentversion before use.

against dirt and water entry. The body shall be of all welded construction and not exceed 96 inches in width.

3.11.1 Fire pump and foam tank compartment. The fire pump and foam tank shall be enclosed in an aluminum compartment at the forward section of the body and shall be self-supporting from the truck frame. An enclosure shall be provided to protect the back side of the instruments on the pump panel. This section shall have a hinged top, latch with operating handle or wing nuts for easy access, and a means of holding the panel section in a horizontal position when open for inspection. If the tank is positioned over the pump, the tank and tank supports must be removable to allow lifting of the pump intact without removing more than the pump suction and discharge fittings. The sides of the pump compartment shall be the same height as the sides of the main hose bed specified in 3.11.5. Provisions for a vertical water supply line to the monitor shall be provided on the centerline of the truck. A removable deck plate (in equally divided sections) shall be provided over the pump compartment and shall be designed to support a 500 lb load plus the monitor assembly with its related operational forces during agent flow. An opening in this deck plate shall be provided for a vertical water supply line to the monitor. An adequate opening in the decking shall be provided for external filling of the foam tank from 5 gallon foam containers. This opening to have a secured, but readily removable cover. The passenger or curbside panel of the pump compartment shall extend vertically from the running board to the bottom edge of the transverse hose bed and horizontally from the cab step rearward to the forward edge of the curbside compartment. This panel shall be removable and constructed of scratch and glare resistant black vinyl material and shall not be painted.

3.11.1.1 Monitor. A monitor (deluge gun) shall be furnished and mounted on the platform area above the pump-compartment and connected to the pump by a... water supply line through the platform floor. A gasketed mating flange fitting shall be furnished at the base of the monitor and at the top of the water supply line at the platform floor to permit ease of monitor removal. A cradle with a quick release fastening device shall be provided to securely hold the nozzle end of the monitor when stowed. The monitor shall be positioned on the centerline of the fire truck and shall be capable of flowing 1,200 gpm. The monitor shall have a non-slip coated handle to facilitate operation of the monitor turret. The water supply valve to the monitor shall be a gear operated handwheel and shall have a waterway equal to the inside diameter of the monitor’s inlet piping. Liquid filled pressure gages shall be provided at the nozzle and on the pump operator’s panel. The pressure gage to be provided at the nozzle shall be the manufacturer’s standard gage. A separate stream shaper or discharge pipe of not less than 15 inches in length with a 2-1/2-inch male and female NH threads connection for use with stacked tips shall be furnished. Stacking type tips, 2-inch, l-3/4-inch and l-1/2-inch shall be furnished. The stream shaper and stacked tips shall be made of lightweight material. The monitor (deluge gun) and non-chromed components of the monitor shall be painted the same color as the truck . The monitor shall be provided with a pressure gage at the pump operator’s panel.

3.11.2 Transverse hose beds. Three transverse hose beds shall be provided side by side forward of main hose bed, no higher than 48 inches above the running board. Each bed shall have the capacity of stowing not less than 200 feet of l-3./2-inch double jacketed, polyester rubber lined fire hose. Each hose bed shall have hose payout openings on the streetside and the curbside of the

Source: https://assist.dla.mil -- Downloaded: 20260-20T13:15Z
Check the source to verify that this is the current version before use.

truck. The length of each transverse hose bed shall be full width of the pump compartment. The transverse hose beds shall be constructed of aluminum and shall have a sub-floor made from removable slatted aluminum. Each hose bed shall be provided with a center mount 1-1/2-inch swivel type discharge connection to permit hose to be removed from either side of the truck. There shall be adequate clearance for making connections to the swivel discharge outlets. Discharge gate controls for each hose bed shall be located at the pump operator's control panel and shall be suitably identified. All hose payout openings shall be fitted with l-1/4-inch polished stainless steel hose rollers on the bottom and sides of the openings. Plumbing to each hose bed shall be a minimum of 2 inch hard pipe with adequate drains provided for each.

3.11.3 Fire pump operator's control panel The truck shall be equipped with a fire pump operator's control panel located on the road/driver's side of the truck. The pump operator's control panel shall be removable and constructed of scratch and glare resistant black vinyl material and shall not be painted. Master pump intake and pump discharge gages shall be provided and located close to each other with the intake gage to the left of the pump discharge gage. The gages shall be the silicone liquid filled type, a minimum of 4-1/2-inches in diameter, with a range between 30 inches Hg vacuum to not less than 400 psi. The accuracy of the gages shall be a minimum of Grade 1A per ANSI B40.1. Al 1 valve opening handles and other controls shall be operable by personnel wearing heavy gloves. All extended controls and handles shall be non-interferting and firmly supported. The panel shall include at least the following:

a. Pump discharge gage; 30 inches Hg (vacuum) to 400 psi.
b. Pump intake gage; 30 inches Hg (vacuum) to 400 psi.
c. Engine tachometer; not less than 3,500 rpm range with a provision in the panel to allow checking accuracy with a test revolution counter.
d. Throttle, pull type with latch and micro-adjustment.
e. Relief valve control.
f. All pump discharge valve controls.
g Tank suction valve control.
h. Primer pump control.
i. Illumination; Minimum of 3 -non-glare lights with 1 light being energized as the pump is engaged.
j. Engine coolant temperature gage.
k. Engine oil pressure gage and low oil warning device.
1. Heat exchanger valve control.
m. Eleven digital flow meters; meters shall be approved for fire service application and located near their respective control handles on the pump panel.
n. Water tank level gage; Electronic type.
o. All other pump panel mounted drains and controls mentioned herein.
P. Discharge valve and throttle handles shall be of black, extreme temperature resisting plastic or brass. All gage rims and other exposed metal shall be chromium plated.
q. Plugged l/4-inch standard pipe connection(s) with pipe or tubing for connection of vacuum and pressure test gage(s) for testing pump pressure and suction gages.
r. Instruction plates as specified in 3.16.
s. Foam system controls and valves specified in 3.11.7 through 3.11.7.4.
t. Torque converter temperature gage, warning light, and audible warning &vice.

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T13:15Z
Check the source to verify that this is the currentversion before use.

u. Indicator light for safe pumping mode.
v. Foam tank level indicator; electronic multiple light type.
w. Water tank fill valve.

All controls, valves, drains, and pressure gauges shall be identified as to their function and shall have a related identification number. All instruments and switches shall be identified as to their function. All identification plates shall be provided with lettering as large as possible and practical.

3.11,4 Water tank. A removable water tank of not less than 750-gallon capacity shall be provided at the rear of the fire pump compartment. The water tank shall not extend beyond the main hose bed sides. The water tank shall be constructed of 10 gauge (0.134 in.) mild steel and shall have double welded (external and internal) seams. The interior surfaces of the tank shall be cleaned by abrasive blasting (glass beaded) to provide the highest degree of cleanliness to accept epoxy coating. The interior surface shall be further prepared with an epoxy primer with a final two coat system of two or three part epoxy resin. The total film thickness of primer and finish epoxy coats shall be the thickness necessary for protection from corrosion deterioration of the interior surface of the tank throughout it's specified life (10 yrs.). The water tank shall be provided with a sacrificial anode system to neutralize the water condition and to protect the tank against corrosion. The water tank shall be the horizontal type with a flat top and a flat bottom, with a sump, and mounted on the truck frame as specified in paragraph 3.11.4.3. The tank top shall be removable, with gasket to prevent leakage, and shall support not less than 200 lb per square foot of surface area. A longitudinal and transverse surge partition shall be provided in the tank. A 2-1/2-inch NST connection shall be provided at the pump panel and piped directly to the tank by a l-1/2-inch diameter pipe for use as a direct supply connectiom, and shall enter the tank or be piped inside the tank so as to not cause cavitation in the tank during pump discharge. A 1-inch tank fill and re-circulating line, properly valve d, shall be provided from the pump discharge directly to the water tank. The tank drain shall be located at the low point of the tank to provide complete drainage and the drain control valve shall be operated/controlled from the pump panel. The water tank drain shall discharge directly to the ground at a point below the bottom of the chassis frame. The tank shall have a nonsplash combination overflow and vent pipe of not less than 4-inch National Pipe Size, directed to the ground at the rear of the rear axle, and extending below the bottom of the truck frame. The tank shall have a warranty for 10 years.

3.11.4.1 Tank filler opening. The tank shall have an accessibly located filler opening not less than 5 inches id and shall be provided with a tight, gasketed, hinged cap. The tank fill opening shall be provided with a removable strainer. The tank filler opening shall not project above the height of the side body sheet metal panels.

3.11.4.2 tank piping. The piping from the tank to the fire pump, unless made of corrosion-resistant metal, shall be galvanized. The pipeline diameter between the tank and the pump shall be 3 inches to permit a flow rate of 500 gpm and shall incorporate a flexible, reinforced, noncollapsible connection(s) to take up any vibration. The tank piping shall provide for discharging the water in the tank through the fire pump discharge manifold. A quick-opening shutoff valve shall be provided with the control extended to the operator's control panel and a drain valve, located at the lowest point, with the control extended

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T13:15Z
Check the source to verify that this is the currentversion before use.

to the operator's control panel. The tank suction pipeline, valves, tank fill lines , and fittings shall withstand not less than 150 psi working pressure.

3.11.4.3 Tank mounting. The tank shall be supported on sills to cushion shock and transfer the load to the truck frame. The tank shall be so mounted and attached to the chassis that it can be removed without removing the truck body . The tank mounting device shall be designed as to allow for frame flexing without transferring stress forces to the water tank.

3.11.5 Main hose bed. The hose bed shall be provided with sufficient capacity for stowing not less than 1,200 feet of 3-inch and 800 feet of 2-1/2-inch double gasketed, polyester, rubber lined, lightweight fire hose. The overall hose bed shall be subdivided lengthwise with aluminum partitions to form four separate hose beds as follows: one permanent aluminum partition to form a hose bed 4 5/8 inches wide located on the left/driver's side and the remaining area is to be subdivided into three hose storage areas by use of two adjustable partitions, Body panels and partitions shall be of the same height. The compartment body and partitions shall be reinforced so as to offer no obstruction to paying out or loading of hose. The hose bed floor shall be removable slatted aluminum. The interior of the hose bed shall be free from all projecting nuts, sharp angles, or brackets. Exposed bolt or rivet heads shall be of the oval type. The equipment holders shall be planned so as not to obstruct the loading or removal of fire hose.

3.11.6 Equipment comparments. All equipment compartments specified herein shall be made of aluminum with a minimum thickness of 0.090 inch, except when noted otherwise. Compartment doors shall be reinforced for strength and rigidity and be the flush-lap type. Stainless steel door handles shall be recessed in the door and shall be the " D" type handle construction operable with heavy gloved hands. All equipment compartments shall be designed for storage of items that require exposure protection from water and dirt. The doors shall be attached with full-length stainless steel piano hinges (hinges are not to be painted). The doors shall be heavy-duty, reinforced, double panel type with exterior plate thickness to be not less than 0.090-inch aluminum, and the interior door panel to be constructed of not less than 0.090-inch aluminum. The compartment doors shall be fully gasketed with heat resistant, neoprene sponge type material to insure a watertight seal. The doors shall be equipped with a Cleveland style stainless steel spring type door hold open device that will limit door opening but allow for easy one hand release for closure. Door catches and latches shall be heavy-duty type and shall be corrosion-resistant. Each compartment shall be illuminated. The compartment lights shall be controlled by a master control switch with an indicator light, located on the pump instrument panel. Each compartment light shall have it's own individual door switch that will energize the light when the door is opened. A red flashing warning light shall be mounted on the forward area of the cab overhead to warn the driver if there is any compartment door open or ajar. Electrical comections/connection blocks located inside compartments shall have insulation protection against contact with items stored within the compartments. Provisions shall be incorporated into the compartment design to permit flushing and cleaning of the inside. Design of the compartment shall prevent entry of dirt and water with doors closed. Drip rails shall be provided over each compartment to allow water run-off to be directed away from door tops and sides- Compartment space shall not be compromised to accommodate piping/plumbing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

3.11.6.1 Side equipment compartments. Equipment compartments shall be provided on each side of the body, front and rear of the wheelhousing, approximately flush with the running boards and the wheel skirting. The width of the front side compartment shall be not less than 20 inches. The width of the rear side compartment shall be not less than 24 inches. The height of the front and rear compartments shall be from the running board to the top of the wheelhousing, but shall not be less than 24 inches. Two additional compartments, one on each side forward of the fire pump, shall be provided. These two compartments shall be a minimum of 20 inches wide and as high and deep as practical, with removable back panels to allow access to the pump and transmission. Each compartment, except for the generator compartment, shall be provided with an adjustable shelf located midway between the top and bottom of the compartment. The adjustable shelves shall have an upturned lip of not less than 3/4 inch at the front of the shelf. The left rear (driver's side) compartment shall be for the location of the auxiliary generator. The auxiliary generator compartment shall be ventilated and the method of ventilation shall not allow water or dirt to enter the compartment. The curbside compartment and wheelhousing tops shall be a continuous heavy-duty aluminum diamond plate surface, the same as furnished for the running boards and rear platform surfaces. An additional compartment shall be added above and forward of the rear tail board compartment and half step. This compartment will be approximately 43″ wide by 13″ high by 11″ deep with a door opening of approximately 38″ by 10″. The door will be hinged at the bottom.

3.11.6.2 Air Rack compartments. Two compartments shall be provided on the driver's side of the truck over the side equipment compartments and wheel well. The front compartment shall have two brackets, mounted as far forward as possible, for securing two complete breathing units (self-contained breathing equipment) . The brackets shall be identical to the brackets used on the back of the jump seats (see para, 3.9.2). Each compartment shall be provided with a door hinged at the top. The compartments shall be the same length as the side body equipment compartments (not less than 100 inches in length). The depth of the compartments shall be not less than 12 inches and shall be the same height as the hose bed (approximately 28 inches). The doors shall be extra heavy-duty and reinforced with cross bracing, and shall be the flush-lap type door. The top hinges of the doors shall be full length stainless steel and shall not be painted. The doors shall have polished stainless steel recessed "D" type handles operable with heavy gloved hands. Doors shall be of the slam shut design, controlled by an over-center, counter balanced spring of the Cleveland style for opening and closing. The compartment top shall be of the heavy-duty aluminum diamond plate surface, the same as furnished for running boards and rear platform surfaces. Two additional spare air bottle compartments shall be installed on each side, one forward and one aft of both rear wheel wells. Each compartment shall have room for one spare air bottle and have a latching flush-lap type door.

3.11.6.3 Rear equipment coumpartments. An equipment compartment with two equal sections shall be provided at the rear of the truck, located on the centerline of the truck, forward of the rear platform. The center rear compartment shall be the same height and depth as the side equipment compartment, with the width fully utilizing the space available between the two rear side compartments (see 3,11.6.1). Each section of the compartment shall be provided with a door designed and constructed as specified in 3.11,6, The top of each rear equipment compartment shall serve as a step which shall have a

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

minimum depth of 6 inches and shall extend the full width of the hose bed. The step shall be covered with heavy-duty aluminum diamond plate. The entire rear area, from the hose bed down to the tailboard platform, shall be covered with heavy-duty aluminum diamond plate. The additional rear compartment, located above the half step shall be provided as described in 3.11.6.1.

3.11.6.4 Engine enclosure. A rectangular shaped, insulated engine 'enclosure constructed of aluminum shall be provided. The enclosure shall be constructed of heavy-duty diamond plate. Access doors or a tilt back hood cover shall be furnished to facilitate engine maintenance, service and repair. When hood panels are provided, they shall be top hinged, fabricated of aluminum diamond plate and fitted with full-length stainless steel hinges. Two work lights with integral switches shall be furnished, one for each side of the engine compartment.

3.11.7 Foam Equipment. The fire truck shall be provided with foam equipment as specified herein. The foam system shall be suitable for operation with AFFF, conforming to MIL-F-24385. The system shall be capable of discharging a foam solution of from 1 to 6 percent (-0/+1.0 percent) at all pump discharge outlets up to 500 gpm.

3.11.7.1 Form proportioner The foam proportioned shall be of the direct injection type meeting all applicable requirements of the NFPA-1901. The AFFF concentrate shall be inducted by venturi action into a line carrying a portion of the solution from the fire pump intake and shall mix with the main water flow. A metering valve shall be provided in the foam liquid line leading into the venturi for controlling the amount of foam liquid entering the venturi. The foam liquid metering valve shall be calibrated and provided with a dial and pointer to regulate the proportioning to discharge percentage of foam liquid to total solution. The dial and pointer shall not be on the bottom of the foam metering valve. The metering valve shall have provisions for adjustments in the field to accommodate for a 1 to 6 percent foam solution.

3.11.7.2 Foam controls. All controls for operating the foam system shall be chrome plated, grouped together, readily accessible to the operator and located on the fire pump operator's control panel. A foam metering chart reflecting visible settings from 0-500 gpm shall be provided and shall be mounted on the pump operator's control panel adjacent to the foam metering control device.

3.11.7.3 Foam liquid tank. A removable commercially available 100-gallon minimum capacity foam liquid tank shall be provided. The foam liquid tank shall be constructed of 12 gauge stainless steel. The foam liquid tank shall be located in the pump compartment above the pump. A 1-1/2-inch drain, with discharge at a point below the bottom of the truck frame and equipped with a valve control extended to the fire pump operator's control panel, shall be provided. Adequate provisions shall be made for filling the foam tank directly from individual 5-gallon containers. The tank configuration and positioning shall provide for liquid level monitoring by dipstick through a filler hole or an additional capped hole in the top of the tank. A dipstick, accurately marked and calibrated shall be provided for checking the foam level. Stowage for the dipstick shall be provided near the foam tank. The tank shall have the filler opening located as not to interfere with monitor operation, and shall be provided with a tight, gasketed, hinged cap, having a spring type holddown catch. A removable strainer of not greater than No. 4 stainless steel mesh

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

shall be provided in the tank fill opening to prevent entry of foreign matter. The foam tank shall include a minimum l-inch vent that will not permit spillage of foam when the truck is operated to verify performance requirements of paragraph 3.6 or when cornering the truck on a 90° turn both left and right, and the outlet shall be designed to prevent vortexing.

3.11.7.4 Foam system piping. All fittings, valves, and piping shall be of material that is fully compatible with the AFFF concentrate, water and their admixtures. Quarter-turn ball valves shall be installed between the foam tank and metering valve and between the fire pump discharge and the eductor. A ball check valve shall be installed between the eductor and metering valve to prevent flow of water into the foam tank. A horizontal swing check valve shall be installed in the water tank suction line to prevent entry of foam solution into the water tank.

3.11.8 Rear Platform and running boards. The fire truck shall be provided with a rear platform and running boards. Construction of the rear platform shall utilize the beavertail design. The beavertail shall be an integral part of the body side panels. The rear platform shall have a load-carrying capacity of not less than 700 lbs. The rear platform length shall be equal to the width of the truck and not less than 18 inches in depth. The rear platform shall have rounded corners, and shall have a rear downward flange of at least 2 inches. The side running boards shall extend from the rear of the cab to the side equipment compartments and extend out to a point flush with the truck body and be equipped with 6 inch high scuff plates all around. Each running board shall have a load-carrying capacity of not less than 500 lbs. The rear platform and running boards shall have aluminum nonslip tread surfaces. The running boards and rear platform shall be located on the same horizontal plane of the truck cab and body. The rear platform and running boards shall be 22 inches. (+2 or -2 inches) above ground level, with the truck loaded as specified in 3.8.1.

3.11.9 Handrails and grab rails. The rear platform shall be provided with two vertical grab rails, one at each side, to assist personnel in climbing onto the rear platform. A horizontal handrail shall be provided not more than 6 inches forward of the rear end of the hose bed and not more than 72 inches above the rear platform. A handrail shall be provided at the top of the right and left sides over the pump compartment and shall be the length of the pump compartment. The handrails and grab rails shall be l-1/4-inch maximum diameter chromium plated brass or chromium plated steel. The handrails and grab rails shall be of the non-twist type and be provided with non-slip protection.

3.11.10 Personnel Steps. Personnel steps, in accordance with NFPA-1901, shall be provided to assist personnel in gaining access to various firefighting body components. As a minimum, steps shall be provided on the fomard end of the body, mounted on each side of the truck. Also, steps shall be provided at the rear of the truck, inboard of the beavertail, on each side of the rear platform for access to the hose bed. 'The maximum stepping height shall not exceed 18 inches with the exception of the ground to the first step. All steps shall sustain a static load of 500 lb. and have skid-resistant surfaces, have a minimum area of 35 sq. in. and be arranged to provide a minimum 8 inch clearance between the front of the step and any obstruction.

3.11.11 Fire truek equimwnt. The following fire truck equipment shall be provided:

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

a. Two lengths of 5-inch hard suction hose, each 10 feet long, with 5-inch NH long handle couplers on female ends; and 5-inch NH rocker lug couplers on male ends. The suction hose shall conform to the requirements of NFPA-1901. The couplers shall be made of lightweight material. The hard suction hose shall be packaged securely and shipped to the consignee with the truck.
b. One 5-inch suction strainer, cylindrical, corrosion-resistant type, with NH female coupling. The suction strainer shall be made of lightweight material.
c. Quick-release fastening devices shall be provided on the right (curbside) of the truck, above the wheel well to securely mount the following complement of ladders and pike pole. All ladders shall conform to NFPA-1931 and shall be of aluminum alloy.

(1) One 10-foot folding attic ladder.
(2) One 12-foot roof ladder with folding hooks.
(3) One 28-foot, three section tongue and groove constructed ladder with a closed length not to exceed 15 feet.
(4) One 10-foot fiberglass pike pole.

3.12 Cleaning treatment and painting. All fire truck surfaces shall be cleaned and treated in accordance with MIL-T-704, Type A. The surfaces to be painted shall have a primer applied to a dry film thiclmess of 1.5-2.5 nils. The primer used shall be compatible with the final paint system. The finish paint shall be polyurethane enamel or equal, applied co a dry film thickness of not less than 2.5 roils. The finish color shall be Lime Yellow, number 13670 of FED-STD-595 and shall be applied to the exterior surfaces of the truck cab, chassis, body and hose beds. The roof and upper part of the cab, down to a line at the botom of the windshield. shall be painted White.,. color chip No. 17886 of Federal Standard 595. A white reflective glow, horizontal “accent” band 10 inches wide, shall be installed along the sides, the full length of the truck and in a plane with the headlights, The reflective band shall also be installed across the front of the cab if there is no metal trim installed. The interior surface of equipment compartments shall be painted with Spatter type paint to reduce problems in repainting due to chipping from equipment storage. Running boards , compartment tops, steps, rear platform, scuff plates, and engine cover shall be bright, unpainted aluminum. The cab interior shall be primed and finish painted with two coats of Black Wrinkle paint. The disk wheels shall be painted the same as the exterior color. Rims , tire locking rings and lugnuts, treated with permaplate or other similar corrosion-resistant treatment, need not be painted.

3.13 RustProofing. The fire truck cab, frame, wheel wells, and all exposed body components shall be protected against rust and oxidation in accordance with FED-STD-297.

3.14 Identification plate. Identification plates shall be furnished as specified in the procurement document for each fire tuck. The contractor shall stamp all the necessary data in the blank spaces provided for that purpose and securely affix the plate to each fire truck on the forward inside wall of the cab, with nonferrous screws or bolts not less than 1/8” id. The following nomenclature shall be stamped on the identification plate: “ TRUCK, FIREFIGHTING, 1,000 GPM, 4 X 2.”

Source: https://assist.dla.mil -- Downloaded: 2026t0-20T13:15Z
Check the source to verify that this is the currentversion before use.

3.15 Identification marking. Identification markings and registration numbers for the fire truck shall be in accordance with MIL-STD-1223, as specified for the Navy. When the rear body surface warrants, the USN may be affixed upon a plate of sufficient size and attached to the raised license plate mounts.

3.16 Instruction plates. Plates shall be of nonferrous base alloy metal or stainless steel and secured to the truck with screws or rivets. The following plates shall be provided:

a. A plate indicating the fire pump delivery rate in gpm at 150, 200, and 250 psig pressure, with manufacturer's specified engine speeds, shall be affixed to the fire pump operator's control panel.
b. All pumping controls, valves, instruments, and such fire truck operating controls shall be provided with suitable instruction plates conspicuously marked to identify the lubricants and their temperature range.

3,17 Lubrication. Means for lubrication shall be in accordance with the manufacturer's standard practice. The lubricating points shall be easily visible and accessible. Hydraulic lubrication fittings shall be in accordance with SAE J534. Where use of high pressure lubricating equipment, 1,000 pound-force per square inch (psi) or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the truck in a conspicuous location.

3.18 Servicing and adjusting. Prior to acceptance of the truck by the Government, the contractor shall service and adjust the truck for immediate operational use as required in the operator's manual. The servicing and adjusting shall include at least the following:

a. Inflation of all tires.
b. Adjustment of brakes.
c. Proper functioning of all lighting and electrical systems.
d. Wheel alignment.
e. Adjustment of engine to include tune-up.
f. Complete lubrication with grades of lubricants recommended for ambient temperature at the delivery point.
g. Cooling system filled to capacity with a clean solution of equal parts by volume of water and antifreeze (ethylene glycol).

3.19 Workmanship.

3.19.1 metal fabdication. The metals used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the metal to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.19.2 Bolted connections. Bolt holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice and all bolts, nuts and screws shall be tight.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

3.19.3 Riveted cormections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes and in full contact with the surface of the member.

3.19.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.19.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping or any other defect which reduces the castings ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection and test requirements, and will provide all test instruments and test site locations as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to ensure supplies and services conform to prescribed requirements.

4.1.1 Responsibility for compliance. All items must meet all requirements of sections 3 and 5. The inspection set forth in this specification shall become a part of the contractor's overall inspection system or quality program. The absence of any inspection requirements in the specification shall not relieve the contractor of the responsibility of ensuring that all products or supplies submitted to the Government for acceptance comply with all requirements of the contract. Sampling inspection, as part of manufacturing operations, is an acceptable practice to ascertain conformance to requirements, however, this does not authorize submission of known defective material, either indicated or actual , nor does it commit the Government to accept defective material.

4.1.2 Component and material inspection. Components and materials shall be inspected in accordance with all the requirements specified herein and in applicable referenced documents.

4.2 Classification of inspections . The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

4.2.1 First artitle inspection. The first article inspection shall be performed on one truck when a first article is required (see 3.2, 6.2, and 6.4), This inspection shall Include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory, provided the item meets the requirements of the specification and is representative of the design, construction and manufacturing technique applicable to the remaining trucks to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall be performed as specified herein. This inspection shall include the examination of 4.3, the tests of 4.5 and the packaging inspection of 4.6.

4.3 Examination. Each truck shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. When a first article is required, the first article shall be tested as specified in 4.4.1 through 4.4.4. The first article tests shall be performed by the contractor under the direction, and In the presence of Government representatives, and documented in accordance with DD Form 1423 requirement. Failure to pass any phase of the required tests shall be cause for rejection.

4.4.1 Operational tests. The fire truck shall be loaded as specified in 3.8.1 and operated to verify performance requirements of 3.6 a. through 3.6 h. During these tests, the functioning of the engine, power train, brakes, steering, truck and body lighting systems, controls and instruments shall be observed for effective operation. A load distribution test shall be conducted to determine that the percentage of gvw at the front axle complies with 3.8.1. The steering mechanism shall be tested to verify conformance to the requirements of 3.8.14.

4.4.2 Fire Pump tests, All tests specified in paragraphs 4.4.2.1 through 4.4.3.1 shall have all test results recorded on the APPARATUS PUMP/SERVICE TEST REPORT form (see page 39) with one copy included as part of First Article Test Report and one copy included with the fire truck manuals,

4.4.2.1 Pressure tests. The pump shall be tested hydrostatically at a pressure of 350 psig for 10 minutes to determine conformance to 3.10. The pump pressure tests may be performed by the pump manufacturer prior to installation on the truck.

4.4.2.2 Run-in test. A 2-hour run-in test shall be performed by the pump manufacturer in accordance with NFPA 1901.

4.4.2.3 Capacity and comporient test, Tests shall be conducted by the truck manufacturer in accordance with the test procedures of NPFA 1901. All tests

Source: https://assist.dla.mil -- Downloaded: 2026t0-20T13:15Z
Check the source to verify that this is the currentversion before use.

and roughness * Repeat readings Total thickness of

shall be performed with calibrated instruments. Copies of calibration certificates shall be included with the test report. The following tests shall be performed:

a. A vacuum test, using the priming pump, with a capped suction at least 20 feet long, shall develop 22 inches of vacuum and hold the vacuum with a drop of not more than 10 inches in 10 minutes. The printer shall not be used after the 10 minute test period has started. The capping device shall allow the hose interior to be observed under the suction tests. The discharge outlets of the pump shall be uncapped.
b. The pump, while drafting water with a minimum lift of 10 feet through 20 feet of 5-inch suction hose, shall deliver, in a continuous operational test, a minimum of:
(1) 1,000 gpm at 150 psig net pump pressure for 2 hrs.
(2) 700 gpn at 200 psig net pump pressure for 1/2 hr.
(3) 500 gpm at 250 psig net pump pressure for 1/2 hr.
c. The pump, while drafting water with a minimum lift of 10 feet through 20 feet of 5-inch suction hose, shall deliver, in a continuous operational test, a minimum of 1,000 gpm at 165 psig net pump pressure for 10 minutes.
d. A test shall be conducted to verify that the relief valve performs in accordance with 3.10.4.
e. The pump shall deliver a minimum of 500 gpm from the water tank to determine conformance to 3.10.

4.4.3 Foam system test. The foam system shall be tested using AFFF conforming to MIL-F-24385. The metering valve shall be set to deliver 3 percent of foam solution for not less than 1 minute while discharging 250 gpm through the rear 2-l/2-inch discharge with 100 feet of 2-1/2-inch hose and fog nozzle. Failure to use at least 15 gallons of foam liquid per minute, at 3 percent, shall constitute failure of this test.

4.4.3.1 Monitoring test. The monitor (deluge gun) shall be tested with AFFF for 1 minute at 500 gpm. At least 30 gallons of AFFF shall be used during the test. The monitor shall be tested to verify a water flow rate of at least 1,000 gpm when drafting through the side suction connection.

4.4.4 Auxiliary generator test. A test shall be conducted to verify that the auxiliary generator conforms to the requirements of 3.8.6.3.

4.4.5 Production sample. Upon acceptance of the first article unit, it shall remain at the manufacturing facility as a production sample, and shall be the last fire truck shipped on the contract. The first article shall unit be reconditioned, including replacement of abnormally worn parts and paint touch-up or repainting, prior to delivery to enable it to be accepted as a contract item. The contractor shall maintain the first article in a serviceable condition for the duration of the contract.

4.5 Quality conformance tests. Each production truck, loaded as specified in 3.8-1, shall be operated and tested as follows:

a. 5 miles over paved roads at maximum speed of not less than 60 mph.
b. 5 miles over graded dirt roads at maximum speeds of not less than 25 mph .

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

c. Steering mechanism shall be tested to verify conformance to the requirements of 3.8.14.

During these tests, the functioning of the engine, power train, brakes, truck and body lighting systems, controls and instruments shall be observed for effective operation.

4.5.1 Production truck fire pump tests. The fire pump on each production truck shall be tested in accordance with the requirements of 4.4.2. 3. Meter readings of all tests performed shall have the results recorded on the Apparatus Pump/Service Test Report form and delivered in accordance with DD Form 1423 requirements.

4.5.2 Production truck foam system test. The foam and monitor system on each production truck shall be tested in accordance with 4.4.3 and 4.4.3.1, except water may be used in lieu of foam concentrate in the foam tank. All tests performed shall have the results recorded on the Apparatus Pump/Service Test Report form and delivered in accordance with DD Form 1423 requirements.

4.6 Packaging inspection. The preservation, packing and marking of the truck shall be inspected to verify conformance to the requirements of section 5.

5. PACKAGING

5.1 Vehicle Processing, The equipment shall be preserved and packed in accordance with the contractor's standard practice. When specified (see 6.2), equipment shall be preserved and packed in accordance with the mobile requirements of MIL-V-62038, with the level of preservation and packing as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

APPARATUS PUMP/SERVICE

TEST REPORT

EQUIPMENT DESCRIPTION		Test Date	Test Location
USN No.	Model No.	Ambient Temp.	Altitude
Contract No.	Manufacturer	Engine Mfg.	Engine Serial No.
Pump Mfg.	Pump Model	Pump Capacity	Pump Type

TEST DATA AND RESULTS

Capacity Test 150 PSI 2 Hrs.

Coolant Temp. Min	Coolant Temp. Max	Oil Pressure Min	Oil Pressure Max	Max Vacuum Inches	Primer Time	Suction Size	Suction Hose Length	Suction Lift

Layout

Nozzle Size

Time	RPM APPAR TACH.	RPM TEST TACH.	Pump Pressure APPAR GAGE	Pump Pressure TEST GAGE	Pitot Reading	GPM	Net Pump Pres.

Overload Test - 10 Min.

Coolant Temp. Min	Coolant Temp. Max	Oil Pressure Min	Oil Pressure Max	Max Vacuum Inches	Primer Time	Suction Size	Suction Hose Length	Suction Lift

Layout

Nozzle Size

Source: https://assist.dla.mil -- Downloaded: 20260-20T13:15Z
Check the source to verify that this is the current version before use.

APPARATUS PUMP/SERVICE (cont'd)
TEST REPORT

	RPM		Pump Pressure				Net
Time	APPAR TACH.	TEST TACH.	APPAR GAGE	TEST GAGE	Pitot Reading	GPM	Pump Pres.

PRESSURE TEST 200 PSI - 30 MIN

Coolant Temp. Min	Coolant Temp. Max	Oil Pressure Min	Oil Pressure Max	Max Vacuum Inches	Primer Time	Suction Size	Suction Hose Length	Suction Lift

Layout

Nozzle Size

	RPM		Pump Pressure				Net
Time	APPAR TACH.	TEST TACH.	APPAR GAGE	TEST GAGE	Pitot Reading	GPM	Pump Pres.

PRESSURE TEST 250 PSI - 30 MIN

Coolant Temp. Min	Coolant Temp. Max	Oil Pressure Min	Oil Pressure Max	Max Vacuum Inches	Primer Time	Suction Size	Suction Hose Length	Suction Lift

Layout

Nozzle Size

Source: https://assist.dla.mil -- Downloaded: 20260-20T13:15Z
Check the source to verify that this is the currentversion before use.

APPARATUS PUMP/SERVICE
TEST REPORT (cont'd)

	RPM		Pump Pressure				
Time	APPAR TACH.	TEST TACH.	APPAR GAGE	TEST GAGE	Pitot Reading	GPM	Net Pump Pres.

Final Results				Hydrostatic Test (350 PSI - 10 Min.)	
FUNCTION	CAPACITY (150 PSI)	200PSI	250PSI	Relief Valve Test:	
				Tank to Pump Test:	
Duration (time)				Discharge Test (monitor):	
				Foam System Test:	
Avg.Nozzle Pres				Dschrg Test(Hose):Rear 2-1/2"	
				Cross Beds - 1-1/2" (Three)	
Avg. Pump Pres				Flow Meter Calibration:	
				Monitor - 1,000 GPM	
GAGE				2-1/2"Dschrg Outlets 500 GPM:	
Correction				1-1/2"Dschrg Outlets 150 GPM:	
Corrected				Witnessed By:	
Pump Pres.					
GPM					
				Contractor _____	
RPM Engine					
RPM Pump				Government _____	

*Dschrg = Discharge

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:15Z
Check the source to verify that this is the current version before use.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The fire truck specified in this specification is intended to be used to suppress fires.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number and date of this specification.
b. Issue of DODISS to be cited in the solicitation, and if required, the specific issue of individual documents referenced (see 2.1.1 and 2.2).
c. When first article is required for inspection and approval (see 3.2, 4.2.1, and 6.4).
d. When engine coolant heater is required (3.8.2.2).
e. When a spare wheel or rim is required (see 3.8.12.2).
f. When MIL-V-62038 presentation is required, and the level of presentation and packing required (see 5.1).

6.3 Data requirements. When this specification is used in an acquisition and data are required to be delivered, the data requirements shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved Contract Data Requirements List (CDRL), incorporated into the contract. When the provisions of DOD FAR Supplement, Part 27, Sub-Part 27.475-1 (DD Form 1423) are invoked and the DD Form 1423 is not used, the data should be delivered by the contractor in accordance with the contract or purchase order requirements.

6.4 First Article. When a first article inspection is required, the item will be tested and should be a first production item or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test and approval of the first article.

6.5 Subject Term (key word) Listing.

Diesel engine
Fire extinguishing truck
Firefighting truck
Performance

Custodian:
Navy - YD

User Activity:
Navy - MC

Preparing Activity:
Navy - YD

(Project 4210-N421)

Source: https://assist.dla.mil -- Downloaded: 202610-20T13:15Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS

1. The preparing activity must complete blocks 1, 2, 3, and 8. In block 1, both the document number and revision letter should be given.
2. The submitter of this form must complete blocks 4, 5, 6, and 7.
3. The preparing activity must provide a reply within 30 days from receipt of the form.

NOTE: This form may not be used to request copies of documents, nor to request waivers, or clarification of requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

I RECOMMEND A CHANGE:	1. DOCUMENT NUMBER	2. DOCUMENT DATE (YYMMDD)
	MIL-T-28571G(NAVY)	910920

3. DOCUMENT TITLE

TRUCK, FIREFIGHTING, STRUCTURAL, 1,000 GPM, 4 BY 2

4. NATURE OF CHANGE (Identify paragraph number and include proposed rewrite, if possible. Attach extra sheets as needed.)

5. REASON FOR RECOMMENDATION

6. SUBMITTER

a. NAME (Last, First, Middle Initial)	b. ORGANIZATION	
c. ADDRESS (Include Zip Code)	d. TELEPHONE (Include Area Code) (1) Commercial (2) AUTOVON (If applicable)	7. DATE SUBMITTED (YYMMDD)

8. PREPARING ACTIVITY

a. NAME	b. TELEPHONE (Include Area Code) (1) Commercial	(2) AUTOVON
A. VILLEGAS	(805) 982-5773	551-5773

c. ADDRESS (Include Zip Code)

NAVAL CONSTRUCTION BATTALION CENTER
CIVIL ENGINEER SUPPORT OFFICE (1564V)
PORT HUENEME, CA 93043-5000

IF YOU DO NOT RECEIVE A REPLY WITHIN 45 DAYS, CONTACT:
Defense Quality and Standardization Office
5203 Leesburg Pike, Suite 1403, Falls Church, VA 22041-3466
Telephone (703) 756-2340 AUTOVON 289-2340

DD Form 1426, OCT 89 — Previous editions are obsolete. — 198/290

Source: https://assist.dla.mil -- Downloaded: 202610-20T13:15Z
Check the source to verify that this is the current version before use.