MILITARY SPECIFICATION

MODULE, WATER TANK

This specificaion is approved for use by the U.S. Marine Corps, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for manufacture and Government acceptance of the Water Tank Module.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. Unless otherwise specified, the following specifications, standards and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DoDISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

ZZ-H-561	Hose, Rubber, and Hose Assemblies, Rubber, Smooth Bore, Water Suction and Discharge

MILITARY

MIL-I-6866	Inspection, Penetrant Method of
MIL-I-6868	Inspection Process, Magnetic Particle
MIL-W-8611	Welding, Metal Arc and Gas, Steels, and Corrosion and Heat Resistant Alloys; Process for
MIL-E-19933	Electrodes and Rods - Welding, Bare Chromium and Chromium-Nickel Steels
MIL-E-22200/2	Electrodes, Welding, Covered (Austenitic Chromium-Nickel Steel, for corrosive and High Temperature Services)
MIL-E-52798	Enamel, Alkyd, Camouflage

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commandant of the Marine Corps, Code LMA-1, Washington D.C. 20380 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 5430

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:00
Check the source to verify that this is the current version before use.

STANDARDS

MILITARY

MIL-STD-105	Sampling Procedures and Tables for Inspection by Attributes
MIL-STD-129	Marking for Shipment and Storage
MIL-STD-130	Identification Marking of U.S. Military Property
MIL-STD-453	Inspection, Radiographic
MIL-STD-470	Maintainability Program (for Systems and Equipments)
MIL-STD-471	Maintainability Demonstration
MIL-STD-781	Reliability Tests: Exponential Distribution
MIL-STD-785	Reliability Program For Systems and Equipment Development and Production
MIL-STD-810	Environmental Test Methods
MIL-STD-889	Dissimilar Metals
MIL-STD-1186	Cushioning, Anchoring, Bracing, Blocking and Waterproofing, with Appropriate Test Methods

2.1.2 Other Government documents, drawings and publications. The following other Government documents, drawings and publications form a part of this specification to the extent specified herein.

DRAWINGS

U.S. Marine Corps

845008A0000	SIXCON Water Tank Module

CODE OF FEDERAL REGULATIONS

49CFR178	Shipping Container Specifications
49CFR451	Testing and Approval of Containers

(Copies of specifications, standards, drawings and publications required by manufacturers in connection with specific acquisition functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ISO 668 - Freight Containers - External Dimensions and Ratings.
ISO 1161 - Series 1 Freight Containers - Corner Fittings - Specification

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:00Z
Check the source to verify that this is the current version before use.

ISO 1496/I - Series 1 Freight Containers - Specification and Testing - Part I: General Cargo Containers
ISO 1496/III - Series 1 Freight Containers - Specification and Testing - Part III: Tank Containers for Liquids and Gases

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY. 10012.)

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1 - Structural Welding Code, Section 5, Qualification - Welding Inspection Manual

(Application for copies should be addressed to the American Welding Society, 2501 N.W. 7th St., Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Welding Qualification, Section IX.

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 4th St., New York, NY 10017.)

2.3. Order of precedence. In the event of a conflict between the text of this specification and the reference cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1. First article. Unless otherwise specified, (see 6.2), the contractor shall furnish three units for first article inspection (see 4.3). The first article shall be manufactured using the same methods, procedures, and tooling proposed for production. Approval of the first article by the procuring activity shall not relieve the contractor of the obligation to supply equipment conforming to this specification. Changes or deviations in production units from the approved first article baseline shall require written authorization by the procuring activity.

3.2 Materials. Materials used in fabrication of the water tank module shall be as specified on Drawing No. 845008A0000. Materials shall be free of defects and imperfections that might affect the serviceability and appearance of the finished product. Substitute material shall not be utilized prior to written authorization by the procuring activity. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Special precautions shall be observed to ensure

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:00Z
Check the source to verify that this is the current version before use.

that materials in contact with potable water do not contain contaminants which would preclude the water's intended use. Materials shall not impart odor, color, or taste to the water, and shall conform to the requirements of the Environmental Protection Agency (EPA).

3.3 Design and construction. The water tank module shall be fabricated and assembled in accordance with Drawing No. 845008A0000 and as specified herein.

3.3.1 Safety approval. Necessary actions as prescribed in 49CFR451 (see Code of Federal Regulations) shall be accomplished to obtain approval of the containers by an appropriate Convention for Safe Containers (CSC) approval authority (see 49CFR451), Subpart B - "Approval of New Containers" and the required CSC Safety Approval Plate shall be provided and affixed to the container as prescribed in 49CFR451, Subpart C - "Safety Approval Plate.") The notice of approval received from the approval authority which authorizes the attachment of CSC Safety Approval Plates shall be furnished to the contracting officer within 30 days of receipt by the contractor. The contractor shall also provide a certificate to the contracting officer stating the serial number, model number, and any pertinent manufacturing identification numbers of the tanks that are covered under each specific Notice of Approval.

3.3.2 Hose. All hose and hose assemblies shall meet the requirements of ZZ-H-561, grade A, type I, style A, class 2. All hoses shall comply with Environmental Protection Agency (EPA) requirements and be suitable for use with chlorinated potable water.

3.3.3 Insulation. The water tank module shall be insulated as specified on Drawing No. 845008A0000.

3.3.4 Cleanliness. All interior surfaces of the water tank module and components which come into contact with potable water during fillings, storage, transport and dispensing operations shall meet the cleanliness requirements of the EPA.

3.3.5 Welding and welders.

3.3.5.1 Welding. The water tank module and its components shall be welded in accordance with Drawing No. 845008A0000. Welding shall meet the requirements of MIL-W-8611. The surface of the parts to the welded shall be free from rust, scale, paint, grease, or other foreign matter. Spot, tack, or intermittent welds for greater strength shall not be permitted, unless otherwise cited in Drawing No. 84500A0000. Weld penetration shall be such as to provide transference of maximum design stress through the base metal juncture. Fillet welds shall be provided when necessary to reduce stress concentration. All finished weldments shall be reasonably straight and true in accordance with

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

good shop practice. Faulty weldments shall be corrected by welding only. Peening shall not be utilized to correct faults. Weld spatters shall be removed. All parts shall be properly aligned and meshed and operable without interference, tight spots, or other irregularities.

3.3.5.2 Welders. All welders shall be qualified for the types of welds required in the fabrication of water tank modules. Before assigning any welder to welding work, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of welding operation to be performed and that such qualification is effective as defined by that particular code.

AWS D1.1, Structural Welding Code, Section 5, Qualification
Boiler and Pressure Vessel Code, Welding Qualification, section IX (ASME)

3.3.5.3 Electrodes. Welding electrodes shall meet the requirements of either MIL-E-19933 or MIL-E-22200/2. Electrodes used to weld class 304L corrosion-resisting steel shall be type MIL-309 or MIL-310 only.

3.3.6 Casting and forgings. Castings and forgings shall be manufactured in accordance with Drawing No. 845008A0000. All castings shall be sound and free from patching, inclusions, misplaced coring, warping, or any other defect that reduces the castings ability to perform its intended function. Forgings shall be uniform in quality and condition, and shall be free from tears, cracks, seams, laps, internal ruptures, imbedded scale, segregation, and other defects.

3.3.7 Bolted and pinned connections. Bolt and pin holes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice and all bolts, nuts, and screws shall be tight.

3.3.8 Machine work. Quality of machine work shall meet accepted standards of the manufacturing industry. Where machined surfaces are required, adequate thicknesses shall be shown on the drawings, making due allowances for heat treating, hardening, finish grinding, and plating or coating based on shop experience and judgement.

3.3.9 Metal fabrication. Metal used in the fabrication of the water tank modules shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Shearing and chipping shall be done accurately. Flame cutting, using a tip suitable for the thickness of the metal, may be employed instead of shearing or sawing. Reentrant cuts may be made with controlled means in order to ensure uniformity of size and shape. Precautions shall be taken to avoid

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T23:00Z
Check the source to verify that this is the currentversion before use.

overheating, and heated metal shall be allowed to cool slowly. The use of dissimilar metals in intimate contact with each other shall be avoided wherever possible. When the use of dissimilar metals cannot be avoided, an interposing material that will eliminate or minimize this galvanic effect shall be used in accordance with MIL-STD-889.

3.3.10 Interchangeability. Water tank modules of the same classification, furnished under any specific contract, shall be physically and mechanically identical. They shall each meet the requirements specified in ISO 668, 1161, 1496/I and 1496/III.

3.4. Reliability. The water tank module shall have a 0.98 (98 percent) probability of completing a 12 hour mission.

3.5 Maintainability. The Mean Time to Repair (MTTR) shall not exceed 1 hour at the organizational level and 2 hours at the direct support level.

3.6 Performance characteristics. The water tank module shall meet the following performance requirements.

3.6.1 Drain. The water tank module shall be capable of dispensing water by gravity flow without restriction from the drain valve.

3.6.2 Tank openings. The water tank module shall meet the pressure and leakage requirements of 49CFR178.253-5, when manifolded with appropriate hose and fittings.

3.6.3 Liquid level indicator. A liquid level indicator shall be provided for each water tank module.

3.6.4 Manhole. The manhole shall incorporate a vent and provide access to the interior of the water tank module for cleaning and repair. The manhole shall be provided with a removable gasket cover to provide a leak proof seal.

3.7 Environmental characteristics. The water tank module shall withstand without leakage the humidity resistance low temperature (-25°F) and high temperature (160°F) and salt fog when tested as specified in 4.5.15.

3.8 Painting. The water tank module shall be painted as specified on Drawing No. 845008A0000 and MIL-E-52798. Color shall be as specified in 6.2.

3.9 Marking/serialization.

3.9.1 Water tank module. The water tank module shall be marked and serialized as specified on Drawing No. 845008A0000.

Source: https://assist.dla.mil -- Downloaded: 202610-20T23:00Z
Check the source to verify that this is the currentversion before use.

3.9.2 Parts and components. Parts and components shall be marked in accordance with MIL-STD-130.

3.9.3 Identification plate. The water tank module identification plate shall be in accordance with Drawing No. 845008A0000.

3.9.4 Instruction plate. The water tank module instruction plate shall be in accordance with Drawing No. 845008A0000.

3.10 Workmanship. All parts, components, and assemblies of the unit including castings, forgings, molded parts, stampings, seals and sealing agents, machined surfaces, and welded parts shall be clean and free from any defects that will reduce the capability of the water tank module to meet the requirements specified herein. Any components and assemblies which have been repaired or modified to overcome deficiencies shall not be used without prior approval of the contracting officer. External surfaces shall be free from burrs, slag, sharp edges, and corners except where sharp edges and corners are required.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) First article inspection (see 4.3)
(b) Quality conformance inspection (see 4.4)
(c) Packaging (see 4.6)

4.3 First article inspection and testing. First article inspection shall consist of the examinations and tests specified in Table I. Failure to pass any test shall be cause for rejection.

Source: https://assist.dla.mil -- Downloaded: 202610-20T23:00Z
Check the source to verify that this is the current version before use.

connection; and all required operating, limit, and safety controls. The

TABLE I

Inspection	Requirement Paragraph	Test Paragraph	First Article	Quality Conformance
Material Certification	3.2	4.5.1	X	X
Hose	3.3.2	4.5.1.1	X	X
Construction	3.3	4.5.2	X	X
Insulation	3.3.3	4.5.3	X	X
Painting	3.8	4.5.4	X	X
Marking/Serialization	3.9	4.5.5	X	X
Workmanship	3.10	4.5.6	X	X
Water Tank Welds	3.3.5.1	4.5.7.1	X	X
Structural Welds	3.5.1	4.5.7.2	X	X
Castings	3.3.6	4.5.8	X	X
Forgings	3.3.6	4.5.9	X	X
Maintainaiblity	3.5	4.5.10	X	
Reliability	3.4	4.5.11	X	
Pressure Test	3.6.2	4.5.14.3	X	
Leak Test	3.6.2	4.5.14.3	X	
Drain	3.6.1	4.5.14.4	X	
Relief Valve	3.6.2	4.5.14.2	X	
Manhole	3.6.4	4.5.12	X	
Environmental	3.7	4.5.15	X	
Cleaning	3.3.4	4.5.16	X	X
Packaging	5.1	4.6	X	X
ISO Testing	3.3.1	4.5.13	X	X
Liquid Level Indicator	3.6.3	4.5.14.1	X	X

4.4 Quality conformance inspection. Quality conformance inspection shall consist of the examinations and tests specified in Table I.

4.4.1 Lot size. An inspection lot shall consist of all water tank modules produced during an identifiable production period and submitted at one time for acceptance inspection. Production period shall be 1 month.

4.4.2 Sampling for inspection. Sampling for inspection from each inspection lot shall be in accordance with inspection level N-II-S of MIL-STD-105. The Acceptable Quality Level (AQL) shall be 0.65 percent for critical defects, 1.0 percent for major defects and 2.5 percent for minor defects.

4.4.3 Inspection failure. Failure of a production water tank module to meet any requirement specified herein during and as a result of the specified inspections and tests shall be cause for rejection of the production water tank modules and shall be cause for refusal by the Government to continue acceptance of production

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

water tank modules until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies in modules previously accepted and produced under the contract shall be accomplished by the contractor at no cost to the Government. Any deficiencies found as a result of any production inspection will be considered prima facie evidence that all water tank modules accepted prior to the completion of the production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Examinations and tests.

4.5.1 Material certification. The contractor shall certify that all materials and parts used in fabrication of the water tank module are in accordance with the requirements of 3.2. Material or part manufacturer's certification of test data will be acceptable for fulfilling this requirement. Acceptance or approval of any material or part shall not be construed as a guarantee of acceptance of the water tank module. The contractor shall be responsible for using parts and assemblies from Qualified Products Lists (QPL's) whenever available. Contractor's inspection records shall specifically list all QPL items by number and date of the QPL, name of contractor, and part number or drawing number(s). When parts and assemblies are approved as qualified products, but not yet listed on the QPL, the contractor shall list the products by number and date of the approved document, and name of supplier(s).

4.5.1.1 Hose. Certified test data and certificate of compliance shall be examined to verify conformance of hose and hose assemblies to the requirements of 3.3.2.

4.5.2 Construction. The water tank module shall be visually examined both prior to and after application of insulation and paint to verify proper assembly and installation of components and assemblies in accordance with the requirements of 3.3.

4.5.3 Insulation. The water tank module shall be inspected to verify conformance to the requirements of 3.3.3.

4.5.4 Painting. The water tank module shall be inspected to verify conformance to the requirements of 3.8.

4.5.5 Marking/serialization. The water tank module shall be visually examined to verify conformance to the requirements of 3.3.1 and 3.9.

4.5.6 Workmanship. The water tank module shall be visually examined to verify conformance to the requirements of 3.10.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:00Z
Check the source to verify that this is the current version before use.

4.5.7 Welding inspection.

4.5.7.1 Water tank module welds. Welds on or to the water tank module shall be inspected in accordance with MIL-W-8611, "Inspection for Production" and "Test Methods" to determine conformance to the requirements of 3.5.1.

4.5.7.2 Structural welds. Welds, other than those in 4.5.7.1, shall be inspected in accordance with MIL-I-6866 or MIL-I-6868 to determine conformance to the requirements of 3.5.1.

4.5.8 Castings. Castings shall be inspected in accordance with MIL-STD-453 to determine conformance to the requirements of 3.3.6.

4.5.9 Forgings. Forgings shall be inspected in accordance with MIL-I-6868 to determine conformance to the requirements of 3.3.6.

4.5.10 Maintainability. Maintainability verification/demonstration/evaluation of the water tank module shall be performed in accordance with MIL-STD-470 and MIL-STD-471 to determine conformance to the requirements of 3.5.

4.5.11 Reliability. Reliability testing of the water tank module shall be conducted in accordance with MIL-STD-781, Test Plan XVIIC with a minimum acceptable mean time between failure (θ1) of 9600 hours and MIL-STD-785 to determine conformance to the requirements of 3.4.

4.5.12 Manhole. The water tank module shall be examined to verify conformance with 3.6.4.

4.5.13 ISO testing. Three water tank modules shall be selected by the Government for ISO testing. The same water tank modules shall be used for the complete series of ISO testing. ISO testing shall be carried out as prescribed in ISO 1496/III for half-high 1C containers with a maximum gross weight of 30,000 pounds. The same water tank modules shall be inspected for compliance with ISO 668. 1101 and 1496/I. All necessary ISO testing shall be accomplished to obtain Convention for Safe Containers (CSC) certification plates (see 3.3.1).

4.5.14. Other testing. Three water tank modules shall be used for the following tests. These tests shall be conducted following ISO testing. Water tank modules shall be assembled in the frame with all components attached and no insulation or paint applied. The three water tank modules shall be functionally connected as a half-high 1C container utilizing the horizontal ISO connectors. The water tank modules shall be manifolded together using the hoses supplied with each water tank module.

4.5.14.1 Liquid level indicator test. With all water drains

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

closed, each water tank module shall be filled via the manhole until full. Potable water shall be used as the test medium. During the filling of each water tank module, the water level indicator shall be checked to ensure that the indicator registers accurately to 1/8 of the tank capacity in the water tank module. The level indicators shall also be checked during water tank module draining. An erroneous water level indicator reading shall constitute failure.

4.5.14.2 Pressure relief valve test. When each water tank module is full of water, the manhole shall be secured. Each water tank module shall be subjected to 6 pounds per square inch gage (psig)air pressure and checked to ensure that the valves vent the pressure. Nonrelief of pressure shall constitute failure to pass the test.

4.5.14.3 Pressure test. A pressure test shall be conducted following completion of ISO testing (4.6.13) during first article. This test shall also be conducted on each water tank module prior to delivery to the Government. The test criteria in 49CFR178.253.5 (see Code of Federal Regulations) shall be used except that the pressure shall be maintained for 30 minutes. Each water tank module shall be tested separately. The design pressure shall be determined as follows:

$$P=(hd/115) - 3$$ Where:

P=Design pressure in psig
h=Inside height of tank in inches
d=Maximum allowable density in pounds per gallon

Inability to meet the requirements of 3.5.2, or any deformation, bulging or leaking shall constitute failure of this test.

4.5.14.4 Draining test. With all water tanks modules filled with water and manifolded together, all vents in normal operating position, and manhole closed, the water tank modules shall be drained through one drain valve. Failure of all water tank modules to drain completely, except for a small amount of water below the drain valve level, shall constitute failure.

4.5.15 Environmental tests.

4.5.15.1 Humidity resistance. The water tank module under test shall be subjected to humidity resistance test in accordance with MIL-STD-810, method 507.1, procedure 4. After testing, the water tank module shall be inspected for evidence of cracking, cracked welds, corrosion, and peeling of paint. Evidence of these conditions of material degradation shall constitute failure of the humidity test.

Source: https://assist.dla.mil -- Downloaded: 2026l0-20T23:00Z
Check the source to verify that this is the currentversion before use.

4.5.15.2 Low temperature. After having been tested and inspected in accordance with the provisions of 4.5.15.1, the water tank module shall be soaked at -25° F for 16 hours minimum. The temperature shall then be raised to ambient conditions, and the water tank module inspected for cracking, cracked welds, and paint disintegration. Evidence of these conditions or material degradation shall constitute failure of the low temperature test.

4.5.15.3 High temperature. After having been tested and inspected in accordance with 4.5.15.2, the water tank module shall be soaked at 160° F (71° C) for 48 hours. The temperature shall then be lowered to ambient conditions, and the water tank module inspected for cracking, cracked welds, and paint disintegration. Evidence of these conditions or material degradation shall constitute failure of the high temperature test.

4.5.15.4 Salt fog. After having been tested and inspected in accordance with 4.5.15.3, the water tank module shall be subjected to salt fog test in accordance with MIL-STD-810, method 509.1. After testing, the water tank module shall be inspected for cracking, cracked welds, corrosion and peeling of paint. Evidence of these conditions or material degradation shall constitute failure of the salt fog test.

4.5.15.5. Leakage. After having been tested and inspected in accordance with 4.5.15.3, the water tank module shall be filled with water and checked for leaks. Any sign of leakage shall constitute failure of the environmental test series.

4.5.16 Cleanliness. The water tank module shall be examined to verify conformance with 3.3.4.

4.6. Packaging. The preservation, packaging, packing and container marking shall be inspected, prior to shipment, to determine conformance to section 5 of this specification.

5. PACKAGING.

5.1 Preparation for delivery. Conventional methods of blocking, bracing, and strapping are to be employed during shipment by rail, truck, and air as described in MIL-STD-1186. Removable markings shall be affixed as specified in MIL-STD-129 to show cubic size and weight as well as the destination specified by the contracting officer. No external crating is required.

6. NOTES

6.1 Intended use. The water tank modules are intended to be used for transport and storage of potable water for combat troops in the field.

Source: https://assist.dla.mil -- Downloaded: 202610-20T23:00Z
Check the source to verify that this is the currentversion before use.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number and date of this specification.
b. When first article is not required (see 3.1)
c. Color required (see 3.8)

6.2.2 Data requirements. When this specification is used in an acquisition which incorporates a Contract Data Requirements List (CDRL) (DD Form 1423), the data requirements identified below shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL incorporated into the contract. When the provisions of DAR 7-104.9(n)(2) are invoked and the DD Form 1423 is not used, the data specified below shall be delivered by the contractor in accordance with the contract or purchase order requirements. Deliverable data required by this specification is cited in the following paragraphs:

Para No.	Data Requirement Title	Applicable DD No.	Option
4.3	First Article Inspection Procedure	DI-T-4901	-
4.3	First Article Inspection Report	DI-T-4902	-

(Data item descriptions related to this specification and identified in section 6 will be approved and listed as such in DoD 5000.19L, Vol. II, AMSDL. Copies of data item descriptions required by the contractors in connection with specific acquisition functions should be obtained from the Naval Publications and Forms Center or as directed by the contracting officer.)

6.3 First article. Any changes or deviations of production welding sets from the approved first article during production will be subject to the approval of the contracting officer. Approval of the first article will not relieve the supplier of his obligation to furnish welding sets conforming to this specification.

Preparing activity:
Navy - MC
Project No. 5430-N151

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-M-29414(MC)	Module, Water Tank

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR ☐ USER ☐ MANUFACTURER ☐ OTHER *(Specify)*:
b. ADDRESS *(Street, City, State, ZIP Code)*	

5. PROBLEM AREAS

a. Paragraph Number and Wording:

b. Recommended Wording:

c. Reason/Rationale for Recommendation:

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE.

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

production water purification units to be furnished, when applicable

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE. This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE NAVY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO. 12503 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Commandant of the Marine Corps
Headquarters U.S. Marine Corps
Code LMA-1
Washington, D. C. 20380

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:00Z
Check the source to verify that this is the current version before use.

MIL-M-29414(MC)
AMENDMENT 1
14 March 1990

MILITARY SPECIFICATION

MODULE, WATER TANK (SIXCON)

This amendment forms a part of MIL-M-29414 (MC), dated 25 April 1984, and is approved for use by the U. S. Marine Corps, Department of the Navy and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

2.1.1, change "MIL-E-52798, Enamel, Alkyd, Camouflage" to "MIL-T-704, Treatment and Painting of Material".

Statement on the bottom of the page, (Beneficial comments), change the address to Commanding General Marine Corps Research, Development and Acquisition Command, Code PSE, Washington, D.C. 20380

PAGE 6

3.8, change "MIL-E-52798 to "MIL-T-704".

PAGE 8

4.4.2, delete second sentence.

PAGE 11

4.5.14.3, change the referenced paragraph "4.6.13" to "4.5.13".

4.5.14.3, change the referenced paragraph, following the equation, "3.5.2" to "3.6.2".

AMSC N/A

FSC 5430

Preparing activity:
MC

(Project 5430-N209)

Distribution Statement A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:00Z
Check the source to verify that this is the current version before use.