MILITARY SPECIFICATION

MODULE, FUEL TANK (SIXCON)

This specification is approved for use by the U.S. Marine Corps, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification establishes the requirements for manufacture and acceptance of the Fuel Tank Module (SIXCON) .

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications, standards and handbooks. Unless otherwise specified, the following specifications, standards, and handbooks of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116	- Preservation, Methods of
MIL-N-5877	- Nozzle, Pressure Fuel Servicing, Locking, Type D1, Normal 2-½ Inch Diameter
MIL-I-6866	- Inspection, Penetrant Method of
MIL-I-6868	- Inspectoon Process, Magnetic Particle
MIL-W-8611	- Welding, Metal Arc and Gas, Steels and Corrosion and Heat Resistant Alloys, Process for
MIL-E-19933	- Electrodes and Rods - Welding, Bare, Chromium and Chromium Nickel Steels

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commandant of the Marine Corps, Code LMA-1, Washington, D.C. 20380, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 20261O-20T23:01Z
Check the source to verify that this is the current version before use.

MIL-E-22200/2 - Electrodes, Welding, Covered (Austenetic Chromium Nickel Steel for Corrosive and High Temperature Services)

MIL-C-27487 - Coupling Halves, Quick Disconnect, Cam-locking Type

MIL-E-52798 - Enamel, Alkyd, Camouflage

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes

MIL-STD-129 - Marking for Shipment and Storage

MIL-STD-130 - Identification Marking of U.S. Military Property

MIL-STD-453 - Inspection, Radiographic

MIL-STD-470 - Maintainability Program Requirements (for Systems and Equipments)

MIL-STD-471 - Maintainability Demonstration

MIL-STD-781 - Reliability Tests: Exponential Distribution

MIL-STD-785 - Reliability Program for Systems and Equipment Development and Production

MIL-STD-794 - Parts and Equipment, Procedures for Packaging and Packing of

MIL-STD-810 - Environmental Test Methods and Engineering Guidelines

MIL-STD-889 - Dissimilar Metals

2.1.2 Other Government documents, drawings and publications. The following other Government documents, drawings and publications form a part of this specification to the extent specified herein.

DRAWINGS

U.S. Marine Corps

845009A0000 SIXCON Fuel Tank Module

Source: https://assist.dla.mil -- Downloaded: 20260-20T23:01Z
Check the source to verify that this is the current version before use.

CODE OF FEDERAL REGULATIONS

49CFR178-	Shipping Container Specification
49CFR451-	Testing and Approval of Cargo Containers

(Copies of specifications, standards, drawings and publications required by manufacturers in connection with specific acquisition functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DoD adopted shall be the issue listed in the current DoDISS and the supplement thereto, if applicable.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ISO 668	- Freight Containers - External Dimensions and Ratings
ISO 1161	- Series 1 Freight Containers - Corner Fittings - Specification
ISO 1496/1	- Series 1 Freight Containers - Specification and Testing - Part I: General Cargo Containers
ISO 1496/ III	- Series 1 Freight Containers - Specification and Testing - Part 111: Tank Containers for liquids and gases

(Applications for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York 10012.)

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1	- Structural Welding Code, Section 5, Qualification - Welding Inspection Manual

(Applications for copies should be addressed to the American Welding Society, 2501 N.W. 7th St., Miami, FL 33125.)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

Boiler and Pressure Vessel Code, Welding Qualification, Section IX

(Application for copies should be addressed to the American Society of Mechanical Engineers, 345 East 4th St. , New York, NY 10017.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

AMERICAN SOCIETY OF TESTING AND MATERIALS (ASTM)

ASTM D3951-82 - Standard Practice for Commercial Packaging

(Application for copies should be addressed to American Society for Testing and Materials, 1916 Race St. , Philadelphia, PA 19103.)

2.3 order of precedence. In the event of a conflic between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 First article. Unless otherwise specified (see 6.2), the contractor shall furnish three units for first article inspection (see 4.3). The first article shall be manufactured using the same methods , procedures, and tooling proposed for production. Approval of the first article by the procuring activity shall not relieve the contractor of the obligation to supply equipment conforming to this specification. Changes or deviations in production units from the approved first article baseline shall require written authorization by the procuring activity.

3.2 Materials. Materials used in fabrication of the fuel tank module shall be as specified on Drawing No. 845009A0000. Materials shall be free of defects and imperfections that might affect the serviceability and appearance of the finished product. Substitute material shall not be utilized prior to written authorization by the procuring activity. Materials not specified shall be selected by the contractor and shall be subject to all provisions of this specification. Special precautions shall be observed to ensure that materials in contact with fuel do not contain contaminants which would preclude its intended use.

3.3 Design and construction. The fuel tank module shall be fabricated and assembled in accordance with Drawing No. 845009A0000 and as specified herein.

3.3.1 Safety approval. Necessary actions as prescribed in 49CFR451 (see Code of Federal Regulations) shall be accomplished to obtain approval of the containers by an appropriate Convention for Safe Containers (CSC) approval authority (see 49CFR451), Subpart B - “Approval of New Containers” and the required CSC Safety Approval Plate shall be provided and affixed to the container as prescribed in 49CFR451, Subpart C - “Safety Approval Plate”. The notice of approval received from the approval authority which authorizes the attachment of CSC Safety Approval Plates shall be furnished to the contracting officer within 30 days of receipt by the contractor. The contractor shall also provide a certificate to the contracting officer stating the serial number, model number, and any pertinent manufacturing identification numbers of the tanks that are covered under each specific Notice of Approval.

Source: https://assist.dla.mil -- Downloaded: 202640-20T23:01Z
Check the source to verify that this is the current version before use.

3.3.2 Fuel tank fittings and valves. Fuel tank modules shall be equipped with a 2-inch, drybreak valve inlet and a 2-inch drybreak disconnect valve outlet. Each shall be fitted with a quick disconnect coupling (male at the outlet, female at the inlet) to facilitate the connection of the hoses. Dust caps and plugs with retention chains shall be provided on all quick disconnect. The quick disconnect couplings shall conform to MIL-C-27487. In addition, each fuel tank shall contain a female fitting to accept the underwing NATO pressure nozzle, type D-1 conforming to MIL-N-5877. The location of this female fitting shall be such that any commercial nozzle meeting the MIL-N-5877 requirements can be engaged even when the 2-inch drybreak outlet is manifolded to adjoining tank modules. The arrangement of inlet fittings should be provided for filling near the bottom of the tank to minimize splashing and build-up of a static charge within the tank. Inlet fittings shall permit filling rates up to 350 gallons per minute.

3.3.3 High level liquid sensor and shutoff valve. The fuel tank module shall contain a shutoff valve and a high level liquid sensor. The high level liquid sensor shall close the shutoff valve when the tank is full to prevent fuel spillage by overflowing the tank. The high level liquid sensor and shutoff valve shall operate without the need for electrical power or other auxiliary energy source.

3.3.4 Liquid level indicator. A liquid level indicator shall be provided for each fuel tank module.

3.3.5 Manhole. The manhole shall be compatible with vapor recovery systems and shall provide access to the interior of the tank for cleaning and repair. The manhole shall be provided with a removable gasketed cover capable of making a leakproof seal. A spring loaded pressure relief valve shall be incorporated in the cover to relieve internal pressure while preventing the entrance of outside air.

3.3.6 Welding and welders.

3.3.6.1 Welding. The fuel tank module and its components shall be welded in accordance with Drawing No. 845009A0000. Welding shall meet the requirements of MIL-W-8611. The surface of parts shall be free from rust, scale, paint, grease, or other foreign matter. spot, tack, or intermittent welds shall not be permitted unless otherwise cited in Drawing No. 845009A0000. Weld penetration shall be such as to provide transference of maximum design stress through the base metal juncture. Fillet welds shall be provided when necessary to reduce stress concentration. All finished weldments shall be reasonably straight and true in accordance with good shop practice. Faulty weldments shall be corrected by welding only. Peening shall not be utilized to correct faults. Weld spatters shall be removed. All parts shall be properly aligned and meshed and operable without interference, tight spots or other irregularities.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

3.3.6.2 Welders. All welders shall be qualified for the types of welds required in the fabrication of fuel tank modules. Before assigning any welder to welding work, the contractor shall provide the contracting officer with certification that the welder has passed qualification tests as prescribed by either of the following listed codes for the type of weldlng operation to be performed and that such qualification is effective as defined by that particular code.

AWS D1.1, Structural Welding Code, Section 5.
Qualification - Welding Inspection Manual

Boiler and Pressure Vessel Code, Welding Qualification,
Section IX (ASME)

3.3.6.3 Electrodes. Welding electrodes shall meet the requirements of either MIL-E-19933 or MIL-E-22200/2. Electrodes used to weld class 304L corrosion - resisting steel shall be type MIL-309 or MIL-310 only.

3.3.7 Castings and forgings. Castings and forgings shall be manufactured in accordance with Drawing No. 845009A0000. All castings shall be free from patching, inclusions, misplaced coring, warping, or any other defect that reduces the castings' ability to perform its intended function. Forgings shall be uniform in quality and condition, and shall be free from tears, cracks, seams, laps, internal ruptures, imbedded scale, segregation and other defects.

3.3.8 Bolted and pinned connections. Bolt and pin holes shall be accurately punched or drilled and shall have the burrs removed.

3.3.9 Machine work. Where machined surfaces are required to be heat treated, hardened, finish grounded, plated or coated, the part dimensions, as specified in Drawing No. 845009A0000, shall be maintained.

3.3.10 Metal fabrication. Metal used in the fabrication of the fuel tank modules shall be free from kinks and sharp bends. The straightening of material shall be done by methods that will not cause injury to the metal. Flame cutting, using a tip suitable for the thickness of the metal, may be employed instead of shearing or sawing. Reentrant cuts may be made with controlled means in order to insure uniformity of size and shape. Precautions shall be taken to avoid overheating, and heated metal shall be allowed to cool slowly. The use of dissimilar metals in intimate contact with each other shall be avoided wherever possible. When the use of dissimilar metals cannot be avoided, an interposing material that will eliminate or minimize the galvanic effect shall be used in accordance with MIL-STD-889.

Source: https://assist.dla.mil -- Downloaded: 202640-20T23:01Z
Check the source to verify that this is the current version before use.

3.3.11 Interchangeability. Fuel tank modules of the same classification, furnished under any specific contract, shall be physically and mechanically identical. They shall meet the requirements specified in ISO 668, 1161, 1496/1, and 1496/111.

3.4 Reliability. The fuel tank module shall have a 0.98 (98 percent) probability of completing a 12-hour mission.

3.5 Maintainability. The mean time to repair (MTTR) shall not exceed 1 hour at the organizational level and 2 hours at the direct support level.

3.6 Performance characteristics. The fuel tank module shall meet the pressure and leakage requirements of 49CFR178.253-5, when manifolded with appropriate hose and fittings.

3.7 Environmental characteristics.

3.7.1 Temperature and humidity. The fuel tank module shall withstand, without leakage, humidity resistance, low temperature (-25°F) and high temperature (160°F) when tested as specified in 4.5.13.

3.7.2 Salt fog. The fuel tank module shall withstand, without cracking, cracked welds, corrosion and peeling of paint, salt fog when tested as specified in 4.5.13.4.

3.7.3 Vibration. Fuel tank modules, when full, must be capable of withstanding a I-hour vibration test without breakage, permanent deformation or leakage (see 4.5.13.5).

3.7.4 Drop test. Fuel tank modules, when full, must be capable of withstanding a 2-foot free drop on a flat, unyielding surface without breakage, permanent deformation, or leakage (see 4.5.13.6) .

3.8 Painting. The fuel tank module shall be painted as specified on Drawing No. 845009A0000 and MIL-E-52798. Color shall be as specified in 6.2.

3.9 Marking/serialization.

3.9.1 Fuel tank module. The fuel tank module shall be marked and serialized as specified on Drawing No. 845009A0000.

3.9.2 Parts and components. Parts and components shall be marked in accordance with MIL-STD-13C.

3.9.3 Identification plate. The fuel tank module identification plate shall be in accordance with Drawing No. 845009A0000.

3.9.4 Instruction plate. The fuel tank module instruction plate shall be in accordance with Drawing No. 845009A0000.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

3.10 Workmanship. All parts, components , and assemblies of the fuel tank module, including castings, forgings, molded parts, stampings, seals and sealing agents, machined surfaces, and welded parts, shall be clean and free from any defects that will reduce the capability of the fuel tank module to meet the requirements specified herein. Any components and assemblies which have been repaired or modified to overcome deficiencies shall not be used without prior approval of the contracting officer. External surfaces shall be free of burrs, slag, sharp edges and corners where sharp edges and corners are required.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibilitty for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein . Except as otherwise specified in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to the prescribed requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

(a) First article inspection (see 4.3)
(b) Quality conformance inspection (see 4.4)
(c) Packaging (see 4.6)

4.3 First article inspection and testing. First article inspection shall consist of the examination and tests specified in Table I. Failure to pass any test shall be cause for rejection.

4.4 Quality conformance inspection. Quality conformance inspection shall consist of the examinations and tests specified in Table I.

4.4.1 Lot size. An inspection lot shall consist of all fuel tank modules produced during an identifiable production period and submitted at one time for acceptance inspection. Production period shall be 1 month.

4.4.2 Sampling for inspection. Sampling for inspection from each inspection lot shall be in accordance with inspection N-II-S of MIL-STD-105. The Acceptable Quality Level (AQL) shall be 0.65 percent for critical defects, 1.0 percent for major defects and 2.5 percent for minor defects.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

TABLE I. Tests.

Inspection	Requirement Paragraph	Test Paragraph	First Article	Quality Conformance
Material Certification	3.2	4.5.1	X	X
Painting	3.8	4.5.2	X	X
Marking/Serialization	3.9	4.5.3	X	X
Workmanship	3.10	4.5.4	X	X
Welding	3.3.2	4.5.5	X	X
Castings	3.3.7	4.5.6	X	X
Forgings	3.3.7	4.5.7	X	X
Maintainability	3.5	4.5.8	X	
Reliability	3.4	4.5.9	X	
Manhole	3.3.5	4.5.10	X	
ISO Testing	3.3.1	4.5.11	X	
Liquid Level Indicator	3.3.4	4.5.12.1	X	
Relief Valve	3.3.5	4.5.12.2	X	
Pressure Test	3.6	4.5.12.3	X	X
Float Valve	3.3.3	4.5.12.4	X	
Environmental	3.7	4.5.13	X	
Packaging	5	4.6	X	X

4.4.3 Inspection failure. Failure of a production fuel tank module to meet any of the requirements specified herein, during and as a result of the specified inspections and tests, shall be cause for rejection of the production fuel tank modules and shall be cause for refusal by the Government to continue acceptance of production fuel tank modules until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies in modules previously accepted and produced under the contract shall be accomplished by the contractor at no cost to the Government. Any deficiencies found as a result of any production inspection will be considered prima facie evidence that all fuel tank modules accepted prior to the completion of the production inspection are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer.

4.5 Examinations and tests.

4.5.1 Material certification. The contractor shall certify that all materials and parts used in fabrication of the fuel tank module are in accordance with the requirements of 3.2. Material or part manufacturer's certification of test data will be acceptable for fulfilling this requirement. Acceptance or approval of any material or part shall not be construed as a guarantee of acceptance of the fuel tank module. The contractor shall be responsible for using parts and assemblies from Qualified products Lists (QPL's) whenever available. Contractor's inspection records shall specifically list

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

all QPL items by number and date of the QPL, name of contractor, and part number or drawing number(s) . When parts and assemblies are approved as qualified products, but not yet listed on the QPL, the contractor shall list the products by number and date of the approved document, and name of supplier(s) .

4.5.2 Painting. The fuel tank module shall be inspected to verify conformance to the requirements of 3.8.

4.5.3 Marking/serialization. The fuel tank module shall be visually examined to verify conformance to the requirements of 3.9.

4.5.4 Workmanship. The fuel tank module shall be visually examined to verify conformance to the requirements **of** 3.10.

4.5.5 Welding inspection.

4.5.5.1 Fuel tank module welds. Welds on or to the fuel tank shall be inspected in accordance with MIL-W-8611, “Inspection for production and “Test Methods” to determine conformance to the requirements of 3.3.6.1.

4.5.5.2 Structural welds. All structural welds other than those in 4.5.5.1 shall be inspected in accordance with MIL-I-6866 or MIL-I-6868.

4.5.6 Castings. Castings shall be inspected in accordance with MIL-STD-453 to determine conformance to the requirements of 3.3.7.

4.5.7 Forgings. Forgings shall be inspected in accordance with MIL-I-6868 to determine conformance to the requirements of 3.3.7.

4.5.8 Maintainability. Maintainability verification/demonstration/evaluation of the fuel tank module shall be performed in accordance with MIL-STD-470 and MIL-STD-471 to determine conformance to the requirements of 3.5.

4.5.9 Reliability. Reliability testing of the fuel tank module shall be conducted in accordance with MIL-STD-781, Test Plan XVIIC with a minimum acceptable mean time between failure of 9600 hours and MIL-STD-785 to determine conformance to the requirements of 3.4.

4.5.10 Manhole. The fuel tank module shall be examined to verify conformance with 3.3.5.

4.5.11 ISO testing. Three fuel tank modules shall be selected by the Government for ISO testing. The same fuel tank modules shall be used for the complete series of ISO testing. ISO testing shall be carried out a prescribed in ISO 1496/111 for half-high IC containers with a maximum gross weight of 30,000 pounds. The same

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

fuel tank modules shall be inspected for compliance with ISO 668, 110, and 1496. All necessary ISO testing shall be accomplished to obtain convention for Safe Containers (CSC) certification plates.

4.5.12 Other testing. Three fuel tank modules shall be used for the following tests. These tests shall be conducted following ISO testing. Unless otherwise noted the three fuel tank modules shall be functionally connected as a half-high IC container utilizing the ISo connectors. The fuel tank modules shall be manifolded together using the hoses supplied with each fuel tank module.

4.5.12.1 Liquid level indicator test. With all drains closed, each fuel tank module shall be filled via the manhole until the module is at least 1/4 full. The liquid level indicator shall be checked to insure taht the indicator registers accurately to 1/8 of the amount of-fuel in the module.

4.5.12.2 Pressure relief valve test. When each fuel tank module is full of liquid, the manhole shall be secured. Each fuel tank module shall be subjected to 3 pounds per square inch gage (psig) air pressure and checked to insure that the valves vent the pressure. Nonrelief of pressure shall constitute failure to pass the test.

4.5.12.3 Pressure test. A pressure test shall be conducted following completion of ISO testing during first article. This test shall also be conducted on each fuel tank module prior to delivery to the Government. The test criteria in 49CFR178.253.5 (see Code of Federal Regulations) shall be used except that the pressure shall be maintained for 30 minutes. Each fuel tank module shall be tested separately. The design pressure shall be 6 psig. Inability to meet the requirements of 3.6 or any deformation, bulging, or leaking shall constitute failure of this test.

4.5.12.4 Float valve. With all drains closed, each tank shall be filled via the manhole until filled. Water shall be used as the test media. The high water level shall raise the float valve, thus shutting off the flow **of** air from the float valve to the outside of the fuel tank.

4.5.13 Environmental tests.

4.5.13.1 Humidity resistance. The fuel tank module under test shall be subjected to humidity resistance test in accordance with MIL-STD-810, method 507.1, procedure IV. After testing, the module shall be inspected for evidence of cracking, cracked welds, corrosion, and peeling of paint. Evidence of these conditions of material degradation shall constitute failure of the humidity test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

4.5.13.2 Low temperature. After having been tested and inspected in accordance with the provisions of 4.5.13.1, the empty fuel tank module shall be soaked at -25°F (-32°C) for 16 hours minimum. The temperature shall then be raised to ambient conditions, and the fuel tank module inspected for cracking, cracked welds, and paint disintegration. Evidence of these conditions or material degradation shall constitute failure of the low temperature test.

4.5.13.3 high temperature. After having been tested and inspected in accordance with the provisions of 4.5.13.2, the fuel tank module shall be soaked at 160°F (71°C) for 48 hours. The temperature shall then be lowered to ambient conditions, and the fuel tank module inspected for cracking, cracked welds, and paint disintegration. Evidence of these conditions for material degradation shall constitute failure of the high temperature test.

4.5.13.4 Salt fog. After having been tested and inspected as specified in 4.5.13.3, the fuel tank module shall be subjected to salt fog test in accordance with MIL-STD-810, method 509.1. After testing, the fuel tank module shall be inspected for cracking, cracked welds, corrosion and peeling of paint. Evidence of these conditions or material degradation shall constitute failure.

4.5.13.5 Vibration test. Using a minimum double amplitude of 1 inch, vibrate the fuel tank module for 1 hour at a frequency that causes the test tank to be raised from the test table so that a flat strap may be passed between the tank and the table. Restrain the tank on the table to prevent any horizontal motion. Any breakage, permanent deformation, or leakage will constitute failure of the fuel tank.

4.5.13.6 Drop test. Raise the full fuel tank module 2 feet from a flat horizontal unyielding surface and drop. Prior to dropping, the module should be positioned at an attitude from which maximum damage to the tank (including piping and fittings) is expected.

4.5.13.7 Leakage. After having been tested and inspected in accordance with 4.5.13.6, the fuel tank module shall be filled with water and checked for leaks. Any sign of leakage shall constitute failure of the environmental test series.

4.6 Packaging. The preservation, packaging, packing and container marking shall be inspected, prior to shipment, to determine conformance to section 5 of this specification.

5. PACKAGING

5.1 Preservation and packaging. Preservation and packaging shall be level A, B, or industrial as specified (see 6.2) .

5.1.1 Level A. The fuel tank module shall be preserved and packaged in accordance with the applicable procedures of MIL-P-116 and MIL-STD-794.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

5.1.2 Level B. The fuel tank module shall be preserved and packaged in accordance with the applicable procedures of MIL-P-116 and MIL-STD-794.

5.1.3 Industrial. The fuel tank module shall be preserved and packaged in accordance with ASTM D3951-82.

5.2 Packing. Packing shall be level A, B, or industrial as specified (see 6.2) .

5.2.1 Level A. The fuel tank module shall be packed in accordance with the applicable procedures of MIL-STD-794.

5.2.2 Level B. The fuel tank module shall be packed in accordance with the applicable procedures of MIL-STD-794.

5.2.3 Industrial. The fuel tank module shall be packed in accordance with ASTM D3951-82.

5.3 Marking. In addition to any special marking required by the contract or purchase order, shipping containers shall be marked in accordance with MIL-STD-129.

6. NOTES

6.1 Intended use. The fuel tank modules are intended to be used for transport and storage of fuel for support of combat equipment in the field in conjunction with fuel tank module. The fuel tank module is a component of the SIXCON, a six-module unit which consists of five fuel or water tank modules and one fuel or water pump module. The six modules attach together to form an ISO/ANSI configured 8-foot by 8-foot by 20-foot module which can be helolifted or transported aboard trucks. It is also suitable for use aboard container ships.

6.2 Ordering data.

6.2.1 Acquisition requirements. Acquisition requirements should specify the following:

(a) Title, number, and date of this specification.
(b) When first article is not required (see 3.1).
(c) Color required (see 3.8).
(d) Levels of preservation, packaging, and packing (see 5.1 and 5.2).

6.2.2 Data requirements. When this specification is used in an acquisition which incorporates a Contract Data Requirements List (CDRL) (DD Form 1423), the data requirements identified below shall be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the approved CDRL

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

incorporated into the contract. When the provisions of DAR 7-104.9 (n) (2) are invoked and the DD Form 1423 is not used, the data specified below shall be delivered by the contractor in accordance with the contract purchase order requirements. Deliverable data required by this specification is cited in the following paragraphs:

Para. No.	Data Requirement Title	Applicable DD No.	Option
4.3	First Article Inspection Procedure	DI-T-4901	--
4.3	First Article Inspection Report	DI-T-4902	--

(Data item descriptions related to this specification and identified in section 6 will be approved and listed as such as DoD 5000.19L, Vol. II, AMSDL. Copies of data item descriptions required by the contractors in connection with specific acquisition functions should be obtained from the Naval Publications and Forms Center or as directed by the contracting officer.)

6.3 First article. Any changes or deviations of production fuel tank modules from the approved first article during production will be subject to the approval of the contracting officer. Approval of the first article will not relieve the supplier of his obligation to furnish fuel tank modules conforming to this specification.

Preparing activity:
Navy-MC
Project No. 2910-N175

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

(See Instructions – Reverse Side)

1. DOCUMENT NUMBER	2. DOCUMENT TITLE
MIL-M-29416(MC)	MODULE, FUEL TANK (SIXCON)

3a. NAME OF SUBMITTING ORGANIZATION	4. TYPE OF ORGANIZATION *(Mark one)*
	☐ VENDOR
	☐ USER
b. ADDRESS *(Street, City, State, ZIP Code)*	☐ MANUFACTURER
	☐ OTHER *(Specify)* _____

5. PROBLEM AREAS

a. Paragraph Number and Wording

b. Recommended Wording

c. Reason/Rationale for Recommendation

6. REMARKS

7a. NAME OF SUBMITTER *(Last, First, MI)* – Optional	b. WORK TELEPHONE NUMBER *(Include Area Code)* – Optional
c. MAILING ADDRESS *(Street, City, State, ZIP Code)* – Optional	8. DATE OF SUBMISSION *(YYMMDD)*

DD FORM 82 MAR 1426 PREVIOUS EDITION IS OBSOLETE

(TO DETACH THIS FORM, CUT ALONG THIS LINE.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.

INSTRUCTIONS: In a continuing effort to make our standardization documents better, the DoD provides this form for use in submitting comments and suggestions for improvements. All users of military standardization documents are invited to provide suggestions. This form may be detached, folded along the lines indicated, taped along the loose edge *(DO NOT STAPLE)*, and mailed. In block 5, be as specific as possible about particular problem areas such as wording which required interpretation, was too rigid, restrictive, loose, ambiguous, or was incompatible, and give proposed wording changes which would alleviate the problems. Enter in block 6 any remarks not related to a specific paragraph of the document. If block 7 is filled out, an acknowledgement will be mailed to you within 30 days to let you know that your comments were received and are being considered.

NOTE This form may not be used to request copies of documents, nor to request waivers, deviations, or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements.

(Fold along this line)

(Fold along this line)

DEPARTMENT OF THE NAVY

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

BUSINESS REPLY MAIL
FIRST CLASS PERMIT NO 12503 WASHINGTON D C

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Commandant of the Marine Corps
Headquarters, U.S. Marine Corps
(Code LMA-3)
Washington, D.C. 20380

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T23:01Z
Check the source to verify that this is the current version before use.