MIL-C-28663A(YD)
15 October 1982
SUPERSEDING
MIL-C-28663(YD)
22 July 1974

MILITARY SPECIFICATION

COMPACTOR, SELF-PROPELLED, EMBANKMENT, COMMERCIAL (ROLLER, SEGMENTED, MOTORIZED, WITH LEVELING BLADE)

This specification is approved for use by the Naval Facilities Engineering Command, Department of the Navy, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the requirements for a commercial, embankment, self-propelled compactor.

1.2 Classification. Self-propelled compactors shall be one of the following types, as specified (see 6.2).

Type I - 35,000-pound weight minimum.
Type II - 55,000-pound weight minimum.

2. APPLICABLE DOCUMENTS

2.1 Government documents.

2.1.1 Specifications and standards. Unless otherwise specified (see 6.2), the following specifications and standards of the issue listed in that issue of the Department of Defense Index of Specifications and Standards (DODISS) specified in the solicitation form a part of this specification to the extent specified herein.

SPECIFICATIONS

FEDERAL

W-B-131 - Battery, Storage, Vehicular, Ignition, Lighting, and Starting.

MILITARY

MIL-V-173 - Varnish, Moisture-and-Fungus-Resistant (For Treatment of Communications, Electronic, and Associated Equipment).
MIL-R-3075 - Roller, Motorized, Road, Diesel- or Gasoline-Engine-Driven, Packaging of.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commanding Officer (Code 156), Naval Construction Battalion Center, Port Hueneme, CA 93043, by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

FSC 3895

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

STANDARD

MILITARY

MIL-STD-209 - Slinging and Tiedown Provisions for Lifting and Tying Down Military Equipment.

2.2 Other Government documents. The following other Government documents form a part of this specification to the extent specified herein.

DEPARTMENT OF LABOR (DOL)
OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA)

Occupational Safety and Health Standards.

(Application for copies should be addressed to the Superintendent of Documents, Government Printing Office, Washington, DC 20402.)

2.3 Other publications. The following documents form a part of this specification to the extent specified herein. The issues of the documents which are indicated as DOD adopted shall be the issue listed in the current DODISS and the supplement thereto, if applicable.

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

D1557 - Moisture-Density Relations of Soil and Soil Aggregate Mixtures Using 10-lb (4.5-kg) Rammer and 18-in. (457-mm) Drop, Test for.
D2487 - Soils for Engineering Purposes, Classification of.

(Application for copies should be addressed to the American Society for Testing and Materials, 1916 Race Street, Philadelphia, PA 19103.)

SOCIETY OF AUTOMOTIVE ENGINEERS, INC. (SAE)

J534 - Lubrication Fittings.
J598 - Sealed Lighting Units for Construction and Industrial Machinery.
J1136 - Braking Performance - Rollers and Compactors, Recommended Practice.

(Application for copies should be addressed to the Society of Automotive Engineers, Inc., 400 Commonwealth Drive, Warrendale, PA 15096.)

(Industry association specifications and standards are generally available for reference from libraries. They are also distributed among technical groups and using Federal agencies.)

2.4 Order of precedence. In the event of a conflict between the text of this specification and the references cited herein, the text of this specification shall take precedence.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), the contractor shall furnish a compactor for first article inspection and approval (see 4.2.1 and 6.4).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

3.2 Standard commercial product. The compactor shall, as a minimum, be in accordance with the requirements of this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not specifically prohibited by this specification but which are a part of the manufacturer's standard commercial product shall be included in the compactor being furnished. A standard commercial product is a product which has been sold or is being currently offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures, and represents the latest production model.

3.3 Materials. Materials used shall be free from defects which would adversely affect the performance or maintainability of individual components or of the overall assembly. Materials not specified herein shall be of the same quality used for the intended purpose in commercial practice. Unless otherwise specified herein, all equipment, material, and articles incorporated in the work covered by this specification are to be new and fabricated using materials produced from recovered materials to the maximum extent possible without jeopardizing the intended use. The term "recovered materials" means materials which have been collected or recovered from solid waste and reprocessed to become a source of raw materials, as opposed to virgin raw materials. None of the above shall be interpreted to mean that the use of used or rebuilt products are allowed under this specification unless otherwise specified.

3.4 Interchangeability. All units of the same classification furnished with similar options under a specific contract shall be identical to the extent necessary to insure interchangeability of component parts, assemblies, accessories, and spare parts.

3.5 Maintainability. The compactor shall be designed so that components are readily accessible for repair or replacement, with minimum removal or disturbance of adjacent parts or components, using general-purpose tools. Operating parts, accessories, and drain outlets shall be readily accessible for regular maintenance service.

3.6 Safety. All rotating or reciprocating parts and all parts subject to high operational temperatures, that are of such nature or are so located as to be or become a hazard to the operating or attending personnel, shall be guarded or insulated to the extent necessary to eliminate the hazard. When specified (see 6.2), a rollover protective structure of the closed cab or open canopy type will be provided. Ladders, steps, and handholds shall be provided for easy access to the control station. Guardrails shall be provided on the outer extremities of the control station except where access is required. All walking surfaces shall be provided with an antiskid surface. An audible reverse alarm shall be provided. All safety features shall be in accordance with applicable DOL, OSHA Standards.

3.7 Performance.

3.7.1 Operation. The compactor shall be capable of light bulldozing and leveling of loose material. The compactor shall be capable of obtaining a speed of not less than 9 miles per hour (mph) for type I and 11 mph for type II in high gear on a firm level surface. The compactor shall be capable of negotiating a 15 percent slope.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

3.7.2 Compaction. The compactor shall be capable of compaction over the complete range of sand-clay class soils with a plasticity index of 10 to 25 in accordance with ASTM D2487 to a density not less than 95 percent Modified Proctor. Plasticity and density shall be determined in accordance with ASTM D1557. Type I compactors shall compact at a rate of not less than 600 compacted cubic yards per hour and type II compactors at a rate not less than 1,500 compacted cubic yards per hour, when tested in accordance with 4.4.2.

3.8 Design. The compactor shall consist essentially of a steel frame, foot- or pad-type steel tamping drums, and a hydraulically actuated leveling blade, and shall be diesel engine-powered. The compactor shall be furnished complete in all details, including those not specifically mentioned herein.

3.8.1 Frame. The frame shall be fabricated from steel plate or rolled sections. The frame shall be of the articulated type. The frame or axle wheel shall be constructed to allow wheel oscillation.

3.8.2 Engine. The compactor shall be powered by one or more diesel engines. The diesel engines shall have horsepower (hp), torque, and speed characteristics to meet satisfactorily all operation and compaction requirements specified herein. Hp shall be not less than 185 net flywheel hp for type I compactors and not less than 300 net flywheel hp for type II compactors. The diesel engines shall start in any temperature above -20° Fahrenheit (F). Starting aids may be either electric glow plug or ether primer. When an ether priming system is required, it shall be of the measured shot type with storage capacity of not less than 12 fluid ounces. The engine shall be furnished with the manufacturer's standard accessories and, as a minimum, complete with the following accessories:

a. An instrument and control panel located at the operator's station fitted with, but not limited to, the following:

   (1) Start-stop control.
   (2) Liquid quantity fuel indicator.
   (3) Lubricating oil pressure indicator.
   (4) Cooling liquid temperature indicator.
   (5) Battery charging indicator.
   (6) Transmission oil temperature indicator.
   (7) Hour meter. An engine hour meter have a totalizing mechanism of not less than 9,999 hours shall be furnished to register accurately the number of hours of engine operating time. Meter shall be of strong rugged construction to insure continuous trouble-free performance under the most extreme equipment operating conditions indicated in this specification.
   (8) Safety control devices of the visual or audible type for high coolant temperature and low lubricating oil pressure.

b. A 12- or 24-volt electrical cranking system. When specified (see 6.2), batteries furnished shall be dry charged in accordance with W-B-131, without electrolyte and with sealed caps to prevent the intrusion of atmospheric moisture.
c. A battery charging alternator with a rating of not less than 35 amperes.
d. A 2-stage, dry-type, intake air cleaner with service indicator.
e. A raincap is to be furnished on vertical exhaust systems.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

3.8.2.1 Engine housing. A housing shall be provided to protect the engine from adverse weather. Housing doors or covers shall be provided to allow accessibility to any engine component requiring routine maintenance or repair. Latches shall be provided to hold all doors or covers in the closed position. Hinged doors or covers shall be designed to permit their being restrained in an open position. The housing shall be removable or otherwise designed to permit engine removal and replacement.

3.8.2.2 Fuel tank. The fuel tank shall be of sufficient capacity for not less than 8 hours of normal operation.

3.8.3 Power train. Engine power shall be transmitted through a torque converter with full power shifting in a minimum of three forward and two reverse gears, or engine power may be transmitted through a full hydrostatic drive with infinitely variable speed control in forward and reverse.

3.8.4 Steering system. Full power hydraulic steering shall be provided.

3.8.5 Brakes. Service brakes and parking brakes shall be independently located and actuated. Parking brakes shall be provided with a warning device located at the control station. Service brakes shall be air or hydraulically actuated. Compactors equipped with airbrakes shall be provided with an air pressure indicator and warning device located at the control station. Service brakes and parking brakes shall meet the performance criteria of SAE J1136.

3.8.6 Operator's station. The operator's station shall be furnished with controls, an instrument panel, and an operator's seat. All controls necessary to operate the compactor shall be located at the station. Instruments shall be visible and controls shall be easily accessible to the operator in his normal sitting position. All controls and instruments shall be clearly identified for their intended operation and function with permanently affixed identification plates made of corrosion-resistant material. The operator's seat shall be adjustable. The seat and backrest shall be covered with a durable, waterproof covering. The seat shall be in a position that shall provide the operator, while seated in a normal operating position, with an unobstructed 360° view.

3.8.7 Compaction wheels. Each wheel shall have a means to prevent the accumulation of material on the wheel when the compactor is propelled in a forward or reverse direction. The tamping foot tips shall be of the replaceable type, either bolt-on, pin-on, or weld-on.

3.8.8 Leveling blade. The leveling blade shall be hydraulically operated and shall have a replaceable cutting edge. The blade width shall be more than the compaction width. The blade height shall be not less than 24 inches. Hydraulic controls shall include lift, lower, float, and hold.

3.8.9 Lighting system. A complete 12- or 24-volt lighting system shall be provided. The lighting system shall include at least two forward and two rearward directed sealed-beam lights. All wiring shall be protected against wearing and weathering and shall be secured so that no section exceeding 3 feet is unsupported. Controls shall be provided for forward and rearward directed lights. Controls shall be clearly identified. Sealed-beam lights shall conform to SAE J598 and shall be provided with lamp housings. Sealed-beam lights shall be used to floodlight the work area and to permit safe travel at night.

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

Panel lamps shall be provided on the instrument panel for night illumination of all instruments. The circuit for panel lamps shall be actuated by the controls for the sealed-beam lights.

3.8.10 Toolbox. The compactor shall be provided with a closed toolbox to carry tools and accessories required for operator maintenance. The toolbox shall have a hinged lid and latching mechanism to keep the lid secured during operation of the compactor. The toolbox shall be mounted in a protected and accessible position.

3.8.11 Lifting and tiedown attachments. The compactor shall be equipped with lifting and tiedown attachments. Lifting and tiedown attachments shall conform to type II or type III of MIL-STD-209. A nonferrous transportation plate shall be provided and mechanically attached to the compactor. Transportation plates shall be inscribed with a diagram showing the lifting attachments and lifting slings, the capacity of each attachment, and the required length and size of each sling cable. A silhouette of the compactor showing the center of gravity shall be provided on the transportation plate. Tiedown attachments may be identified by stenciling or other suitable marking. Tiedown marking shall clearly indicate that the attachments are intended for tying down the compactor on the carrier when shipped.

3.9 Lubrication. Lubrication means shall be provided for all moving parts requiring lubrication. Hydraulic fittings shall be in accordance with SAE J534. Pressure lubrication fittings shall not be used where normal lubricating pressure may damage grease seals or other parts. The compactor shall be lubricated prior to delivery with lubricants designated for use in the 0° to 32°F temperature range. The unit shall be conspicuously tagged to identify the lubricants and their temperature range.

3.10 Instruction plates. The compactor shall be equipped with instruction plates suitably located, describing any special or important procedures to be followed in operating and servicing the equipment. Plates shall be of a material which will last and remain legible for the life of the equipment and shall be securely affixed thereto with nonferrous screws or bolts of not less than 0.125-inch diameter.

3.11 Nameplate. A nameplate will be furnished by the contracting officer for each compactor. The contractor shall stamp all necessary data in the blank spaces of the plate provided for that purpose, and securely affix a plate to each compactor in a conspicuous place with brass screws or bolts not less than 0.125 inch in diameter. The applicable nomenclature contained in the contract item description shall be placed in the top blank.

3.12 Cleaning, treatment, and painting. Surfaces normally painted in good commercial practice shall be cleaned, treated, and painted as specified herein. The color of the finish coat shall be as specified (see 6.2). Surfaces to be painted shall be cleaned and dried to insure that they are free from contaminants such as oil, grease, welding slag and spatter, loose mill scale, water, dirt, corrosion product, or any other contaminating substances. As soon as practicable after cleaning, and before any corrosion product or other contamination can result, the surfaces shall be prepared or treated to insure the adhesion of the coating system. The painting shall consist of at least one coat of primer and one finish coat. The primer shall be applied to a clean,

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

dry surface as soon as practicable after cleaning and treating. Painting shall be with manufacturer's current materials according to manufacturer's current processes and the total dry film thickness shall be not less than 2.5 mils over the entire surface. The paint shall be free from runs, sags, orange peel, or other defects. When specified (see 6.2), the compactor, allied equipment, and attachments shall be the same color.

3.13 Fungus resistance. When specified (see 6.2), electrical components and circuit elements, including terminal and circuit connections, shall be coated with varnish conforming to MIL-V-173, except that:

a. Components and elements inherently inert to fungi or in hermetically sealed enclosures need not be coated.
b. Current-carrying contact surfaces, such as relay contact points, shall not be coated.

3.14 Workmanship.

3.14.1 Steel fabrication. The steel used in fabrication shall be free from kinks, sharp bends, and other conditions which would be deleterious to the finished product. Manufacturing processes shall not reduce the strength of the steel to a value less than intended by the design. Manufacturing processes shall be done neatly and accurately. All bends shall be made by controlled means to insure uniformity of size and shape.

3.14.2 Bolted connections. Boltholes shall be accurately punched or drilled and shall have the burrs removed. Washers or lockwashers shall be provided in accordance with good commercial practice, and all bolts, nuts, and screws shall be tight.

3.14.3 Riveted connections. Rivet holes shall be accurately punched or drilled and shall have the burrs removed. Rivets shall be driven with pressure tools and shall completely fill the holes. Rivet heads, when not countersunk or flattened, shall be of approved shape and of uniform size for the same diameter of rivet. Rivet heads shall be full, neatly made, concentric with the rivet holes, and in full contact with the surface of the member.

3.14.4 Welding. Welding procedures shall be in accordance with a nationally recognized welding code. The surface of parts to be welded shall be free from rust, scale, paint, grease, or other foreign matter. Welds shall be of sufficient size and shape to develop the full strength of the parts connected by the welds. Welds shall transmit stress without permanent deformation or failure when the parts connected by the weld are subjected to proof and service loadings.

3.14.5 Castings. All castings shall be sound and free from patching, misplaced coring, warping, or any other defect which reduces the casting's ability to perform its intended function.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract or purchase order, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

in the contract or purchase order, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2.1).
b. Quality conformance inspection (see 4.2.2).

4.2.1 First article inspection. The first article inspection shall be performed on a compactor when a first article is required (see 3.1 and 6.2). This inspection shall include the examination of 4.3 and the tests of 4.4. The first article may be either a first production item or a standard production item from the supplier's current inventory provided the item meets the requirements of the specification and is representative of the design, construction, and manufacturing technique applicable to the remaining items to be furnished under the contract.

4.2.2 Quality conformance inspection. The quality conformance inspection shall include the examination of 4.3, the test of 4.5, and the packaging inspection of 4.6.

4.3 Examination. Each compactor shall be examined for compliance with the requirements specified in section 3 of this specification. Any redesign or modification of the contractor's standard product to comply with specified requirements, or any necessary redesign or modification following failure to meet specified requirements, shall receive particular attention for adequacy and suitability. This element of inspection shall encompass all visual examinations and dimensional measurements. Noncompliance with any specified requirements or presence of one or more defects preventing or lessening maximum efficiency shall constitute cause for rejection.

4.4 First article tests. The first article compactor shall be subjected to the tests specified in 4.4.1, 4.4.2, and 4.4.3. Failure to pass one or more tests shall be cause for rejection.

4.4.1 Operational test. The test course shall have a relatively level grade with a rough surface. The degree of roughness shall be sufficient to measure the wheels ability to oscillate to the required limit. The course shall be not less than 200 feet long. The width shall be sufficient to allow the compactor to turn around without reversing. The operator shall maintain the highest possible travel speed as dictated by the roughness of the course and without jeopardizing good safety practices. The compactor shall be operated 8 hours in both figure eight forward and reverse modes of operation. Two hours of the test shall consist of figure eight turns at the minimum turning radius and at the maximum safe operating speed. The compactor shall utilize all available transmission ranges during the operational phase of the test. After the test area is compacted to a density of 90 percent Modified Proctor the soil shall be loosened. Auxiliary equipment may be utilized to loosen the soil. The compactor blade shall be utilized for leveling of loose material

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

over the test area. The compactor will again begin compaction of the soil and shall continue compaction and blade cycle until 8 hours of operation has elapsed. At the start of the operational test, while the brake shoes and brake drums are cold, the compactor shall be driven at maximum speed in reverse gear and the brakes shall be applied in a panic stop. The compactor shall then be driven at maximum forward speed and the brakes shall be applied in a panic stop. The compactor shall be observed to determine conformance to the maintainability, performance, and design requirements of 3.5, 3.7, and 3.8.

4.4.2 Compaction test. The compaction test shall be performed on an area of ground not less than 40 feet by 300 feet. Prior to testing, the test area shall be cleared of 6 inches of soil, including all organic material, and compacted to a density of not less than 95 percent Modified Proctor. Material used for the compaction test shall be as designated in 3.7.2. A lift of sufficient thickness to give a compacted lift of 6 to 8 inches shall be spread over the area. Water distribution equipment may be used as required. Methods for soil and water distribution shall provide for the least amount of traffic over the test area before compaction. The compactor shall be operated on the test area until a density of not less than 95 percent Modified Proctor is achieved. The procedure shall be repeated until three lifts have been compacted. Density testing shall be accomplished by a nuclear testing meter calibrated against the soil being tested. The production rate shall be measured in compacted cubic yards per hour. Production rates less than those specified in 3.7.2 shall be cause for rejection.

4.4.3 Brake test. The compactor shall be completely stopped five times with the service brakes from maximum speed on dry level ground. The distance from the point of application to the actual stop shall be measured on the fifth pass to determine conformance to 3.8.5. The test shall be conducted in both forward and reverse. Parking brake test shall be conducted with the compactor headed up and down slope to determine conformance to 3.8.5.

4.5 Quality conformance test. Each compactor shall be completely assembled, properly adjusted, and otherwise serviced for operation. Each compactor shall be operated for not less than 1 hour. All controls shall be operated as many times as necessary, but not less than 30 times, to determine ease of operation, effectiveness, and responsiveness and that the mechanisms actuated by the controls operate promptly, fully, and without restriction, malfunction, or excessive vibration. Gearcases, bearings, and other moving parts shall be examined for excessive heating or abnormal operation insofar as is practicable and possible. The entire compactor shall be examined for evidence of failure, slippage, or deformation. Failure to pass any phase of this test shall be cause for rejection.

4.6 Packaging inspection. The inspection of the preservation, packing, and marking shall be in accordance with the requirements of section 4 of MIL-R-3075. The inspection shall consist of the quality conformance inspection and, when specified (see 6.2), a preproduction pack shall be furnished for examination and test within the time frame required (see 6.2).

5. PACKAGING

5.1 Preservation, packing, and marking. Preservation, packing, and marking shall be in accordance with the requirements of MIL-R-3075 with the level of preservation and the level of packing as specified (see 6.2).

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

6. NOTES

6.1 Intended use. Compactors covered by this specification will be used for embankment compaction on dams, runways, or roadways.

6.2 Ordering data. Acquisition documents should specify the following:

a. Title, number, and date of this specification.
b. Type of compactor (see 1.2).
c. Issue of document required if other than as specified (see 2.1.1).
d. When a first article is required for inspection and approval (see 3.1, 4.2.1, and 6.4).
e. When a rollover protection structure is required and which type (see 3.6).
f. When batteries furnished are to be dry charged (see 3.8.2).
g. Required finish coat color (see 3.12).
h. When treatment for fungus resistance is required (see 3.13).
i. When a preproduction pack inspection is required and the time frame required for submission (see 4.6).
j. Level of preservation and level of packing required (see 5.1).

6.3 Data requirements. When this specification is used in an acquisition which incorporates a DD Form 1423 and invokes the provisions of paragraph 7-104.9(n) of the Defense Acquisition Regulations (DAR), the data requirements will be developed as specified by an approved Data Item Description (DD Form 1664) and delivered in accordance with the Contract Data Requirements List (DD Form 1423) incorporated into the contract. When the provisions of DAR 7-104.9(n) are not invoked, the data shall be delivered in accordance with the contract requirements.

6.4 First article. When a first article inspection is required, the item will be tested and should be a first article sample, or it may be a standard production item from the contractor's current inventory as specified in 4.2.1. The first article should consist of one unit. The contracting officer should include specific instructions in acquisition documents regarding arrangements for examination, test, and approval of the first article.

6.5 Changes from previous issue. Asterisks are not used in this revision to identify changes with respect to the previous issue, due to the extensiveness of the changes.

Custodian:

Navy - YD

Preparing activity:

Navy - YD

Project No. 3895-N205

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

INSTRUCTIONS: This form is provided to solicit beneficial comments which may improve this document and enhance its use. DoD contractors, government activities, manufacturers, vendors, or other prospective users of the document are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity. A response will be provided to the submitter, when name and address is provided, within 30 days indicating that the 1426 was received and when any appropriate action on it will be completed.

NOTE: This form shall not be used to submit requests for waivers, deviations or clarification of specification requirements on current contracts. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. 3895-N205

DOCUMENT IDENTIFIER *(Number)* AND TITLE MIL-C-28663A(YD) - COMPACTOR, SELF-PROPELLED, EMBANKMENT, COMMERCIAL (ROLLER, SEGMENTED, MOTORIZED, WITH LEVELING BLADE)

NAME OF ORGANIZATION AND ADDRESS OF SUBMITTER

☐ VENDOR ☐ USER ☐ MANUFACTURER

1. ☐ HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE? ☐ IS ANY PART OF IT TOO RIGID, RESTRICTIVE, LOOSE OR AMBIGUOUS? PLEASE EXPLAIN BELOW.

A. GIVE PARAGRAPH NUMBER AND WORDING

B. RECOMMENDED WORDING CHANGE

C. REASON FOR RECOMMENDED CHANGE(S)

2. REMARKS

SUBMITTED BY *(Printed or typed name and address — Optional)*

TELEPHONE NO.

DATE

DD FORM 1426 1 OCT 76

Replaces edition of 1 Jan 72 which may be used.

S/N 0102-LF-001-4260

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.

FOLD

DEPARTMENT OF THE NAVY

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

NO POSTAGE
NECESSARY
IF MAILED
IN THE
UNITED STATES

BUSINESS REPLY MAIL

FIRST CLASS PERMIT NO. 12503 WASHINGTON D. C.

POSTAGE WILL BE PAID BY THE DEPARTMENT OF THE NAVY

Commanding Officer (156)
Naval Construction Battalion Center
Port Hueneme, CA 93043

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-20T13:34Z
Check the source to verify that this is the current version before use.