MILITARY SPECIFICATION

TRANSMITTING SET, RADIO AN/ART-36(*)

This specification has been approved by the
Bureau of Naval Weapons, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall provide the radio frequency transmission facility for the combined Data Communication Systems AN/USC-2. Operationally, the equipment shall provide transmission of UHF signals frequency shift modulated with digital data information.

1.2 Classification - The AN/ART-36 shall consist of the following items:

Item	Type Designation	Appl. Par.
Transmitter, Radio	T-713(*)/ART-36	3.4.1
Mounting	MT-2108(*)/ART-36	3.4.1.2

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids, form a part of this specification to the extent specified herein:

SPECIFICATIONS

Military

MIL-C-172	Cases; Bases, Mounting; and Mounts, Vibration (For Use with Electronic Equipment in Aircraft)
MIL-E-4682	Electron Tubes and Transmitters, Choice and Application of
MIL-W-5088	Wiring; Aircraft, Installation of
MIL-E-5400	Electronic Equipment, Aircraft, General Specification for
MIL-T-5422	Testing, Environmental, Aircraft Electronic Equipment
MIL-I-6181	Interference Control Requirements, Aircraft Equipment
MIL-P-17555	Preparation for Delivery of Electronic, Electrical, and Electro-Mechanical Equipment and Associated Repair Parts

FSC 5821

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.

MIL-T-18303	Test Procedures, Preproduction and Inspection, For Aircraft Electronic Equipment, Format for
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronic and Associated Equipment

STANDARDS

Military

MIL-STD-704	Electric Power, Aircraft, Characteristics and Utilization of
MS 25245	Connections, Input Power Airborne Electronic Equipment; 28-Volt DC, 115-Volt Single-Phase AC, or 115/200 Volt 3-Phase AC, or Combinations.

PUBLICATIONS

Bureau of Naval Weapons

SAR-300	Material Changes and Material Bulletins, Preparation of

2.2 Availability of Documents

(1) When requesting specifications, standards, drawings, and publications refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code CDS, 5801 Tabor Avenue, Philadelphia 20, Pennsylvania.

3. REQUIREMENTS

3.1 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing the following shall govern:

(1) Parts and materials requirements shall conform to Specification MIL-E-5400.

(2) Nonrepairable subassemblies, as outlined in specification MIL-E-5400, shall be used when practicable. The general size of the subassembly, and the amount of circuitry to be included therein shall be approved by the procuring activity. Nonrepairable subassemblies must be reliable. A mean-time-to failure of more than 5000 hours should be the goal of each.

(3) When previously produced models of this equipment did not use nonrepairable subassemblies, the design shall not be changed to employ nonrepairable assemblies without the approval of the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 202640-19T13:38Z
Check the source to verify that this is the currentversion before use.

3.1.1 Nonstandard Parts and Material Approval - Approval for the use of nonstandard parts and materials shall be obtained as outlined in Specification MIL-E-5400.

3.1.2 Electron Devices - Electron tubes, transistors and diodes shall be chosen and applied, and the complements reported as outlined in Specification MIL-E-4682. The complement report must be submitted to the procuring activity for review and approval prior to preproduction testing.

3.2 Design and Construction:

3.2.1 General - The equipment shall conform with all the applicable requirements of Specification MIL-E-5400 for design, construction and workmanship, unless otherwise specified herein.

3.2.2 Total Weight - The total weight of the equipment, excluding cables, shall be a minimum consistent with good design and shall not exceed 49.2 pounds.

3.2.3 Operating Life -

3.2.3.1 Operational Stability - The equipment shall operate with optimum performance for 20 hours, continuously or intermittently, without the necessity for readjustment of any controls which are inaccessible during flight.

3.2.3.2 Reliable Operating Life - The equipment shall have a reliable operating life of at least 200 hours without removal for bench servicing. Parts requiring servicing or replacement at the end of this interval to renew this service life shall be specified by the manufacturer.

3.2.3.3 Total Operating Life - The equipment shall have a minimum total operating life of 2000 hours with reasonable servicing and replacement of parts. Parts requiring replacement within this interval and the life of such parts shall be specified by the manufacturer.

3.2.4 Cabling and Connections -

3.2.4.1 Cables and Connectors - The equipment shall provide for the use of Cables and connectors in accordance with Specification MIL-E-5400.

3.2.4.2 Interconnection Cabling - The equipment shall be capable of satisfactory operation using external wiring in accordance with the applicable requirements of Specification MIL-W-5088. The external wiring shall be unshielded, except that a minimum number of the individual wires may be shielded when demonstrated as necessary to meet interference control requirements and provided the assembly of the cable to its plugs may be easily accomplished. External cables and that portion of the connectors attached to the cables shall not be supplied as part of the equipment.

3.2.4.3 Input Power Connection - Input power connections shall be in accordance with MS 25245.

3.2.5 Interchangeability - The equipment shall meet the interchangeability requirements as defined in Specification MIL-E-5400.

3.2.6 Interference Control - The generation of radio interference by the equipment and the vulnerability of the equipment to radio interference shall be controlled within the limits of Specification MIL-I-6181.

Source: https://assist.dla.mil -- Downloaded: 202610-19T13:38Z
Check the source to verify that this is the currentversion before use.

3.2.7 Maintenance Provisions and Field Testing - Provisions for maintenance shall be as specified in Specification MIL-E-5400. Specific test points and test facilities shall be provided to the greatest extent practicable for ease of field testing and maintenance.

3.2.8 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.2.9 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient (30° ±10°C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity
Input power voltage	115 ±1.0 V AC and/or 27.5 ± 0.5 V DC

3.2.10 Service Conditions - The equipment shall operate satisfactorily under any of the environmental service conditions or reasonable combination of these conditions as specified in Specification MIL-E-5400 for Class 1 equipment, except as modified herein.

3.2.10.1 Vibration - The equipment shall operate satisfactorily when subjected to the vibration requirements of Curves I and II of Specification MIL-E-5400.

3.2.11 Warm-Up Time - The time required for the equipment to warm-up prior to operations shall be kept to a minimum and shall not exceed 5 minutes under standard conditions and 5 minutes at extreme service conditions.

3.2.12 Primary Input Power Requirements - The equipment shall meet all applicable requirements of MIL-STD-704 and shall give specified performance from the following power sources with characteristics as defined in MIL-STD-704 having limits as specified therein. The power required shall not exceed the specified amounts.

(1) AC Power (Three-Phase) 115/200V, Category "B" 320 VA

(2) DC Power 28V Category "B" 0.5 Amp Normal transmit
7.5 Amps Channel Change

3.2.12.1 Undervoltage Protection - The equipment shall not be damaged by voltages under the minimum specified herein and shall automatically resume normal operation when the voltage returns within limits.

3.2.13 Terminations - The equipment shall have the following input and output terminations:

3.2.13.1 Transmitter RF - The r-f output load (dummy antenna) shall consist of ten feet of AN type RG-8U transmission line, terminated in a 52-ohm non-inductive load which shall include means suitable for measuring the r-f power output.

3.2.13.2 Transmitter Data Input - The data input circuit of the transmitter shall present a load of not less than 2500 ohms to the signal source.

3.2.14 Presurization - The requirements of this equipment shall comply with the appropriate paragraphs of MIL-E-5400 except that a desiccant is not required, a safety valve is not required, mechanical pressurization pumps shall not be built into the equipment and the case shall be designed to be pumped with dry air to a differential of 2 to 4 pounds per square inch at sea level pressures and room ambient temperatures.

Source: https://assist.dla.mil -- Downloaded: 20260-19T13:38Z
Check the source to verify that this is the current version before use.

3.3 Performance

3.3.1 General - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.3.2 Frequency Channels - By means of Control, Radio Set C-2736/ARC or equivalent, it shall be possible to select any frequency in the range of 225.0 mc to 399.9 mc in 0.1 mc increments. These main channel frequencies shall correspond with the arithmetic series 225.00, 225.10, 225.20, 225.30 - - - - - - - - 399.9 mc.

3.3.3 R-F Power Output - The transmitter shall be capable of delivering the following values of r-f carrier energy within the range described below:

	225.0 to 399.9 mc
Standard Conditions	20 watts average, 16 watts minimum
Service Conditions	9 watts
Reduced Performance Test	500 mw

3.3.4 Modulation Characteristics - The transmitter shall meet the following requirements for modulation when operated under both standard and service conditions:

3.3.4.1 Type of Modulation - The transmitter shall employ frequency shift modulation.

3.3.4.2 Capability - The modulation capability shall be such that +5.0 volts applied to the data input terminals shall increase the carrier frequency 20 kc (-10%) and -5.0 volts applied to the data input terminals shall decrease the carrier frequency 20 kc (-10%).

3.3.4.3 Transmitter Noise Level - Without modulation, the frequency deviation developed by internal noise shall not exceed 5% of the peak-to-peak deviation of the data signal.

3.3.4.4 Transmitter Frequency Linearity - The FSK modulated r-f frequency shall be linear within 5% of the maximum peak-to-peak frequency deviation over a range of data input voltage levels between 0 volts and ±5.0 volts.

3.3.4.5 Transmitter Frequency Response - The peak-to-peak frequency deviation shall not vary more than 5% with a sine wave modulated signal applied to the data input terminals of constant level and over the frequency range from 0 to 7000 cps.

3.3.5 Spurious Radiation - The magnitude of all radiated signals on other than the carrier frequency shall be 40 db or more below the carrier signal, except that harmonic frequencies shall be attenuated not less than 55 db at 450 mc with a linear increase to 75 db at 525 mc. The attenuation above 525 mc shall be 75 db or greater.

3.3.6 Frequency Stability - The frequency stability of the complete equipment after operation under either standard or service conditions for five minutes or more shall be such as to maintain the equipment frequencies within ±7 kc provided the external ambient temperature does not exceed 55°C. These limits shall include drift and calibration.

3.3.7 Channel Changing Cycles - The time elapsing between the instant the channel selector switch is positioned to select a given channel and the instant the equipment is in an operative condition on the selected channel shall not be greater than six seconds under service conditions. This requirement shall hold for shifting the operating frequency of the equipment between any two available channels.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.

3.3.8 Accuracy of Automatic Tuning - When the same frequency channel is selected several times in succession, the transmitter r-f power output shall not vary by more than 0.5 db from the power output obtained initially. This requirement shall be met under standard or service conditions provided such conditions are static.

3.3.9 Cable Length - Under the standard or service conditions the equipment shall operate as required by this specification when using control cables up to 25 feet in length fabricated from #22 AWG copper wire, or when using cables up to 110 feet in length fabricated from #16 AWG wire.

3.3.10 Leakage Power - Leakage r-f power from the transmitter shall not exceed -85 dbm at the operating frequency when in a condition prepared to transmit.

3.3.11 Carrier - On Operation - The T-713/ART-36 shall normally remain in a condition prepared to transmit. Application of an A-C keying voltage having the following characteristics shall key the transmitter. The magnitude of the keying pulses shall be between 13 volts peak to peak and 25 volts peak to peak, maximum deviation of the voltage shall be within +10 volts and -30 volts.

3.3.12 Carrier - On Keying Time - 80% of the specified r-f output power shall be developed within 160 microseconds after application of each "Carrier - On" pulse. The r-f output power shall decrease to not more than -85 dbm within 80 microseconds after cessation of the "Carrier - On" pulse.

3.4 Detail Requirements

3.4.1 Transmitter, Radio T-713(*)/ART-36 - The transmitter shall meet the following requirements:

3.4.1.1 Function - The transmitter shall generate r-f power and transmit it to the load specified herein. The r-f energy shall be frequency shift keyed by digital information supplied in time division sequence from associated data multiplex equipment.

3.4.1.2 Form Factor and Mounting - The transmitter shall be contained in a single sealed case which shall meet the applicable requirements of Specification MIL-C-172 and shall be capable of being mounted in an aircraft by means of Mounting MT-2108/ART-36. It shall be possible to dismount the unit from its mounting base and remove it from the case using ordinary hand tools and without requiring removal of any cables other than the front panel coaxial and power connectors. Mounting MT-2108/ART-36 shall be arranged to furnish all support required by the transmitter unit and shall provide space between the mounting rails for the entrance air duct which is part of the sealed case assembly. The transmitter dimensions shall not exceed 7-1/2 inches high by 10-1/8 inches wide by 18-1/2 inches long and the mounting shall not exceed 3 inches high by 11-1/4 inches wide by 18 inches long. When the transmitter unit is attached to the mounting and located on a horizontal plane surface, the overall dimensions shall not exceed 8-1/8 inches high by 11-1/4 inches wide by 18-9/16 inches long.

3.4.1.3 Contents of the Unit - This unit shall contain the complete transmitter, FSK modulator, direct crystal-controlled frequency generator, frequency selection system, automatic tuning devices, directional coupler, low pass filter, and all other parts to make the equipment function as a unit except the radio set control specified herein. It shall be possible to remove or replace any plug-in unit located on the main chassis using ordinary hand tools and without unsoldering any connections. It shall be further possible to replace any plug-in unit with another without resynchronization except that realignment of tuning elements may be necessary.

3.4.1.4 Weight - The combined weight of the transmitter and mounting shall not exceed 49.2 pounds. The transmitter weight shall not exceed 46.0 pounds and the mounting 3.2 pounds.

Source: https://assist.dla.mil -- Downloaded: 2026[illegible]
Check the source to verify that this is the current version before use.

3.4.1.5 Electrical Connections

3.4.1.5.1 External - The following electrical connections shall be provided on the front panel of the transmitter.

(1) Coaxial connector Type N, for connection of transmitter to the antenna circuits.

(2) Amphenol Type 165-45 or equivalent connector shall be provided for connection of power and control circuits.

3.4.1.6 Controls External - The following controls shall be located on the front panel of the transmitter:

(1) Data input level control.

(2) Momentary contact switch for "Carrier - On" test purposes.

3.5 Associated Equipment - The equipment shall operate with the following associated equipment, which shall not be supplied as part of this equipment:

(1) Control, Radio Set C-2736/ARC or equivalent.

(2) AN/ASC-(*), AN/ASW-14 Digital Data Transmission system

(3) Antenna AT-141A/A (with RG-8/U Cable)

4. QUALITY ASSURANCE PROVISIONS

4.1 General - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable requirements:

(1) Preproduction Tests

(2) Production Sample Tests

(3) Acceptance Tests

(4) Life Tests

4.2 Preproduction Tests - Preproduction tests shall be made on one or more equipments representative of the production equipments to be supplied under the contract. Preproduction tests shall consist of the following:

(1) Contractor's Demonstration Tests

(2) Service Approval Tests

4.2.1 Contractor's Demonstration Tests - Contractor's demonstration tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure of 4.6. Data obtained by the contractor in conducting these tests shall be submitted to the procuring activity for review and approval prior to shipping the equipment to the specified destination for service approval tests. The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the service of a commercial testing laboratory satisfactory to the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.

4.2.2 Service Approval Tests - At the completion of the contractor's demonstration tests and when requested by the procuring activity, the equipment shall be delivered to a specified government laboratory for additional testing. This additional testing may consist of duplicating tests previously conducted and such other tests as are deemed necessary to determine compliance with all applicable design and performance requirements.

4.2.2.1 Accessory Material - In addition to the complete equipment submitted for service approval tests, the contractor shall also submit the accessory material and design and test data specified in Specification MIL-E-5400. This information shall indicate the physical and electrical characteristics of the equipment and establish the equipment's compliance with applicable requirements.

4.2.3 Scope of Tests - Preproduction tests shall include all tests deemed necessary to determine that the equipment meets all the requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with Specification MIL-T-5422 and interference tests in accordance with Specification MIL-I-6181.

4.2.4 Preproduction Approval - Approval of the preproduction model shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction model. Prefabrication of production equipment prior to the approval of the preproduction model is at the contractor's own risk. The approved preproduction model will be returned to the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction model shall not be considered as one of the equipments under the contract; however, it may be reworked by the contractor and submitted for acceptance as a production equipment.

4.3 Production Sample Tests - When requested by the procuring activity, one equipment shall be selected from the first 10 production equipments submitted for acceptance and sent to a designated government laboratory for tests. The equipment shall be selected by the government inspector after the equipment has successfully passed all individual tests.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction and performance and that it meets all applicable requirements.

4.3.2 Production Sample Approval - Approval of the production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Upon failure of the production sample to pass any of the tests, delivery of equipment under the contract shall cease until proper corrective action is approved and accomplished. Corrective action shall also be accomplished on equipment previously accepted when requested by the procuring activity.

4.3.3 Reconditioning of Production Test Sample - On completion of the production sample test the equipment shall be reworked by the contractor by replacing all wear or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T15:38Z
Check the source to verify that this is the current version before use.

(1) Individual Tests

(2) Sampling Tests

(3) Special Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, operational adequacy and reliability. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product

(2) Operational Test

(3) Manufacturing Reliability Test

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Reliability Test - Each equipment shall be operated under the conditions specified herein for a period of 6 hours without failure. A failure shall be defined as anything which causes malfunctioning of the equipment. Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

Temperature	Ambient room
Humidity	Ambient room
Vibration (10 minutes)	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of ± 3 g's

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 6-hour period of operation. Where feasible, the equipment shall be operated, during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to that plane for 5 minutes. Where it is not feasible to vibrate the equipment in 2 directions the vertical direction shall be used. During the 6-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The 6-hour period specified above may be composed of two 3-hour periods to conform with standard working hours.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.

4.4.2 Sampling Tests - Sampling tests shall be conducted on equipments which have successfully passed the individual tests. The following equipments shall be selected by the Government Inspector for sampling tests:

Quantity of Equipments Offered for Acceptance	Quantity to be Tested
First 10	1
Next 50	1
Next 75	1
Next 100	1
	1 for each additional 200 or fraction thereof

4.4.2.1 Scope of Tests - As a minimum, each equipment selected for sampling tests shall be subjected to the following tests:

(1) Complete operational test at ambient room conditions, making all necessary measurements to assure that all applicable specification requirements have been met.

(2) Operational test at certain environmental conditions. The conditions may vary for each equipment tested and should be based on results of the preproduction and special tests.

(3) Manufacturing reliability test specified in para. 4.4.1.3 except that the test duration shall be 120 hours with no restriction on the number of failures. However, each failure shall be analyzed as to cause and remedial action necessary to reduce the possibility of its recurrence in future equipment.

4.4.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the sampling tests.

4.4.3.1 Special Tests Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early production equipment.

(2) On an equipment midway of the production run.

(3) On an early equipment after an engineering change.

(4) Whenever failure reports or other information indicated additional equipments should be tested. (This will be determined by the procuring activity.)

Exceptions from the above may be necessary when the number of equipments procured under contract or other factors affecting performance may require a variation to assure satisfactory control.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.

4.4.3.2 Scope of Tests - Special tests shall consist of such tests as are approved by the procuring activity. Test procedures previously approved for the preproduction and sampling tests shall be used where applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests. As a minimum, the following tests shall be made, except that for those equipments selected as a result of design changes and failure reports, only those tests required to check the characteristics in question need be conducted.

(1) Temperature - Altitude Tests

(2) Vibration Test (60 minutes cycling in each of 3 planes)

(3) Humidity Tests

4.4.4 Equipment Failure - Should a failure occur during either the sampling of special tests, the following action shall be taken:

(1) Determine the cause of failure.

(2) Determine if the failure is an isolated case or design defect.

(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occuring in future tests.

(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.5 Life Test - A 300-hour life test shall be conducted at the contractor's plant on an early equipment representative of the current production. The life test shall be performed under the conditions specified in 4.5.1. The life test sample shall be selected by the government inspector in accordance with the following: When a production sample equipment is submitted to the procuring activity for test then the first equipment specified below need not be selected or subjected to this test. (Equipments which have successfully passed the sampling tests or special tests may be selected for life tests.

Quantity of Equipments Offered for Acceptance	Quantity to be Tested
First 25	1
Next 175	1
Next 300	1
	1 for each additional 500 or fraction thereof

Source: https://assist.dla.mil -- Downloaded: 202640-19T13:38Z
Check the source to verify that this is the currentversion before use.

4.5.1 Test Conditions - The life test shall be conducted under the following simulated service conditions

Temperature	Normal room
Altitude	Normal ground (0 - 5000 ft.)
Humidity	Room ambient
A. C. voltage	115 ± 5 volts (at lowest applicable frequency)
D. C. voltage	27.0 ± 2.0 volts

4.5.2 Test Periods - The test may be run continuously or intermittently. Any period of operation shall be of sufficient duration to permit the equipment temperature to stabilize. Periodically, the equipment shall be turned on and off several times and put through its various phases of operation.

4.5.3 Performance Check - At approximately 8-hour intervals during the test, a limited performance check shall be made. The performance check proposed by the contractor shall be subject to approval by the procuring activity.

4.5.4 Test Data - The contractor shall keep a daily record of the performance of the equipment, making particular note of any deficiencies or failures. In the event of part failures, the defective part shall be replaced and the operation resumed for the balance of the test period. A record shall be kept of all failures throughout the test, including all tube failures. This record shall indicate the following:

(1) Part type number

(2) The circuit reference symbol number

(3) The part function

(4) Name of the manufacturer

(5) Nature of the failure

(6) The number of hours which the part operated prior to failure

4.5.4.1 Failure Report - In the event of a failure, the government inspector shall be notified immediately. A report shall be submitted to the procuring activity upon completion of the test. In this report, the contractor shall propose suitable and adequate design or material corrections for all failures which occurred. The procuring activity will review such proposals and determine whether they are acceptable.

4.5.5 Reconditioning of Life Test Samples - An equipment which has been subjected to the life test shall be reconditioned as follows:

(1) On completion of the life test, the equipment shall be reworked by the contractor by replacing all tubes and "wear" items. The "wear" items shall be determined by agreement between the contractor and the procuring activity.

(2) After reworking, the contractor may resubmit the equipment for acceptance.

Source: https://assist.dla.mil -- Downloaded: 20261O-19T13:38Z
Check the source to verify that this is the current version before use.

4.6 Test Procedures - The procedures used for conducting preproduction tests, acceptance tests and life tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When test procedures are available from previous contracts such procedures may be used when approved by the procuring activity.

4.7 Presubmission Testing - No item, part or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.8 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector. Units rejected after retest shall not be resubmitted without the specific approval of the procuring activity.

4.9 Equipment Changes - After approval of the preproduction model, no changes which affect weight, installation interchangeability and interchangeability of maintenance parts or assemblies shall be incorporated in the equipment unless approved by the procuring activity. To obtain procuring activity approval, the contractor shall submit an Engineering Change Proposal (ECP) giving the necessary information concerning the change. This shall apply for either a procuring activity's recommended change or a contractor's proposed change. When required, the contractor shall also prepare a Material Change (MC) and a Material Bulletin (MB) to cover the approved change. Engineering Change Proposals, Material Changes and Material Bulletins shall be prepared in accordance with SAR-300.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-P-17555.

6. NOTES

6.1 Test Values - Normal and limiting values of performance data shall be determined at input voltages of 27.5 ± 0.5 V DC and 115 ± 1.0 V AC. These data are to be used in testing the equipment at installation points for compliance with minimum acceptable standard of performance.

6.2 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specification.

(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 20261O-19T13:38Z
Check the source to verify that this is the current version before use.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.3 The parentheses (*), when used in the type designation, shall be replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.2.8. The complete type number shall be used on nameplates, shipping records and instruction books, as applicable.

6.4 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance or reliability will result from the use of materials, parts and processes other than those specified in Specification MIL-E-5400, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

NOTICE - When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished or in any way supplied the said drawings, specifications or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any way be related thereto.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T13:38Z
Check the source to verify that this is the current version before use.