MILITARY SPECIFICATION

SIGHT, INFINITY: 8635466

This amendment forms a part of Military Specification MIL-S-46371(MU), dated 12 April 1963.

* Paragraph 2.1, under Drawings:

Delete: "IEL 8635466 - Index of Inspection Equipment List for Sight, Infinity: 8635466" and "LSQAP 8635466 - Supplementary Quality Assurance Provision List for Sight, Infinity: 8635466".

Add: "F8565556 Pressure Tester Two Station"

Paragraph 3.5: Delete and substitute:

"3.5 Alignment.- With the mounting surface in a vertical plane and the locating key horizontal within 1.0 minute, the center of the reticle pattern shall be projected 26° ± 1.0 minute below a horizontal plane."

Add new paragraph 3.6 as follows:

"3.6 Environmental"

* Paragraph 3.6.4: Delete and substitute:

"3.6.4 Sealing.- The Infinity Sight shall show no evidence of leakage in excess of 0.2 pounds per square inch (psi) when subjected to an internal pressure of 5. ± 0.10 psi for a minimum of 2 hours. The interior atmosphere of the accepted sight shall contain nitrogen having a dew point at lease as low as minus 25°F at atmospheric pressure. The sight shall then be sealed with an internal pressure of between 0.25 and 0.50 psig of dry nitrogen.

Paragraphs 4.3 and 4.3.1: Delete and substitute as follows:

"4.3 First article (initial production) approval.- The requirement for first article approval and the responsibility (Government or contractor) for first article testing shall be as specified in the

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:45Z
Check the source to verify that this is the current version before use.

contract. The sample for first article approval tests shall consist of 3 infinity sights manufactured in the same manner using the same materials, equipment, processes, and procedures as used in regular production. All parts and materials, including packaging and packing shall be obtained from the same source of supply as used in regular production.

4.3.1 Government testing.- When the Government is responsible for conducting first article approval tests, the contractor, prior to submitting the sample to the Government, shall inspect the sample to insure that it conforms to all the requirements of the contract and submit a record of this inspection with the sample, including certificates of conformance for materials."

Add new paragraph 4.3.2 as follows:

"4.3.2 Contractor testing.- When the contractor is responsible for conducting first article approval tests, the sample shall be inspected by the contractor for all the requirements of the contract. The sample and a record of this inspection, including certificates of conformance for materials, shall be submitted to the Government for approval. The Government reserves the right to witness the contractor's inspection."

* Paragraph 4.5.1: Delete "Supplementary Quality Assurance Provisions List (LSQAP) 8635466" and substitute "the technical data package (TDP)."

Paragraph 4.6.2.3: Delete and substitute:

"4.6.2.3 Device used to test accuracy requirement.- The device shall position the sight on a keyed locating surface with the mounting surface in a vertical plane and the key horizontal within 1.0 minute. The surface used for measuring the projected reticle image shall be graduated in 1.0 ± 0.2 mil increments, horizontally and vertically, in a manner suitable for measuring the subtended angle of the projected reticle pattern and the boresight adjustment requirements. The surface shall be positioned 26° ± 1.0 minute from a horizontal plane."

* Paragraph 4.6.2.6: Delete and substitute:

"4.6.2.6 Sealing.- Special testing equipment to test sealing of Infinity Sight shall conform to the internal pressure test requirements of Drawing F8565556, pressure tester - two station."

* Paragraph 4.7.8: Delete and substitute:

"4.7.8 Sealing.- Internal pressurizing of the infinity sight shall be performed with special testing equipment conforming to 4.6.2.6. Pressurize the infinity sight with dry nitrogen gas, having a dew point at least as low as minus 25 degrees Fahrenheit, to 5 pounds per square inch (psi) in accordance with the procedure for internal testing on Drawing F8565556. Retain the applied pressure in the infinity sight for the time duration specified in 3.6.4. During the first 50 minutes of this time period, the elevation and deflection knobs shall be rotated to their clockwise and counterclockwise extremes, a minimum of 3 times.

Source: https://assist.dla.mil -- Downloaded: 20261O-22T05:45Z
Check the source to verify that this is the current version before use.

At the end of the 2 hour time period there shall be no evidence of leakage as indicated on the pressure gage of the testing equipment, to determine compliance with 3.6.4. Upon satisfactory completion of the sealing test, the infinity sight shall then be flushed with the dry nitrogen gas specified herein. The interior atmosphere of the infinity sight shall be periodically sampled through a dew point meter until the atmosphere shows a dew point at least as low as minus 25 degrees Fahrenheit. When this atmosphere is attained within the infinity sight, the infinity sight shall then be sealed in accordance with 3.6.4. The internal atmosphere of the infinity sight shall conform to the requirements of 3.6.4."

* The outside margins have been marked to indicate where additions to the previous amendment have been made. This has been done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content as written irrespective of the marginal notation and relationship to the last previous issue.

Custodian:

Army - MU

Preparing activity:

Army - MU

Project No. 1240-A277

Source: https://assist.dla.mil -- Downloaded: 202610-22T05:45Z
Check the source to verify that this is the current version before use.