INCH-POUND

MIL-DTL-82939A(OS)
19 December 2025
SUPERSEDING
MIL-DTL-82939(OS)
11 February 2000

DETAIL SPECIFICATION

SEPARATOR, EXPLOSIVE (1W18)

This specification is approved for use by the Naval Surface Warfare Center Indian Head Division (NSWC IHD) and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers the requirements for an explosive separator (1W18), Drawing 838AS220, hereto referred to as "separator" and its explosive component BBU-55/B explosive bolt, Drawing 838AS221.

2. APPLICABLE DOCUMENTS

2.1 General. The documents listed in this section are specified in sections 3 and 4 of this specification. This section does not include documents cited in other sections of this specification or recommended for additional information or as examples. While every effort has been made to ensure the completeness of this list, document users are cautioned that they must meet all specified requirements of documents cited in sections 3 and 4 of this specification, whether or not they are listed.

2.2 Government documents.

2.2.1 Specifications, standards, and handbooks. The following specifications, standards, and handbooks form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

DEPARTMENT OF DEFENSE SPECIFICATIONS

MIL-DTL-23659 - Initiators, Electric, General Design Specification for

DEPARTMENT OF DEFENSE STANDARDS

MIL-STD-1168 - Ammunition Lot Numbering and Ammunition Data Card

(Copies of these documents are available online at https://quicksearch.dla.mil.)

2.2.2 Other Government documents, drawings, and publications. The following other Government documents, drawings, and publications form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

NAVAL AIR SYSTEMS COMMAND (CAGE CODE 30003) DRAWINGS

838AS220 - Explosive Separator

838AS221 - BBU-55/B, Explosive Bolt

838AS222 - Shock Vibration, Fixture Assembly

Comments, suggestions, or questions on this document should be addressed to Commander, Naval Sea Systems Command, ATTN: SEA 05S, 1333 Isaac Hull Avenue, SE, Stop 5160, Washington Navy Yard, DC 20376-5160 or emailed to CommandStandards@navy.mil, with the subject line "Document Comment". Since contact information can change, you may want to verify the currency of this address information using the ASSIST Online database at https://assist.dla.mil.

AMSC N/A FSC 1377

Distribution Statement A. Approved for public release: distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

(Copies of these documents are available from Commander, Indian Head Division, Naval Surface Warfare Center, CAD/PAD Data Management Branch (Code E26), 4393 Benson Road, BLDG 1557, Indian Head, MD 20640-5092. Refer questions, inquires, or problems to nswc_iheodtd_dmo@navy.mil.)

2.3 Non-Government publications. The following documents form a part of this document to the extent specified herein. Unless otherwise specified, the issues of these documents are those cited in the solicitation or contract.

ASTM INTERNATIONAL

ASTM E1742/E1742M - Standard Practice for Radiographic Examination

(Copies of this document are available online at www.astm.org.)

2.4 Order of precedence. Unless otherwise noted herein or in the contract, in the event of a conflict between the text of this document and the references cited herein, the text of this document takes precedence. Nothing in this document, however, supersedes applicable laws and regulations unless a specific exemption has been obtained.

3. REQUIREMENTS

3.1 First article. When specified (see 6.2), a sample of separators shall be subjected to first article inspection (see 6.3) in accordance with 4.2. Because the explosive bolt is an integral part of the separator, first article testing for the bolt shall be conducted in fully assembled separators only in accordance with 4.2.

3.2 Design and construction. The explosive bolt and separator shall be manufactured in accordance with Drawings 838AS221 and 838AS220, respectively.

3.3 Materials. All materials used in the manufacture of the explosive bolts and separators shall be in accordance with the respective Naval Air Systems Command drawings unless specific approval in writing covering a departure therefrom has been obtained by the Technical Authority (see 6.5.1) prior to manufacture (see 6.2).

3.4 Primary component. Only the BBU-55/B explosive bolt is classified as a primary component. The primary component shall have been manufactured not more than 1 year prior to the date of separator assembly. Only one lot of each primary component shall be used in a separator lot. One primary component lot may be used in more than one separator lot.

3.5 Explosive bolt production. The bolt shall be manufactured in accordance with Drawing 838AS221. Each production bolt shall meet the requirements of 3.5.1 through 3.5.5.

3.5.1 Visual inspection requirement. The bolts shall not have illegible descriptive markings, dents, deep scratches, or other defects that may prevent proper installation or function when examined in accordance with 4.4.1.1.

3.5.2 Radiographic inspection requirement. All bolts shall show proper assembly, presence of parts, and sealing with no metallurgical defects when examined radiographically in accordance with 4.4.2.

3.5.3 Bridgewire resistance. The bridgewire resistance of circuits AB and CD in each bolt shall be 1.15±0.15 ohms when tested in accordance with 4.4.3.

3.5.4 Insulation resistance. The bolt insulation resistance shall be a minimum of 5 megohms when tested in accordance with 4.4.4.

3.5.5 Leakage. The bolt hermetic seal shall not exhibit a leakage rate in excess of 1×10^{-5} cubic centimeters per second air (2.4×10^{-5} cubic centimeters per second helium) when tested in accordance with 4.4.5.

3.5.6 Explosive bolt performance. Bolts shall be capable of meeting the requirements of 3.5.6.1 through 3.5.6.4.

3.5.6.1 Electrostatic discharge. The bolt shall not fire or dud when static discharge-tested in accordance with 4.4.6.

3.5.6.2 No-fire. The bolt shall not ignite or dud when tested in accordance with 4.4.7.

3.5.6.3 Proof load. The bolt body shall be capable of withstanding a 90,000-pound axial load and a 750-inch-pound torsional load without permanent deformation when tested in accordance with 4.4.8.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

3.5.6.4 Bolt function. The bolt shall fire and fracture completely within 50 milliseconds in a no-proof load condition, as installed in the separator, when 5 amperes is applied to either bridgewire circuit when tested in accordance with 4.4.14.

3.6 Separator production. The assembled separators shall be manufactured in accordance with Drawing 838AS220. Each production separator shall meet the requirements of 3.6.1 through 3.6.4.

3.6.1 Visual inspection requirement. The separators shall not have illegible descriptive markings, dents, deep scratches, or other defects that may prevent proper installation or function when examined in accordance with 4.4.1.2.

3.6.2 Radiographic inspection requirement. All separators shall show proper assembly, presence of parts, and sealing when examined radiographically in accordance with 4.4.2.

3.6.3 Bridgewire resistance. The bridgewire resistance of circuits AB and CD in each separator shall be 1.15±0.15 ohms when tested in accordance with 4.4.3.

3.6.4 Insulation resistance. The separator insulation resistance shall be a minimum of 5 megohms when tested in accordance with 4.4.4.

3.6.5 Separator performance. Separators shall be capable of meeting the requirements of 3.6.5.1 through 3.6.5.9.

3.6.5.1 Electrostatic discharge. The separator shall not fire or dud when static discharge-tested in accordance with 4.4.6.

3.6.5.2 No-fire. The separator shall not ignite or dud when tested in accordance with 4.4.7.

3.6.5.3 Temperature, humidity, and altitude (THA) cycling. The separator shall not incur damage nor deformation when subjected to THA cycling in accordance with 4.4.9.

3.6.5.4 48-hour salt fog. The separator shall not incur damage nor deformation when subjected to the 48-hour salt fog test in accordance with 4.4.10.

3.6.5.5 Shock. The separator shall not incur damage nor deformation when subjected to the shock test in accordance with 4.4.11.

3.6.5.6 Vibration. The separator shall incur neither damage nor deformation when subjected to the vibration test in accordance with 4.4.12.

3.6.5.7 6-foot drop. The separator shall incur neither damage nor deformation that shall prevent installation when subjected to the 6-foot drop test in accordance with 4.4.13.

3.6.5.8 Proof load. All separators shall be capable of withstanding a 90,000-pound axial load and a 750-inch-pound torsional load in accordance with 4.4.8. The separators shall show no visual evidence of permanent deformation or structural failure.

3.6.5.9 Separator function. The separator shall separate completely within 50 milliseconds when a current of 5 amperes is applied to either bridgewire circuit when tested in accordance with 4.4.14.

3.7 Workmanship. The bolt and separator shall be constructed and finished in a manner to ensure compliance with all requirements of this specification.

4. VERIFICATION

4.1 Classification of inspections. The inspection requirements specified herein are classified as follows:

a. First article inspection (see 4.2).

b. Conformance inspection (see 4.3).

4.2 First article inspection. Unless otherwise specified (see 6.2), an acceptable first article sample of 15 separators shall be prepared using the same procedures and methods proposed for the production lot. This inspection shall include the examinations and tests specified in table I. Any damage inflicted by the environmental treatments that would adversely affect the performance of the item in the service application shall be cause for rejection of the first article sample. Any further production prior to notification by the contracting agency of first

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

article acceptability shall be at the contractor's risk. Failure of any separator to comply with the requirements specified in table I shall be cause for rejection of the first article represented.

TABLE I. First article test schedule.

Test	Requirement	Test Method	Sample Groups							
			A	B	C	D	E	F	G	Total
Visual inspection	3.6.1	4.4.1.2	2	2	2	2	3	2	2	15
Radiographic inspection	3.6.2	4.4.2	2	2	2	2	3	2	2	15
Bridgewire resistance	3.6.3	4.4.3	2	2	2	2	3	2	2	15
Insulation resistance	3.6.4	4.4.4	2	2	2	2	3	2	2	15
Electrostatic discharge	3.6.5.1	4.4.6	2	2	2	2	3	2	2	15
No-fire	3.6.5.2	4.4.7						2	2	4
THA cycling	3.6.5.3	4.4.9	2							2
48-hour salt fog	3.6.5.4	4.4.10		2						2
Shock	3.6.5.5	4.4.11			2					2
Vibration	3.6.5.6	4.4.12				2				2
6-foot drop	3.6.5.7	4.4.13					3			3
Radiographic inspection	3.6.2	4.4.2			2	2	3			7
Bridgewire resistance	3.6.3	4.4.3	2	2	2	2	3	2	2	15
Proof load	3.6.5.8	4.4.8	2	2	2	2	3	2	2	15
Functional: -65 °F 70 °F 165 °F	3.6.5.9	4.4.14	 2	 2	 2	 2	 3	 2 	 2	15

4.3 Conformance inspection. The conformance inspection shall consist of the inspections specified in 4.3.1 through 4.3.3.

4.3.1 Explosive bolt production inspection. All explosive bolts shall be inspected and screened for defects as specified in tables IIA and IIB. Bolts failing to meet the requirements of table IIA shall be rejected and removed from the lot. If bolts are being procured for use in separators not manufactured by the bolt manufacturer, a sample of bolts shall be subjected to the tests of table IIB. The sample shall be in accordance with table IIC. Failure of any sample bolt to comply with the tests of table IIB shall be cause for rejection of the lot represented.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

TABLE IIA. Explosive bolt production inspection.

Test	Requirement	Test Method
Design and construction	3.2	4.4.1.1
Materials	3.3	4.4.1.1
Visual inspection	3.5.1	4.4.1.1
Radiographic inspection	3.5.2	4.4.2
Bridgewire resistance	3.5.3	4.4.3
Insulation resistance	3.5.4	4.4.4
Leakage	3.5.5	4.4.5
Electrostatic discharge	3.5.6.1	4.4.6
Proof load	3.5.6.3	4.4.8

TABLE IIB. Explosive bolt lot acceptance inspection.

Test	Requirement	Test Method
Visual inspection	3.5.1	4.4.1.1
Radiographic inspection	3.5.2	4.4.2
Bridgewire resistance	3.5.3	4.4.3
Insulation resistance	3.5.4	4.4.4
Leakage	3.5.5	4.4.5
Electrostatic discharge	3.5.6.1	4.4.6
No-fire	3.5.6.2	4.4.7
Proof load	3.5.6.3	4.4.8
Bolt function	3.5.6.4	4.4.14

TABLE IIC. Explosive bolt lot acceptance sampling.

Lot Size	Sample Size
9 to 25	4
26 to 90	6
91 to 150	8
151 to 280	13
281 to 500	20

4.3.2 Separator production inspection. All separators shall be inspected and screened for defects as specified in table III. Any separator failing to meet the requirements of table III shall be rejected and removed from the lot.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

TABLE III. Separator production inspection.

Test	Requirement	Test Method
Design and construction	3.2	4.4.1.2
Materials	3.3	4.4.1.2
Primary components	3.4	4.4.1.2
Visual inspection	3.6.1	4.4.1.2
Radiographic inspection	3.6.2	4.4.2
Bridgewire resistance	3.6.3	4.4.3
Insulation resistance	3.6.4	4.4.4
Proof load	3.6.5.8	4.4.8

4.3.3 Separator lot acceptance inspection. Lot acceptance inspection shall consist of the examinations and tests in table IV. Failure of any sample separator to comply with the requirements listed in table IV shall be cause for rejection of the lot represented.

TABLE IV. Separator lot acceptance inspection.

Test	Requirement	Test Method	Quantity
Visual inspection	3.6.1	4.4.1.2	Test and retain sample
Radiographic inspection	3.6.2	4.4.2	Test and retain sample
Bridgewire resistance	3.6.3	4.4.3	Test and retain sample
No-fire	3.6.5.2	4.4.7	Test
Proof load	3.6.5.8	4.4.8	Test
Functional: -65 °F 165 °F	3.6.5.9	4.4.14	 ½ test sample ½ test sample

4.3.3.1 Sample size. A random sample, including the retained sample for investigative purposes, shall be selected from the production lot in accordance with table V. An additional two separators shall be provided with each test sample for investigative purposes. Test sample separators and separators for investigative purposes shall not be applied as part of the quantity specified for delivery.

TABLE V. Lot acceptance sampling.

Lot Size	Destructive Test Sample Size	Retain Sample Size	Total Sample Size
9 to 25	4	2	6
26 to 90	6	2	8
91 to 150	8	2	10
151 to 280	13	2	15
281 to 500	20	2	22

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

4.4 Inspections and tests.

4.4.1 Visual inspections.

4.4.1.1 Explosive bolt inspection. All bolts shall be visually inspected and screened for defects. The external condition and appearance of the bolts shall be determined by comparison to Drawing 838AS221. Specific inspections of the electrical connector, lead wires, threads, and identification markings shall be conducted, at a minimum. Each bolt shall meet the requirements of 3.5.1 and 3.7.

4.4.1.2 Separator inspection. All separators shall be visually inspected and screened for defects. The external condition and appearance of the separators shall be determined by comparison to Drawing 838AS220. Specific inspections of the electrical connector, shunt device, threads, and identification label shall be conducted, at a minimum. Each separator shall meet the requirements of 3.6.1 and 3.7.

4.4.2 Radiographic inspection. Radiographic examination shall be in accordance with ASTM E1742/E1742M. The bolts or separators shall be positioned for the most revealing exposure with the long axis perpendicular to the radiographic beam. Each bolt or separator shall be identified with serial numbers beginning with 001 prior to examination. The bolts and separators shall be arranged on boards or trays in consecutive order with any missing serial numbers identified on the radiographic plate. Each radiograph shall carry a permanent identification of the items displayed thereon in a 4 x 6-inch region, maximum. The radiographic identification shall include the drawing number, the contractor part number, the complete lot number in accordance with MIL-STD-1168, the contract number, and the span of serial numbers displayed. Radiographs of the entire production lot shall accompany the ballistic sample to the activity conducting the tests (see 6.2). Any observable imperfections as outlined in 3.5.2 or 3.6.2 shall be cause for rejection of the bolt or separator, respectively. Defective bolts or separators found during radiographic review shall be marked on the radiographic plate and removed from the production lot.

4.4.3 Bridgewire resistance. The bridgewire resistance of circuits AB and CD in each bolt or separator shall be determined and recorded using a test meter having an accuracy within 0.01 ohm and an impressed current limited to 10 milliamperes. Bolts or separators that fail to meet the requirement of 3.5.3 or 3.6.3 respectively shall be cause for rejection of the bolt or separator.

4.4.4 Insulation resistance. Each bolt or separator in a sample shall have 500±25 volts direct current applied between the pins in parallel circuit and the separator case for 60 seconds. A leakage current that exceeds 0.1 milliampere shall be cause for rejection of the bolt or first article sample separator lot. The insulation resistance test shall not dud or adversely affect the bolt or cause the bolt to fire, arc-over, flash-over, or break down. Bolts or separators that fail to meet the requirement of 3.5.4 or 3.6.4 respectively shall be cause for rejection of the bolt or separator. The bolt or separator resistance shall be measured following this test.

4.4.5 Leakage. Each bolt shall be subjected to helium at a pressure differential of 1.0±0.1 atmospheres for 1 hour. The bolts shall be removed from the helium environment and tested in a helium spectrometer within 15 minutes of removal. If a bolt fails to meet the leakage requirement of 3.5.5, this shall be cause for rejection of that bolt.

4.4.6 Electrostatic discharge. Each bolt or separator shall be subjected to an electrostatic discharge between the pins shorted together and the case of the separator per test procedures of MIL-DTL-23659. The bolt or separator shall not fire, dud, or otherwise be affected when subjected to the electrostatic discharge. Units failing to meet the requirements of 3.5.6.1 or 3.6.5.1 respectively shall be cause for rejection of the bolt or separator.

4.4.7 No-fire. Each sample bolt or separator shall be subjected to 1 ampere and 1 watt applied through both bridgewires in series for a minimum of 5 minutes. Only the bolt shall meet the requirement at 70±5 °F and 220±5 °F. If any of the sample bolts or separators subjected to no-fire fail to meet the requirements of 3.5.6.2 or 3.6.5.2 respectively, the entire production lot shall be rejected.

4.4.8 Proof load tests. Each bolt or separator in a lot shall be installed in a test fixture capable of producing a 90,000-pound axial load and a 750-inch-pound torsional load. The torsional load shall be introduced before the axial load. The 90,000-pound axial load shall be maintained for a minimum of 5 seconds, then released. The bolt or separator shall be visually examined for permanent deformation or structural failure. Failure to meet the requirements of 3.5.6.3 and 3.6.5.8 shall result in rejection of the unit.

4.4.9 THA. THA testing shall be 28 days in accordance with MIL-DTL-23659. The separators shall withstand the THA environment and then meet the post-test inspections of table I and functional performance requirements.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

4.4.10 48-hour salt fog. Salt fog testing shall be 48 hours in accordance with MIL-DTL-23659. The separators shall withstand the salt fog environment and then meet the post-test inspections of table I and functional performance requirements.

4.4.11 Shock. Separators shall be mounted in a fixture conforming to Drawing 838AS222 and subjected to 10 shocks of 15 g maximum acceleration in one axis only. The maximum acceleration of 15 g shall be reached in a maximum of 8 milliseconds, and the acceleration shall exceed 8 g for at least 11 milliseconds. The 15 g shall be applied normal to the longitudinal axis. The separator shall not fire when subjected to shock testing. Each separator shall also meet the post-test inspections of table I and functional performance requirements.

4.4.12 Vibration. Separators shall be securely installed in a fixture conforming to Drawing 838AS222. The separator shall not fire when subjected to vibration testing. Each separator shall also meet the post-test inspections of table I and functional performance requirements.

4.4.12.1 Procedure. The vibration test shall be conducted with the frequency cycling between 10 and 2,000 hertz (logarithmically) in 15-minute cycles with an amplitude of 0.018 inch (total excursion 0.036 inch) or an applied acceleration of ±10 g, whichever is the limiting value. Two separators shall be vibrated in each of the following orientations: parallel to the longitudinal axis of the explosive bolt and perpendicular to the axis (see figure 1 for the definition of axes). Vibration times shall be in accordance with table VI.




FIGURE 1. Definition of axes for an explosive separator (1W18).

TABLE VI. Vibration test schedule.

Type	Vibration at Room Temperature	Vibration at +160 °F	Vibration at -65 °F
Cycling	60 minutes	15 minutes	15 minutes
Resonance	60 minutes	15 minutes	15 minutes
NOTE: Times refer to one position.			

4.4.12.2 Resonance. Resonance frequencies shall be determined by varying the frequency of applied vibration through the specified range at amplitudes or accelerations not exceeding those shown on figure 2 for each position. The test specimen shall then be vibrated at the most severe resonant frequencies with the applied amplitude shown on figure 2. If no resonant frequencies are found, the specimen shall be vibrated for twice the time shown in table VI for resonance at a frequency of 55 hertz and an applied amplitude of 0.030 inch (total excursion of 0.060 inch).

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.




FIGURE 2. Vibration test amplitudes.

4.4.13 6-foot drop. Separators shall be dropped onto a 2-inch-thick steel plate embedded in concrete from a minimum height of 6 feet. The items shall be oriented so that they impact the steel plate as follows: (1) body, release end up; (2) body, release end down; (3) horizontal. A new separator shall be used for each drop. The separators shall not fire when dropped from a height of 6 feet. Each separator shall meet the post-test inspections of table I and functional performance requirements.

4.4.14 Functional test. One-half of the lot acceptance test sample shall be subjected to functional testing at 165 °F and the other half at -65 °F. The temperature conditioning time shall be a minimum of 4 hours after temperature stabilization (see 6.5.3) and a maximum of 24 hours at the respective temperature. The tests at each respective temperature shall be conducted with one-half the sample at extreme load (see 3.6.5.8) and the other half with no load (see 6.5.2) present. If the sample is not evenly divisible by four, priority of test conditions shall be at the discretion of NSWC IHD. The functional test shall be performed in a test fixture capable of producing a 90,000-pound axial load and a 750-inch-pound torsional load. The bolt or separator shall be functioned by applying 5 amperes to either bridgewire circuit. Bolts or separators that fail to meet the requirement of 3.5.6.4 or 3.6.5.9 respectively shall be cause for rejection of the lot or first article.

4.4.14.1 Test failure. If a test failure is attributable to an assignable cause, excluding the test bolt or separator, the original test results shall be discarded and the test reconducted.

5. PACKAGING

5.1 Packaging. For acquisition purposes, the packaging requirements shall be as specified in the contract or order (see 6.2). When packaging of materiel is to be performed by DoD or in-house contractor personnel, these personnel need to contact the responsible packaging activity to ascertain packaging requirements. Packaging requirements are maintained by the Inventory Control Point's packaging activities within the Military Service or Defense Agency, or within the military service's system commands. Packaging data retrieval is available from the managing Military Department's or Defense Agency's automated packaging files, CD-ROM products, or by contacting the responsible packaging activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

6. NOTES

(This section contains information of a general or explanatory nature that may be helpful, but is not mandatory.)

6.1 Intended use. The separator is used to release any load from the CH-53E or MH-53E helicopter single point cargo hook in the event of an emergency. As the separator is designed for use only with cargo hooks on military helicopters, it has no commercial application.

6.2 Acquisition requirements. Acquisition documents should specify the following:

a. Title, number, and date of this specification.

b. When first article inspection is required (see 3.1 and 4.2).

c. Requirement for obtaining Technical Authority approval to depart from material requirements herein (see 3.3).

d. Production lot size and test activity (see 4.3.3.1).

e. Directions for shipping radiographs of explosive bolts and the entire production lot of separators accompanying the ballistic sample to the activity conducting production lot acceptance tests (see 4.4.2).

f. Packaging requirements (see 5.1).

g. Ammunition data cards in accordance with MIL-STD-1168.

h. Submission of rework procedures, acceptance test and inspection procedures, and explosive bolt acceptance test and inspection results.

i. That the safety precaution requirements of DoD Manual 4145.26, DoD Contractor's Safety Manual for Ammunition and Explosives, are applicable. NOTE: When this specification is used as part of the description of work to be accomplished by a Government activity, the safety precaution requirements of OP 5, Ammunition and Explosives Safety Ashore, are applicable.

6.3 First article. When a first article inspection is required, the contracting officer should provide specific guidance to offerors whether the items should be a first article sample or a sample selected from the first production items (see 3.1). The contracting officer should also include specific instructions in acquisition documents regarding arrangements for examination, approval of first article test results, and disposition of first articles. Invitations for bids should provide that the Government reserves the right to waive the requirement for samples for first article inspection to those bidders offering a product that has been previously acquired or tested by the Government, and that bidders offering such products, who wish to rely on such production or test, must furnish evidence with the bid that prior Government approval is presently appropriate for the pending contract. Bidders should not submit alternate bids unless specifically requested to do so.

6.4 Loaded assembly hazard information.

DoD, DOT, NATO Hazard Classification	Class 1, Division 4
United Nations Serial Number	0173
Storage Compatibility Grouping	S
DoD Markings	Explosive Separator

6.5 Definitions.

6.5.1 Technical Authority. The Technical Authority has the authority, responsibility, and accountability to establish, monitor, and approve technical standards, tools, and processes in conformance to higher authority policy, requirements, architectures, and standards. NAVSEA 05S may be contacted to determine the appropriate Technical Authority for any given requirement related to equipment and systems of U.S. Navy ships and submarines.

6.5.2 No load. Unit hangs free in test fixture with no loads applied (no 90,000-pound axial load and no 750-inch-pound torsional load).

6.5.3 Stabilized. A stabilized separator is the same temperature throughout.

6.6 Subject term (key word) listing.

Helicopter

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.

6.7 Changes from previous issue. Marginal notations are not used in this revision to identify changes with respect to the previous issue due to the extent of the changes.

CONCLUDING MATERIAL

Preparing activity:
Navy – OS
(Project 1377-2025-008)

NOTE: The activities listed above were interested in this document as of the date of this document. Since organizations and responsibilities can change, you should verify the currency of the information above using the ASSIST Online database at https://assist.dla.mil.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T07:31Z
Check the source to verify that this is the current version before use.