MIL-A-46556B (MU)
20 June 1966
SUPERSEDING
MIL-A-46556A (MU)
27 January 1964

MILITARY SPECIFICATION

ACTUATOR, EXPLOSIVE, LINEAR, M2
LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the quality assurance provisions, and special requirements not covered by the drawings, for the loading, assembling and packing of one type of electrically actuated, gas operated power source designated as Actuator, Explosive, Linear, M2.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons; General Specification for.
MIL-I-45607 - Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105).
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-1167 - Ammunition Data Cards.
MIL-STD-1168 - Lot Numbering of Ammunition.
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FSC: 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

DRAWINGS

ORDNANCE CORPS

8848555 - Actuator, Explosive, Linear, M2, Assembly.
8853722 - Carton, Packing, Ammunition, for Actuator, Explosive, Linear, M2.
8853723 - Box, Packing, Ammunition, for Actuator, Explosive, Linear, M2.

PUBLICATIONS

ORDNANCE CORPS

ET-8848555 - Equipment Tabulation Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Assemblies.-The assemblies shall comply with all requirements specified on Drawing (dwg.) 8848555 and with all requirements specified in applicable specifications.

3.3 Functioning.-The actuator shall function on the first attempt when the electrical energy from a 0.04 microfarad capacitor charged to a maximum of 55 volts is discharged between the lead wires. The actuator shall not rupture or show evidence of parts separation after functioning. The actuator shall move a ten pound weight for a minimum distance of one inch horizontally at any temperature from minus 40 degrees Fahrenheit to plus 165 degrees Fahrenheit.

3.4 Workmanship.-The assemblies shall be loaded and assembled in a thorough, workmanlike manner. They shall be clean and free of burrs, distortion beyond drawing requirements, surface defects, dirt, grease, corrosion products and other foreign matter. The cleaning method used shall not in injurious to any part nor shall the parts be contaminated by the cleaning agent. All required

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

marking shall be neat and sharply defined. All packing components shall be dry.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define the terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time of the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions specified within this specification.
b. Number of units of product inspected.
c. Results obtained, by defect code, for all inspections performed.
d. Drawing, specification number and date, together with an identification and date of changes.
e. Statement of any findings on ignition charge and motor charge composition and certificates of conformance on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.
f. Number of items in the lot.
g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

4.1.2 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial Production Inspection

4.2.1 Submission.-Prior to the start of regular production, the contractor shall submit an initial production sample to a Government approved facility as designated by the Contracting Officer (see 6.4) for evaluation in accordance with the provisions of 4.2.2. The initial production sample shall consist of sixty (60) complete actuators which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of analysis for materials. An initial production sample, or portion thereof, as directed by the Contracting Officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the Contracting Officer.

4.2.2 Inspections to be performed.-Components will be subjected by the Government to any or all of the examinations specified in this specification and any or all requirements of the applicable drawings.

4.2.3 Rejection.-If any assembly or component fails to comply with any of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

terminate its inspection upon any failure of an assembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

4.3 Inspection provisions.

4.3.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot shall contain:

a. Ignition charge from not more than one batch or homogeneous blend of batches.

b. Motor charge from not more than one batch or homogeneous blend of batches.

Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105, except that inspection for critical defects,

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 may be used, for defects other than critical, if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Plug and wire assembly (see dwg. 8848559 covering a detail of dwg. 8848557).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Foreign matter on bridge area....	Visual	01001
Minor:	None defined		

4.3.2.2 Bridge and plug assembly (see dwg. 8848558 covering a detail of dwg. 8848555).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Metal visible through bridge....	Visual	02001
102.	Bridge missing.....	Visual	02002
103.	Ferrule loose or not fully seated.....	Visual-Manual	02003
Minor:	None defined		

4.3.2.3 Plug loading assembly, prior to assembly of disc and motor charge (see dwg. 8848557 covering a detail of dwg. 8848555).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Evidence of cracks, voids or separations on ignition charge...	Visual	03001
102.	Ignition charge missing.....	Visual	03002

Minor: None defined

4.3.2.4 Plug, loading assembly, prior to assembly of motor charge (see dwg. 8848557 covering a detail of dwg. 8848555).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Disc missing or damaged.....	Visual	04001
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4).....	Visual	04002

4.3.2.5 Plug loading assembly (see dwg. 8848557 covering a detail of dwg. 8848555).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Charge missing.....	Visual	05001
102.	Charge not pressed.....	Visual	05002
Minor:	AQL 1.50 percent		
201.	Total length, maximum (max.).....	Gage	05003
202.	Charge not sealed.....	Visual	05004
203.	Evidence of poor workmanship (see 3.4).....	Visual	05005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

4.3.2.6 Actuator, Explosive, Linear, M2 Assembly (see dwg. 8848555).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Crimp missing or incomplete.....	Visual	06001
102.	Lead wires not shorted.....	Visual	06002
Minor:	AQL 2.50 percent		
201.	Diameter at crimp, max.....	Gage	06003
202.	Total length, max.....	Gage	06004
203.	Crimp not sealed.....	Visual	06005
204.	Insulation damaged.....	Visual	06006
205.	Marking missing or illegible.....	Visual	06007
206.	Evidence of poor workmanship (see 3.4).....	Visual	06008
207.	Outside diameter, max.....	Gage	06009

4.3.2.7 Carton, unsealed (see dwg. 8853722).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Quantity in foil wrap incorrect..	Visual-Manual	07001
102.	Quantity of wrapped packs incorrect.....	Visual-Manual	07002
Minor:	AQL 0.65 percent		
201.	Packed improperly.....	Visual	07003

4.3.2.8 Carton, sealed (see dwg. 8853722).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

Major:	AQL 0.40 percent		
101.	Barrier bag improperly sealed or damaged (when applicable).....	Visual	08001
Minor:	AQL 1.00 percent		
201.	Contents loose.....	Manual	08002
202.	Marking missing, misleading or unidentifiable.....	Visual	08003

4.3.2.9 Box, sealed (see dwg. 8853723).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Contents of box exposed.....	Visual	09001
102.	FSC number missing or misleading.	Visual	09002
103.	Board broken.....	Visual	09003
104.	Strapping missing, broken or loose.....	Visual-Manual	09004
105.	Hardware missing, broken or loose (when applicable).....	Visual-Manual	09005
Minor:	AQL 2.50 percent		
201.	Marking missing, misleading or unidentifiable.....	Visual	09006
202.	Strapping improperly engaged.....	Visual-Manual	09007
203.	Hardware improperly engaged (when applicable).....	Visual-Manual	09008
204.	Car seal missing, unsealed or improperly positioned (when applicable).....	Visual-Manual	09009
205.	Handle missing or insecure, (when applicable).....	Visual-Manual	09010

4.3.3 Testing

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

4.3.3.1 Continuity (see dwg. 8848555) - Code No. 06010 - Major defect.-This test shall be performed 100 percent. Any complete assembly exhibiting a resistance outside the range specified on the drawing shall be classed defective and removed from the lot. Testing shall be as specified in 4.4.1.

4.3.3.2. Functioning (see 3.3) - Major defect - Code No. 06011. A sample of 40 complete actuators shall be randomly selected from each lot for this test. 20 Units of the sample shall be conditioned at minus 38 to 42 degrees Fahrenheit for 2 hours, minimum and 20 shall be conditioned at plus 163 to 167 degrees Fahrenheit for the same period. Failure of one, or more, units of the sample to meet the requirements of 3.3 shall reject the lot. Testing shall be as specified in 4.4.2.

4.3.4 Inspection Equipment.-Equipment Tabulation Number ET-8848555 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed in the ET shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment.-The contractor shall make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment and verification of its accuracy, shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 Continuity.-The complete actuator shall be tested using the applicable equipment of 4.3.4. The resistance shall be

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

observed between the lead wires with the applied current limited to 30 microamperes, maximum. Any unit exhibiting a resistance outside the permitted range shall be classed defective.

4.4.2 Functioning.-The actuator shall be tested using the equipment specified in 4.3.4. During conditioning and until just prior to test, the units shall be contained in a plastic foam container which maintains the units at conditioning temperature. Observation shall be made for function travel, rupture and parts separation. Any unit failing to meet the applicable requirement shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.-The actuator shall be packaged in accordance with dwg. 8853722.

5.1.2 Level C.-The actuator shall be packaged in accordance with dwg. 8853722.

5.2 Packing.

5.2.1 Level A.-The packaged actuator shall be packed and marked in accordance with dwg. 8853723.

5.2.2 Level C.-The packaged actuator shall be packed and marked in accordance with dwg. 8853723.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (OO Form 1242-3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the EL by the following codes:

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

6.3.7 Submission of contractor designs.-Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

6.4 Submission of test data and ammunition data cards.- In addition to the normal distribution of records, for loaded items procured by the Deaprtment of the Army, one copy of all ballistic test data and ammunition data cards shall be forwarded to the following:

Commanding Officer
Picatinny Arsenal
Dover, New Jersey
ATTN: SMUPA-ND5

6.5 Check test for possible deterioration.-The following test is designed to prevent the use of Actuators which have deteriorated during storage. The test shall be performed on - detonators from any lot which has:

a. been stored under normal conditions for more than two years.

b. encountered adverse conditions for any time period.

If the specification for the ammunition item into which the actuators are loaded soes require that the check test be performed, the Contracting Officer should insert a provision for the performance of the check test in that contract. The Contracting Officer will arrange for the contractor to be reimbursed for expenses incurred in the performance of the check test for possible deterioration.

6.5.1 Functioning.-Testing shall be as specified in 4.3.3.2, with the exception that lot rejection will now occur with failure of two or more units of the sample to meet the requirements of 3.3.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1375-A1027

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity.

SPECIFICATION

ORGANIZATION | CITY AND STATE

CONTRACT NO | QUANTITY OF ITEMS PROCURED | DOLLAR AMOUNT $

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1 HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A GIVE PARAGRAPH NUMBER AND WORDING

B RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2 COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3 IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES" IN WHAT WAY?

4 REMARKS (*Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.*)

SUBMITTED BY (*Printed or typed name and activity*) | DATE

DD FORM 1426
1 APR 63

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:17Z
Check the source to verify that this is the current version before use.