MILITARY SPECIFICATION

PRIMERS, PERCUSSION, M28A2 AND M28B2

PARTS FOR

This Amendment forms a part of Military Specification MIL-P-46562A (MU), dated 3 April 1964

Page 1, paragraph 2.1, Specifications, Military: Delete reference to "MIL-I-45208".

Page 1, paragraph 2.1, Standards, Military, MIL-STD-105: Add "(ABC-STD-105)".

Page 3, paragraphs 4.1, 4.1.1, 4.1.2 and 4.1.3: Delete these paragraphs in their entirety and substitute the following:

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all of the quality assurance provisions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspections performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of compliance on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:18
Check the source to verify that this is the current version before use.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

Page 6, paragraph 4.3.2, next to last sentence: Delete AQL "0.40" and substitute AQL "0.65". Delete AQL "0.25" and substitute AQL "0.40".

Page 6, paragraph 4.3.2.1, Major category: Delete AQL "0.40" and substitute AQL "0.65".

Page 7, paragraph 4.3.2.2. Minor category: Delete AQL "6.50" and substitute AQL "4.00".

Page 8, paragraph 4.3.2.3, Major category: Delete AQL "0.65" and substitute AQL "1.00".

Page 9, paragraph 4.3.2.4, Major category: Delete AQL "0.40" and substitute "0.65".

Page 11, paragraph 5.2: Delete this paragraph in its entirety.

Page 11, paragraph 6.1: Add "b. Data cards shall be prepared for each lot in accordance with information specified in Standard MIL–STD–1167."

Page 11, paragraphs 6.3. 6.3.1, 6.3.2, 6.3.3, 6.3.4, 6.3.5, 6.3.6 and 6.3.7: Delete these paragraphs in their entirety and substitute the following:

6.3 Inspection equipment. The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:18Z
Check the source to verify that this is the current version before use.

CDCF — Contractor's design responsibility on contractor format.

AD — Army design.

ADMU — Army design, mandatory for use.

CE — Commercial equipment.

SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory: When an inspection equipment list references mandatory Army designs, the contractor "shall comply with, and use these designs accordingly. The contractor may, however, in con nection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF "shall comply with the format and requirements of MIL–D–45608 and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black line on

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:18Z
Check the source to verify that this is the current version before use.

white background and shall provide a legible print produced via the 35MM microfilm process. Contractor shall submit one copy of the final design as a rolled set or flat set.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs."

Page 14, paragraphs 6.6, 6.6.1 and 6.6.2: Delete these paragraphs in their entirety.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1390–A505

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:18Z
Check the source to verify that this is the current version before use.