# MILITARY SPECIFICATION

## CABLE ASSEMBLY, ROCKET FOR DEMOLITION KIT, CRATERING, M180 ASSEMBLING AND PACKING

This specification is approved for use by US Army Armament Research and Development Command, and is available for use by all Departments and Agencies of the Department of Defense.

## 1. SCOPE

1.1 This specification contains the parts, assembly and packing of cable assembly, rocket for one type of rocket motor designated as Rocket Motor for Demolition Kit, Cratering, M180.

## 2. APPLICABLE DOCUMENTS

2.1 Issues of documents.-The following documents of the issue in effect on date of invitation for bids or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-48078 - Ammunition, Standard Quality Assurance Provisions, General Specification For.

STANDARDS

MILITARY

MIL-STD-1169 - Packaging, Packing and Marking for Shipment of Inert Ammunition Components.

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: Commander, US Army Armament Research and Development Command, Attn. DRDAR-QA, Dover, New Jersey 07801 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.

DRAWINGS (see 6.4)

US ARMY ARMAMENT RESEARCH AND DEVELOPMENT COMMAND

9318062 - Cable Assembly, Rocket

3. REQUIREMENTS

3.1 Materials.-Materials shall be in accordance with applicable drawings and specifications.

3.2 Components and assembly.-The components and assembly shall comply with all requirements specified on Dwg. 9318062 and associated drawings, and with all requirements specified in applicable specifications and standards.

3.3 Continuity and resistance of the cable assembly, rocket.-There shall be continuity and no more than 0.65 ohm resistance measured at the two blasting cap wires when tested as specified in 4.5.2.

3.4 Continuity and resistance of shorting plug assembly 7P connected to cable assembly, rocket.-There shall be continuity and no more than 0.080 ohm resistance measured at the two blasting cap wires when tested as specified in 4.5.3.

3.5 Soldering.-All soldering shall comply with the requirements of the soldering specification listed on the drawing.

3.6 First article inspection.-This specification contains technical provisions for first article inspection. Requirements for submission of first article samples by the contractor shall be as specified in the contract.

3.7 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough, workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, unblended radii, surface defects, dirt, grease, rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any parts, nor shall the parts be contaminated by the cleaning agents. All marking and stamping shall be neat and sharply defined.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.

## 4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection and standard quality assurance provisions.-Unless otherwise specified herein or in the contract, the provisions of MIL-A-48078 shall apply and are hereby made a part of this detail specification.

4.2 Classification of inspections.-The following types of inspection shall be conducted on this item:

a. First article inspection

b. Quality conformance inspection

4.3 First article inspection.

4.3.1 Submission.-The contractor shall submit a first article sample designated by the Contracting Officer for evaluation in accordance with provisions of 4.3.2. The first article sample shall consist of the following items in sample quantities as indicated.

| Part Description | Drawing | Quantity |
|---|---|---|
| Cable Assembly, Rocket | 9318062 | 5 |

4.3.2 Inspections to be performed.-See MIL-A-48078 and Table I specified herein.

4.3.3 Rejection.-See MIL-A-48078.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.

TABLE I - FIRST ARTICLE INSPECTION

**CLASSIFICATION OF DEFECTS & TESTS**

MIL-C-63085 (AR)

| PARAGRAPH | TITLE | SHEET 1 OF 1 | DRAWING NUMBER |
|---|---|---|---|
| | Cable Assembly, Rocket | | See Below |
| | | | NEXT HIGHER ASSEMBLY |

| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
|---|---|---|---|---|---|
| | Cable Assembly, Rocket (Dwg. 9318062) Examination for Defects | 5 | - | 3.2 | 4.4.2.1 |
| | Continuity and resistance of cable assembly, rocket | 5 | - | 3.3 | 4.5.2 |
| | Continuity and resistance of shorting plug, assembly 7P connected to cable assembly, rocket | 5 | - | 3.4 | 4.5.3 |

NOTES:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10
Check the source to verify that this is the current version before

4.4 Quality conformance inspection.

4.4.1 Inspection lot formation.-Inspection lots shall comply with the lot formation provisions of MIL-A-48078.

4.4.2 Examination.-See MIL-A-48078.

a. Sampling plans.-Unless otherwise specified in the Classification of Defects and Test Tables, sampling plans for major and minor defects shall be in accordance with MIL-STD-105, Inspection Level II.



Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.

# CLASSIFICATION OF DEFECTS & TESTS



| PARAGRAPH | TITLE | SHEET | DRAWING NUMBER |
|---|---|---|---|
| 4.4.2.1 | Cable Assembly, Rocket | 1 OF 3 | 9318062 |
| | | | NEXT HIGHER ASSEMBLY 9244401 |

| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
|---|---|---|---|---|---|
| Critical | None defined | | | | |
| Major | | | | | |
| 101 | Soldering improper prior to assembling connectors and sealing threads | | 0.40% | 3.5 | Visual |
| 102 | Any component missing, improperly assembled or damaged | | 0.40% | 3.2 | Visual |
| 103 | Improper wiring | | 0.40% | 3.2 | Visual |
| 104 | Improper color coding of wires to connector pins. | | 0.40% | 3.2 | Visual |
| 105 | Length of bare wires before twisting | | 0.40% | 3.2 | Visual |
| 106 | Distance from end of sleeving insulation to edge of insulation on two twisted wires | | 0.40% | 3.2 | Gage |
| 107 | Connectors do not mate at assembly | | 0.40% | 3.2 | Visual |
| 108 | Receptacle covers missing | | 0.40% | 3.2 | Visual |
| 109 | Safety streamer missing from 12D receptacle cover and marking missing, misleading or unidentifiable | | 0.40% | 3.2 | Visual |
| 110 | Notice tag missing from 10D receptacle cover and marking missing, misleading or unidentifiable | | 0.40% | 3.2 | Visual |
| 111 | Wrong connectors | | 0.40% | 3.2 | Visual |
| 112 | Continuity plug 3S not electrically wired (A to B) and soldered. | | 0.40% | 3.2 | Visual |

NOTES:



Source: https://assist.dla.mil -- Downloaded: 2022-10-23T[illegible]
Check the source to verify that this is the current version.

## CLASSIFICATION OF DEFECTS & TESTS



| PARAGRAPH | TITLE | | SHEET 2 OF 3 | | DRAWING NUMBER |
|---|---|---|---|---|---|
| 4.4.2.1 | CONTINUATION SHEET | | | | 9318062 |
| | | | | | NEXT HIGHER ASSEMBLY |
| | | | | | 9244401 |
| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
| 113 | Shorting plug 7P not electrically wired (C to A to B) and soldered. | | 0.40% | 3.2 | Visual |
| 114 | Continuity and resistance of cable assembly, rocket | | 100% | 3.3 | 4.5.2 |
| 115 | Continuity and resistance of electrical plug with connector 7P connected to cable assembly, rocket | | 100% | 3.4 | 4.5.3 |
| Minor | | | | | |
| 201 | Distance from connector 3P to blasting cap wires | | 0.65% | 3.2 | Gage |
| 202 | Distance from connector 7S to blasting cap wires | | 0.65% | 3.2 | Gage |
| 203 | Distance from end of blasting cap wires to two wires twisted | | 0.65% | 3.2 | Gage |
| 204 | Distance from igniter assembly wires to two wires twisted | | 0.65% | 3.2 | Gage |
| 205 | Distance from end of igniter assembly wires to two wires twisted | | 0.65% | 3.2 | Gage |
| 206 | Distance from connector 3S to igniter assembly wires | | 0.65% | 3.2 | Gage |
| 207 | Distance from end of connector 3P to end of twisted wires | | 0.65% | 3.2 | Gage |

NOTES:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23
Check the source to verify that this is the current version b

# CLASSIFICATION OF DEFECTS & TESTS



| PARAGRAPH | TITLE | SHEET | DRAWING NUMBER |
|---|---|---|---|
| 4.4.2.1 | CONTINUATION SHEET | 3 OF 3 | 9318062 |
| | | | NEXT HIGHER ASSEMBLY: 9244401 |

| CATEGORY | EXAMINATION OR TEST | NO. OF SAMPLE UNITS | AQL OR 100% | REQUIREMENT PARAGRAPH | PARAGRAPH REFERENCE /INSPECTION METHOD |
|---|---|---|---|---|---|
| 208 | Bushing, cable adapters missing | | 0.65% | 3.2 | Visual |
| 209 | Length of sleeving insulation | | 0.65% | 3.2 | Gage |
| 210 | Improper assembly of sleeving insulation | | 0.65% | 3.2 | Visual |
| 211 | Chain not removed | | 0.65% | 3.2 | Visual |
| 212 | Thread sealant missing | | 0.65% | 3.2 | Visual |
| 213 | S hook not closed | | 0.65% | 3.2 | Visual |
| 214 | Specified twisting of wires omitted | | 0.65% | 3.2 | Visual |
| 215 | Evidence of poor workmanship | | 1.00% | 3.7 | Visual |

NOTES:

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02
Check the source to verify that this is the current version befo

4.4.3 Testing.-Testing is described in the First Article and Quality Conformance Inspection Tables.

4.4.4 Inspection equipment.-The inspection equipment required to perform the examinations and tests prescribed herein is described in the 'Paragraph Reference/Inspection Method' column in the tables starting with paragraph 4.4.2.1. The contractor shall submit for approval inspection equipment designs in accordance with the terms of the contract. See Section 6 of MIL-A-48078 and 6.3 herein.

4.5 Test methods and procedures.

4.5.1 Materials, components and processes.-Compliance with all requirements of Section 3 of this specification shall be ascertained by current and continuing examination of inspection and test data to determine that all components (parts, subassemblies, and materials) have been inspected and tested and found to comply with their respective drawing and specification requirements, and that all specified manufacturing processes have been followed.

4.5.1.1 Visual and mechanical inspections.-The visual, manual and mechanical inspections and tests shall verify compliance with the requirements of Sections 3 and 5 of this specification in accordance with 4.4.2 herein and Table I.

4.5.2 Continuity and resistance test of the cable assembly, rocket.-The continuity and resistance shall be measured on each rocket cable assembly at the two blasting cap wires with the two rocket igniter assembly wires shorted. The firing lead assembly 3P and continuity plug assembly 3S shall be in place and the shorting plug assembly 7P removed. Test equipment shall be as specified in 4.4.4. If any cable assembly, rocket fails to meet the requirement specified, it shall be classed defective.

4.5.3 Continuity and resistance test of the shorting plug assembly 7P connected to cable assembly, rocket.-The continuity and resistance shall be measured for each shorting plug assembly 7P at the blasting cap wires with the two igniter assembly wires unshorted. The shorting plug assembly 7P shall be in place with the firing lead assembly 3P and continuity plug assembly 3S removed. Test equipment shall be as specified in 4.4.4. If any shorting plug assembly 7P fails to meet the requirements specified, it shall be classed defective.

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.

4.5.4 Packaging inspection.-The sampling and inspection of the preservation-packaging, packing and container marking shall be in accordance with requirements of MIL-STD-1169.

5. PACKAGING

5.1 Preservation and packaging.

5.1.1 Level C.-The cable assembly, rocket shall be preserved and packaged in accordance with MIL-STD-1169.

5.2 Packing.

5.2.1 Level C.-The cable assembly, rocket shall be packed in accordance with MIL-STD-1169.

5.3 Marking.-Marking of the carton shall comply with MIL-STD-1169.

5.4 Shipping.-When shipments from more than one lot are shipped as a carload, each lot shall be kept separate, and the division between lots clearly indicated to prevent mixing of the lots in transit.

6. NOTES

6.1 Intended use.-The cable assembly, rocket covered by this specification is used in the Rocket Motor Assembly and is a component of the Demolition Kit, Cratering M180.

6.2 Ordering data.-See MIL-A-48078.

6.3 Submission of inspection equipment designs for approval. See MIL-A-48078.-Submit equipment designs, as required, to Commander, US Army Armament Research and Development Command, ATTN: DRDAR-QAR-I, Dover, New Jersey 07801.

6.4 Drawings.-Drawings listed in Section 2 of this specification under the heading US Army Armament Research and Development Command (ARRADCOM) may also include drawings prepared by, and identified as, Edgewood Arsenal, Frankford Arsenal, Rock Island Arsenal or Picatinny Arsenal drawings. Technical data originally prepared by these activities is now under the cognizance of ARRADCOM.

Custodian:
Army-AR

Preparing Activity:
Army-AR

Project Number: 1340-A 529

Source: https://assist.dla.mil -- Downloaded: 2026-10-23T02:10Z
Check the source to verify that this is the current version before use.