MIL-H-52702(ME)
AMENDMENT 2
22 March 1977
SUPERSEDING
AMENDMENT 1
7 November 1974

MILITARY SPECIFICATION

HULL, ASSEMBLY, WELDED, FOR BRIDGE/FERRY

TRANSPORTER

This amendment forms a part of Military Specification MIL-H-52702(ME), dated 7 January 1971.

PAGE 1

* 2.1, under SPECIFICATIONS, FEDERAL delete

"PPP-T-60	- Tape: Pressure-Sensitive Adhesive, Waterproof, for Packaging.
QQ-S-781	- Strapping, Steel, Flat, and Seals."

and substitute

"PPP-T-60	- Tape: Packaging, Waterproof.
QQ-S-781	- Strapping, Steel, and Seals."

Add:

"L-P-378	- Plastic Sheet and Strip, Thin Gauge, Polyolefin.
TT-E-522	- Enamel, Phenolic, Outside."

2.1, under SPECIFICATIONS, MILITARY, delete

"MIL-P-116	- Preservation, Methods of."

and substitute

"MIL-P-116	- Preservation-Packaging, Methods of."

FSC 5420

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

PAGE 2

* 2.1, under SPECIFICATIONS, MILITARY, delete:

"MIL-R-45774 - Radiographic Inspection, Soundness Requirements for Fusion Welds in Aluminum and Magnesium Missile Components."

Add:

"MIL-E-52798 - Enamel, Alkyd, Camouflage."

2.1, under DRAWINGS, ME, delete "DL13207E3300" and substitute "TA13207E3300".

PAGE 3

2.2, delete all reference to the AMERICAN WELDING SOCIETY and substitute:

"AMERICAN WELDING SOCIETY, INC. (AWS)

D1.1 - Structural Welding Code, Section 5, Qualification.

(Application for copies should be addressed to the American Welding Society, Inc., 2501 N.W. 7th Street, Miami, FL 33125.)"

3.1, lines 1 and 2, delete "Data List DL13207E3300" and substitute "Top Assembly TA13207E3300".

3.1.1, line 2, delete "engineering design" and substitute "end product".

3.2, last sentence, delete and substitute: "Examination and tests shall be as specified in Section 4; and, unless otherwise specified herein, all examinations and tests shall be conducted by the contractor subject to surveillance and approval by the Government (see 6.3). When specified (see 6.2), the Government will conduct any or all of the first-produced hull assembly examination and tests, as specified (see 6.2)."

3.4, at end of paragraph, add: "Aluminum materials shall be provided with the material manufacturer's name or trademark and the applicable alloy and temper designations in accordance with the respective ASTM Specifications cited on the drawings."

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

PAGE 4

* 3.10, delete and substitute:

"3.10 Treatment and painting. The exterior of the hull assembly, and the interiors of the wheel wells and cab assembly, and interior of the hull assembly up to a height between 12 and 18 inches, shall be cleaned, treated, and painted in accordance with MIL-T-704, Type B, finish coat shall be forest green conforming to TT-E-522 modified to meet color, reflectance, gloss, sheen, and pigmentation of MIL-E-52798, except the finish coat on the interior of the hull shall be semigloss white, to range between Color No. 27875 and No. 27778 of FED. STD. No. 595. Masking to provide a well-defined paint departure line on the interior of the hull is not required. The primer and finish coat shall not be applied until after the hull assembly has successfully passed the required water and air tests specified in 4.7.2. The nonslip coating shall be applied to all areas designated on the drawings. The nonslip coating shall conform to MIL-W-5044, Type II, and the finish coat shall be forest green color pigmentation of MIL-E-52798. The finish coat of the eight superstructure supports located on top of the fenders shall conform to yellow, lusterless, Color No. 33538, of FED. STD. No. 595. Dissimilar metals shall be isolated as specified on the drawings."

3.11, item 4, under "Qty" delete: "(with each chest)"; under "Identification" delete "AMSMO-FB-P 715-106" and substitute "P 715-106, included in Top Assembly Microfilm".

3.11, second line from end of paragraph, delete "chest No. 8" and substitute "Chest No. 7"; last line, delete "chest No. 9" and substitute "Chest No. 8".

PAGE 5

3.12.1, line 15, delete "3/32" and substitute "3/16".

3.12.2, line 3, delete "(see 6.5)"; lines 6 through 12, delete "Prior to the production . . . . . for class 'A' welds." and substitute "Prior to the production fabrication of any MIL-W-45205, Class 'A' aluminum weldment, the contractor shall prepare and submit to the contracting officer for approval, surface preparation, cleaning, welding procedures and workmanlike specimens in accordance with MIL-W-45205. When approved by the contracting officer, such procedures and specimens shall be the minimum weld quality acceptable to the Government for Class 'A' welds."

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

PAGE 6

3.12.4, lines 8 through 10, delete and substitute:

"Steel welding - AWS D1.1 - Structural Welding Code, Section 5, Qualification.
Aluminum alloy welding - Welding Qualifications of the ASME, Section IX."

* 4.1, delete and substitute:

"4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements."

PAGE 8

4.4, at end of paragraph, add: "In addition to any test specified as part of the initial production test, the Government reserves the right to conduct any or all other tests contained in this specification as part of the initial production test, and failure of such additional tests shall have the same effect as failure of those tests specified as initial production tests."

PAGES 8 and 9

4.6 and 4.6.1, delete and substitute:

"4.6 Inspection comparision. The Government may select hull assemblies at any time during the contract production period and subject these hull assemblies to the examination and tests specified in 4.4 to determine conformance to the requirements of this specification. The inspection will be performed by the Government, at a site selected by the Government, on hull assemblies selected at random from those which have been accepted by the Government and will not include the previously inspected first-produced and initial production hull assemblies. In addition to any test specified as part of the inspection comparison, the Government reserves the right to conduct any and all other tests contained in this specification as part of the inspection comparison, and failure of such additional tests shall have the same effect as failure of those tests specified as inspection comparison.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

4.6.1 Inspection failure. Failure of an inspection comparison hull assembly to meet any requirement specified herein during and as a result of the examination and tests specified in 4.6 shall be cause for rejection of the inspection comparision hull assembly and shall be cause for refusal by the Government to continue acceptance of production hull assemblies until evidence has been provided by the contractor that corrective action has been taken to eliminate the deficiencies. Correction of such deficiencies shall be accomplished by the contractor at no cost to the Government on hull assemblies previously accepted and produced under the contract. Any deficiencies found as a result of the inspection comparision will be considered prima facie evidence that all hull assemblies accepted prior to the completion of inspection comparision are similarly deficient unless evidence to the contrary is furnished by the contractor and such evidence is acceptable to the contracting officer."

4.7.1, line 5, delete: "AMSMO-FB".

PAGES 9 and 10

4.7.1.1, delete and substitute:

"4.7.1.1 Aluminum weld examination. All areas affected by the welding processes shall be examined prior to painting for evidence of defects, including base metal cracks adjacent to or behind welds, arc strikes, cracks in weld metal, undercutting, lack of fusion, porosity, lack of penetration, lack of prescribed fit, incorrect cleaning or preparation for welding, inclusions, incorrect weld size, reduction of adjacent material thickness, or nonadherence to the welding procedures specified in 3.12.2. Weld quality shall be examined and compared against the welding workmanship requirements and the approved welding specimens submitted. Subassembly welds shall be examined before final installation, wherever feasible. All aluminum welds shall be visually examined with the aid of a 5X magnifying glass. Welds identified on the drawings with the symbol 'RT' shall be radiographically examined in accordance with MIL-STD-453. Evidence of weld defects in excess of that exhibited by the Government-approved welding specimens or the radiographic soundness requirements shall constitute failure of this examination."

PAGE 10

4.7.1.2, line 9, add period after "specimens" and delete: "submitted (see 6.5)."

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:30Z
Check the source to verify that this is the currentversion before use.

4.7.1.3, delete and substitute:

"4.7.1.3 Weld repair examination. All weld repair areas shall be visually examined with the aid of a 5X magnifying glass. Weld repairs which evidence defects in excess of that exhibited by the weld specimens, the radiographic soundness requirements, or the requirements of MIL-W-45205, MIL-W-45210, and MIL-STD-1261, as applicable, shall constitute failure of this examination."

4.7.2.2, line 3, delete and substitute: "draft of 50 inches (measured from the bottom sheet) by loading not less than two of the eight".

PAGE 12

* 4.8.1.3, Defect 114, delete: "holding devices and".
Defect 120, delete: "with tape".
After Defect 125, add:

"126. Plastic plugs not used to close holes in holding devices."

PAGE 13

* 5., delete "PREPARATION FOR DELIVERY" and substitute "PACKAGING".

* 5.1, delete and substitute:

"5.1 Preservation. Preservation shall be Level A or Commercial, as specified (see 6.2)."

* 5.1.1, delete and substitute: "Level A."

* 5.1.2, delete entirely.

* 5.1.2.1, line 4, delete "type P-6 preservative" and substitute "Type P-1 and P-6 preservatives respectively"; line 5, delete entire second sentence and substitute: "The superstructure spline assembly shall be tightly covered with black plastic film conforming to L-P-378, Type I, Class 1, 5 mils minimum thickness, which shall be secured in place with tape conforming to PPP-T-60, Type IV. Holes in the holding devices shall be sealed with tapered plastic plugs."

* 5.1.2.2, lines 5 and 6, delete entirely and substitute: "black plastic film as specified in 5.1.2.1 and secured with waterproof tape."

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:30Z
Check the source to verify that this is the currentversion before use.

* 5.1.2.4, line 8, delete "1/4-inch" and substitute "1/2-inch"; delete "exterior grade" and substitute "Grade B (CD interior with exterior glue)"; line 11, delete "1/4-inch" and substitute "1/2-inch"; lines 11 and 12, delete "exterior grade" and substitute "Grade B (CD interior with exterior glue)"; lines 12 through 14, delete "with 1 inch thick waterproof cushioning material secured between the panels and the windshield and window frames, and secured with the waterproof tape specified herein and by" and substitute "secured with"; lines 14 and 15, delete "two bands of steel banding" and substitute "two steel bands"; line 15, delete "type I, class B" and substitute "Class 1, Type I, Finish B, 3/4 X 0.023 inch minimum size,"; line 17, delete "wiring" and substitute "soft wire".

* 5.1.3, add new paragraph as follows:

"5.1.3 Commercial. The hull assembly shall be preserved as specified for Level A, except that materials used for preserving and wrapping shall be of commercial quality and types which will assure prevention of deterioration and damage."

PAGE 14

* 5.2, delete "Marking shall be in accordance with MIL-STD-129." and substitute "Marking for Level A shall be in accordance with MIL-STD-129. Marking for commercial packaging shall include nomenclature, stock number, contract number, and other marking required by the contracting officer. Marking shall be applied with waterproof materials by any means providing legibility."

* 6.2(f), delete: "and packaging".

After 6.2(f), add:

"(g) When the Government will conduct any or all of the first-produced hull assembly examination and tests. When the Government will conduct some but not all of the first-produced hull assembly examination and tests, the contracting officer should specify which examinations and tests will be conducted by the Government and which examinations and tests shall be conducted by the contractor (see 3.2)."

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.

PAGES 14, 15, and 16

* 6.5, 6.5.1, 6.5.1.1, and 6.6, delete.

The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 5420-A301

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:30Z
Check the source to verify that this is the current version before use.