MIL-T-52900A(ME)
29 November 1976
SUPERSEDING
MIL-T-52900(ME)
26 April 1976

MILITARY SPECIFICATION

TRUCK, DUMP, 20 TON, 8X6, XM917

COMMERCIAL CONSTRUCTION EQUIPMENT (CCE)

This specification is approved for use by The Mobility Equipment Research and Development Command, Department of the Army, and is available for use by all Departments and Agencies of the Department of Defense.

1. SCOPE

1.1 Scope. This specification covers an on-off road, heavy-duty commercial dump truck having at least a 75,000 GVWR, at least a 12 cubic yard struck dump body, and features permitting sustained load, haul, and dump cycles on earthmoving and construction jobs. The dump truck consists of a dump truck body and hydraulic hoist system (as described in this specification) mounted on a Type III, 8x6 chassis as described in MIL-T-PD-9156, as a Type D truck.

2. APPLICABLE DOCUMENTS

2.1 Issues of documents. The following documents of the issue in effect on date of invitation for bids or request for proposal form a part of this specification to the extent specified herein:

FSC 3805

Beneficial comments (recommendations, additions, deletions) and any pertinent data which may be of use in improving this document should be addressed to: US Army Mobility Equipment Research and Development Command, ATTN: DRXFB-DS, Fort Belvoir, VA 22060 by using the self-addressed Standardization Document Improvement Proposal (DD Form 1426) appearing at the end of this document or by letter.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:39Z
Check the source to verify that this is the current version before use.

SPECIFICATIONS

MILITARY

MIL-T-PD-9156 - Truck Chassis, and Truck Tractors; Commercial, Diesel Engine Driven, 55,000 to 75,000 Pounds GVWR, 6x4, 6x6, and 8x6; XM915, XM916, XM917, XM918, XM919 and XM920.

(Copies of specifications and standards required by contractors in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

2.2 Other publications. The following documents form a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on the date of invitation for bids or request for proposal shall apply.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI B 93.31 - Multi-Pass Method for Evaluating the Filtration Performance of a Fine Hydraulic Fluid Power Filter Element.

(Application for copies should be addressed to the American National Standards Institute, 1430 Broadway, New York, NY 10018.)

DEPARTMENT OF LABOR (DOL)

29 CFR 1926 - Occupational Safety and Health Administration Standards (OSHA)

(Application for copies should be addressed to the Superintendent of Documents, US Government Printing Office, Washington, DC 20402.)

DEPARTMENT OF TRANSPORTATION (DOT)

49 CPR 571 - Federal Motor Vehicle Safety Standards (FMVSS).
49 CFR 393 - Federal Motor Carrier Safety Regulations (FMCSR).

(Application for copies should be addressed to the Superintendent of Documents, US Government Printing Office, Washington, DC 20402).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.

NATIONAL ASSOCIATION OF METAL NAME PLATE MANUFACTURERS, INC., (NAME)

Metal Name Plate Industry Standards and Practices.

(Application for copies should be addressed to the National Association of Metal Name Plate Manufacturers, Inc., 1000 Vermont Avenue, NW, Washington, DC 20005.)

SOCIETY OF AUTOMOTIVE ENGINEERS (SAE)

SAE Handbook.

(Application for copies should be addressed to the Society of Automotive Engineers, 400 Commonwealth Drive, Warrendale, PA 15096.)

TRUCK-TRAILER MANUFACTURERS ASSOCIATION, INC. (TTMA)

TTMA Recommended Practices.
TTMA Technical Bulletins.

(Application for copies should be addressed to the Truck-Trailer Manufacturers Association, Inc., Suite 203, 2430 Pennsylvania Ave., NW, Washington, DC 20037.)

TRUCK BODY EQUIPMENT ASSOCIATION (TBEA)

TBEA Hydraulic Hoist Classification Chart.

(Application for copies should be addressed to the Truck Body Equipment Association, Inc., Suite 1220, 5530 Wisconsin Ave., NW, Washington, DC 20015.)

TECHNICAL INFORMATION PACKAGE

(Application for copies should be addressed to US Army Mobility Equipment Research and Development Command, ATTN: DRXFB-H, Fort Belvoir, VA 22060.)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

3. REQUIREMENTS

3.1 Description. The dump truck shall be as specified herein and, unless otherwise specified (see 6.2), the chassis cab shall be as specified in the chassis-cab specification, MIL-T-PD-9156. The dump truck shall include dump body, hydraulic hoist, and chassis-cab assemblies. The dump truck body shall be a commercial, on-off road type for severe construction applications. The dump truck shall be the current commercial production product line model of the contractor and shall have demonstrated industry acceptability by having been marketed in significant numbers for at least on year prior to opening of the technical proposal or bid. For recently introduced models, the contractor shall supply sufficient operational data. The dump truck body shall be equipped with all components, furnished as standard and optional equipment, whether specified herein or not, that are necessary to enable the dump truck to function safely, reliably, and efficiently in severe, sustained construction job operations. Established component and vehicle ratings and capacities shall not be increased to meet the requirements of this specification.

3.1.1 Environmental conditions. The dump truck shall start, travel, and function as specified herein under world-wide climatic conditions from minus 25° F to plus 125° F and from sea level to minimum 5000 foot altitude.

3.2 Dump body assembly construction.

3.2.1 Body assembly. The dump body assembly shall be of the extra heavy-duty contractor type intended for severe usage in world-wide dump truck service. The dump body assembly shall include cab protector, rear dump body, and heavy hydraulic hoist system, all mounted on an on-off-road chassis-cab.

3.2.2 Performance. The dump body assembly, as installed on the chassis-cab, shall comply with the interrelated requirements as follows:

(a) Perform dumping cycles involving the transporting of payload materials in the function of loading, hauling, dumping, and returning empty.

(1) Dump in a fixed location, such as stockpiling;
(2) Dump in a controlled, uniform, spreading lift while traveling forward and rearward;

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

(3) Load, negotiate, and dump on off-road terrain, longitudinal grades, side slopes, and uneven ground normally encountered at earthmoving construction job sites;
(4) Load, transport, and dump payloads of sand and gravel aggregates, crushed rock, hot paving mixes, earth, clay, rubble, and large boulders and shot rock onto an earth cushion floor of the body;
(5) Perform short haul cycles on secondary roads of under 3 miles for at least 10 hours per day;
(6) Perform long haul-cycles on secondary roads and sustained high speeds, minimum up to 50 mph, on highways for a minimum of 200 miles per day;
(7) Transport payloads, up to GVWR, on expressways, primary highways, unpaved secondary roads, construction haul roads, and off-road mud, snow, and water crossings up to the limits of speed or traction.

(b) Be compatible with the following construction equipment:

(1) Concrete Pavers.
(2) Asphalt Paver.
(3) Chip Spreaders.
(4) Rock Crushers.
(5) Conveyors.
(6) Storage Bins and Hoppers.
(7) Asphalt Pug Mills.
(8) Scoop Loaders, 2-1/2 through 5 cubic yard size.
(9) Power Shovel, Clamshell, Dragline and Backhoe up to 2 cubic yard size.

(c) Have an over-the-sides, loading height, of the dump body without side boards in place, of not greater than 102 inches above level ground.

3.2.3 Cab protector. The cab protector shall be of the full size, load-bearing type having the following features:

(a) Full width and to cover cab to at least within 6 inches rearward of the windshield.
(b) Withstand an aggregate load of minimum 2000 pounds without breaking or permanent deformation.

Source: https://assist.dla.mil -- Downloaded: 202640-22T21:39Z
Check the source to verify that this is the current version before use.

(c) Fabricated of HTLA (high tensile, low alloy) steel minimum 8 gage thickness.
(d) Equipped with a body target which drops down in view of the driver, when the body is seated in the traveling position.

3.2.4 Dump body. The dump body shall be of the rear dump type having a volume capacity, as measured by SAE J741, of minimum 12 cubic years struck and minimum 14 cubic yards heaped (without the use of sideboards). The body shall be as follows:

(a) Provide dump body fabricated of HTLA (high tensile, low alloy) steel; minimum 8 gage sheet for head, sides, and tailgate and minimum 1/4 inch plate for floor.
(b) Provide a full box type top side rail equipped with side rail ends to accept user furnished sideboards up to 12 inches high.
(c) Provide a slanted, double acting tailgate having off-set type, top hinges; provide both horizontal and vertical bracing of tailgate sheet; provide chains for both controlled payload spreading and for lowering the tailgate level with the bed of the body to accommodate extra long loads; provide minimum 18 inches overhang rearward of the tires.
(d) Provide manual tailgate control having lever on left front of body, a chained safety loop for securing lever, and nonbinding rods and mechanisms.
(e) Provide all horizontal body members of the nonspill, dirt shedder type.
(f) Provide body access steps per SAE J185 on left front, exterior of dump body.
(g) Provide twin, positive hoist lock maintenance struts to hold the dump body safely in the raise position in accordance with OSHA requirements.
(h) Provide dump body electrical system in accordance with the legal requirements of DOT.

(1) Provide weatherproof wiring in accordance with SAE J555 and J163, and TTMA RP No. 14.
(2) Provide minimum running lamps of flush mounted or recessed type for maximum protection; and lamps with polycarbonate lenses.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

(i) Provide a heavy weight tarpaulin, sized to completely cover a heaped payload and provide a sufficient number of shock cord tie-downs along the sides to prevent loss of any part of the load. Tarpaulin will not adhere to or be damaged by hot-mix asphalt. Stowage for the tarpaulin assembly shall be provided on the dump truck and the stowed tarpaulin shall not interfere with loading the dump truck body.

3.2.5 Hydraulic hoist system. The dump body shall be actuated by a front mounted telescopic ram hydraulic hoist system having a minimum Class 100, TBEA Hoist Classification and a minimum 30-ton rated capacity. The hydraulic hoist system shall be as follows:

(a) Provide the complete hydraulic system having all components as required by the hydraulic pump and hoist cylinder system:

(1) Operate with rated payload without binding, malfunction, or permanent deformation;
(2) Provide a fail-safe system (see 3.2.5(g)) protected from accidental lowering or overturning due to any hydraulic system failure other than telescopic cylinder;
(3) All components and lines clean and free of foreign matter.

(b) Provide a hydraulic hoist pump in accordance with SAE J744 of the positive displacement type:

(1) At governed engine rpm and a minimum of 40,000 pounds of payload, provide dump body hoist time of not more than 40 seconds and dump body lower time of not more than 30 seconds;
(2) Provide relief valve characteristics per SAE J747 as dictated by the hoist system.

(c) Provide a hydraulic reservoir as follows:

(1) Capacity matched to telescopic cylinder system;
(2) Provide filler cap captive chained to a strainer in the filler neck, and parking "HYD RES" on or near reservoir cap;
(3) Provide self-sealing dipstick or sealed and guarded oil level indicator;

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

(4) Provide a reservoir air breather;
(5) Provide a reservoir mounting to prevent damage from vibration and from off-road terrain.

(d) Provide hydraulic system filter in accordance with ANSI B93.31 an automatic by-pass valve, and a filter element service indicator gage.
(e) Provide a dump hoist control valve characteristics per SAE J747 as dictated by the hoist system.

(1) Provide in-cab lever control, accessible to the driver from his seated position;
(2) Provide lever with tower type neutral "HOLD" lock of the hinged gate type, preventing accidental raising or lowering of the dump body;
(3) Provide lever to valve push-pull control cable of the corrosion-resistant, low friction type.
(4) Provide automatic, fail-safe valve spool return to "HOLD" position from "RAISE" position, when dump body is at maximum dump angle;
(5) Provide in-cab hoist control identification and position labeling on quadrant.

(f) Provide flexible hydraulic hose lines between all components and a test point connection at pump outlet for measuring pressure.
(g) Provide corrosion-resistant telescopic hoist cylinder system matched to the dump body having sufficient mounting structure to spread the loadings over the dump body framing and over the chassis-cab framing: Provide hydraulic cylinder fail-safe check valve (see 3.2.5 (a)(2) above).

3.3 Chassis. The dump body and hoist assembly shall be installed on a chassis as specified in 3.1 and 6.2. The dump truck performance, in the truck's lowest working speed shall be that required to accurately spread a controlled lift of bluechip gravel on a prepared roadway in both the forward and the reverse direction while hoisting the dump body. The dump truck's main transmission driven PTO and hydraulic hoist pump shall be tailored in speed and power to match the dump body hydraulic hoist system. The PTO

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

control shall be equipped with a panel mounted flashing red indicator lamp illuminated whenever the PTO is engaged. The fender requirements for the rear tridem shall be met by the dump body and splash shields. Captive chained alligator clamps or splash shield holder brackets shall be furnished to raise and secure the rear splash shields out of contact with hot asphalt mix, when the dump truck is discharging the mix into asphalt paving machines.

3.4 Lubrication. Lubrication means shall be provided for all moving parts that require lubrication.

3.5 Maintenance characteristics. The dump truck design shall permit ready access to all items requiring periodic maintenance service in the field. Periodic maintenance shall be accomplished with the use of conventional general purpose tools normally associated with equipment of this type. The adjustment of components and accessories shall be accomplished with minimum drainage requirements and minimum disturbance to other elements of the dump truck.

3.6 Safety. All rotating or reciprocating parts and other parts subject to high operational temperatures that are of such a nature or are so located as to be or become a hazard to the operating or attending personnel, shall be substantially guarded, or insulated to the extent necessary to eliminate the hazard. External equipment including steps and handrail shall be designed for durability and operator safety. All steps shall be provided with anti-skid surfacing. All steps and handholds shall be of such design to permit unhampered and nonhazardous access to and from the truck.

3.7 Treatment and painting. The inaccessible areas of the dump body assembly shall be treated with anti-rust coating in accordance with TTMA Technical Bulletin No. 56.

3.8 Basic issue items and manuals. Each truck shall be overpacked with the following when specified (see 6.2):

(a) The items specified in the Basic Issue Items List.
(b) Two copies of the Government approved Operator, Parts, Maintenance and Overhaul Manuals, and Lubrication Order.
(c) Technical publications.
(d) Special tools as required for operator maintenance.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.

3.9 Identification and instruction plates. The manufacturer shall provide all identification and instruction plates normally furnished. The plates and their installation shall conform to the "Metal Name Plate Industry Standards and Practices" published by NAME. The plates shall be permanently affixed to the dump truck in a conspicuous location.

3.10 Certification. Prior to the first article evaluation (see 4.2), the manufacturer shall provide certification that the truck conforms to the following to the extent specified herein:

(a) DOT FMVSS.
(b) DOT FMCSR
(c) DOL OSHA Regulations.
(d) Exterior Noise Level.
(e) Industry Standardization Document Compliance.

3.11 Technical Information Package. The Technical Information Package provided with the solicitation shall be completed by the contractor to depict the truck exactly as it will be furnished (see 6.2).

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection. Unless otherwise specified in the contract, the contractor is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract, the contractor may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.2 First article evaluation. The first produced dump truck with its components, shall be compared with this document, the chassis cab document (see 3.1), the manufacturer's completed Technical Information Package, published literature, calculations and test data, bill of Materials and Assembly Line Build-up Sheet, to verify conformance to this specification. In addition, the truck shall be subjected to a demonstration as specified herein. Nonconformance to any requirement contained herein shall be cause for rejection of the truck.

4.2.1 Performance. Demonstrate the ability of the dump truck to perform the following:

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

(a) Perform dumping cycles of loading, hauling, and dumping of sand and aggregate.
(b) Dump in a fixed location for stock piling.
(c) Dump in a controlled uniform spreading lift while traveling forward and rearward.
(d) Load, haul, and dump a load of oversized boulders or shot rock having a largest dimension of at least 5 foot size.
(e) Demonstrate compatibility of the truck with scoop loaders and asphalt pavers, as a minimum.

4.2.2 Compatibility. Demonstrate the compatibility of the dump truck with earthmoving and construction equipment as follows:

(a) Load the truck with scoop loader to produce a heaped dump body load.
(b) Load the truck with a bin or hopper to produce a heaped dump body load.
(c) Dump the load into the hopper of a bituminous paver, of the wheel roller type, without spillage or interference during forward travel while laying asphalt pavement or, optionally, simulate laying of asphalt pavement.

4.2.3 Dump body mounting. Demonstrate the stability and mounting of the dump body on the chassis-cab as follows:

(a) With a heaped load of earth, wet down and compacted by the bucket of a scoop loader, and with the tailgate closed, hoist the dump bed to the dumping position at an angle of not less than 30 degrees and drive the truck forward over obstacles at least 4 inches high, first under the left rear tandem and then placed under the right rear tandem. While on the 4-in obstacle with the rear tandem raised on the opposite side of the exhaust stack, raise and lower the dump body. Observe the stability of the truck, the hoist, and dump bed hinge points. Observe the dump bed to exhaust stack or other chassis components for areas of possible interference.
(b) With a heaped load of wet down earth, in the travel position, demonstrate the body mounting on the truck by accelerating forward at wide-open-throttle from stop to at least 10 mph and make a panic stop. Repeat this cycle 10 times. Accelerate in reverse at wide-open-throttle and make a panic stop. Repeat this cycle 10 times.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

Observe for any body, hoist, or component displacement, and, while dumping the load observe for evidence of binding or malfunction. Evidence of permanent deformation, shifting of components or misalinement shall constitute failure of this test.

4.2.4 Truck weights. Determine the following dump truck weights by weighing, and recording the results, under the following conditions:

(a) Determine weights both axle-by-axle and total with the pusher axle both load carrying and in the raised position:

(1) Dump truck's curb weight;
(2) Dump truck's actual GVW with a payload of 40,000 pounds evenly distributed in the dump body;
(3) Dump truck's actual payload at GVWR.

(b) With the pusher axle raised, determine the dump truck's recommended maximum speeds allowed by the TRA Yearbook with a payload of 40,000 pounds correctly distributed in the dump body;
(c) Compare the actual pusher axle air bag pressures and axle weights with the load pressure chart furnished.

4.2.5 Highway speed. Demonstrate the truck's maximum high-gear, highway speed capability on hard surfaced roadway with the vehicle loaded to GVWR. Average the speed for four runs, two in each direction.

4.2.6 Gradeability. Both calculate and demonstrate the gradeability of the truck as specified in 3.1. The calculations shall be in accordance with SAE J688 and the demonstrations shall be in accordance with SAE J950. Dump truck compliance shall be at both the straight truck GVWR and at the truck-trailer GCWR minimums.

4.2.7 Dump truck mobility. The dump truck mobility shall be performed as required herein. Permanent deformation, overheating, malfunction, failure to complete any test or leakage of lubricants or hydraulic fluid shall be cause for rejection of the first article.

Terrain	Speed	Loading
Primary Highway Types	50 miles at up to max. mph	GVWR
Primary Highway Types	50 miles at up to max. mph	Empty
Secondary Roads	25 miles at up to 60% max. mph	GVWR
Secondary Roads	25 miles at up to 60% max. mph	Empty
Off-Road Terrain	10 miles at safe speeds	GVWR
Off-Road Terrain	5 miles at safe speeds	Empty

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

During the operaton, demonstrate the following:

(a) Ability to load, transport, and unload.
(b) Based on the primary highway fuel consumption both loaded and empty, calculate travel distance per tank full.
(c) Rocking of the dump truck with load in soft, slippery, off-road terrain by cycle shifting at not more than 2 second intervals from forward to reverse and back, continuously for at least 60 seconds. Achieve at least 3/4 wide-open-throttle power in each gear. Repeat the cycle rocking without load.

4.2.8 Turning capability. Demonstrate vehicle clearance circle and curb clearance circle in accordance with SAE J695, Field Test Procedures.

4.2.9 Braking capability. Demonstrate the brake capability of the truck. Conduct service, emergency, and parking ability demonstrations in accordance with the specified requirements.

4.2.10 Certification. The contractor shall be responsible for insuring that components and materials used in the truck are manufactured, examined, and tested in accordance with the requirements and references specified herein. As a minimum, the contractor shall be required to certify the following, as specified (see 3.1):

(a) In effect at actual time of manufacture:

(1) DOT FMVSS.
(2) DOT FMCSR.
(3) DOL OSHA Regulations.
(4) Exterior Noise Level.

(b) In effect at time of solicitation for bid:

(1) Industry Standardization Document Compliance.

4.3 Run-in. Each dump truck shall be subjected to a run-in and servicing as specified herein. Inability to complete the run-in, malfunction of any control, evidence of leakage of lubricants or hydraulic fluid shall be cause for rejection of the truck by the Government until such deficiencies are corrected.

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.

4.3.1 Dump body portion. Each dump body shall be run-in, and lubricated in accordance with the body manufacturer's current procedures.

4.3.2 Dump truck.

4.3.2.1 Travel. Demonstrate starting, shifting up and down through all gears, braking, steering, and high speed travel for a distance of at least 15 miles (see 3.1 in reference to chassis specification.)

4.3.2.2 Servicing and adjustment. As specified in the chassis specification (see 3.1), prior to delivery, the manufacturer shall service and adjust each truck for customer operational use.

4.4 First article demonstration report. The contractor shall prepare and submit the first article demonstration report to the contracting officer for approval within the time frame specified (see 6.2). The report shall include a detailed description of the examination and demonstration performed, deficiencies encountered and actions taken to correct the deficiencies.

4.5 First article. The first produced truck shall be compared with this document, the contractor's completed Technical Information Package and published literature to verify conformance to this specification.

5. PACKAGING

5.1 Vehicle processing. Vehicle shall be processed for shipping from manufacturer's plant to initial receiving activity in accordance with manufacturer's standard commercial practice.

6. NOTES

6.1 Intended use. The dump trucks covered by this specification are intended for world-wide, earthmoving and construction projects by the Armed Forces in engineer troop support use.

6.2 Ordering data. Procurement documents should specify the following:

(a) Title, number, and date of this specification.
(b) Items listed in the Basic Issue Item List (see 3.8).
(c) Time frame for submitting the first article demonstratoion report (see 4.4).

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.

(d) When the dump truck chassis is required to conform to another specification in lieu of MIL-T-PD-9156 the title, number, and date of the required chassis specification (see 3.1).

Custodian:
Army - ME

Preparing activity:
Army - ME

Project 3805-A093

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

FOLD

POSTAGE AND FEES PAID
DEPARTMENT OF THE ARMY
DOD – 314

OFFICIAL BUSINESS
PENALTY FOR PRIVATE USE $300

Commander
US Army Mobility Equipment Research
and Development Command
ATTN: DRXFB-DS
Ft. Belvoir, VA 22060

FOLD

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T21:39Z
Check the source to verify that this is the current version before use.

STANDARDIZATION DOCUMENT IMPROVEMENT PROPOSAL

OMB Approval
No. 22-R255

INSTRUCTIONS: The purpose of this form is to solicit beneficial comments which will help achieve procurement of suitable products at reasonable cost and minimum delay, or will otherwise enhance use of the document. DoD contractors, government activities, or manufacturers/ vendors who are prospective suppliers of the product are invited to submit comments to the government. Fold on lines on reverse side, staple in corner, and send to preparing activity. Comments submitted on this form do not constitute or imply authorization to waive any portion of the referenced document(s) or to amend contractual requirements. Attach any pertinent data which may be of use in improving this document. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity.

DOCUMENT IDENTIFIER AND TITLE: MIL-T-52900A(ME) Truck, Dump, 20 Ton, 8x6, XM917 Commercial Construction Equipment (CCE)

NAME OF ORGANIZATION AND ADDRESS

CONTRACT NUMBER

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE DOCUMENT CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?
   A. GIVE PARAGRAPH NUMBER AND WORDING.

   B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES

2. COMMENTS ON ANY DOCUMENT REQUIREMENT CONSIDERED TOO RIGID

3. IS THE DOCUMENT RESTRICTIVE?

   ☐ YES ☐ NO *(If "Yes", in what way?)*

4. REMARKS

SUBMITTED BY *(Printed or typed name and address - Optional)*

TELEPHONE NO.

DATE

DD FORM 1 JAN 72 1426 REPLACES EDITION OF 1 JAN 66 WHICH MAY BE USED

Source: https://assist.dla.mil -- Downloaded: 202610-22T21:39Z
Check the source to verify that this is the current version before use.