M1L-M-50383A(AR)
AMENDMENT 2
5 January 1990
SUPERSEDING
AMENDMENT 1
17 August 1984

MILITARY SPECIFICATION

MOUNT, TELESCOPE: M134A1

This Amendment forms a part of Military Specification MIL-M-50383A(MU) dated 26 September 1974, and is approved for use by the US Army Armament, Munitions and Chemical Command and is available for use by all Departments and Agencies of Department of Defense.

PAGE 1

2.1 standards: Delete "MIL-STD-1458".

Drawings: Change “Frankford Arsenal” to “Armament Research, Development and Engineering Center (ARDEC)”.

PAGE 2

* Add new paragraph 2.2:

“2.2 Other publications. The following document forms a part of this specification to the extent specified herein. Unless otherwise indicated, the issue in effect on date of invitation for bids or request for proposal shall apply.

Defense Agency Manual

DSAM 4145.8 Radioactive Commodities in the DOD Supply Systems

(Copies may be obtained from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402) .

3.1: Change "MIL-STD-1458" to "DSAM 4145.8".

3.3: Delete and substitute:

“3.3 General specification. The contractor shall be responsible for the compliance with the requirements of specification MIL-F-13926.”

AMSC N/A

FSC 1240

DISTRIBUTION STATEMENT A. Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

PAGE 5

3.6: Delete and substitute new 3.6:

"3.6 Illumination.

3.6.1 Level Vial. The level vial bubbles and graduation lines shall each be visible in all ambient light conditions.

3.6.2 External tritium contamination. There shall be no trace of tritium in excess of 1000 disintegrations per minute (dpm)/100 sq. cm. on the external surface of the mount. "

PAGE 7

4.3.2.2, MAJOR : Delete "AQL 1.% Defective" and substitute "100% Inspection".

112. Delete "3.5.12" and substitute "3.5.11".
Add "114. Fabrication, 3.2, MIL-F-13926, Visual/Tactile
115. External tritium contamination 3.6.3 4.6.4
116. Packaging 5.1 4.6.5".

4.4.1: Delete "Special sampling" paragraph and substitute:

"4.4.1 Special sampling. Three telescopes shall be selected at random by a Government representative as a special sample from each 100 produced or from each month's production, whichever occurs first. Samples shall have met all the requirements and tests outlined in Table IV Prior to being subjected to the examinations and tests of Table V: ".

Table V: Delete 301, 302, and 303.

PAGE 12

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

"4.6.4 External tritium contamination. Contamination test shall be performed by wiping the telescope with filter paper moistened in distilled water. The wiping shall be performed with moderate finger pressure. The damp filter paper shall be placed in a container with the proper portion of scintillation liquid. The scintillating system used to measure contamination must be calibrated and shall be within 10% of the known standard value when counted to a total of 2000 disintegrations. The actual test for determining contamination is performed by placing the container into the scintillation system. The measured contamination shall be within the limits specified in 3.6.3."

"4.6.5 Packaging. The preservation, packing, and marking shall be inspected to verify conformance to the requirements of 5.1."

5.1, line 2: After "with" add "MIL-P-142232 and".

PAGE 13

6.2: Add new subparagraph e:

"e. Contract data requirements for submission of inspection equipment designs conforming to Data Item Description DI-R-1714. (See 6.4.1)."

Add new paragraphs 6.4 and 6.4.1:

"6.4 Inspection equipment design.

6.4.1 Submission of designs for approval. Contractor designs for final acceptance inspection shall be approved by the Government prior to fabrication or procuring the equipment. The contractor is referred to MIL-HDBK-204 for guidance. Submission of design concept on inspection equipment is permissible for tentative approval. The completion date for design review will be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract. Submit

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

designs as required to: Commander, US Army Armament Research and Development Center, ATTN: DRSMC-QAF-1(D), Dover, NJ 07801-5001. When the contractor submits inspection equipment designs to the Government for approval he shall give the following information in his letter of transmittal:

a. The contract number.

b. The contract item (name, model number, etc.).

c. The designs remaining to be submitted and the expected date of submittal."

AMENDMENT 1

2.1 Specifications: Delete "MIL-L-50778".

2.2: Delete "MIL-HDBK-204".

NOTE: The margins of this amendment are marked with an asterisk to indicate where changes (additions, modification, corrections, deletions) from the previous amendment were made. This was done as a convenience, only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship.to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

(Project 1240-A944)

Source: https://assist.dla.mil -- Downloaded: 2026t0-22T20:23Z
Check the source to verify that this is the currentversion before use.