INCH-POUND

MIL-T-503B4(AR)
AMENDMENT 2
25 JAN 1990
SUPERSEDING
AMENDMENT 1
17 August 1984

MILITARY SPECIFICATION

TELESCOPE, ELBOW: M114E1

This Amendment forms a part of Military Specification MIL-T-50384(MU), dated 16 June 1970, and is approved for use by the U.S. Army Armament, Munitions and Chemical command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 1

Title: Change from "M114E1" to "M114A1" and wherever it appears in the specification.

* Drawings: Change from "Frankford Arsenal" to "Armement Research, Development and Engineering Center"

PAGE 2

* 2.2: Delete "of DSAM 4158.8".

* 3.3: Delete and substitute:

"3.3 General specifications. The contractor shall be responsible for the compliance with the requirements of specification MIL-F-13926."

* 3.10: Delete and substitute 3.10 and add 3.10.1 and 3.10.2:

"3.10: Illumination.

3.10.11 Reticle. The Reticle markings shall be visible in ambient light conditions ranging from dusk into night. When required, the use of a mask with a 3/4" aperture, located on the entrance window, will be permitted to meet the requirements.

3.10.2 External tritium contamination. There shall be no trace of trtium in excess of 1000 disintegrations per minute (dpm)/100 sq. cm. on the external surface ofr the telescope.

DISTRIBUTION STATEMENT A. Approved for public. release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026t0-22T20:23Z
Check the source to verify that this is the current version before use.

PAGE 6

* 4.3.2.2, Table II: After CRITICAL: Change to "None".

Add "MAJOR: 100% Inspection".

Delete "MAJOR: AQL 1.0% Defective" and renumber as follows: Characteristic 1 to 101, 2 to 102, 101 to 103, 102 to 104, 103 to 105, etc.

114: After operability: Add "(60°F(16°C) to 90°F(32°C))".

115: Change "3.10" to "3.10.1",

Add: "117 External Tritium contamination 3.10.2 4.2.16
118 Fabrication 3.2 MIL-F-13926
119 Packaging Inspection 5.1 4.7"

PAGE 11

4.6.2.15, lines 8 and 13: Change "3.1O to 3.10.1".

* Add new paragraphs 4.2.16 and 4.7:

"4.2.16 External tritium contamination. Contamingation test shall be performed by wiping the telescope with filter paper moistened in distilled water. The wiping shall be performed with moderate finger pressure. The damp filter paper shall be placed in a container with the proper portion of scintillation liquid. The scintillating system used to measure contamination must be calibrated and shall be within 10% of the known standard value when counted to a total of 2000 disintegrations. The actural test for determining contamination is performed by placing the container into the scintillation system. The measured contamination shall be within the limits specified in 3.10.3."

"4.7 Packaging inspection. The preservation, packaging, and marking shall be inspected to verify conformance to the to the requirements of 5.1."

PAGE 12

6.2: Add new subparagraph d:

"d. Contract data requirements for submission of inspection equipment designs conforming to Data Item Description DI-R-1714, Tailored. See 6.4.1."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.

Add new paragraphs 6.4 and 6.4.1:

"6.4 Inspection equipment design."

"6.4.1 Submission of designs for approval. Contractor designs for final inspection acceptance inspection shall be approved by the Government prior to fabrication or procuring the equipment. The contractor is referred to MIL-HDBK-204 for guidance. Submission of design concept on inspection equipment is permissible for tentative approval. The completion date for design review eill be based on the date of the final submission of designs and the required delivery schedule as stipulated in the contract. Submit designs as required to: Commander, US Army Armament Research, Development and Engineering Center, Attn: AMSMC-QAF-I(D) , Picatinny Arsenal, NJ 07896-5000. When the contractor submits inspection equipment designs to the government for approval, he shall give the following information in his letter of transmittal:

a. The contract number.

b. The contract item (name, model number, etc.).

c. The designs remaining to be submitted and the expected date of submittal.

AMENDMENT 1

2.1: Delete "MIL-L-50778" and "MIL-HDBK-204".

NOTE: The margins of this Amendment are marked with asterisks to indicate where changes (additions? modifications corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army-AR

Preparing activity:
Army-AR

Project (1240-A948)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:23Z
Check the source to verify that this is the current version before use.