DATA ITEM DESCRIPTION

Form Approved
OMB No. 0704-0188

Public reporting burden for collection of this information is estimated to average 110 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. TITLE	2. IDENTIFICATION NUMBER
TEST PROGRAM SET(TPS) ACCEPTANCE TEST REPORT (ATR)	DI-ATTS-80283B

3. DESCRIPTION / PURPOSE

3.1 The Acceptance Test Report is a compilation of the results of the Operational Test Program Set (OTPS) and Test Program Set (TPS) tests.

3.2 This ATR is the means by which the Government accepts Test Programs.

4. APPROVAL DATE (YYMMDD)	5. OFFICE OF PRIMARY RESPONSIBILITY	6a. DTIC APPLICABLE	6b. GIDEP APPLICABLE
970211	N/PMA-260		

7. APPLICATION / INTERRELATIONSHIP

7.1 This DID contains the format and content preparation instructions for the data product generated by the specific and discrete task requirements as delineated in the contract.

7.2 This DID is related to DI-ATTS-80281, Test Program SET (TPS) Integration Logbook and DI-ATTS-80282B, Test Program Set (TPS) Acceptance Test Procedures (ATP).

7.3 This DID supersedes DI-ATTS-80283A.

8. APPROVAL LIMITATION	9a. APPLICABLE FORMS	9b. AMSC NUMBER
		N7237

10. PREPARATION INSTRUCTIONS

10.1 Reference Document. The applicable issue of the documents cited herein, including their approval dates and dates of any applicable amendments, notices, and revisions, shall be as specified in the contract.

10.2 Format. Figures 1 through 6 provide sample data sheet format.

10.3 Contents.

10.3.1 Test Results. The ATR shall contain the results of the acceptance tests performed by the contractor to demonstrate that the OTPS (Test Programs, Interface Hardware, and documentation) conforms to the performance specifications, work authorization document, or contract requirements.

10.3.2 Data Sheets. The ATR shall contain appropriate data sheets of the test results as specified in DI-ATTS-80282B, Test Program (TP) Acceptance Test Procedures (ATP's).

(continued on page 2)

11. DISTRIBUTION STATEMENT

Distribution Statement A: Approved for public release; distribution is unlimited.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

Block 10, Preparation Instructions (continued)

10.3.3 Supplemental data. The appropriate "MATERIAL AND RECEIVING REPORT (DD FORM 250)" and any special waivers, deviations, open items, and exceptions shall be attached to the ATR.

10.3.4 Correction of deficiencies. The ATR shall specify when and how the test deficiencies will be corrected.

10.3.5 Cover sheet. The ATR shall contain a cover signature sheet for the contractor program manager, quality assurance representative, TP engineer, and the Government acceptance representative.

10.4 Acceptance test reports. ATR's shall include the results of the following TP acceptance tests:

a. First Article

(1) Functional Configuration Audit (FCA)

(2) Physical Configuration Audit

(3) Transportability Demonstration

(4) Repeatability Demonstration

(5) Maintainability Review

b. Production units

10.4.1 The ATR shall include a narrative summary of test results.

10.4.2 Data sheets (see sample Figures 1 through 6.)

10.4.2.1 The Design Verification Test Fault Selection List data sheets shall be included as part of the ATR.

10.4.2.2 The Maintainability Review/Analysis Test Report data sheets shall be included as part of the ATR.

10.4.3 Correction of deficiencies.

10.4.4 Open items.

10.4.4.1 Recommended solutions.

10.4.4.2 Schedules for completion of open items.

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

ACCEPTANCE TEST REPORT
TPS, UUT, TESTER IDENTIFICATION DATA SHEET

TPS Part Number _____ Date of Test _____

NOMENCLATURE	PART NUMBER	SERIAL NUMBER
TEST STATION		
UUT UNDER TEST		
ID ELEMENTS SRA's, CHASSIS TEST FIXTURES CABLES, etc.		
TEST PROGRAM INSTRUCTION		
TEST PROGRAM MEDIUM		
ANCILLARY TEST EQUIPMENT		

Witness / Date

Contractor Quality Assurance _____ / _____

Government Representative _____ / _____

FIGURE 1. ATR Identification Data Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

ACCEPTANCE TEST REPORT
SOFTWARE IDENTIFICATION DATA SHEET

TPS Part Number _____ Date of Test _____

NOMENCLATURE	PART NUMBER	REVISION NUMBER
OPERATING SYSTEM		
TEST EXECUTIVE		
COMPILER		
POST PROCESSOR		
ATE SELF TEST PART NUMBER		
ATPG SYSTEM		
OTHER		

Witness / Date

Contractor Quality Assurance _____ / _____

Government Representative _____ / _____

FIGURE 2. ATR Software Identification Data Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

ACCEPTANCE TEST REPORT
TPS DVT DATA SUMMARY SHEET

TPS Part Number _____ Date of Test _____

SUMMARY OF RESULTS

TPS VISUAL INSPECTION	SATISFACTORY _____ UNSATISFACTORY _____ EXPLAIN, IF NECESSARY _____ _____ _____
TPS PERFORMANCE TESTS	NUMBER OF MINOR DEFECTS _____ NUMBER OF MAJOR DEFECTS _____ NUMBER OF CRITICAL DEFECTS _____
FAULT INSERTION TEST	Ft - Total Faults Inserted _____ Fs - Faults Successfully Isolated _____ Fu - Faults unsuccessfully isolated _____ % Isolated = $\frac{Fs}{Ft}$ X 100 _____

Witness / Date

Contractor Quality Assurance _____ / _____

Government Representative _____ / _____

FIGURE 3. ATR TPS DVT Data Summary Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

ACCEPTANCE TEST REPORT
TP PERFORMANCE TEST DATA SHEET
(END-TO-END RUN)

TPS PART NUMBER _____ DATE _____

END TO END TEST RESULTS

ELAPSED TIME _____ SUCCESSFUL _____ UNSUCCESSFUL _____

DESCRIPTION OF DEFECT

CONTRACTOR, QA _____ GOVERNMENT REPRESENTATIVE _____

DESCRIPTION OF CORRECTION

END TO END RETEST RESULTS

ELAPSED TIME _____ SUCCESSFUL _____ UNSUCCESSFUL _____

CONTRACTOR, QA _____ GOVERNMENT REPRESENTATIVE _____

FIGURE 4. ATR TPS End To End Performance Test Data Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

FIRST ARTICLE ACCEPTANCE TEST
FAULT INSERTION DATA SHEET

TPS PART No. _____ DATE OF TEST _____

TPS PART No.		INITIAL TEST	RETEST
FAULT No.			
FAULT INSERTION DESCRIPTION	SUCCESSFUL		
	MINOR DEFECT		
	MAJOR DEFECT		
	CRITICAL DEFECT		

FAULT INSERTION TEST RESULT

FAILED PERFORMANCE TEST No _____ FAILED DIAGNOSTICS TEST No. _____ REMOVE & REPLACE MESSAGE

ELAPSED TIME _____ _____
AMBIGUITY GROUP CALLOUT SIZE _____ _____
AMBIGUITY GROUP REQUIREMENT _____ _____

DESCRIPTION OF DEFECT

CONTRACTOR _____ DGAR _____

DESCRIPTION OF CORRECTION

FAULT RE-INSERTION TEST RESULT

DATE OF TEST _____

FAILED PERFORMANCE TEST No. _____ FAILED DIAGNOSTICS TEST No. _____ REMOVE & REPLACE MESSAGE

ELAPSED TIME _____ _____
AMBIGUITY GROUP CALLOUT SIZE _____ _____
AMBIGUITY GROUP REQUIREMENT _____ _____

CONTRACTOR QA _____ DGAR _____

FIGURE 5. ATR TPS End To End Performance Test Data Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.

ACCEPTANCE TEST REPORT
TPS DOCUMENTATION REVIEW SHEET

TPS Part Number _____ Date of Test _____

OPERATIONAL TEST PROGRAM INSTRUCTION _____

TEST PROGRAM INSTRUCTION _____

	Sat	Unsat	N/A
OTPI Title Page			
OTPI Table of Contents			
OTPI Record of Revisions/Changes			
TPI Title Page			
Introduction			
Revisions/Changes			
Reference Documents			
List of Illustrations			
List of Tables			
Pre-testing Data			
Reference Documents			
ATE Resources Required			
TPS Hardware Required			
Ancillary Equipment Required			
Special Tools			
No-Fault End t End Run Time			
Precautionary Notes			
Testing Data			
Program Start Procedures			
Partition Entry Points			
Test Instructions			
UUT Parts Location			
Functional Flow Chart			

	Sat	Unsat	N/A
Post-Testing Data			
Program Termination			
Disconnect and Removal Instructions			
Test Diagrams			
Test Program Listing			
Master Test Program Set Index			
TPS Hardware			
TPS Software			
TPS Ancillary Equipment			
Additional Data			
Engineering Support Data			
Test Strategy Report			
ATPG Support Data			
TPS Source Files/Computer Program Aids			

DESCRIPTION OF DEFECT

Contractor _____ Government Representative _____

DESCRIPTION OF CORRECTION

Contractor _____ Government Representative _____

FIGURE 6. ATR TPS End To End Performance Test Data Sheet Sample

Source: https://assist.dla.mil -- Downloaded: 2026-10-26T10:36Z
Check the source to verify that this is the current version before use.