MIL-F-46473A (MU)
21 June 1963
SUPERSEDING
MIL-F-46473 (Ord)
27 January 1961

MILITARY SPECIFICATION

FUZE, POINT DETONATING M535 LOADING, ASSEMBLING AND PACKING

1. SCOPE

1.1 This covers the loading, assembling and packing for one type of fuze designated as Fuze, Point Detonating, M535.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-A-2550 - Ammunition and Special Weapons, General Specification for.
MIL-I-45208 - Inspection Requirements, General Specification for.
MIL-I-45607 - Inspection Equipment, Supply and Maintenance for.
MIL-D-46432 - Detonator, Stab, M18, Loading, Assembling and Packing.

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes.
MIL-STD-109 - Quality Assurance Terms and Definitions.
MIL-STD-350 - Jolt Test for Use in Production of Fuzes.
MIL-STD-351 - Jumble Test for Use in Production of Fuzes.

FSC: 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

MIL-STD-1235 - Single, Multilevel Continuous Sampling Procedures for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8861213 - Box, Wirebound, Packing, Ammunition, for Artillery Type Fuzes.
7548400 - Box, Packing, Ammunition, for Standard Contour Fuzes w/Boosters in Fiber Container M43A2.
7548401 - Container, Amm., Fiber M43A2 for Standard Contour Fuzes w/Booster.
8864492 - Box, Amm., Metal Parts, Artillery Type Fuzes.
8866760 - Fuze, Point Detonating M535, Assembly.

PUBLICATIONS

ORDNANCE CORPS

IEL - 8866760 - Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings, and publications required by contractors in connection with the specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer).

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Fuze Assembly.-The loaded fuze assemblies shall comply with all requirements specified on Drawing (dwg.) 8866760.

3.3 Head Assembly Torque.-The head assembly shall show no evidence of loosening when subjected to an unscrewing force of not less than 75 nor more than 100 inch-pounds when tested as specified in 4.4.3.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

3.4 Jolt and jumble.-The loaded fuze assemblies shall have no explosive elements explode, shall have its interrupter remain in the unarmed position (completely obstruct flash hole), shall not come apart, and shall have no parts broken, deformed or displaced in such a manner as to render the fuze unsafe to handle or dangerous to fire when subjected to the jolt test as specified in MIL-STD-350 and the jumble test specified in Standard MIL-STD-351. These test shall be performed as specified in 4.3.3.1.

3.5 Functioning.-The fuzes shall comply with the following requirements when tested as specified in 4.3.3.2.

3.5.1 Super-quick phase.

3.5.1.1 Safety-The fuze shall show no evidence of premature burst or separation of metal parts in gun tube or in flight (see 6.4).

3.5.1.2 Firing.-The fuze shall cause the projectile to function high order with no evidence of reverse functioning. (see 6.5)

3.5.2 Delay phase.

3.5.2.1 Safety.-The fuze shall show no evidence of premature burst or separation of metal parts in gun tube or in flight (see 6.4).

3.5.2.2 Firing.-The fuze shall not fail to function, shall fire within a zone of 75 feet, min., to 250 feet, max., behind the screen, and shall show no evidence of reverse functioning. (see 6.5)

3.6 Workmanship.-All parts and assemblies shall be fabricated and loaded in a thorough workmanship manner. They shall be free of burrs, sharp edges, cracks, dirt, rust and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous and all required markings shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions.-The supplier is responsible for the performance of all inspection requirements specified herein. Except as otherwise specified, the supplier may utilize his own or any other inspection facilities and services acceptable to the Government. Inspection records of the examinations and tests shall be kept complete and available to

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

the Government as specified in the contract or order. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure that supplies and services conform to prescribed requirements. Reference shall be made to Standard MIL-STD-109 in order to define terms used herein. The provisions of Specification MIL-A-2550 shall apply.

4.1.1 Contractor quality assurance system.-The contractor shall provide and maintain an effective quality assurance system in compliance with the requirements of Specification MIL-I-45208.

4.1.2 Submission of product.-At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all quality assurance provisions of the approved current written description of the system.

b. Number of units of product inspected.

c. Results obtained for all inspection performed.

d. Drawing, specification number and date, together with an identification and date of changes.

e. Certificates of analyses on all material purchased directly by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

f. Number of items in the lot.

g. Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.1.3 Government verification.-Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be in accordance with Specification MIL-I-45208 and will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

4.2 Initial production inspection.

4.2.1 Submission.-Prior to initiation of regular production, the contractor shall submit a sample of 156 assemblies to a Government proving grounds designated by the Contracting Officer for testing in accordance with the provisions of 4.2.2. All parts and materials shall be the same as will be used in production and shall be obtained from the same source of supply. Prior to submission, the sample shall be inspected by the contractor to the degree necessary to assure that it conforms to the requirements of the contract.

4.2.2 Inspections to be performed.-Assemblies will be subjected by the Government to the following tests:

a. Jolt and jumble (see 4.3.3.1.1)
b. Functioning (see 4.3.3.2.1)

The number of assemblies to be subjected to each test and the number of assemblies in each phase and setting for the functioning test shall be in accordance with 4.3.3.1.1 and 4.3.3.2.1.

4.2.3 Rejection.-Rejection of the sample submitted shall be in accordance with 4.3.3.1.1 and 4.3.3.2.1. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample. Until the initial production sample is accepted, the contractor is not authorized by the Government to proceed with regular production unless otherwise directed by the Contracting Officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.3 Inspection provisions.

4.3.1 Lot formation.-A lot shall consist of fuze assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot interfix number. Each lot shall contain:

a. Parts and parts assemblies of one interfix lot number from one manufacturer.

b. Booster assemblies of one interfix lot number from one manufacturer.

c. Delay plunger assemblies of one interfix lot number from one manufacturer.

d. Detonator assemblies of one interfix lot number from one manufacturer.

4.3.2 Examination.-Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL-STD-105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL-STD-1235 (Ord) may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.25 percent for each major defect and an AQL of 0.40 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Head Assembly (see dwg. 7549043 covering a detail of dwg. 8866760).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined.		
Major:	AQL 0.40 percent		
101.	Detonator missing or inverted (when viewed through aft opening with detonator retaining screw removed, the green disc should be observed).	Visual	01001
102.	Detonator cushion missing.....	Visual	01002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

103.	Detonator retaining screw stake missing	Visual	01003
104.	Detonator retaining screw not fully seated	Visual	01004

Minor: AQL 0.40 percent

201.	Evidence of poor workmanship (see 3.6)	Visual	01005

4.3.2.2 Assembly, prior to assembling flash tube and booster assembly (see dwg. 8866760).

Categories	Defects	Method of Inspection	Code No.
Critical:			
1.	Delay plunger assembly missing or incorrectly positioned	Visual	02001
2.	Interrupter does not completely obstruct flash hole (in armed or partly armed position)	Visual	02002
Major:	AQL 0.25 percent		
101.	Foreign matter in flash hole, in booster assembly cavity or on delay plunger assembly	Visual	02003
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	02004

4.3.2.3 Assembly prior to assembly of head assembly (see dwg. 8866760).

Categories	Defects	Method of Inspection	Code No.
Critical: None defined.			
Major:	AQL 0.25 percent		
101.	Flash tube stake missing	Visual	03001
102.	Foreign matter in flash tube cavity	Visual	03002
Minor:	AQL 0.40 percent		
201.	Evidence of poor workmanship (see 3.6)	Visual	03003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.3.2.4 Assembly (see dwg. 886760).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 1.0 percent		
101.	Total length, maximum (max.)	Gage	04001
102.	Length to shoulder above threads, max	Gage	04002
103.	Ogive partially covers setting sleeve rendering it inaccessible	Visual	04003
104.	Setting sleeve incorrectly positioned	Visual	04004
105.	Body thread damaged	Visual	04005
106.	Booster cup cracked or split	Visual	04006
107.	Firing pin closing disc missing or damaged (punctured, cracked or dented)	Visual	04007
108.	Delay time not specified on body	Visual	04008
109.	Crack or puncture at ogive head stake or dimples	Visual	04009
110.	Ogive cracked, dented or deformed	Visual	04010
111.	Ogive head stake or booster assembly stake missing or inadequate	Visual	04011
Minor:	AQL 2.5 percent		
201.	Protective coating missing from stakes	Visual	04012
202.	Marking misleading or unidentifiable	Visual	04013
203.	Wrench slots damaged to the extent they will not receive a wrench	Visual	04014
204.	Protective coating damaged	Visual	04015
205.	Evidence of poor workmanship (see 3.6)	Visual	04016

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.3.2.5 Carton (sealed) (see dwg. 7548401).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Assembly damaged so that contents are exposed or liable to become exposed	Visual	05001
102.	Sealing strip incomplete badly wrinkled, or not in contact with surface for at least 1/2 inch around entire carton	Visual	05002
Minor:	AQL 1.0 percent		
201.	Contents move when carton is shaken	Manual	05003
202.	Marking misleading or unidentifiable	Visual	05004

4.3.2.6 Container, metal, sealed (see dwg. 8864492) when applicable (see 5.1.1).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Puncture or deep scratch	Visual	06001
102.	Container dented or deformed	Visual	06002
Minor:	AQL 1.5 percent		
201.	Contents move when container is tilted	Manual	06003
202.	Bare spot on exterior	Visual	06004
203.	Key missing	Visual	06005
204.	Marking misleading or unidentifiable	Visual	06006

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.3.2.7 Box, packing (prior to insertion into box) (see dwg. 8861213 or 7548400, as applicable).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.25 percent		
101.	Waterproofness destroyed by separation of heat seal, rip, tear, or puncture	Visual	07001
Minor:	AQL 1.0 percent		
201.	Label missing or peeling	Visual	07002
202.	Marking misleading or unidentifiable	Visual	07003

4.3.2.8 Box, packing (sealed) (see dwg. 8861213 or 7548400, as applicable).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined.		
Major:	AQL 0.65 percent		
101.	Hardware missing, broken or loose	Visual-Manual	08001
102.	Strapping missing, broken or loose	Visual-Manual	08002
103.	Contents exposed	Visual	08003
104.	Board broken or split	Visual	08004
105.	DOD symbol misleading or unidentifiable	Visual	08005
Minor:	AQL 2.5 percent		
201.	Hardware improperly engaged	Visual	08006
202.	Handle missing or insecure	Visual-Manual	08007

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

203.	Contents loose (when box is tilted)	Manual	08008
204.	Strapping improperly assembled.	Visual	08009
205.	Marking misleading or unidentifiable	Visual	08010
206.	Car seal missing, unsealed or improperly positioned	Visual	08011

4.3.3 Testing

4.3.3.1 Jolt and jumble (see 3.4) Critical defect. Code No. 09001.

4.3.3.1.1 First three (3) production lots.-Beginning with the first production lot and continuing until 3 consecutive lots have passed the acceptance criteria prescribed, thirty-six (36) loaded fuze assemblies shall be selected and tested from each lot. If one or more fuze assemblies fail to comply with the requirements the lot shall be rejected. The tests shall be performed as specified in 4.4.1. using equipment in accordance with 4.3.4.

4.3.3.1.2 Regular production.-After three consecutive lots have met the criteria of 4.3.3.1.1, twelve (12) loaded fuze assemblies shall be selected from each lot and tested as specified in 4.4.1 using equipment in accordance with 4.3.4. If one or more fuze assemblies fail to comply with the requirements specified the lot shall be rejected.

4.3.3.2 Functioning (see 3.5).-Critical defect if any premature burst occurs; major defect for all others. Code No. 10001.

4.3.3.2.1 First three (3) production lots.-Beginning with the first production lot and continuing until 3 consecutive lots have passed the acceptance criteria prescribed, one hundred twenty (120) loaded fuze assemblies shall be selected from each lot and tested as specified in 4.4.2 using equipment in accordance with 4.3.4. The acceptance rejection criteria and number of fuzes to be tested in each phase and setting shall be as specified in Table I.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

TABLE I

Samples			Acceptance Rejection Criteria		
Phase	Weapon	Sample Size	Defect	No. defects Accept	No. defects Reject
Super Quick	76 mm gun	35	Premature burst	0	1
	4.2 inch mortar	35	Fuze break-up in gun tube or in flight	0	1
			failure to cause projectile to function high order (dud)	2	3
			evidence of reverse functioning	4	5
Delay	75 mm gun	20	Premature burst (all guns)	0	1
			fuze break-up in gun tube or in flight (all guns)	0	1
	76 mm gun	15	projectile functions outside zone of 75 ft. behind screen (76 mm gun)	4	5
	105 mm Howitzer	15	evidence of reverse functioning (all guns)	4	5
			Total duds (all guns)	5	6
			Duds or low order (75 mm gun)	1	2
			Duds or low order (76 mm gun)	4	5
			Duds or low order (105 mm Howitzer)	1	2

4.3.3.2.2 Regular Production.-After three consecutive lots have met the criteria of 4.3.3.2.1, loaded fuze assemblies shall be selected from each lot and tested as specified in 4.4.2, using equipment in accordance with 4.3.4. Sample sizes shall be in accordance with the double sampling plan specified in Table II. A total of thirty-five (35) loaded fuze assemblies shall be selected from each lot for the first sample, and a total of seventy (70) shall be selected for the second sample if necessary. Acceptance and rejection criteria shall be in accordance with Table II.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

TABLE II

Samples			
Phase	Weapon	First Sample Size	Second sample size if necessary
Super Quick	76 mm gun	10	20
	4.2 inch mortar	10	20
Delay	75 mm gun	5	10
	76 mm gun	5	10
	105 mm Howitzer	5	10

Acceptance Rejection Criteria					
		First Sample		Combined first and second sample	
Phase	Defects	Number Defects Accept	Number Defects Reject	Number Defects Accept	Number Defects Reject
Super Quick	Premature burst	0	1	0	1
	Fuze break-up in gun tube or in flight	0	1	0	1
	failure to cause projectile to function high order (dud)	0	2	1	2
	Evidence of reverse functioning	0	3	2	3
Delay	Premature burst (all guns)	0	1	0	1
	fuze break-up in gun tube or in flight (all guns)	0	1	0	1
	evidence of reverse functioning	0	4	3	4
	Duds (all guns)	0	5	4	5
	Projectile functions outside zone of 75 ft. min. to 250 ft. max. behind screen (76mm gun)	0	4	3	4
	Duds or low order 75 mm gun	0	2	1	2
	Duds or low order 76 mm gun	0	4	3	4
	Duds or low order 105 mm How.	0	2	1	2

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.3.3.3 Check test for deterioration of detonators (see Military Specification MIL-D-46432) Major defect - Code No. 11001 If the total time between original acceptance of any detonator lot and the assembly of that lot into the fuzes exceeds two years, at any time since previous tests, the detonator lot shall be subjected to, and must satisfactorily pass, the check test for deterioration specified in Military Specification MIL-D-46432 immediately before the detonator lot is assembled into the fuzes. This test shall be performed by the contractor on detonators selected by the Government inspector at the facility assembling the detonators into the cartridges. The test shall be conducted at Government expense without cost to the contractor who loaded. The detonators or the contractor assembling the detonators into the fuzes, and shall not constitute a basis for rejection against either contractor except where deterioration has occurred as a direct result of carelessness in handling, storage, etc. permitted while the detonator lot was under the jurisdiction of either contractor (see 6.5).

4.3.4 Inspection Equipment.-Index of Inspection Equipment Number IEL 8866760 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 Supply and maintenance.-Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL-I-45607.

4.3.4.3 Government use of contractor's inspection equipment.-The contractor shall as required make available to the Government all inspection equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor, as required by the Government in performance of its examination or test.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.4 Test methods and procedures.

4.4.1 Jolt and jumble.-The loaded fuze assemblies shall be subjected to the jolt test in accordance with Standard MIL-STD-350. After completion of the jolt test, the fuzes subjected to the jolt test shall not be disassembled but shall be subjected to the jumble test in accordance with MIL-STD-351 and 30 plus or minus 2 revolutions per minute. Disassembly and examination of the fuzes shall be accomplished after both jolt and jumble tests have been completed. Examination shall be made to determine compliance with 3.4.

4.4.2 Functioning.-The fuzes shall be assembled into any projectile of the specified caliber for which the fuze is standard and tested in accordance with Table III, 4.5.2.1 and 4.5.2.2.

TABLE III

Phase	Sample Size	Weapon	Muzzle Vel. * ft/sec	Pressure (p.s.i.)	Target	Range
SQ	10	76mm gun	-	43,000	3/4"plywood	400 ft.
SQ	10	4.2" Mortar	-	7 incr.	***ground impact	**conv.
Delay	5	75mm gun	-	42,000	4" wood	400
Delay	5	76mm gun	2600	36,000 (min.)	ground impact	conv.
Delay	5	105mm How.	650	-	ground impact	conv.

* feet per second
** convenient
*** ground impact

4.4.2.1 Superquick phase.-Twenty (20) fuzes shall be set in the superquick position. Referring to Table III, the fuzes shall be fired as follows:

a. Ten (10) fuzes shall be fired from a 76mm gun with a chamber pressure of approximately 43,000 pounds per square inch (p.s.i.) for impact against a 3/4 inch plywood screen placed not less than 400 feet from the muzzle of the gun.

b. Ten (10) fuzes shall be fired from a 4.2 inch mortar with a seven increment charge, for impact on firm ground at any convenient range to insure impact on the noze of the fuze.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

4.4.2.2 Delay phase.-The remaining fifteen (15) fuzes shall be set in the "Delay" position. Referring to Table III, the fuzes shall be fired as follows:

a. Five (5) fuzes shall be fired as specified in 4.4.2.1. (a) except that chamber pressure shall be approximately 42,000 psi for impacting against a four inch wood screen.

b. Five (5) fuzes shall be fired from a 75 mm gun with a muzzle velocity of approximately 2600 feet per second (f.p.s.) and a chamber pressure exceeding 36,000 psi for impact or firm ground at any convenient range to insure impact on the nose of the fuze.

c. Five fuzes (5) shall be fired from a 105 mm Howitzer with a muzzle velocity of approximately 650 fps for impact on firm ground at any convenient range to insure impact on the nose of the fuze.

4.4.3 Head assembly torque.-The head assembly shall be subjected to an unscrewing force of not less than 15 nor more than 16 inch-pounds to determine compliance with 3.3.

4.4.4 Booster assembly torque.-The booster assembly torque test shall be performed using equipment in accordance with 4.3.4 to determine compliance with the requirements specified on the applicable drawing. The test shall be performed prior to staking.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging.

5.1.1 Level A.-Packaging for Fuze, M535, shall be in accordance with dwg. 8864492.

5.1.2 Level C.-Packaging for Fuze, M535, shall be in accordance with dwg. 7548401.

5.2 Packing

5.2.1 Level A.-Packing for Fuze, M535, shall be in accordance with dwg. 8861213.

5.2.2 Level C.-Packing for Fuze, M535 shall be in accordance with dwg. 7548400.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

5.3 Marking.-Marking shall be as specified on the applicable packing drawing.

5.4 Data cards.-Data card information shall be as specified in Military Specification MIL-A-2550.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor will design inspection equipment as required by the referenced Inspection Equipment Lists in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists (IEL) indicate the availability of inspection equipment design by showing in the "number" column of the list of inspection equipment (00 Form 1242-3) the numbers of drawings of existing equipment designs or codes indicating "commercial item" or "contractor design". Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.2 and 6.3.3. Action required by the contractor with respect to "commercial item" inspection equipment is described in paragraph 6.3.4. The contractor will be required to prepare drawings for all the equipment coded as "contractor design" in the number column. The code will further indicate whether detailed or specification control drawings are required. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Ordnance Designs.-Ordnance designs are detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Ordnance design is

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

listed for an item of inspection equipment. Ordnance designs fall into two basic classifications; mandatory and non-mandatory. When an IEL references mandatory Ordnance designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment to facilitate his operations. Such contractor prepared designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.3 Specification control drawings.-Specification control drawings depict the device in outline, descriptive, diagrammatic, or pictorial form only and specify the required performance or other characteristics. Contractors must prepare drawings of their designs in support of specification control drawings. The IEL code will indicate whether drawings must be detailed. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirement of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Commercial items.-Commercial item inspection equipment is equipment that has a universal application for a specific function. It is comprised of items commonly used by industry and government. Contractors are not required to furnish drawings of commercial item inspection equipment but a list of such equipment must be approved by the Government. Lists will be submitted for approval to the inspection element of the agency administering the contract.

6.3.5 IEL codes.-The inspection equipment referenced in paragraphs 6.3.1, 6.3.2, 6.3.3, and 6.3.4 will be designated in the IEL by the following codes:

CDOF - Contractor's design responsibility on Ordnance format; ORDM-608-12.
CDCF - Contractor design responsibility on contractor format.
OD - Ordnance design.
ODMU - Ordnance design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.

6.3.6 Use of standard measuring equipment.-If the contractor desires to use standard measuring equipment in lieu of government or contractor designed gages, diagrammatic sketches or other descriptions of the use of such equipment shall be submitted for approval as specified in 6.3.7.

6.3.7 Submission of contractor designs.-Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Premature bursts.-Premature burst is defined as the functioning of the fuze in the weapon bore or in flight before impact.

6.5 Reverse Functioning.-Reverse functioning is defined as superquick (SQ) functioning of the fuze when set in the "Delay" position, or delay functioning in the "SQ" position.

6.6 Check test.-The contracting officer will arrange for the contractor to be reimbursed for the expense incurred in the performance of the detonator check test.

Notice.-When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1390-A312

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T06:02Z
Check the source to verify that this is the current version before use.